

STORMWATER MANAGEMENT FACILITIES MAINTENANCE PROGRAM

- THE FOLLOWING MAINTENANCE PLAN HAS BEEN DEVELOPED TO MAINTAIN THE PROPER FUNCTION OF ALL DRAINAGE AND EROSION AND SEDIMENT CONTROL FACILITIES: • MINIMIZE THE USE OF ROAD SALT FOR MAINTENANCE OF DRIVEWAY AREAS.
- DRAINAGE INLETS SHALL BE VACUUM SWEPT TWICE A YEAR, AT THE CONCLUSION OF THE LANDSCAPE SEASON IN THE FALL AND AT THE CONCLUSION OF THE SAND AND DE-ICING SEASON IN THE SPRING. INSPECT EXFILTRATION/ATTENUATION GALLERY FOR SEDIMENT AND REMOVE SAME IF FOUND.
- THE PERMANENT MAINTENANCE PROGRAM WILL BE MANAGED BY THE FUTURE HOMEOWNERS UPON COMPLETION OF CONSTRUCTION AND ACCEPTANCE OF THE IMPROVEMENTS.

CONTRACTOR SHALL CONTACT DESIGN ENGINEER TO SCHEDULE A SITE INSPECTION PRIOR TO BACKFILLING INFILTRATION/ATTENUATION SYSTEM(S). SHOULD THE CONTRACTOR BACKFILL PRIOR TO INSPECTION, THE CONTRACTOR SHALL EXPOSE THE SYSTEM AT THEIR OWN EXPENSE.

ANY ALTERATIONS OR REVISIONS OF THESE PLANS, UNLESS DONE BY OR UNDER THE DIRECTION OF THE NYS LICENSED AND REGISTERED ENGINEER THAT PREPARED THEM, IS A VIOLATION OF THE NYS EDUCATION LAW.

NOTES: 1. THE BUILDING INSPECTOR OR VILLAGE ENGINEER MAY REQUIRE ADDITIONAL 1. THE BUILDING INSPECTOR OR VILLAGE ENGINEER MAY REQUIRE ADDITIONAL 1. THE BUILDING INSPECTOR OR VILLAGE ENGINEER MAY REQUIRE ADDITIONAL

- EROSION CONTROL MEASURES IF DEEMED APPROPRIATE TO MITIGATE UNFORESEEN SILTATION AND EROSION OF DISTURBED SOILS. "AS-BUILT" DRAWINGS OF THE SITE IMPROVEMENTS SHALL BE SUBMITTED TO
- THE VILLAGE ENGINEER FOR REVIEW PRIOR TO OBTAINING CERTIFICATE OF
- INFILTRATION SYSTEM ACCESS PORTS SHALL BE SHOWN ON THE "AS-BUILT". THE INFILTRATION SYSTEM MUST NOT BE CONNECTED UNTIL CONSTRUCTION IS
- COMPLETE AND THE SITE IS STABILIZED. NO EXISTING UTILITIES WILL BE DISTURBED BY PROPOSED WORK.
- ROOT ZONES OF ALL EXISTING TREES SHALL BE PROTECTED WITH A MINIMUM OF 6-INCHES OF WOOD CHIPS OR MULCH IN AREAS PRONE TO COMPACTION DUE TO CONSTRUCTION ACTIVITIES.
- LOCATION OF ALL EXISTING UTILITIES TO BE VERIFIED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION.

- ESTABLISH CONSTRUCTION STAGING AREA. INSTALL TREE PROTECTION ON TREES AS NOTED ON PLANS.
- 4. SELECTIVE VEGETATION AND TREE REMOVAL FOR SILT FENCE INSTALLATION.
- 5. INSTALL SILT FENCE DOWN SLOPE OF ALL AREAS TO BE DISTURBED AS SHOWN 6. STRIP TOPSOIL AND STOCKPILE AT THE LOCATIONS SPECIFIED ON THE PLANS (UP GRADIENT OF EROSION CONTROL MEASURES). TEMPORARILY STABILIZE
- TOPSOIL STOCKPILES (HYDROSEED DURING MAY 1ST THROUGH OCTOBER 31ST PLANTING SEASON OR BY COVERING WITH A TARPAULIN(S) NOVEMBER 1ST THROUGH APRIL 30TH. INSTALL SILT FENCE AROUND TOE OF SLOPE. 7. EXCAVATE AND INSTALL EXFILTRATION SYSTEMS PER MANUFACTURER'S RECOMMENDATIONS AND REQUIREMENTS. EXFILTRATION SYSTEMS SHALL BE TEMPORARILY PLUGGED UNTIL THE COMPLETION OF CONSTRUCTION AND THE SITE
- IS STABILIZED. 8. INSTALL ALL CATCH BASINS AND PIPING
- 9. EXCAVATE FOR ADDITION FOUNDATION. 10. CONSTRUCTED PROPOSED ADDITIONS.
- 11. INSTALL SUB-BASE COURSE. FINE GRADE AND SEED ALL DISTURBED AREAS. CLEAN DRAIN LINES AND CATCH BASINS. CLEAN EXFILTRATION SYSTEM. ENSURE

INSTALL LANDSCAPE PLANTINGS. SPREAD SALT HAY OVER SEEDED AREAS.

- GRASS STAND IS ACHIEVED. 12. UNPLUG EXFILTRATION SYSTEMS. INSTALL AND CONNECT ALL ROOF DRAIN
- LEADERS TO PREVIOUSLY INSTALLED EXFILTRATION SYSTEMS. 13. INSTALL 4"-6" TOPSOIL, FINE GRADE, SEED THE ENTIRE PROJECT SITE AND
- 14. INSTALL BITUMINOUS CONCRETE TOP COURSE. 15. REMOVE ALL TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES AFTER THE SITE IS STABILIZED WITH VEGETATION. *SOIL EROSION AND SEDIMENT CONTROL MAINTENANCE MUST OCCUR WEEKLY

AND PRIOR TO AND AFTER EVERY 1/2" OR GREATER RAINFALL EVENT.

EXISTING INFORMATION SHOWN HEREON PROVIDED BY CSE CONSTRUCTION LAND SURVEYING DATED FEBRUARY 17, 2021

DEPTH - 98"

0-6" TOPSOIL

NO GROUNDWATER

NO LEDGE ROCK

DEPTH - 101" 0-6" TOPSOIL

NO LEDGE

6-33" REDDISH BROWN SANDY LOAM

33-98" BROWN SAND WITH SMALL ROCKS

*(30 INCHES/HOUR WAS UTILIZED)

6-30" MIXED SANDS WITH SMALL ROCKS

*(30 INCHES/HOUR WAS UTILIZED)

30-48" REDDISH BROWN SANDY SILT

PERC. = 101.70 INCHES/HOUR

WITH SMALL ROCKS

PERC. = 120 INCHES/HOUR

48-101" MIXED SANDS

NO GROUNDWATER

GRAPHIC SCALE (IN FEET) 1 inch = 10 ft.

SITE LOCATION LOCATION MAP SCALE: 1"=500'

GENERAL NOTES:

LEGEND

- 1. THE ENGINEER SHALL NOT BE RESPONSIBLE FOR THE SUPERVISION OF THE
- NO CHANGES SHALL BE MADE TO THESE PLANS EXCEPT AS PER NYS LAW CHAPTER 987 ALL WORK AND MATERIALS SHALL COMPLY WITH ALL APPLICABLE CODES, INCLUDING BUT NOT LIMITED TO ACL. AISC. ZONING, AND THE NEW YORK STATE BUILDING CODE.
- ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES. ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER AND ANY SUCH CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND

4. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE

- ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS
- OF HIS EMPLOYEES, SUBCONTRACTORS AND THEIR AGENTS AND EMPLOYEES, AND OTHER PERSONS PERFORMING ANY OF THE WORK UNDER A CONTACT WITH THE CONTRACTOR. 8. SAFETY DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL CONFORM TO ALL LOCAL, STATE AND FEDERAL AGENCIES IN EFFECT DURING THE
- PERIOD OF CONSTRUCTION. 9. THE CONTRACTOR AND HIS SUBCONTRACTORS SHALL MAKE APPLICATION TO RECEIVE ALL NECESSARY PERMITS TO PERFORM THE WORK UNDER CONTRACT. THE CONTRACTOR AND HIS SUBCONTRACTORS SHALL BE LICENSED TO DO ALL WORK AS REQUIRED BY THE LOCAL, COUNTY, AND STATE AGENCIES WHICH MAY HAVE JURISDICTION OVER THOSE RADES, AND SHALL PRESENT THE OWNER WITH COPIES OF ALL LICENSES AND INSURANCE CERTIFICATES.
- 10. FINAL GRADING AROUND THE BUILDING AREA SHALL SLOPE AWAY FROM THE STRUCTURE. 11. ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS.
- 12. ADJOINING PUBLIC AND PRIVATE PROPERTY SHALL BE PROTECTED FROM DAMAGE DURING CONSTRUCTION, REMODELING AND DEMOLITION WORK. PROTECTION MUST BE PROVIDED FOR FOOTINGS, FOUNDATIONS, PARTY WALLS, CHIMNEYS, SKYLIGHTS AND ROOFS. PROVISIONS SHALL BE MADE TO CONTROL WATER RUNOFF AND EROSION DURING CONSTRUCTION OR DEMOLITION ACTIVITIES. THE PERSON MAKING OR CAUSING AN EXCAVATION TO BE MADE SHALL PROVIDE WRITTEN NOTICE TO THE OWNERS OF ADJOINING BUILDINGS ADVISING THEM THAT THE EXCAVATION IS TO BE MADE AND THAT THE ADJOINING BUILDING SHOULD BE PROTECTED. SAID NOTIFICATION SHALL BE DELIVERED NOT LESS THAN 10 DAYS PRIOR TO THE SCHEDULED STARTING DATE OF THE
- 13. OWNER SHALL INSURE THAT THE INSURANCE PROVIDED BY THE CONTRACTOR HIRED TO PERFORM THE WORK SHALL BE ENDORSED TO NAME HUDSON ENGINEERING & CONSULTING, P.C., AND ANY DIRECTORS, OFFICERS, EMPLOYEES, SUBSIDIARIES, AND AFFILIATES, AS ADDITIONAL INSURED ON ALL POLICIES AND HOLD HARMLESS DOCUMENTS, AND SHALL STIPULATE THAT THIS INSURANCE IS PRIMARY, AND THAT ANY OTHER INSURANCE OR SELF-INSURANCE MAINTAINED BY HUDSON ENGINEERING & CONSULTING. P.C., SHALL BE EXCESS ONLY AND SHALL NOT BE CALLED UPON TO CONTRIBUTE WITH THIS INSURANCE. ISO ADDITIONAL INSURED ENDORSEMENT FORM NUMBER CG2010 1185 UNDER GL. COPIES OF THE INSURANCE POLICIES SHALL BE SUBMITTED TO HUDSON ENGINEERING & CONSULTING, P.C., FOR APPROVAL PRIOR TO THE SIGNING OF THE
- CONTRACT. 14. INDUSTRIAL CODE RULE 753: THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES 72 HOURS PRIOR TO THE START OF HIS OPERATIONS AND SHALL COMPLY WITH ALL THE LATEST INDUSTRIAL CODE RULE 753 REGULATIONS.

INSTALLATION & MAINTENANCE OF EROSION CONTROL:

CONSTRUCTION SCHEDULE NOTIFY APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 5 DAYS PRIOR TO START.

EROSION CONTROL MEASURES INSTALL ALL EROSION CONTROL MEASURES PRIOR TO START OF CONSTRUCTION. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING

JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH. INSPECTION BY MUNICIPALITY

MAINTENANCE (TO BE PERFORMED DURING ALL PHASES OF CONSTRUCTION) AFTER ANY RAIN CAUSING RUNOFF, CONTRACTOR TO INSPECT HAYBALES, ETC. AND REMOVE ANY EXCESSIVE SEDIMENT AND INSPECT STOCKPILES AND CORRECT ANY PROBLEMS WITH SEED ESTABLISHMENT.

APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION.

INSPECTION BY MUNICIPALITY — FINAL GRADING REMOVE UNNEEDED SUBGRADE FROM SITE. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.

INSPECTIONS SHALL BE DOCUMENTED IN WRITING AND SUBMITTED TO THE

INSPECTION BY MUNICIPALITY - LANDSCAPING

SPREAD TOPSOIL EVENLY OVER AREAS TO BE SEEDED. HAND RAKE LEVEL. BROADCAST 1.25 LB. BAG OF JONATHAN GREEN "FASTGROW" MIX OR EQUAL OVER AREA TO BE SEEDED. APPLY STRAW MULCH AND WATER WITHIN 2 DAYS OF COMPLETION OF TOPSOILING. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.


INSPECTION BY MUNICIPALITY - FINAL LANDSCAPING

GRASS ESTABLISHED. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.

INSPECTION BY MUNICIPALITY - FINAL INSPECTION

ALL EROSION CONTROL MEASURES REMOVED AND GRASS ESTABLISHED. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.

PROPOSED ADDITIONS & ALTERATIONS 24 ELDREDGE PLACE VILLAGE OF DOBBS FERRY WESTCHESTER COUNTY - NEW YORK




STORMWATER MANAGEMENT PLAN

HUDSON ENGINEERING CONSULTING, P.C. 5 Knollwood Road – Suite 201 Elmsford, New York 10523 T: 914-909-0420

F: 914-560-2086

Designed By: S.(Checked By: M.S

© 2021



W/ S.S. CAP SCREW LID

6" INTERNAL COUPLING

12" CLASS "C"

CONCRETE COLLAR


PAVED SURFACE INSTALLATION DETAIL

1. WHEN ACCESS PORT IS UTILIZED AS SYSTEM OVERFLOW, INSTALL NDS

ADJACENT GRADE TO PITCH AWAY FROM ACCESS PORT IN ALL

2. INSPECTION PORT NOT TO SERVE AS OVERFLOW WHEN INSTALLED IN

MODEL 50 GRATE. GRATE TO BE SET 1/2" ABOVE ADJACENT GRADE.



RECHARGER 330XLHD

- NATURALLY COMPACTED

FINISHED GRADE

58.0" [1473 mm] MIN.

CENTER TO CENTER

<u>GENERAL NOTES</u>
RECHARGER 330XL HD BY CULTEC, INC. OF BROOKFIELD, CT.

STORAGE PROVIDED = $11.32 \text{ CF/FT } [1.05 \text{ m}^3/\text{m}] \text{ PER DESIGN}$

REFER TO CULTEC, INC.'S CURRENT RECOMMENDED INSTALLATION

THE CHAMBER WILL BE DESIGNED TO WITHSTAND TRAFFIC LOADS

WHEN INSTALLED ACCORDING TO CULTEC'S RECOMMENDED


INSTALLATION INSTRUCTIONS

HEAVY DUTY CHAMBER

12.0' [3.66 m]


MAX. BURIAL DEPTH

CULTEC INSPECTION PORT




- 1. THE WASHOUT SHALL BE INSTALLED PRIOR TO USING MATERIALS THAT REQUIRE WASHOUT ON THIS PROJECT.
- 2. AS NECESSARY, SIGNS SHALL BE PLACED THROUGHOUT THE SITE TO
- INDICATE THE LOCATION OF THE WASHOUT. 3. THE WASHOUT AREA WILL BE REPLACED AS NECESSARY TO MAINTAIN
- CAPACITY FOR LIQUID WASTE 4. WASHOUT RESIDUE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF
- AT AN APPROVED WASTE FACILITY. 5. DO NOT WASHOUT INTO STORM DRAINS, OPEN DITCHES, STREETS, OR
- 6. AVOID DUMPING EXCESS CONCRETE IN NON-DESIGNATED DUMPING AREAS.
- 7. LOCATE WASHOUT AT LEAST 50' (15 METERS) FROM STORM DRAIN, OPEN DITCHES, OR WATER BODIES.
- 8. THE WASHOUT SHALL BE USED ONLY FOR NON-HAZARDOUS WASTES.

CORRUGATED CONCRETE WASHOUT



STEEL TRENCH DRAIN



NDS SQUARE CATCH BASIN

STAKE SPACING -12' O.C. ─ 66" T-STAKES DRIVEN 48" HIGH DENISTY ORANGE POLYETHYLENE SAFETY FENCE TIES TO SECURE SAFETY FENCE TO POSTS **FINISHED** GRADE **CONSTRUCTION FENCE**

CULTEC NO. 410 NON-WOVEN GEOTEXTILE AROUND

CRUSHED STONE

├--- 52.0" [1321 mm]—-|

LENGTH OF THE CHAMBER.

REGULATIONS

CULTEC RECHARGER 330XLHD

CULTEC NO. 66 WOVEN GEOTEXTILE (FOR SCOUR

PROTECTION) TO BE PLACED BENEATH INTERNAL

MANIFOLD FEATURE AND BENEATH ALL INLET/OUTLET

ALL RECHARGER 330XL HD HEAVY DUTY UNITS ARE MARKED

WITH A COLOR STRIPE FORMED INTO THE PART ALONG THE

ALL RECHARGER 330XL HD CHAMBERS MUST BE INSTALLED IN

ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL

- HVLV FC-24 FEED CONNECTOR WHERE SPECIFIED

_6.0" [152 mm] MIN.

30.5" [775 mm]


12.0" [305 mm] MIN.

─ 1-2 INCH [25-51 mm] DIA. WASHED,

STONE. TOP, SIDES, AND BOTTOM MANDATORY

- 3' LONG NDS CHANNEL GRATE (NDS PART # 540, 541, 542, 543, OR 544) COLOR TO BE SELECTED BY OWNER -RECESSED 1/8" " MIN. PAVING STONES 1" STONE DUST DRAIN 2" ITEM #4 4" GRAVEL 4x4 W2.9/2.9 WELDED WIRE MESH PIPING SPACED NDS ANCHOR STAKE OR APPROVED EQUAL 6" COLLECTION PIPING SLOPED @ 36" O.C. @ 2.0% NDS MINI CHANNEL DRAIN


SOIL STOCKPILING



1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.
2. SOILS OR FILL TO BE STOCKPILED ON SITE DURING CUTTING AND FILLING ACTIVITIES SHOULD BE LOCATED ON LEVEL PORTIONS OF THE SITE WITH A MINIMUM OF 50-75 FOOT SETBACKS FROM TEMPORARY DRAINAGE SWALES. 3. MAXIMUM SLOPE OF STOCKPILE SHALL BE 1:2. 4. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH EITHER SILT FENCING OR STRAWBALES, THEN STABILIZED WITH VEGETATION OR COVERED.

5. STOCKPILES REMAINING IN PLACE FOR MORE THAN A WEEK SHOULD BE SEEDED AND MULCHED OR COVERED WITH GEOTEXTILE FABRIC SURROUNDED BY SILT FENCE. 6. SEE SPECIFICATIONS (THIS MANUAL) FOR INSTALLATION OF SILT FENCE.


SILT FENCE



JOINING SECTIONS OF FENCING

INSTALLATION NOTES:


1. EXCAVATE A 4 INCH * 4 INCH TRENCH ALONG THE LOWER PERIMETER OF THE SITE. 2. UNROLL A SECTION AT A TIME AND POSITION THE POSTS AGAINST THE BACK (DOWNSTREAM) WALL OF THE TRENCH (NET SIDE AWAY FROM DIRECTION OF FLOW). 3. DRIVE THE POST INTO THE GROUND UNTIL THE NETTING IS APPROXIMATELY 2 INCHES FROM THE TRENCH BOTTOM. 4. LAY THE TOE-IN FLAP OF FABRIC ONTO THE UNDISTURBED BOTTOM OF THE TRENCH, BACKFILL THE TRENCH AND TAMP THE SOIL. STEEPER SLOPES REQUIRE AN INTERCEPT 5. JOIN SECTIONS AS SHOWN ABOVE



NOTES (STORM SEWER):

1. REFER TO PLAN FOR SPECIFIC PIPE SIZING AND SLOPE SPECIFICATIONS; HOWEVER, IN GENERAL, ALL STORM SEWER SERVICES TO BE 6" SCH. 40 @ 1.0% MINIMUM. 2. CLEANOUTS SHALL BE PLACED BEFORE SIGNIFICANT PIPE BEND LOCATIONS (I.E., JUNCTIONS, 90-DEGREE BENDS, ETC.) UNLESS A ROOF LEADER DOWNSPOUT CONNECTION IS

SEWER CLEANOUT DETAIL (GRAVITY)





STONE & BLOCK DROP INLET PROTECTION

CONSTRUCTION SPECIFICATION

- LAY ONE BLOCK ON EACH SIDE OF THE STRUCTURE ON ITS SIDE FOR DEWATERING. FOUNDATION SHALL BE 2 INCHES MINIMUM BELOW REST OF INLET AND BLOCKS SHALL BE PLACED AGAINST INLET FOR SUPPORT.
- 2. HARDWARECLOTH OR 1/2" WIRE MESH SHALL BE PLACED OVER BLOCK OPENINGS TO SUPPORT STONE.
- 3. USE CLEAN STONE OR GRAVEL 1/2-3/4 INCH IN DIAMETER PLACED 2 INCHES BELOW TOP OF BLOCK ON A 2:1 SLOPE OR FLATTER.
- 4. FOR STONE STRUCTURES ONLY, A 1 FOOT THICK LAYER OF THE FILTER STONE WILL BE PLACED AGAINST THE 3 INCH STONE AS SHOWN ON THE DRAWINGS. MAXIMUM DRAINAGE AREA 1 ACRE.

FENCING AND ARMORING










PROPOSED ADDITIONS & ALTERATIONS 24 ELDREDGE PLACE VILLAGE OF DOBBS FERRY WESTCHESTER COUNTY - NEW YORK **DETAILS**



HUDSON

ENGINEERING CONSULTING, P.C. 45 Knollwood Road – Suite 201 Elmsford, New York 10523 T: 914-909-0420

F: 914-560-2086

© 2021

Designed By: S.G Checked By: M.S

ANY ALTERATIONS OR REVISIONS OF THESE PLANS, UNLESS DONE BY OR UNDER THE DIRECTION OF THE NYS LICENSED AND REGISTERED ENGINEER THAT PREPARED THEM, IS A VIOLATION OF THE NYS EDUCATION LAW.

6" BELOW SURFACE

95% COMPACTED FILL -

PAVEMENT -

PAVED/TRAFFIC AREAS.