MIXED-USE BUILDING

185-191 ASHFORD AVENUE, DOBBS FERRY, NY 10522

C H R I S T I N A G R I F F I N A R C H I T E C T P C

10 Spring Street, Hastings-on-Hudson, NY 10706



OWNER	ARCHITECT	CIVIL ENGINEER	DATES	LIST OF DRAWINGS
ASHFORD AVENUE APARTMENTS, LLC ANDREW CORTESE 145 PALISADE ST. SUITE 318E DOBBS FERRY NY 10522 914-478-4250 ANDREW@CORTESECONSTRUCTION.COM	CGA STUDIO CHRISTINA GRIFFIN AIA LEED AP CPHC 10 SPRING STREET HASTINGS-ON-HUDSON, NY 10706 914.478.0799 CG@CGASTUDIO.COM	HUDSON ENGINEERING & CONSULTING, P.C. 45 KNOLLWOOD ROAD SUITE 201 ELMSFORD, NY 10523 914.909.0420 HUDSONEC.COM	PLANNING BOARD SUBMISSION PLANNING BOARD / BOT REVISIONS PLANNING BOARD SUBMISSION PLANNING BOARD/BOT SUBMISSION PLANNING BOARD SUBMISSION PLANNING BOARD SUBMISSION PLANNING BOARD SUBMISSION	A-0 TITLE SHEET, 3D RENDERING, DATES, LIST OF DRAWINGS S-1 ZONING COMPLIANCE S-2 SITE PLAN S-3 LOCATION MAP, PHOTOS OF NEIGHBORING PROPERTIES 10-16-20 S-4 STREETSCAPE OF NEIGHBORING PROPERTIES 12-12-20 R-1 3D RENDERINGS B-1 BASEMENT PLAN, PHOTOS OF EXISTING CONDITIONS A-1 FIRST FLOOR PLAN A-2 SECOND FLOOR PLAN A-2 SECOND FLOOR PLAN A-4 ROOF PLAN A-5-A-7 EXTERIOR ELEVATIONS E-1 ELECTRICAL PLAN - EXTERIOR D7-22-21 HUDSON ENGINEERING DRAWINGS: C-1 EXISTING & DEMOLITION PLAN C-2 EROSION & SEDIMENT CONTROL PLAN C-3 STORMWATER MANAGEMENT PLAN - C-4 DETAILS

	REQUIRED	EXISTING	PROPOSED	
LOT AREA	NO MINIMUM LOT AREA	16,712 SF	16,712 SF	
NUMBER OF DWELLING UNITS	N/A	3 RETAIL & 2 RESIDENTIAL	2 RETAIL & 12 RESIDENTIAL	
MINIMUM RESIDENTIAL UNIT SIZE	600 SF PER UNIT	1,800 - 1,900 SF PER UNIT	703 -1,367 SF PER UNIT	
MAXIMUM BUILDING COVERAGE	60% (10,027 SF)	+/- 25% (+/-4,241 SF)	46% (7,643 SF)	
MAXIMUM IMPERVIOUS COVERAGE	80% (13,370 SF)	+/- 92% (+/-15,412)	80% (13,370 SF)	
MINIMUM PERVIOUS COVERAGE	20%	+/- 8% (+/-1,300 SF)	20% (3,349 SF) 1,577 SF PLANTINGS + 1,699 SF PERVIOUS PAVING + 292 SF GRASS BLOCK OR CONCRETE PERVIOUS PAVERS WITH MIN. 25% PERVIOUS 25% X 292 SF = 73 SF 1,577 + 1,699 + 73 SF = 3,349 SF	
MINIMUM LOT WIDTH FRONTAGE	N/A	164.45 FT	164.45 FT	
MAXIMUM BUILDING HEIGHT	3 STORIES / 35 FT	2 STORIES / +/-26.5 FT	3 STORIES / 35 FT	
BULKHEAD AREA	MAX. 20% TOTAL ROOF AREA	N/A	AREA OF ROOF: 5,941 SF AREA OF BULKHEAD: 580 SF (9.7%)	
FRONT YARD SETBACK	0 FT	0 FT	0 FT	
REAR YARD SETBACK	25 FT	45.8 FT	27.8 FT	
SIDE ONE	5 FT	0.3 FT	0.3 FT EXIST. NON-CONFORMING	
SIDE TWO	5 FT	72.3 FT	42.0 FT	
TOTAL OF TWO SIDES	10 FT	72.6 FT	42.3 FT	
DRIVEWAY SLOPE	14%	5%	2% - 5%	
PARKING REQUIREMENT RESIDENTIAL:	19 PARKING SPACES REQUIRED PARKING CALCULATION	19 PARKING SPACES	20 PARKING SPACES	
1 SPACE PER DWELLING UNIT +	RESIDENTIAL:			
½ PER BEDROOM	PROPOSED NUMBER OF UNITS:			
4 PER BEDROOM	(8) 2-BEDROOM X 1.5 = 12 PARKING SPACES			
RETAIL:	(4) 1-BEDROOM X 1.25 = 5 PARKING SPACES			
1 SPACE PER 500 SF OF FLOOR AREA (OFFICE/RETAIL)	17 RESIDENTIAL PARKING SPACES REQUIRED			
	RETAIL:			
	(2) SPACES AT 999 SF / 500 SF = 2			
	2 RETAIL / LIVE-WORK PARKING SPACES REQUIR	<u>RED</u>		
AFFORDABLE HOUSING	10% AFFORDABLE HOUSING UNITS =	N/A	(1) AFFORDABLE UNIT	
	10% X 12 = 1.2 OR (1) AFFORDABLE UNIT			
300-40: FOR RESIDENTIAL DEVELOPMENTS CONTAINING 10 DWELLING UNITS OR MORE,	AFFORDABLE UNIT MUST BE MIN. 80% OF FLOOR AREA OF COMPARABLE MARKET RATE UNIT		AFFORDABLE UNIT AREA UNIT 2 1,079 SF	
IO LESS THAN 10% OF ALL UNITS IN SUCH	AVERAGE SIZE OF MARKET RATE 2-BEDROOM UNIT			
DEVELOPMENT SHALL MEET THE DEFINITION OF	UNIT 1 1,350 SF			
AN "AFFORDABLE HOUSING UNIT."	UNIT 3 1,289 SF			
	UNIT 0 1 121 SE			
	UNIT 10 1 267 SE			
	UNIT 10 1,367 SF			
	UNIT 12 1 295 SE			
	UNIT 12 1,385 SF			
	TOTAL 8,900 SF / 7 UNITS = 1,271 SF			
	$1,271 \text{ SF} \times 80\% = 1,017 \text{ SF} = MIN. SIZE OF AFFORDABLE UNIT$			

MIXE-USE BUILDING AT 185-191 ASHFORD AVENUE DOBBS FERRY, NY 10522

CHRISTINA GRIFFIN ARCHITECT PC
10 Spring Street
Hastings-on-Hudson, New York 10706
914.478.0799
www.christinagriffinarchitect.com

 Date
 DESIGN DRAWINGS 5-29-20
 PB

 DESIGN DRAWINGS 6-24-20
 BOT SUBMISSION 8-14-20

 REVISED BOT SUBMISSION 10-16-20
 PLANNING BOARD SUBMISSION 12-21-20

Drawing Title ZONING DATA

Soale:


S-1



Date
PLANNING BOARD PRESENTATION 5-5-21
PB SUB. 5-12-21
PB SUB. 6-17-21
PB SUB. 7-22-21

SITE PLAN

S-2










AREA MAP / PHOTOS OF NEIGHBORING PROPERTIES

SCALE: NTS





STREETSCAPE OF NEIGHBORING PROPERTIES

SCALE: $\frac{1}{16}$ " = 1'-0"







RENDERING OF PROPOSED BUILDING

SCALE: NTS



CHRISTINA GRIFFIN ARCHITECT PC 10 Spring Street Hastings-on-Hudson, New York 10706

 DRAWINGS 5-29-20
 PB SUB. 5-12-21

 DRAWINGS 6-24-20
 PB SUB. 5-18-21

 3MISSION 8-14-20
 PB SUB. 5-18-21

 INS 9-23-20
 PB SUB. 6-17-21


 D BOT SUBMISSION 10-16-20
 PB SUB. 7-22-21


 VG BOARD SUBMISSION 12-21-20

 VG BOARD / BOT REVISIONS 1-27-21

FIRST FLOOR PLAN


A-1






SECOND FLOOR PLAN

1 2



THIRD FLOOR PLAN




ROOF PLAN



П **1**

ARCHITECT CHRISTINA GRIFFI
10 Spring Street
Hastings-on-Hudso
914.478.0799
www.christinagriffir



EAST ELEVATION

SCALE: 3/16" = 1'-0"

THINBRICK BY

GLEN-GERY OR SIMILAR

CEMENTITIOUS

1ST FLOOR EL. 241.0

EXIST.
DRIVEWAY
GRADE

SIDEWALK AT MIDPOINT OF

PANELS



Ш

9

L

Z

 \times

 \sum

ARCHITECT




CHRISTINA GRIFFI
PB SUB. 6-17-21
PB SUB. 7-22-21
1-27-21
Hastings-on-Hudso
914.478.0799
www.christinagriffir

SUBMISSION 8-14-20
SED BOT SUBMISSION 10-16-20
NING BOARD SUBMISSION 12-21-20
NING BOARD / BOT REVISIONS 1-27-21
NING BOARD REVISIONS 3-12-21
NING BOARD SUBMISSION 3-24-21
NING BOARD SUBMISSION 4-22-21


BOT SUBMISSION 8-14-20
REVISED BOT SUBMISSION 10-1
REVISED BOT SUBMISSION 10-1
PLANNING BOARD SUBMISSION
PLANNING BOARD / BOT REVISIONS 3

Scale:
AS SHOWN

SETERED ANCHIAMARIE GRANT



NORTH ELEVATION




ARCHITECT



TAAG 6 WALL SCONCE BY TECH LIGHTING, 5" W. x 5.9" H. x 5.7" D., **CHARCOAL FINISH** (OR TAAG 10, 10.2" W, 9.8 H. 10.2" D.)








PITCH WALL SCONCE BY TECH LIGHTING, 5" W. x 5" H. x 3.9" D., CHARCOAL FINISH



LED SQUARE STEP/WALL LIGHT BY WAC LIGHTING, 2.75" W. x 3.25" H. x 1.88" D., **BRONZED STAINLESS** STEEL FINISH



FENCE POST LIGHT.


VERSA STAR RECESSED LIGHT BY BK LIGHTING, 5" DIAMETER, ALUMINUM FINISH





LANDSCAPING LIGHT BY BK LIGHTING, STYLE "J" 2 ½" DIA,, 12" H., **ALUMINUM FINISH**


PLANT SCHEDULE

<u>Key</u>	<u> Qty.</u>	Common & Botanical Name	<u>Síze</u>	<u>Root</u>
AR	1	October Glory Maple Acer Rubrum October Glory	3-3 ½" Cal.	B∉B
TC	3	Greenspire Linden Tilia cordata	3"-3 ½" Cal.	BŧB
TO	14	Green Giant Arbrovitae Thuja standishii x plicata	8'-10' Ht.	B\$B
HOL	5	Dragon Lady Holly llex x aquipernyi 'Dragon Lady'	5' Ht.	
HYD	16	All Summers Beauty Hydrangea 'All Summers Beauty'	#5 Cont.	
CA	2Ø	Feather Reed Grass Calamagrostis acutiflora 'Karl Fo	#2 Cont. erster'	
PEN	50	pensylvania sedge Carex pensylvanica	#2 Cont.	
DAY	22	Happy Returns Daylily Hemerocallis 'Happy Returns'	#I Cont.	
LIR	28	Big Blue Lilly Turf Liriope muscari	#I Cont.	












1 OF 1



191 ASHFORD AVENUE EXISTING AND DEMOLITION PLAN BASED UPON EXISTING INFORMATION PROVIDED BY SUMMIT LAND SURVERYING P.C. LOCATED AT 21 DRAKE LANE, WHITE PLAINS, NY 10607, DATED MAY 8, 2020





PROPOSED BUILDING
191 ASHFORD AVENUE
VILLAGE OF DOBBS FERRY
WESTCHESTER COUNTY — NEW YORK

EXISTING AND DEMOLITION PLAN



HUDSON

ENGINEERING

8

CONSULTING, P.C.

45 Knollwood Road - Suite 201


Elegated Now York 10522


T: 914-909-0420

F: 914-560-2086

Date: 03/23/21 | Sheet | 1" = 10' | Designed By: D.Y. | Checked By: M.S. | Sheet No. | Checked By: Designed By: Designed By: D.Y. | Checked By: M.S. | Checked By: Designed By: D.Y. | Checked By: M.S. | Checked By: D.Y. | Checked By: M.S. | Checked By: D.Y. | C

ANY ALTERATIONS OR REVISIONS OF THESE PLANS, UNLESS DONE BY OR UNDER THE DIRECTION OF THE NYS LICENSED AND REGISTERED ENGINEER THAT PREPARED THEM, IS A VIOLATION OF THE NYS EDUCATION LAW.





LEGEND

PROPERTY LINE CONCRETE CURB PROPOSED _____238_____ CONTOUR PROPOSED SPOT +238.5 GRADE PROPOSED STORM PIPE PROPOSED DRAIN INLET PROPOSED CHANNEL DRAIN PROPOSED TRENCH DRAIN TEMPORARY INLET PROTECTION TEMPORARY SILT TEMPORARY CONSTRUCTION FENCE TEMPORARY SOIL STOCKPILE AREA STABILIZED CONSTRUCTION PROPOSED LIMIT OF DISTURBANCE PROPOSED TREE PROTECTION PROPOSED ASPHALT DRIVEWAY/PARKING LOT PROPOSED PERVIOUS GRASS PAVERS PROPOSED PERVIOUS

INSTALLATION & MAINTENANCE OF EROSION CONTROL:

CONSTRUCTION SCHEDULE NOTIFY APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 5 DAYS

JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.

EROSION CONTROL MEASURES
INSTALL ALL EROSION CONTROL MEASURES PRIOR TO START OF CONSTRUCTION.
CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING

INSPECTION BY MUNICIPALITY MAINTENANCE (TO BE PERFORMED DURING ALL PHASES OF CONSTRUCTION)

AFTER ANY RAIN CAUSING RUNOFF, CONTRACTOR TO INSPECT HAYBALES, ETC. AND REMOVE ANY EXCESSIVE SEDIMENT AND INSPECT STOCKPILES AND CORRECT ANY PROBLEMS WITH SEED ESTABLISHMENT. INSPECTIONS SHALL BE DOCUMENTED IN WRITING AND SUBMITTED TO THE

APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION.

INSPECTION BY MUNICIPALITY — FINAL GRADING REMOVE UNNEEDED SUBGRADE FROM SITE. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.

INSPECTION BY MUNICIPALITY - LANDSCAPING

SPREAD TOPSOIL EVENLY OVER AREAS TO BE SEEDED. HAND RAKE LEVEL. BROADCAST 1.25 LB. BAG OF JONATHAN GREEN "FASTGROW" MIX OR EQUAL OVER AREA TO BE SEEDED. APPLY STRAW MULCH AND WATER WITHIN 2 DAYS OF COMPLETION OF TOPSOILING. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.

INSPECTION BY MUNICIPALITY - FINAL LANDSCAPING

GRASS ESTABLISHED. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.

INSPECTION BY MUNICIPALITY - FINAL INSPECTION

ALL EROSION CONTROL MEASURES REMOVED AND GRASS ESTABLISHED. CALL FOR INSPECTION FROM THE APPROPRIATE MUNICIPAL AGENCY HAVING JURISDICTION AT LEAST 2 DAYS PRIOR TO FINISH.


VILLAGE NOTES:


1. TEMPORARY PEDESTRIAN TRAFFIC CONTROLS WILL BE REQUIRED TO MAINTAIN SAFE AND ACCESSIBLE USE OF THE SIDEWALK THROUGHOUT CONSTRUCTION. ADDITIONAL TRAFFIC CONTROLS MAY BE REQUESTED BY THE VILLAGE IF DEEMED APPROPRIATE.

2. THE LIMITS OF POROUS PAVEMENT AND PERVIOUS GRASS BLOCK PAVERS

SHALL BE SHOWN ON THE "AS-BUILT" SURVEY SUBMITTED TO THE VILLAGE

191 ASHFORD AVENUE EROSION & SEDIMENT CONTROL PLAN BASED UPON EXISTING INFORMATION PROVIDED BY SUMMIT LAND SURVERYING P.C. LOCATED AT 21 DRAKE LANE, WHITE PLAINS, NY 10607, DATED MAY 8, 2020





PROPOSED BUILDING 191 ASHFORD AVENUE VILLAGE OF DOBBS FERRY WESTCHESTER COUNTY - NEW YORK

EROSION & SEDIMENT CONTROL PLAN




HUDSON ENGINEERING CONSULTING, P.C. T: 914-909-0420

F: 914-560-2086

© 2021

Designed By: D.Y. Checked By: M.S.

ANY ALTERATIONS OR REVISIONS OF THESE PLANS, UNLESS DONE BY OR UNDER THE DIRECTION OF THE NYS LICENSED AND REGISTERED ENGINEER THAT PREPARED THEM, IS A VIOLATION OF THE NYS EDUCATION LAW.



3. AS-BUILT PLANS OF THE PROPOSED DRIVEWAY AND DRAINAGE IMPROVEMENTS SHALL BE SUBMITTED TO THE VILLAGE ENGINEER FOR REVIEW PRIOR TO ISSUANCE OF CERTIFICATE OF OCCUPANCY.

2. THE VILLAGE ENGINEER MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES IF

DEEMED APPROPRIATE TO MITIGATE UNFORESEEN SILTATION AND EROSION OF DISTURBED

- 4. FILL MATERIAL IMPORTED TO THE SITE SHALL BE CERTIFIED IN WRITING BY A NEW YORK LICENSED PROFESSIONAL ENGINEER AS CLEAN, NON-CONTAMINATED FILL SUITABLE FOR THE INTENDED USE
- 5. "BEFORE THE SITE PLAN IS SIGNED BY THE CHAIRMAN OF THE PLANNING BOARD, THE APPLICANT SHALL BE REQUIRED TO POST A PERFORMANCE BOND OR OTHER TYPE OF ACCEPTABLE MONETARY GUARANTY WHICH SHALL BE IN AN AMOUNT DETERMINED BY THE PLANNING BOARD AND THE VILLAGE ENGINEER AND IN A FORM SATISFACTORY TO THE VILLAGE ATTORNEY".
- 6. THE APPLICANT SHALL NOTIFY THE BUILDING DEPARTMENT OR VILLAGE'S CONSULTING ENGINEER IN WRITING AT LEAST 48 HOURS BEFORE ANY OF THE FOLLOWING SO THAT ANY INSPECTION MAY BE PERFORMED.
 - 6.2. INSTALLATION OF SEDIMENT AND EROSION CONTROL MEASURES.
- 6.3. COMPLETION OF SITE CLEARING.
- 6.6. CLOSURE OF CONSTRUCTION. 6.7. COMPLETION OF FINAL LANDSCAPING; AND
- 6.8. SUCCESSFUL ESTABLISHMENT OF LANDSCAPING IN PUBLIC AREAS 7. "THE OWNER OR OPERATOR SHALL HAVE A QUALIFIED INSPECTOR INSPECT AND DOCUMENT THE EFFECTIVENESS OF ALL EROSION AND SEDIMENTATION CONTROL PRACTICES AND PREPARE INSPECTION REPORTS AT LEAST ONCE A MONTH. THESE REPORTS MUST BE KEPT ON SITE AND AVAILABLE FOR REVIEW".

EARTHWORK ANALYSIS

108.94 CU. YD. 44.10 CU. YD. 64.84 CU. YD. CUT>

- . NO CHANGES SHALL BE MADE TO THESE PLANS EXCEPT AS PER NYS LAW CHAPTER 987. 3. ALL WORK AND MATERIALS SHALL COMPLY WITH ALL APPLICABLE CODES, INCLUDING BUT NOT LIMITED
- TO ACI, AISC, ZONING, AND THE NEW YORK STATE BUILDING CODE 4. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES. 5. ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER AND ANY SUCH CHANGES
- SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT. 6. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT.

EMPLOYEES, SUBCONTRACTORS AND THEIR AGENTS AND EMPLOYEES, AND OTHER PERSONS PERFORMING

ANY OF THE WORK UNDER A CONTACT WITH THE CONTRACTOR. 8. SAFETY DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL CONFORM TO ALL LOCAL, STATE AND FEDERAL AGENCIES IN EFFECT DURING THE PERIOD OF CONSTRUCTION.

7. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS

- 9. THE CONTRACTOR AND HIS SUBCONTRACTORS SHALL MAKE APPLICATION TO RECEIVE ALL NECESSARY PERMITS TO PERFORM THE WORK UNDER CONTRACT. THE CONTRACTOR AND HIS SUBCONTRACTORS SHALL BE LICENSED TO DO ALL WORK AS REQUIRED BY THE LOCAL, COUNTY, AND STATE AGENCIES WHICH MAY HAVE JURISDICTION OVER THOSE TRADES, AND SHALL PRESENT THE OWNER WITH COPIES OF ALL LICENSES AND INSURANCE CERTIFICATES. 10. FINAL GRADING AROUND THE BUILDING AREA SHALL SLOPE AWAY FROM THE STRUCTURE
- 11. ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS. 12. ADJOINING PUBLIC AND PRIVATE PROPERTY SHALL BE PROTECTED FROM DAMAGE DURING CONSTRUCTION, REMODELING AND DEMOLITION WORK. PROTECTION MUST BE PROVIDED FOR FOOTINGS, FOUNDATIONS, PARTY WALLS, CHIMNEYS, SKYLIGHTS AND ROOFS. PROVISIONS SHALL BE MADE TO CONTROL WATER RUNOFF AND EROSION DURING CONSTRUCTION OR DEMOLITION ACTIVITIES. THE PERSON MAKING OR CAUSING AN EXCAVATION TO BE MADE SHALL PROVIDE WRITTEN NOTICE TO THE OWNERS OF ADJOINING BUILDINGS ADVISING THEM THAT THE EXCAVATION IS TO BE MADE AND THAT THE ADJOINING BUILDING SHOULD BE PROTECTED. SAID NOTIFICATION SHALL BE DELIVERED NOT LESS THAN 10 DAYS PRIOR TO THE SCHEDULED STARTING DATE OF THE EXCAVATION.
- 13. OWNER SHALL INSURE THAT THE INSURANCE PROVIDED BY THE CONTRACTOR HIRED TO PERFORM THE WORK SHALL BE ENDORSED TO NAME HUDSON ENGINEERING & CONSULTING, P.C., AND ANY DIRECTORS, OFFICERS, EMPLOYEES, SUBSIDIARIES, AND AFFILIATES, AS ADDITIONAL INSURED ON ALL POLICIES AND HOLD HARMLESS DOCUMENTS, AND SHALL STIPULATE THAT THIS INSURANCE IS PRIMARY, AND THAT ANY OTHER INSURANCE OR SELF-INSURANCE MAINTAINED BY HUDSON ENGINEERING & CONSULTING, P.C., SHALL BE EXCESS ONLY AND SHALL NOT BE CALLED UPON TO CONTRIBUTE WITH THIS INSURANCE. ISO ADDITIONAL INSURED ENDORSEMENT FORM NUMBER CG2010 1185 UNDER GL. COPIES OF THE INSURANCE POLICIES SHALL BE SUBMITTED TO HUDSON ENGINEERING & CONSULTING, P.C., FOR
- APPROVAL PRIOR TO THE SIGNING OF THE CONTRACT. 14. INDUSTRIAL CODE RULE 753: THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES 72 HOURS PRIOR TO THE START OF HIS OPERATIONS AND SHALL COMPLY WITH ALL THE LATEST INDUSTRIAL CODE RULE 753 REGULATIONS.

THE BUILDING INSPECTOR OR VILLAGE ENGINEER MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES IF DEEMED APPROPRIATE TO MITIGATE UNFORESEEN SILTATION AND EROSION OF DISTURBED SOILS.


LEGEND

+238.5

- "AS-BUILT" DRAWINGS OF THE SITE IMPROVEMENTS SHALL BE SUBMITTED TO THE VILLAGE ENGINEER FOR REVIEW PRIOR TO OBTAINING CERTIFICATE OF OCCUPANCY. "THE RESTORATION FOR WORK PERFORMED WITHIN THE VILLAGE
- RIGHT-OF-WAY SHALL BE PERFORMED TO THE SATISFACTION OF THE VILLAGE ENGINEER AND DEPARTMENT OF PUBLIC WORKS." "BEFORE THE SITE PLANS ARE SIGNED BY THE CHAIRMAN OF THE PLANNING BOARD, THE APPLICANT SHALL BE REQUIRED TO POST A PERFORMANCE BOND OR OTHER TYPE OF ACCEPTABLE MONETARY GUARANTY WHICH SHALL BE IN THE AMOUNT DETERMINED BY THE PLANNING BOARD AND THE VILLAGE ENGINEER IN A FORM SATISFACTORY TO THE VILLAGE
- ATTORNEY." CONTRACTOR SHALL VERIFY ALL UTILITIES PRIOR TO CONSTRUCTION.

191 ASHFORD AVENUE STORMWATER MANAGEMENT PLAN BASED UPON EXISTING INFORMATION PROVIDED BY SUMMIT LAND SURVERYING P.C. LOCATED AT 21 DRAKE LANE, WHITE PLAINS, NY 10607, DATED MAY 8, 2020

GRAPHIC SCALE (IN FEET) 1 inch = 10 ft.



PUMPING SYSTEM SECTION

STORMWATER MANAGEMENT FACILITIES MAINTENANCE PROGRAM

TIMING, ACTIVITY, AND LOCATION

	INSPECTION	
GENERAL MAINTENANCE (STORM SEWER, CATCH BASINS/ DRAIN INLETS, MANHOLES, PRE-TREATMENT DEVICE AND INFILTRATION BASIN)	ALL	ALL STORMWATER FACILITIES SHALL BE INSPECTED IMMEDIATELY AFTER COMPLETION OF CONSTRUCTION, AND THEN MONTHLY FOR THE FIRST THREE (3) MONTHS FOLLOWING THE COMPLETION OF THE PROJECT. WITHIN THE FIRST THREE (3) MONTHS, INSPECTIONS SHALL IMMEDIATELY BE PERFORMED FOLLOWING A LARGE STORM EVENT (I.E. PRODUCING 1/2" (ONE—HALF INCH) OF RAIN OR GREATER. THEREAFTER, THESE FACILITIES SHALL BE INSPECTED AS DESCRIBED AS FOLLOWS. UPON INSPECTION, FACILITIES SHALL BE IMMEDIATELY MAINTAINED AND/OR CLEANED AS MAY BE REQUIRED. ANY SITE AREAS EXHIBITING SOIL EROSION OF ANY KIND SHALL BE IMMEDIATELY RESTORED AND STABILIZED WITH VEGETATION, MULCH OR STONE, DEPENDING ON THE AREA TO BE STABILIZED. UPON EACH INSPECTION, ALL VISIBLE DEBRIS INCLUDING, BUT NOT LIMITED TO, TWIGS, LEAF AND FOREST LITTER SHALL BE REMOVED FROM THE BASIN, OVERFLOW DISCHARGE POINTS AND FRAMES AND GRATES OF DRAINAGE STRUCTURES.
SUMPS — CATCH BASIN/DRAIN INLETS AND DRAIN MANHOLES	UPON COMPLETION OF CONSTRUCTION: -ONCE A MONTH FOR THE FIRST THREE (3) MONTHS AFTER FIRST THREE (3) MONTHS: -EVERY FOUR (4) MONTHS THEREAFTER	ALL CATCH BASIN/DRAIN INLETS AND DRAIN MANHOLES WITH SUMPS HAVE BEEN DESIGNED TO TRAP SEDIMENT PRIOR TO ITS TRANSPORT TO THE INFILTRATION PRACTICE AND, ULTIMATELY, DOWNSTREAM. THESE SUMPS WILL REQUIRE PERIODIC INSPECTION AND MAINTENANCE TO ENSURE THAT ADEQUATE DEPTH IS MAINTAINED WITHIN THE SUMPS. THE OWNER, OR THEIR DULY AUTHORIZED REPRESENTATIVE, SHALL TAKE MEASUREMENTS OF THE SUMP DEPTH. IF SEDIMENT HAS ACCUMULATED TO 1/2 (ONE—HALF) THE DEPTH OF THE SUMP, ALL SEDIMENT SHALL BE REMOVED FROM THE SUMP. SEDIMENTS CAN BE REMOVED WITH HAND—LABOR OR WITH A VACUUM TRUCK. THE USE OF ROAD SALT SHALL BE MINIMIZED FOR MAINTENANCE OF ROADWAY AND DRIVEWAY AREAS.
SUBSURFACE EXFILTRATION CHAMBERS/DRY WELL	UPON COMPLETION OF CONSTRUCTION: -IMMEDIATELY AFTER CONSTRUCTION -EVERY SIX (6) MONTHS THEREAFTER (SPRING & FALL) BY INDIVIDUAL HOMEOWNERS)	ALL EXFILTRATION SYSTEMS SHALL BE INSPECTED EVERY SIX (6) MONTHS (SPRING AND FALL) FOR EXCESS SEDIMENT ACCUMULATION AND CLOGGING OF INLET AND OUTLET PIPING. DURING DRY WEATHER CONDITIONS, WHEN SEDIMENT HAS ACCUMULATED TO AN AVERAGE DEPTH EXCEEDING 3" (THREE INCHES), THE GALLERY SHALL BE WATER JETTED CLEAN, AND ALL ACCUMULATED SEDIMENTS SHALL BE VACUUMED OUT OR REMOVED MANUALLY. A STADIA ROD MAY BE INSERTED TO DETERMINE THE DEPTH OF THE SEDIMENT. MAINTENANCE OF THE INFILTRATION SYSTEMS LOCATED ON EACH INDIVIDUAL LOT SHALL BE THE RESPONSIBILITY OF THE INDIVIDUAL PROPERTY OWNER.
PERMEABLE PAVER AND PAVEMENT	UPON COMPLETION OF CONSTRUCTION: -GENERAL MAINTENANCE PROCEDURES	PERMEABLE PAVEMENT AND PAVER AREA SHOULD BE SWEPT/BLOWN CLEAN AS PART OF GENERAL LAWN/YARD MAINTENANCE SCHEDULE. AREA SHOULD REMAIN FREE OF CONTAMINANTS SUCH AS GRASS/HEDGE CLIPPINGS, MULCH, SOIL, ETC. TO ENSURE MAXIMUM PERMEABILITY. PERMEABLE PAVEMENT AND PAVER AREA SHALL BE TWICE A YEAR (EARLY SPRING & LATE FALL) TO MAINTAIN MAXIMUM INFILTRATION. IF PONDING IS OBSERVED, THE AREA SHALL BE VACUUMED AND JOINT AGGREGATE REPLACED TO THE LIP OF THE PAVER. PAVEMENT WASHING SYSTEMS OR COMPRESSED AIR UNITS ARE NOT RECOMMENDED FOR MAINTENANCE. IMMEDIATELY CLEAN ANY SOIL DEPOSITED ON THE SURFACE.
	-WINTER MAINTENANCE PROCEDURES	ABRASIVES SUCH AS SAND OR CINDERS SHOULD NOT BE APPLIED ON OR ADJACENT TO THE PERVIOUS PAVEMENT AND PAVERS. SNOW PLOWING IS ACCEPTABLE, PROVIDED IT IS DONE BY SETTING THE BLADE SLIGHTLY HIGHER THAN USUAL (APPROXIMATELY 1 INCH). SALT IS ACCEPTABLE FOR USE AS A DEICER ON THE PERVIOUS SURFACE, THOUGH NONTOXIC, ORGANIC DEICERS APPLIED EITHER AS BLENDED MAGNESIUM CHLORIDE BASED LIQUID PRODUCTS, OR AS PRETREATED SALT ARE PREFERABLE.

PROPOSED BUILDING 191 ASHFORD AVENUE VILLAGE OF DOBBS FERRY WESTCHESTER COUNTY - NEW YORK STORMWATER MANAGEMENT PLAN



T: 914-909-0420

HUDSON Designed By: D.Y. Checked By: M.S. ENGINEERING CONSULTING, P.C. Knollwood Road – Suite 201 Elmsford, New York 10523

© 2021

F: 914-560-2086

TO AND AFTER EVERY 1/2" OR GREATER RAINFALL EVENT. ANY ALTERATIONS OR REVISIONS OF THESE PLANS, UNLESS DONE BY OR UNDER THE DIRECTION OF THE NYS LICENSED AND REGISTERED ENGINEER THAT PREPARED THEM, IS A VIOLATION OF THE NYS EDUCATION LAW.

1. ESTABLISH A CONSTRUCTION ENTRANCE TO THE DEVELOPMENT AREA.

4. INSTALL SILT FENCE DOWN SLOPE OF ALL AREAS TO BE DISTURBED AS SHOWN ON THE

STOCKPILES (HYDROSEED DURING MAY 1ST THROUGH QCTOBER 31ST PLANTING SEASON

5. STRIP TOPSOIL AND STOCKPILE AT THE LOCATIONS SPECIFIED ON THE PLANS (UP

OR BY COVERING WITH A TARPAULIN(S) NOVEMBER 151 THROUGH APRIL 301H

6. DEMOLISH ANY EXISTING SITE FEATURES AND/OR STRUCTURES NOTED AS BEING

REMOVED ON THE CONSTRUCTION DOCUMENTS, AND DISPOSE OF OFF-SITE.

RECOMMENDATIONS AND REQUIREMENTS. EXFILTRATION SYSTEMS SHALL BE

TEMPORARILY PLUGGED UNTIL THE COMPLETION OF CONSTRUCTION AND THE SITE IS

12. FINE GRADE AND SEED ALL DISTURBED AREAS. CLEAN DRAIN LINES, CATCH BASINS,

PRETREATMENT DEVICES AND EXFILTRATION SYSTEMS. ENSURE GRASS STAND IS

13. UNPLUG INFILTRATION/EXFILTRATION/ SYSTEMS. CONNECT ALL PROPOSED PIPING TO

14. INSTALL 4"-6" TOPSOIL, FINE GRADE, SEED THE ENTIRE PROJECT SITE AND INSTALL

LANDSCAPING) UTILIZING MODEL AE401H5T AERATOR AS MANUFACTURED BY BILLY

17. REMOVE ALL TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES AFTER THE

*SOIL EROSION AND SEDIMENT CONTROL MAINTENANCE MUST OCCUR WEEKLY AND PRIOR

15. DE-COMPACT AND AERATE ALL DISTURBED AREAS TO BE PLANTED (LAWN &

8. EXCAVATE AND INSTALL EXFILTRATION SYSTEMS PER MANUFACTURER'S

9. INSTALL ALL PRETREATMENT DEVICES, CATCH BASINS AND PIPING.

PREVIOUSLY INSTALLED EXFILTRATION/ATTENUATION GALLERIES.

LANDSCAPE PLANTINGS. SPREAD SALT HAY OVER SEEDED AREAS.

GRADIENT OF EROSION CONTROL MEASURES). TEMPORARILY STABILIZE TOPSOIL

3. SELECTIVE VEGETATION REMOVAL FOR SILT FENCE INSTALLATION.

2. ESTABLISH CONSTRUCTION STAGING AREA.

INSTALL SILT FENCE AROUND TOE OF SLOPE.

10. EXCAVATE AND CONSTRUCT FOUNDATION.

16. PAVE PARKING LOT AS SHOWN ON PLANS

SITE IS STABILIZED WITH VEGETATION.

7. ROUGH GRADE SITE.

11. CONSTRUCT BUILDING

STABILIZED

6.1. START OF CONSTRUCTION.

6.4. INSTALLATION OF SMP'S. 6.5. COMPLETION OF FINAL GRADING AND STABILIZATION OF DISTURBED AREAS.

