

## **Peppermint Test Procedure**

- **Verify that all plumbing traps have water in them**
- **Plug house trap, fresh air and all vent terminals**
- **Close all windows and doors**
- **Add two ounces of Oil of Peppermint followed by 10 quarts of hot water, then cap the point the peppermint was introduced**
- **Person who handled the peppermint must stay outside**
- **The Inspector will then walk through the building, if no odor of peppermint is detected the plumber will then release the house trap plug for the Inspector to verify that peppermint was in the system**