



VILLAGE OF DOBBS FERRY BOARD OF TRUSTEES AGENDA

MEETING DATE: SEPTEMBER 28, 2021

AGENDA ITEM SECTION: DISCUSSION ITEMS

AGENDA ITEM NO. : 5

AGENDA ITEM: CONSIDER A RESOLUTION SETTING A PUBLIC HEARING FOR THE PROJECT AT MASTERS SCHOOL, 49 CLINTON AVENUE AFTER REVIEW OF REFERRAL MEMO FROM THE PLANNING BOARD FOR SITE PLAN APPROVAL

ITEM BACKUP DOCUMENTATION:

1. SITE PLAN SUBMITTAL FORM FOR 49 CLINTON AVENUE
2. LETTER & ATTACHMENTS DATED SEPTEMBER 17, 2021 FROM BRAD SCHWARTZ/ZARIN & STEINMETZ
3. 49 CLINTON AVENUE DESIGN APPENDIX
4. 49 CLINTON AVENUE DRAWINGS
5. STORMWATER POLLUTION PREVENTION PLAN
6. LETTER & ATTACHMENTS DATED SEPTEMBER 21, 2021 FROM VALERIE MONASTRA, AICP TO MAYOR ROSSILLO AND THE BOARD OF TRUSTEES
7. DRAFT RESOLUTION

Plan Submittal Form

Address: 49 Clinton Avenue, Dobbs Ferry, NY 10522

Application #: _____

Project: Masters Innovation and Entrepreneurship Center

Name: Ed Biddle

Email: ed.biddle@mastersny.org

Phone: (914) 479-6431

Plans attached are being submitted for (check appropriate box):


- Building permit application 1 PDF copy & 2 paper copies ¼ scale
- Amendment to an application or permit, 2 sealed copies
- Final As Built to close permit, 1 sealed copy
- Final survey to close permit, 1 sealed copy

Plans attached are submitted at the direction of the Building Inspector for review by the following board (check all that apply):

- BOT- 1 PDF copy + 5 paper copies ¼ scale
- PB - 1 PDF copy + 7 paper copies ¼ scale
- ZBA - 1 PDF copy + 4 paper copies ¼ scale
- AHRB – 1 PDF copy + 2 paper copies ¼ scale

Received Stamp:

September 17, 2021

**Via Electronic and Overnight Mail**

Hon. Vincent Rossillo
Mayor of the Village of Dobbs Ferry
and Members of the Board of Trustees
112 Main Street
Dobbs Ferry, New York 10522

***Re: The Masters School
Site Plan Application for "Innovation and Entrepreneurship Center"
49 Clinton Avenue***

Dear Mayor Rossillo and Members of the Village Board of Trustees:

The Masters School is excited to return to the BOT to complete the Site Plan process for this project. We make this submission to request that the BOT place this matter on its September 28th agenda for the purpose of scheduling a Public Hearing on October 12th (Masters would be glad to appear on September 28th to make a short presentation). Masters also asks that the BOT authorize a draft resolution (with conditions) to be ready for your consideration at the October 12th meeting. Masters would like to complete the foundation work before winter temperatures become prohibitive. An approval on October 12th would allow Masters to proceed to Building Department review and hopefully stay on its planned construction schedule; even a couple additional weeks at this stage would affect the overall schedule. While this may appear aggressive, we think this request is reasonable given all the work accomplished during the Planning Board and AHRB reviews.

Since the project was last before the BOT, the Masters School has completed the following key steps in the process:

- Planning Board – positive recommendation (copy enclosed)
- AHRB – positive recommendation

- SHPO – determination of “no adverse impact” (regarding potential impacts to Estherwood Mansion and Carriage House)
- DEC – determination of “no adverse impact” (regarding potential impacts to fish in the Hudson River)
- Village Fire Department – approval of site emergency access

In addition, the Site Plan drawings and supporting materials have been updated to reflect comments received from the Planning Board, AHRB, and the Village’s engineering and planning consultants. This includes: (i) a SWPPP prepared in accordance with DEC and Village requirements for stormwater management, (ii) more advanced architectural design, including regarding window width, quantity and distribution, (iii) a temporary construction access road to avoid queueing along Clinton Avenue in response to Village and neighbor comments, and (iv) various other technical engineering and planning items.

Importantly, the proposed building footprint and height have not changed. Building height was reviewed in detail with the AHRB to confirm it does not conflict with the historic Estherwood mansion or carriage house.

Masters will submit a complete updated Site Plan drawing set for the BOT’s record and in advance of the Public Hearing when advised to do so by the Village.

Thank you for the BOT’s continued attention to this project.

Respectfully submitted,

ZARIN & STEINMETZ

By: Brad Schwartz

Brad K. Schwartz

Encl.

cc: Ed Manley, Building Official/Land Use Officer
Dan Roemer, Assistant Building Inspector
Lori Lee Dickson, Esq.
Daniel Pozin, Esq.
Valerie Monastra, AICP
Anthony Oliveri, P.E.
The Masters School
Marvel
MFS Engineering & Surveying



VILLAGE OF DOBBS FERRY
112 Main Street
Dobbs Ferry, New York 10522
TEL: (914) 231-8500 • FAX: (914) 693-3470

RESOLUTION X-2021

VILLAGE OF DOBBS FERRY PLANNING BOARD RECOMMENDATION RESOLUTION

**Property: 49 Clinton Avenue (Section Block and Lot 3.90-66-1 and EI,
Educational/Institutional Zoning District)**

Background

WHEREAS, the Masters School ("Applicant") is seeking Site Plan approval to construct a three-story (plus cellar), approximately 22,361 square foot Innovation and Entrepreneurship Center ("IEC") on its campus in front of the Middle School Building ("Project"). The subject property is located at 49 Clinton Avenue, Dobbs Ferry New York, Section Block and Lot 3.90-66-1 ("Project Site"). The Project Site is located in the Educational/Institutional (EI) Zoning District; and

WHEREAS, this application requires Site Plan approval by the Village Board of Trustees and a recommendation by the Planning Board per Section 300-52 of the Zoning and Land Use chapter; and

WHEREAS, The Planning Board has carefully examined the Application and the Applicant's materials as follows:

1. Site Plan Application Form dated April 1, 2021
2. Full Environmental Assessment Form February 16, 2021
3. Coastal Assessment Form dated April 1, 2021
4. Stormwater Pollution Prevention Plan by MFS Consulting Engineers & Surveyor dated August 30, 2021
5. Revised Site Plan Designs prepared by Marvel, last revised August 31, 2021
 - a. G001V Sheet Index
 - b. G-010 and G-011 Survey, prepared BY Kenneth B. Salzman dated January 27, 2021
 - c. Z-100 Zoning Map
 - d. C-101 Civil Notes
 - e. C-300 Demolition and Site Clearing Plan
 - f. C-400 Soil and Erosion Control Plan
 - g. C-500 Site Plan
 - h. C-502 Construction Access Plan
 - i. C-600 Proposed Grading and Drainage Plan
 - j. C-700 Utility Plan
 - k. C-701 Utility Relocation Plan
 - l. C-900 and C-901 Construction Details

- m. L-100 Layout Plan
- n. L-200 Material Plan
- o. L-400 Tree Plan
- p. L-410 Understory Plan
- q. L-600 and L-601 Site Section
- r. L-620 Site Plan
- s. L-700 and L-701 Typical Details
- t. A-100 through A-104 Floor Plans
- u. A-300 and A-301 Building Elevations
- v. A-320 and A-321 Building Sections
- w. S-501 Retailing Wall Detail
- x. S-505 Typical Details
- y. LL-010 Site Lighting Plan
- z. LL-011 Site Lighting Photometric

WHEREAS, the Planning Board has also reviewed and examined letters, reports, and memorandum from the Board's consulting engineer and planner; and

WHEREAS, the Planning Board conducted a duly noticed public hearing on July 1, 2021, at which time all those wishing to be heard were given the opportunity to be heard, and the public hearing remained open until August 5, 2021; and

WHEREAS, the Planning Board deliberated in public on the Applicant's request for recommendation.

Planning Board Determination

NOW, THEREFORE, BE IT RESOLVED, the Planning Board recommends the application for Site Plan approval with the following additional recommendations as set forth below:

1. The Village Board should require the Applicant to address to the full satisfaction of the Village Engineer, all outstanding stormwater, and engineering issues raised in the hearings and documents submitted to the Board, including the September 7, 2021, engineering review letter.

Motion By:

Seconded by:

CHAIRMAN HUNTER	<input type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
STEPHEN BROSNAHAN	<input type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
ROB LANE	<input type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
ALLEN HALE	<input type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
LAURA HAUPT	<input type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
PETER WINDER, 1ST ALTERNATE MEMBER	<input type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
VOTE TOTALS	<input type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
RESULT:	MOTION:				

I hereby attest that the above Resolution was approved by the Planning Board at its September 9, 2021 meeting, and that I have been authorized to sign this Resolution by decision of the Planning Board.

Chairman Hunter

Date



THE MASTERS SCHOOL

INNOVATION AND ENTREPRENEURSHIP CENTER

VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
BOARD OF TRUSTEES SUBMISSION
2021 0920

MARVEL

PROJECT ARCHITECT AND LANDSCAPE ARCHITECT
145 HUDSON STREET THIRD FLOOR
NEW YORK, NY 10013

Zoning Map




EI ZONING

Village of Dobbs Ferry
Town of Greenburgh
Westchester County, New York


- | | |
|-----------------------------------|------------------------------|
| Residential Districts | Commercial Districts |
| OF-1 One Family Residential 1 | CO-1 Commercial Business |
| OF-2 One Family Residential 2 | ET Downtown Transit |
| OF-3 One Family Residential 3 | EO Downtown Gateway |
| OF-4 One Family Residential 4 | |
| OF-5 One Family Residential 5 | Special Districts |
| OF-6 One Family Residential 6 | SP-1 Historical District 1 |
| OF-7 One Family Residential 7 | SP-2 Historical District 2 |
| OF-8 One Family Residential 8 | SP-3 Historical District 3 |
| OF-9 One Family Residential 9 | SP-4 Historical District 4 |
| OF-10 One Family Residential 10 | SP-5 Historical District 5 |
| OF-11 One Family Residential 11 | SP-6 Historical District 6 |
| OF-12 One Family Residential 12 | SP-7 Historical District 7 |
| OF-13 One Family Residential 13 | SP-8 Historical District 8 |
| OF-14 One Family Residential 14 | SP-9 Historical District 9 |
| OF-15 One Family Residential 15 | SP-10 Historical District 10 |
| OF-16 One Family Residential 16 | SP-11 Historical District 11 |
| OF-17 One Family Residential 17 | SP-12 Historical District 12 |
| OF-18 One Family Residential 18 | SP-13 Historical District 13 |
| OF-19 One Family Residential 19 | SP-14 Historical District 14 |
| OF-20 One Family Residential 20 | SP-15 Historical District 15 |
| OF-21 One Family Residential 21 | SP-16 Historical District 16 |
| OF-22 One Family Residential 22 | SP-17 Historical District 17 |
| OF-23 One Family Residential 23 | SP-18 Historical District 18 |
| OF-24 One Family Residential 24 | SP-19 Historical District 19 |
| OF-25 One Family Residential 25 | SP-20 Historical District 20 |
| OF-26 One Family Residential 26 | SP-21 Historical District 21 |
| OF-27 One Family Residential 27 | SP-22 Historical District 22 |
| OF-28 One Family Residential 28 | SP-23 Historical District 23 |
| OF-29 One Family Residential 29 | SP-24 Historical District 24 |
| OF-30 One Family Residential 30 | SP-25 Historical District 25 |
| OF-31 One Family Residential 31 | SP-26 Historical District 26 |
| OF-32 One Family Residential 32 | SP-27 Historical District 27 |
| OF-33 One Family Residential 33 | SP-28 Historical District 28 |
| OF-34 One Family Residential 34 | SP-29 Historical District 29 |
| OF-35 One Family Residential 35 | SP-30 Historical District 30 |
| OF-36 One Family Residential 36 | SP-31 Historical District 31 |
| OF-37 One Family Residential 37 | SP-32 Historical District 32 |
| OF-38 One Family Residential 38 | SP-33 Historical District 33 |
| OF-39 One Family Residential 39 | SP-34 Historical District 34 |
| OF-40 One Family Residential 40 | SP-35 Historical District 35 |
| OF-41 One Family Residential 41 | SP-36 Historical District 36 |
| OF-42 One Family Residential 42 | SP-37 Historical District 37 |
| OF-43 One Family Residential 43 | SP-38 Historical District 38 |
| OF-44 One Family Residential 44 | SP-39 Historical District 39 |
| OF-45 One Family Residential 45 | SP-40 Historical District 40 |
| OF-46 One Family Residential 46 | SP-41 Historical District 41 |
| OF-47 One Family Residential 47 | SP-42 Historical District 42 |
| OF-48 One Family Residential 48 | SP-43 Historical District 43 |
| OF-49 One Family Residential 49 | SP-44 Historical District 44 |
| OF-50 One Family Residential 50 | SP-45 Historical District 45 |
| OF-51 One Family Residential 51 | SP-46 Historical District 46 |
| OF-52 One Family Residential 52 | SP-47 Historical District 47 |
| OF-53 One Family Residential 53 | SP-48 Historical District 48 |
| OF-54 One Family Residential 54 | SP-49 Historical District 49 |
| OF-55 One Family Residential 55 | SP-50 Historical District 50 |
| OF-56 One Family Residential 56 | SP-51 Historical District 51 |
| OF-57 One Family Residential 57 | SP-52 Historical District 52 |
| OF-58 One Family Residential 58 | SP-53 Historical District 53 |
| OF-59 One Family Residential 59 | SP-54 Historical District 54 |
| OF-60 One Family Residential 60 | SP-55 Historical District 55 |
| OF-61 One Family Residential 61 | SP-56 Historical District 56 |
| OF-62 One Family Residential 62 | SP-57 Historical District 57 |
| OF-63 One Family Residential 63 | SP-58 Historical District 58 |
| OF-64 One Family Residential 64 | SP-59 Historical District 59 |
| OF-65 One Family Residential 65 | SP-60 Historical District 60 |
| OF-66 One Family Residential 66 | SP-61 Historical District 61 |
| OF-67 One Family Residential 67 | SP-62 Historical District 62 |
| OF-68 One Family Residential 68 | SP-63 Historical District 63 |
| OF-69 One Family Residential 69 | SP-64 Historical District 64 |
| OF-70 One Family Residential 70 | SP-65 Historical District 65 |
| OF-71 One Family Residential 71 | SP-66 Historical District 66 |
| OF-72 One Family Residential 72 | SP-67 Historical District 67 |
| OF-73 One Family Residential 73 | SP-68 Historical District 68 |
| OF-74 One Family Residential 74 | SP-69 Historical District 69 |
| OF-75 One Family Residential 75 | SP-70 Historical District 70 |
| OF-76 One Family Residential 76 | SP-71 Historical District 71 |
| OF-77 One Family Residential 77 | SP-72 Historical District 72 |
| OF-78 One Family Residential 78 | SP-73 Historical District 73 |
| OF-79 One Family Residential 79 | SP-74 Historical District 74 |
| OF-80 One Family Residential 80 | SP-75 Historical District 75 |
| OF-81 One Family Residential 81 | SP-76 Historical District 76 |
| OF-82 One Family Residential 82 | SP-77 Historical District 77 |
| OF-83 One Family Residential 83 | SP-78 Historical District 78 |
| OF-84 One Family Residential 84 | SP-79 Historical District 79 |
| OF-85 One Family Residential 85 | SP-80 Historical District 80 |
| OF-86 One Family Residential 86 | SP-81 Historical District 81 |
| OF-87 One Family Residential 87 | SP-82 Historical District 82 |
| OF-88 One Family Residential 88 | SP-83 Historical District 83 |
| OF-89 One Family Residential 89 | SP-84 Historical District 84 |
| OF-90 One Family Residential 90 | SP-85 Historical District 85 |
| OF-91 One Family Residential 91 | SP-86 Historical District 86 |
| OF-92 One Family Residential 92 | SP-87 Historical District 87 |
| OF-93 One Family Residential 93 | SP-88 Historical District 88 |
| OF-94 One Family Residential 94 | SP-89 Historical District 89 |
| OF-95 One Family Residential 95 | SP-90 Historical District 90 |
| OF-96 One Family Residential 96 | SP-91 Historical District 91 |
| OF-97 One Family Residential 97 | SP-92 Historical District 92 |
| OF-98 One Family Residential 98 | SP-93 Historical District 93 |
| OF-99 One Family Residential 99 | SP-94 Historical District 94 |
| OF-100 One Family Residential 100 | SP-95 Historical District 95 |





Source: Village of Dobbs Ferry GIS Data
Map Date: December 2010
August 10, 2010




CAMPUS AERIAL PHOTOGRAPH




ZONING MAP
THE MASTERS SCHOOL
INNOVATION AND ENTREPRENEURSHIP CENTER
VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
BOARD OF TRUSTEES SUBMISSION
2021.09.20



CAMPUS PLAN AND SITE SECTION
 THE MASTERS SCHOOL
 INNOVATION AND ENTREPRENEURSHIP CENTER
 VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
 BOARD OF TRUSTEES SUBMISSION
 2021 0920



KEY PLAN
NTS





- BIORETENTION GARDEN
- STONE STAIRWAY TO LOWER TERRACE
- LOADING AREA
- NATIVE VEGETATION / STORMWATER SWALE
- LOWER ENTRANCE
- UPPER TERRACE
- BIOSWALE / NATIVE GARDEN
- ADA GRAVEL PATH
- SAFE PEDESTRIAN CROSSING
- ASPHALT PATH AT GRADE
- PROTECT EXISTING TREES

LANDSCAPE PLAN

THE MASTERS SCHOOL
 INNOVATION AND ENTREPRENEURSHIP CENTER
 VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
 BOARD OF TRUSTEES SUBMISSION
 2021 0920

WEST ELEVATION



BIORETENTION GARDEN
STAIR TO LOWER TERRACE

ARCHITECTURAL CAST IN
PLACE CONCRETE WITH
BOARD FORMED FINISH

HARKNESS GARDEN
NATIVE VEGETATION /
STORMWATER SWALE

BLACK ANODIZED
ALUMINUM INSULATED
CURTAIN WALL SYSTEM
NATURAL FINISH ZINC
STANDING SEAM
FAÇADE CLADDING

UPPER TERRACE

ANODIZED ALUMINUM
CLADDING OVER TOP OF STEEL
FRAME STRUCTURE WITH
WOOD PLANK MATERIAL AT
UNDERSIDE

PROTECT MATURE TREES
ADA PATH TOWARDS MIDDLE
SCHOOL / LOWER TERRACE

EAST ELEVATION



PARKING

UPPER TERRACE

NATIVE VEGETATION /
STORMWATER SWALE
BLACK ANODIZED ALUMINUM
INSULATED PUNCHED
WINDOW SYSTEM

NATURAL FINISH ZINC STANDING
SEAM FAÇADE CLADDING

LOWER TERRACE

ARCHITECTURAL CAST IN
PLACE CONCRETE WITH BOARD
FORMED FINISH

ANODIZED ALUMINUM
ARCHITECTURAL EXHAUST
LOUVER TO MATCH
CURTAIN WALL SYSTEM

ANODIZED ALUMINUM CLADDING
OVER TOP OF STEEL FRAME
STRUCTURE WITH WOOD PLANK
MATERIAL AT UNDERSIDE


BUILDING AND
LANDSCAPE ELEVATIONS

THE MASTERS SCHOOL
INNOVATION AND ENTREPRENEURSHIP CENTER
VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
BOARD OF TRUSTEES SUBMISSION
2021 0920

MARVEL

240 HUGSON SQUARE, THIRD FLOOR
NEW YORK, NY 10013

SOUTH ELEVATION



UPPER ENTRY

BLACK ANODIZED ALUMINUM INSULATED CURTAIN WALL SYSTEM

ARCHITECTURAL CAST IN PLACE CONCRETE WITH BOARD FORMED FINISH

NATURAL FINISH ZINC STANDING SEAM FACADE CLADDING

NORTH ELEVATION



NATIVE VEGETATION / STORMWATER SWALE

LOWER ENTRY

BLACK ANODIZED ALUMINUM INSULATED CURTAIN WALL SYSTEM

ARCHITECTURAL CAST IN PLACE CONCRETE WITH BOARD FORMED FINISH

NATURAL FINISH ZINC STANDING SEAM FACADE CLADDING

BUILDING AND LANDSCAPE ELEVATIONS

THE MASTERS SCHOOL
INNOVATION AND ENTREPRENEURSHIP CENTER
VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
BOARD OF TRUSTEES SUBMISSION
2021 0920



V1 - LOOKING EAST FROM CLINTON AVE AT PARK COTTAGE




V2 - LOOKING EAST FROM CLINTON AVE AT SOCCER FIELD



V3 - LOOKING EAST FROM CLINTON AVE AT COCHRANE



CAMPUS AERIAL PHOTOGRAPH



V4 - LOOKING WEST FROM ESTHERWOOD AVE



V5 - LOOKING WEST FROM ESTHERWOOD AVE



V6 - LOOKING WEST FROM ESTHERWOOD AVE

MARVEL
120 HULSTON STREET, NEW YORK, NY 10013

NEIGHBORHOOD CONTEXT
 THE MASTERS SCHOOL
 INNOVATION AND ENTREPRENEURSHIP CENTER
 VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
 BOARD OF TRUSTEES SUBMISSION
 2021 0920



v1 - LOOKING NORTH TOWARD ESTHERWOOD MANSION



v2 - LOOKING SOUTH FROM ESTHERWOOD MANSION



v3 - LOOKING EAST TOWARD CARRIAGE HOUSE



v4 - LOOKING EAST TOWARD MIDDLE



CAMPUS AERIAL PHOTOGRAPH



V5 - LOOKING SOUTH TOWARD CAMPUS



V6 - LOOKING WEST TOWARD SOFTBALL AND CLINTON AVE



V7 - LOOKING WEST ON PRIVATE DRIVEWAY



V8 - LOOKING NORTH TOWARD SITE

BUILDING SITE CONTEXT
 THE MASTERS SCHOOL
 INNOVATION AND ENTREPRENEURSHIP CENTER
 VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
 BOARD OF TRUSTEES SUBMISSION
 2021 0920

MARVEL

145 HULLSEN STREET, 11TH FLOOR
 NEW YORK, NY 10013



SITE CONTEXT RENDERINGS
THE MASTERS SCHOOL
INNOVATION AND ENTREPRENEURSHIP CENTER
VILLAGE OF DOBBS FERRY SITE PLAN APPLICATION
BOARD OF TRUSTEES SUBMISSION
2021.0920

MARVEL
240 WALL ST. 11TH FLOOR
NEW YORK, NY 10038

- OWNER:** **THE MASTERS SCHOOL**
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
- PROJECT ARCHITECTS + LANDSCAPE ARCHITECTS:** **MARVEL ARCHITECTS**
145 HUDSON STREET, FLOOR 3
NEW YORK, NEW YORK 10013
- GEOTECHNICAL/CIVIL ENGINEER:** **MFS ENGINEERS & SURVEYORS, DPC**
2780 HAMILTON BOULEVARD
SOUTH PLANINFIELD, NEW JERSEY 07080
- STRUCTURAL ENGINEER:** **SILMAN**
32 OLD SLIP, FLOOR 10
NEW YORK, NEW YORK 10005
- BUILDING SYSTEMS ENGINEER:** **POLISE CONSULTING ENGINEERS, DPC**
133 WEST 19TH STREET
NEW YORK, NEW YORK 10011
- VERTICAL TRANSPORTATION:** **VDA**
145 WEST 30TH STREET, FLOOR 4
NEW YORK, NEW YORK 10011
- AV/IT/SECURITY CONSULTANT:** **COSENTINI ASSOCIATES, INC**
498 SEVENTH AVENUE
NEW YORK, NEW YORK 10018
- ACOUSTICS CONSULTANT:** **LSTN CONSULTANTS**
76 BEAVER STREET
NEW YORK, NEW YORK 10005
- AV/IT/SECURITY CONSULTANT:** **COSENTINI ASSOCIATES, INC**
498 SEVENTH AVENUE
NEW YORK, NEW YORK 10018
- ENVELOPE CONSULTANT:** **MW-SKINS**
1 WHITEHALL STREET, FLOOR 14
NEW YORK, NEW YORK 10004
- LIGHTING DESIGNER:** **DOT DASH LIGHTING DESIGN**
160 BROADWAY, SUITE 1215
NEW YORK, NEW YORK 10038
- CODE AND ACCESSIBILITY CONSULTANT:** **CODE CONSULTANTS, INC**
440 PARK AVENUE S.
NEW YORK, NEW YORK 10016
- ARCHITECTURAL SPECIFICATIONS:** **CONSTRUCTION SPECIFICATIONS, INC**
22 TENNENT ROAD
MORGANVILLE, NEW JERSEY 07751



THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER

49 CLINTON AVENUE, DOBBS FERRY, NEW YORK 10522
PROJECT NO. 2029

SITE APPLICATION SUBMISSION - BOT SEPTEMBER 20, 2021




MARVEL
145 HUDSON STREET, FLOOR 3 NEW YORK, NY 10013
212.618.8628

- OWNER:**
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914.474.6886
PROJECT: ARCHITECTS + LANDSCAPE ARCHITECTS
- ARCHITECT:**
MARVEL
145 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 212.618.8628
- CLIENTS/PRINCIPALS/ENGINEER:**
MFS ENGINEERS & SURVEYORS, DPC
2780 HAMILTON BOULEVARD
SOUTH PLANINFIELD, NEW JERSEY 07080
TEL: 908.922.4622
- STRUCTURAL ENGINEER:**
SILMAN
32 OLD SLIP, FLOOR 10
NEW YORK, NY 10005
TEL: 212.687.8700
- BUILDING SYSTEMS ENGINEER:**
POLISE CONSULTING ENGINEERS, DPC
133 WEST 19TH STREET
NEW YORK, NY 10011
TEL: 212.646.1022
- VEHICULAR TRANSPORTATION:**
VDA
145 WEST 30TH STREET, FLOOR 4
NEW YORK, NY 10011
TEL: 212.687.8700
- AV/IT/SECURITY CONSULTANT:**
COSENTINI ASSOCIATES, INC
498 SEVENTH AVENUE
NEW YORK, NY 10018
TEL: 212.687.8700
- ACOUSTICS CONSULTANT:**
LSTN CONSULTANTS
76 BEAVER STREET
NEW YORK, NY 10005
TEL: 212.687.8700
- ENVELOPE CONSULTANT:**
MW-SKINS
1 WHITEHALL STREET, FLOOR 14
NEW YORK, NY 10004
TEL: 212.687.8700
- LIGHTING DESIGNER:**
DOT DASH LIGHTING DESIGN
160 BROADWAY, SUITE 1215
NEW YORK, NY 10038
TEL: 212.687.8700
- CODE AND ACCESSIBILITY CONSULTANT:**
CODE CONSULTANTS, INC
440 PARK AVENUE S.
NEW YORK, NY 10016
TEL: 212.687.8700
- MOTION PICTURES/SPECIAL EFFECTS:**
CONSTRUCTION SPECIFICATIONS, INC
22 TENNENT ROAD
MORGANVILLE, NEW JERSEY 07751
TEL: 908.922.4622

REV.	DATE	DESCRIPTION
1	09/20/2021	ISSUANCE OF EXHIBIT FERRY
2	09/20/2021	SITE APPLICATION
3	09/20/2021	SITE APPLICATION
4	09/20/2021	SITE APPLICATION
5	09/20/2021	SITE APPLICATION

09/20/2021



KEY PLANNING

2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

TITLE SHEET

SCALE: 12" = 1'-0"



DRAWING #
T-000
of
DOB JOB: -
DOB STAMP ZONE



MARVEL
140 HUDSON STREET, PL. 3 NEW YORK, NY 10013
CLINTON

OWNER:
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10022
TEL: 914 978-9880

PROJECT: ARCH/SC/SE - LANDSCAPE ARCH/SECT'S

DESIGNER:
RUSSELL W. HULL, FLSHCIP
NEW YORK, NEW YORK 10022
TEL: 212 625-1797

CONSULTANT:
ARCH/SC/SE - LANDSCAPE ARCH/SECT'S
RUSSELL W. HULL, FLSHCIP
NEW YORK, NEW YORK 10022
TEL: 212 625-1797

CONSULTANT:
STRUCTURAL ENGINEERING
7370 MANHATTAN AVENUE
DOVER PLACE, L210 NEW YORK, NY 10021
TEL: 212 463-9332

CONSULTANT:
MECHANICAL ENGINEERING
150 WEST 41 ST 14 FL 11
NEW YORK, NEW YORK 10018
TEL: 212 625-1797

CONSULTANT:
ELECTRICAL ENGINEERING
125 WEST 41 ST 14 FL 11
NEW YORK, NEW YORK 10018
TEL: 212 625-1797

CONSULTANT:
CONSTRUCTION SPECIFICATIONS
23 LEXINGTON ROAD
MORGANTOWN, NY 10022
TEL: 518 525-5750

SHEET INDEX - SITE PLAN APPLICATION - BOT

CATEGORY	SHEET #	SHEET NAME	SITE PLAN APP. 08/17/2021	SITE APP. REVISIONS 08/17/2021	SITE APP. REVISIONS 07/23/21	SITE APP. - BOT 08/22/21
GENERAL	G-000	TITLE SHEET	X	X	X	X
13 COLONIAL	G-011	TRAIL, MECH. RT.	X	X	X	X
G-012	MAINTENANCE SCHEDULE	X	X	X	X	
G-013	MAINTENANCE SCHEDULE	X	X	X	X	
G-014	MAINTENANCE SCHEDULE	X	X	X	X	
G-015	MAINTENANCE SCHEDULE	X	X	X	X	
13 EXISTING	E-000	EXISTING MAP FOR MAP PLN & FLOOR MAP	X	X	X	X
13 CIVIL	C-001	NOTES	X	X	X	X
C-002	GENERAL NOTES	X	X	X	X	
C-003	GENERAL NOTES & S.D. CLEARING PLAN	X	X	X	X	
C-004	GENERAL NOTES & S.D. CLEARING PLAN	X	X	X	X	
C-005	GENERAL NOTES	X	X	X	X	
C-006	CONCRETE FOUNDATION ACCESS PLAN	X	X	X	X	
C-007	CONCRETE FOUNDATION ACCESS PLAN	X	X	X	X	
C-008	PROPOSED LANDING & DRIVeway PLAN	X	X	X	X	
C-009	UTILITY PLAN	X	X	X	X	
C-010	UTILITY FOUNDATION PLAN	X	X	X	X	
C-011	UTILITY FOUNDATION PLAN	X	X	X	X	
C-012	CONCRETE FOUNDATION	X	X	X	X	
C-013	CONCRETE FOUNDATION	X	X	X	X	
13 LANDSCAPE	L-001	GENERAL NOTES	X	X	X	X
L-002	LANDSCAPE PLAN	X	X	X	X	
L-003	LANDSCAPE PLAN	X	X	X	X	
L-004	TRAIL PLAN	X	X	X	X	
L-005	TRAIL PLAN	X	X	X	X	
L-006	TRAIL PLAN	X	X	X	X	
L-007	TRAIL PLAN	X	X	X	X	
L-008	TRAIL PLAN	X	X	X	X	
L-009	TRAIL PLAN	X	X	X	X	
L-010	TRAIL PLAN	X	X	X	X	
L-011	TRAIL PLAN	X	X	X	X	
L-012	TRAIL PLAN	X	X	X	X	
L-013	TRAIL PLAN	X	X	X	X	
L-014	TRAIL PLAN	X	X	X	X	
L-015	TRAIL PLAN	X	X	X	X	
L-016	TRAIL PLAN	X	X	X	X	
L-017	TRAIL PLAN	X	X	X	X	
L-018	TRAIL PLAN	X	X	X	X	
L-019	TRAIL PLAN	X	X	X	X	
L-020	TRAIL PLAN	X	X	X	X	
L-021	TRAIL PLAN	X	X	X	X	
13 LIFTING	L-022	UTILITY PLAN	X	X	X	X
L-023	UTILITY PLAN	X	X	X	X	

REV.	DATE	DESCRIPTION
1	07/17/2021	VILLAGE OF DOBBS FERRY SITE PLAN
2	08/17/2021	S.D. MAP CA-ON REVISION
3	07/22/2021	S.D. MAP CA-ON REVISION
4	08/19/2021	S.D. MAP CA-ON REVISION
5	08/25/2021	S.D. MAP CA-ON REVISION

09/20/2021



KEY PLAN NTS
2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10022


SHEET INDEX - BOT

SCALE:



DRAWING # **G-001Y**
of
DOB JOB # _____


DOB STAMP ZONE



NOT FOR CONSTRUCTION

Note
Refer to Sheet 2 of 2 for Notes and Legend

COPYRIGHT © 2021 by Kenneth B. Szarmann
All rights reserved. Unauthorized reproduction is a violation of applicable laws.



Sheet 1 of 2

Building Site Survey
for the proposed
Innovation and Entrepreneurship Center
to be constructed at
The Masters School
located at
49 Clinton Avenue
Village of Dobbs Ferry
Westchester County, New York
Scale 1" = 20' January 22, 2021

Kenneth B. Szarmann, Land Surveyor, NY Lic. No. 49712
19 Malabar Lane, PO Box 498, Poughkeepsie, NY 12564 (845) 893-3055




MARVEL
145 HUDSON STREET, FLOOR 3, NEW YORK, NY 10013
CLARENCE

- OWNER**
THE MASTERS SCHOOL
45 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914 673-8600
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS**
MARVEL
145 HUDSON STREET - FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 914 673-8600
- CLIENT / ARCHITECT / CIVIL ENGINEER**
MFE ENGINEERS & ARCHITECTS, P.C.
2700 WHEATON ROAD, SUITE 100
SCOTTS VALLEY, NEW YORK 10589
TEL: 914 673-8600
- STRUCTURAL ENGINEER**
SEAN
32 CALISTO FLOOR 10
NEW YORK, NEW YORK 10005
TEL: 212 682-7870
- BUILDING PHYSICAL ENGINEER**
POLSKIE CONSULTING ENGINEERS, P.C.
133 WEST 101ST STREET
NEW YORK, NEW YORK 10021
TEL: 212 462-1000
- MERCHANDISE CONSULTATION**
USA
100 WEST 101ST STREET - FLOOR 4
NEW YORK, NEW YORK 10021
TEL: 212 682-7870
- ALL / IT / SECURITY CONSULTANT**
CORNERSTONE SECURITY, INC.
400 BLENHEIM AVENUE
NEW YORK, NEW YORK 10018
TEL: 212 675-3600
- MECHANICAL CONSULTANT**
LSTR CONSULTANTS
70 BROAD STREET
NEW YORK, NEW YORK 10002
TEL: 212 510-0000
- ELECTRICAL CONSULTANT**
ENLAWERS CONSULTANTS
100 WEST 101ST STREET - FLOOR 14
NEW YORK, NEW YORK 10018
TEL: 212 682-7870
- LEAD PIPING DESIGNER**
ROCKLAND ENGINEERING DESIGN
100 BROADWAY, SUITE 100
NEW YORK, NEW YORK 10002
TEL: 212 367-0000
- GENERAL ACCESSIBILITY CONSULTANT**
CODE CONSULTANTS, INC.
NEW YORK, NEW YORK 10018
TEL: 212 447-8233
- MECHANICAL SPECIALIST**
CORNERSTONE SPECIFICATIONS, INC.
22 TOWNHAT ROAD
ROCKY HILL, NEW HAMPSHIRE 07870
TEL: 781 870-0700

REV	DATE	DESCRIPTION
1	02/11/2021	SUBMITTAL OF DOBMS PERMITS
2	06/17/2021	SELF APPLICATION SUBMISSION
3	07/22/2021	SELF APPLICATION SUBMISSION
4	08/19/2021	SELF APPLICATION SUBMISSION
5	09/20/2021	SELF APPLICATION SUBMISSION REV

09/20/2021




KEY PLAN: NTS

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
45 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

**EMERGENCY ACCESS
SITE PLAN**

SCALE: As indicated



1 EMERGENCY ACCESS SITE PLAN



DRAWING #
G-031
of
DOB JOB -

DATE: 09/20/2021



MARVEL
100 HUDSON STREET, FLR 2, NEW YORK, NY 10013
212.619.6689

- OWNER:**
THE MASTERS SCHOOL
45 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914 473-8400
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS:**
MARVEL
100 HUDSON STREET, FLOOR 2
NEW YORK, NEW YORK 10013
TEL: 212 619 6689
- CLIENTS/PRINCIPAL CONSULTANTS:**
MVP ENGINEERS & SURVEYORS, INC.
2780 HANCOCK PARKWAY
SCOTTS VALLEY, CA, NEWARKLY 97003
TEL: 503 862 4922
- STRUCTURAL ENGINEER:**
BAM BAM
100 CLINTON AVENUE, FLOOR 10
NEW YORK, NEW YORK 10522
TEL: 212 662 7970
- Mechanical, Electrical, Plumbing, Fire, Life Safety, and Energy Engineering:**
POMER CONSULTING ENGINEERS, INC.
130 HILLSIDE ROAD, SUITE 100
NEW YORK, NEW YORK 10011
TEL: 212 645 1037
- VERTICAL TRANSPORTATION:**
VISA
100 HILLSIDE ROAD, SUITE 100, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212 668 8000
- AV / IT / SECURITY CONSULTANT:**
COMBENT ASSOCIATES, INC.
400 WALL STREET, SUITE 1000
NEW YORK, NEW YORK 10019
TEL: 212 619 3800
- ACoustics CONSULTANT:**
L&R CONSULTANTS
100 HILLSIDE ROAD, SUITE 1000
NEW YORK, NEW YORK 10011
TEL: 212 668 8000
- ENVIRONMENTAL CONSULTANT:**
MVP ENGINEERS & SURVEYORS, INC.
2780 HANCOCK PARKWAY
SCOTTS VALLEY, CA, NEWARKLY 97003
TEL: 503 862 4922
- LEADING DESIGNER:**
MVP ENGINEERS & SURVEYORS, INC.
2780 HANCOCK PARKWAY
SCOTTS VALLEY, CA, NEWARKLY 97003
TEL: 503 862 4922
- LOCAL AND ACCESSIBILITY CONSULTANT:**
CORR CONSULTANTS, INC.
400 WALL STREET, SUITE 1000
NEW YORK, NEW YORK 10019
TEL: 212 668 8000
- ARCHITECTURAL SPECIFICATIONS:**
CONSTRUCTION SPECIFICATIONS, INC.
22 CLAMANT ROAD
MIDDLETOWN, NEW JERSEY 07758
TEL: 732 475 0700

ZONING
PER TABLE B-10: CP AND E1 DISTRICTS DIMENSIONAL STANDARDS

REQUIREMENT (PER TABLE B-10)	EDUCATIONAL/INSTITUTIONAL DISTRICT REQUIREMENTS	PROVIDED BY MASTERS IEC	NOTES
LOT SIZE	MINIMUM LOT SIZE	-	-
BUILDING HEIGHT	MAXIMUM LOT AREA PER DWELLING UNIT (SF)	40,000	N/A DUE TO CAMPUS
	MAX STORES	4	3
	MAX HEIGHT (FT)	52'-0"	43'-1"
	MIN STORES	-	-
LOT COVERAGE	MAX LOT COVERAGE BY BUILDINGS	50%	4.9%
	MAX LOT COVERAGE BY IMPERVIOUS COVER	80%	10.16%
LOT COVERAGE	MIN FRONT YARD SETBACK (FEET)	25	N/A DUE TO CAMPUS
	MAX FRONT YARD SETBACK (FEET)	-	N/A DUE TO CAMPUS
	MIN REAR YARD SETBACK (FEET)	25	N/A DUE TO CAMPUS
	MIN SIDE YARD SETBACK (EACH) (FEET)	10	N/A DUE TO CAMPUS
	MIN SIDE YARD SETBACK (BOTH) (FEET)	25	N/A DUE TO CAMPUS
	MAX SIDE YARD SETBACK (EACH) (FEET)	-	N/A DUE TO CAMPUS

GROSS BUILDING AREA

PROPOSED GBA	
BASEMENT	5,897 GSF
FIRST FLOOR	5,479 GSF
SECOND FLOOR	5,575 GSF (BAM BAM)
THIRD FLOOR	5,575 GSF (BAM BAM)
MECHANICAL PLANT GBA	293 GSF
TOTAL	27,380 GSF

10/15/2020


Zoning Map




Village of Dobbs Ferry

- CP-1
- CP-2
- CP-3
- CP-4
- CP-5
- CP-6
- CP-7
- CP-8
- CP-9
- CP-10
- CP-11
- CP-12
- CP-13
- CP-14
- CP-15
- CP-16
- CP-17
- CP-18
- CP-19
- CP-20
- CP-21
- CP-22
- CP-23
- CP-24
- CP-25
- CP-26
- CP-27
- CP-28
- CP-29
- CP-30
- CP-31
- CP-32
- CP-33
- CP-34
- CP-35
- CP-36
- CP-37
- CP-38
- CP-39
- CP-40
- CP-41
- CP-42
- CP-43
- CP-44
- CP-45
- CP-46
- CP-47
- CP-48
- CP-49
- CP-50
- CP-51
- CP-52
- CP-53
- CP-54
- CP-55
- CP-56
- CP-57
- CP-58
- CP-59
- CP-60
- CP-61
- CP-62
- CP-63
- CP-64
- CP-65
- CP-66
- CP-67
- CP-68
- CP-69
- CP-70
- CP-71
- CP-72
- CP-73
- CP-74
- CP-75
- CP-76
- CP-77
- CP-78
- CP-79
- CP-80
- CP-81
- CP-82
- CP-83
- CP-84
- CP-85
- CP-86
- CP-87
- CP-88
- CP-89
- CP-90
- CP-91
- CP-92
- CP-93
- CP-94
- CP-95
- CP-96
- CP-97
- CP-98
- CP-99
- CP-100

10/15/2020




2 SOUTH ELEVATION - ZONING
1/8" = 1'-0"



1 EAST ELEVATION
1/8" = 1'-0"

REV.	DATE	DESCRIPTION
1	09/20/2021	SUBMITTAL OF DOBBS FERRY
2	09/20/2021	SOIL APPLICATION
3	09/20/2021	SOIL APPLICATION
4	09/20/2021	SOIL APPLICATION
5	09/20/2021	SOIL APPLICATION

09/20/2021



KEY PLAN NTS
2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
45 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

ZONING MAP, TAX MAP, PLOT PLAN & FLOOD MAP


SCALE: As indicated



DRAWING #
Z-100
of
DOB JOB -


DOB STAMP ZONE

LEGEND	
DEMOLISH & REMOVE	-----
EXISTING VEGETATION TO BE REMOVED	▨
EXISTING ASPHALT TO BE REMOVED	▩
EXISTING CONCRETE TO BE REMOVED	▧
EXISTING TREES TO BE REMOVED	X



MARVEL
 140 WASHINGTON STREET, FLOOR 3 NEW YORK, NY 10013
 212.645.8400

- OWNER**
 THE MASTERS SCHOOL
 49 CLINTON AVENUE
 DOBBS FERRY, NEW YORK 10522
 TEL: 914.878.8833
- PROJECT ARCHITECTS / LANDSCAPE ARCHITECTS**
MARVEL
 140 WASHINGTON STREET, FLOOR 3
 NEW YORK, NEW YORK 10013
 TEL: 212.645.8400
- GEOTECHNICAL / CIVIL ENGINEER**
MPS ENGINEERS & SURVEYORS, P.C.
 200 J.P. KELLY AVENUE, SUITE 200
 DOBBS FERRY, NEW YORK 10522
 TEL: 914.878.8833
- STRUCTURAL ENGINEER**
BLISS
 32 OLD SLIP FLOOR 10
 NEW YORK, NEW YORK 10003
 TEL: 212.697.9700
- BUILDING SYSTEMS ENGINEER**
PK&E CONSULTING ENGINEERS, P.C.
 100 WEST 85TH STREET
 NEW YORK, NEW YORK 10024
 TEL: 212.686.1800
- VERTICAL TRANSPORTATION**
MOA
 140 WEST 80TH STREET, SUITE 400
 NEW YORK, NEW YORK 10024
 TEL: 212.698.8900
- ASSET SECURITY CONSULTANT**
CONSENTIAL ASSOCIATES, INC.
 400 BROADWAY
 NEW YORK, NEW YORK 10018
 TEL: 212.610.3800
- ACCESSIBILITY CONSULTANT**
LEVIN CONSULTANTS
 18 BLANCK HILL
 NEW YORK, NEW YORK 10003
 TEL: 347.789.3810
- LANDSCAPE CONSULTANT**
W&S&S
 100 WASHINGTON STREET, FLOOR 14
 NEW YORK, NEW YORK 10003
 TEL: 212.697.9700
- 100% DESIGN**
DOY DESIGN GROUP, INC.
 100 W. 49th STREET, SUITE 800
 NEW YORK, NEW YORK 10020
 TEL: 212.697.9700
- DEVELOPER**
PK&E CONSULTANTS, INC.
 400 BROADWAY
 NEW YORK, NEW YORK 10018
 TEL: 212.610.3800
- ARCHITECTURAL SPECIFICATIONS**
CONSTRUCTION SPECIFICATIONS, INC.
 22 ELMWOOD PLACE
 MIDDLETOWN, NEW YORK 10941
 TEL: 845.376.3700
- GEOTECHNICAL ENGINEER**



REV	DATE	DESCRIPTION
1	07/17/2021	ISSUED FOR DOBBS FERRY SITE APPLICATION
2	08/11/2021	ISSUED FOR DOBBS FERRY SUBMISSION
3	07/22/2021	ISSUED FOR DOBBS FERRY SUBMISSION
4	08/16/2021	ISSUED FOR DOBBS FERRY SUBMISSION
5	08/25/2021	ISSUED FOR DOBBS FERRY SUBMISSION

09/20/2021



KEY PLAN TITS
 2029
**THE MASTERS SCHOOL
 INNOVATION AND
 ENTREPRENEURSHIP
 CENTER**
 49 CLINTON AVENUE
 DOBBS FERRY, NEW YORK 10522

**DEMOLITION & SITE
 CLEARING PLAN**

SCALE: AS NOTED



DRAWING #
C-301
 3 of 10
 DOB JOB -

1 DEMOLITION & SITE CLEARING PLAN
 Scale: 1"=10'



**-PRELIMINARY-
 NOT FOR CONSTRUCTION**






DOB STAMP ZONE



MARVEL

49 CLINTON AVENUE, 3RD FLOOR
DOBBS FERRY, NY 10522

- OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10522
TEL: 914 781 5433
- ARCHITECT
MARVEL ARCHITECTS + LANDSCAPE ARCHITECTS
167 FALGOUT STREET, 2ND FLOOR
NEW YORK, NY 10013
TEL: 212 868 5533
- GEOTECHNICAL CIVIL ENGINEER
MPS ENGINEERS & SURVEYORS, P.C.
200 PARK AVENUE, 15TH FLOOR
NEW YORK, NY 10022
TEL: 212 692 4422
- STRUCTURAL ENGINEER
BLUMAN
32 OLD SLIP FLOOR 10
NEW YORK, NY 10013
TEL: 212 352 7810
- BUILDING SYSTEMS ENGINEER
PWA-NE CONSULTING ENGINEERS, P.C.
150 WEST 89TH STREET
NEW YORK, NY 10024
TEL: 212 684 1000
- VERTICAL TRANSPORTATION
NSA
165 WEST 36TH STREET, SUITE 4
NEW YORK, NY 10018
TEL: 212 692 0522
- AS-BUILT SECURITY CONSULTANT
CONSENTAL ASSOCIATES, INC.
405 BUCKLEY PLACE
NEW YORK, NY 10019
TEL: 212 613 9900
- ACCIDENT CONSULTANT
LERN CONSULTANTS
78 ELMER STREET
NEW YORK, NY 10003
TEL: 347 728 3110
- LANDSCAPE CONSULTANT
MMAHAKS
100 WEST 25TH STREET, 11TH FLOOR
NEW YORK, NY 10001
TEL: 212 352 8910
- LIGHTING CONSULTANT
BOB SAKS ENGINEERING DESIGN
100 N. 4TH STREET, SUITE 402
NEW YORK, NY 10003
TEL: 212 613 8880
- CEE AND ACCESSIBILITY CONSULTANT
CORE CONSULTANTS, INC.
400 PARK AVENUE, 11TH FLOOR
NEW YORK, NY 10022
TEL: 212 647 9100
- MULTI-DISCIPLINARY SPECIFICATIONS
CONSULTING ENGINEERS, P.C.
22 ELWELL AVENUE
MORRISTOWN, NJ 07960
TEL: 908 529 5500
- GEOTECHNICAL ENGINEER



1 SITE PLAN
SCALE: 1" = 10'

REV	DATE	DESCRIPTION
1	02/1/2021	ALLIANCE OF DOBBS
2	06/11/2021	DOBT SITE APPLICATION SITE APPLICATION
3	02/22/2021	SITE APPLICATION SITE APPLICATION
4	08/13/2021	SITE APPLICATION SITE APPLICATION
5	09/20/2021	SITE APPLICATION SITE APPLICATION SUBMISSION: R01

09/20/2021

KEY PLAN NTS
2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

OVERALL SITE PLAN



SCALE: AS NOTED



DRAWING #
C-500
4 of 10
DOB JOB #

-PRELIMINARY-
NOT FOR CONSTRUCTION

DOB STAMP ZONE




- NOTES:**
- SEE CONSTRUCTION PLAN SHEETS FOR DRIVEWAY FINISH AND UTILITY LOCATIONS.
 - PROVIDE SLOPE TO SMOOTH ROLLER DRUM TO BE COMPLETED TO FINAL SECTION TOGETHER.
 - CONTRACTOR TO EXCAVATE 2" OF TOPSOIL AND PLACE IN THE SURROUNDING FROM TO CONTRACTOR OF THE TEMPORARY ACCESS ROADWAY.

DATE: 09/20/2021

NO.	REV.	DESCRIPTION
1		ISSUED FOR PERMIT
2		ISSUED FOR PERMIT
3		ISSUED FOR PERMIT
4		ISSUED FOR PERMIT
5		ISSUED FOR PERMIT
6		ISSUED FOR PERMIT
7		ISSUED FOR PERMIT
8		ISSUED FOR PERMIT
9		ISSUED FOR PERMIT
10		ISSUED FOR PERMIT

(A-A) DRIVEWAY SECTION DETAIL
 SCALE: NOT TO SCALE

- NOTES:**
- THE EXISTING SIDEWALK AND CURB WILL LIKELY BE DISTURBED. A SAFE AND ACCESSIBLE PEDESTRIAN ROUTING ACROSS THE TEMPORARY FENCE SHOULD BE PROVIDED.
 - THE SIDEWALK, CURB AND RIGHT-OF-WAY SHALL BE RESTORED TO THE SATISFACTION OF THE WALKWAY DEPARTMENT.



MARVEL
 140 HUDSON STREET, PLR 3 NEW YORK, NY 10013
 212 476 8400

OWNER:
 THE MASTERS SCHOOL
 49 CLINTON AVENUE
 DORRIS FERRY, NEW YORK 10027
 TEL: 718 476 8400

PROJECT ARCHITECTS / LANDSCAPE ARCHITECTS:
MARVEL
 140 HUDSON STREET, PLR 3
 NEW YORK, NY 10013
 TEL: 212 476 8400

GEOTECHNICAL / CIVIL ENGINEER:
WFE ENGINEERS & SURVEYORS, P.C.
 2180 WALKER DRIVE, SUITE 100
 SUDBURY, MA 01486
 TEL: 978 325 4000

STRUCTURAL ENGINEER:
BLM
 300 BROADWAY, SUITE 1000
 NEW YORK, NY 10013
 TEL: 212 693 7000

ELECTRICAL ENGINEER:
PERM CONSULTING ENGINEERS, P.C.
 100 W. 42ND STREET, SUITE 1001
 NEW YORK, NY 10018
 TEL: 212 646 5333

MECHANICAL ENGINEER:
PERM CONSULTING ENGINEERS, P.C.
 100 W. 42ND STREET, SUITE 1001
 NEW YORK, NY 10018
 TEL: 212 646 5333

PLUMBING ENGINEER:
PERM CONSULTING ENGINEERS, P.C.
 100 W. 42ND STREET, SUITE 1001
 NEW YORK, NY 10018
 TEL: 212 646 5333

VEHICLE TRANSPORTATION:
MOA
 400 WEST 34TH STREET, SUITE 4
 NEW YORK, NY 10018
 TEL: 212 693 8300

AVIATION SECURITY CONSULTANT:
COBERT ASSOCIATES, INC.
 400 W. 34TH STREET, SUITE 4
 NEW YORK, NY 10018
 TEL: 212 693 8300

ACQUISITION CONSULTANT:
LEVIN CONSULTANTS
 150 N. WALKER STREET, SUITE 400
 NEW YORK, NY 10013
 TEL: 212 693 8300

LANDSCAPE ARCHITECT:
WMS ARCH
 100 W. 42ND STREET, SUITE 1001
 NEW YORK, NY 10018
 TEL: 212 646 5333

LIGHTING DESIGNER:
BLM
 300 BROADWAY, SUITE 1000
 NEW YORK, NY 10013
 TEL: 212 693 7000

CONSTRUCTION ACCESSIBILITY CONSULTANT:
CONSTRUCTION ACCESSIBILITY CONSULTANTS, INC.
 100 W. 42ND STREET, SUITE 1001
 NEW YORK, NY 10018
 TEL: 212 646 5333

ARCHITECTURAL SPECIFICATIONS CONSULTANT:
CONSTRUCTION SPECIFICATIONS CONSULTANTS, INC.
 100 W. 42ND STREET, SUITE 1001
 NEW YORK, NY 10018
 TEL: 212 646 5333

GEOTECHNICAL ENGINEER:
WFE ENGINEERS & SURVEYORS, P.C.
 2180 WALKER DRIVE, SUITE 100
 SUDBURY, MA 01486
 TEL: 978 325 4000

REV.	DATE	DESCRIPTION
1	09/20/2021	ISSUED FOR PERMIT
2	09/20/2021	ISSUED FOR PERMIT
3	09/20/2021	ISSUED FOR PERMIT
4	09/20/2021	ISSUED FOR PERMIT
5	09/20/2021	ISSUED FOR PERMIT

09/20/2021

KEY PLANNING
 2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
 49 CLINTON AVENUE
 DORRIS FERRY, NEW YORK 10027


CONSTRUCTION ACCESS PLAN

SCALE: AS NOTED

DRAWING #
C-502
 5 of 10
 DOB JOB -


DOB STAMP ZONE

LEGEND	
EXISTING CONTOUR	---
PROPOSED MAJOR CONTOUR	—+—
PROPOSED MINOR CONTOUR	—•—
PROPOSED SLOPE ELEVATION	4.0:1
SLOPE ANGLE	7.7°
PROPOSED TOP OF FIN. ELEVATION	100.00



MARVEL
141 HOBSON STREET, FLOOR 3 NEW YORK, NY 10013
212.676.6622

- CONSULTANTS:
- THE MASTERS SCHOOL
48 CLINTON AVENUE
DOBS FERRY, NY 10022
TEL: 212.478.9222
 - PROJECT ARCHITECTS + LANDSCAPE ARCHITECTS
MARVEL
141 HOBSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 212.676.6622
 - SEITZINGER & CO., ENGINEER
100 WEST 30TH STREET, SUITE 1000
NEW YORK, NY 10018
TEL: 212.676.6622
 - STRUCTURAL ENGINEER
BIRDA
100 WEST 30TH STREET, SUITE 1000
NEW YORK, NY 10018
TEL: 212.676.6622
 - BUILDING SYSTEMS ENGINEER
PDR INC CONSULTING ENGINEERS
133 WEST 18TH STREET, SUITE 1001
NEW YORK, NY 10011
TEL: 212.676.6622
 - MECHANICAL ENGINEER
VDA
140 WEST 30TH STREET, FLOOR 4
NEW YORK, NY 10018
TEL: 212.676.6622
 - AV / IT SECURITY CONSULTANT
COSENTINA ASSOCIATES, INC.
408 WEST 14TH STREET, SUITE 100
NEW YORK, NY 10019
TEL: 212.676.6622
 - ACoustics CONSULTANT
LBN CONSULTANTS
100 WEST 30TH STREET, SUITE 1000
NEW YORK, NY 10018
TEL: 212.676.6622
 - ENVIRONMENTAL CONSULTANT
W&A
100 WEST 30TH STREET, FLOOR 14
NEW YORK, NY 10018
TEL: 212.676.6622
 - LANDSCAPE DESIGNER
BOYD SMITH LANDSCAPE DESIGN
100 WEST 30TH STREET, SUITE 1000
NEW YORK, NY 10018
TEL: 212.676.6622
 - CODE AND ACCESSIBILITY CONSULTANT
CODE CONSULTANTS, INC.
400 PARK AVENUE, SUITE 1000
NEW YORK, NY 10022
TEL: 212.676.6622
 - ARCHITECTURAL SPECIFICATION CONSULTANT
CONSTRUCTION SPECIFICATIONS
22 TIVOLIT ROAD
MIDDLETOWN, NY 10941
TEL: 845.376.5700
- GEOTECHNICAL ENGINEER



REV.	DATE	DESCRIPTION
1	08/17/2021	ISSUE FOR PERMITS
2	08/17/2021	REVISED SITE PLAN
3	08/22/2021	REVISED SITE PLAN
4	08/22/2021	REVISED SITE PLAN
5	08/22/2021	REVISED SITE PLAN

09/20/2021

KEY PLAN NTS
2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
48 CLINTON AVENUE
DOBS FERRY, NEW YORK 10022

PROPOSED GRADING
& DRAINAGE PLAN

SCALE: AS NOTED


DRAWING #
C-600
6 of 10
DOB JOB #

DOB STAMP ZONE

-PRELIMINARY-
NOT FOR CONSTRUCTION

1 GRADING & DRAINAGE PLAN
Scale: 1"=10'

LEGEND	
PROPERTY LINE	- - - - -
PROPOSED ELECTRIC SERVICE	—●—●—●—
PROPOSED SANITARY SERVICE	—S—S—S—
PROPOSED GAS SERVICE	—G—G—G—
PROPOSED FIRE SERVICE	—F—F—F—
PROPOSED WATER SERVICE	—W—W—W—
PROPOSED TELECOM SERVICE	—T—T—T—



MARVEL
140 HUDSON STREET, SUITE 300 NEW YORK, NY 10013
212.633.3453

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10027
TEL: 914.478.2422

PROJECT ARCHITECT / LANDSCAPE ARCHITECTS
MARVEL
140 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 212.633.3453

GEOTECHNICAL CIVIL ENGINEER
W&B ENGINEERS & ARCHITECTS
200 WYOMING ST., SUITE 200
NEW JERSEY 07102
TEL: 908.822.4222

STRUCTURAL ENGINEER
W&B
165 WEST 30TH STREET, FLOOR 4
NEW YORK, NY 10011
TEL: 212.633.3453

BUILDING SYSTEMS ENGINEER
PAULS CONSULTING ENGINEERS, P.C.
123 WEST 45TH STREET
NEW YORK, NY 10019
TEL: 212.463.1000

VERTICAL TRANSPORTATION
W&B
165 WEST 30TH STREET, FLOOR 4
NEW YORK, NY 10011
TEL: 212.633.3453

ARCHITECTURAL CONSULTANT
COHEN ASSOCIATES, INC.
400 BROADWAY, SUITE 200
NEW YORK, NY 10013
TEL: 212.633.3453

ADVISOR CONSULTANT
LEVIN CONSULTANTS
18 ALBANY FALLS
NEW YORK, NY 10005
TEL: 347.788.5020

LANDSCAPE CONSULTANT
W&B
165 WEST 30TH STREET, FLOOR 4
NEW YORK, NY 10011
TEL: 212.633.3453

LIGHTING DESIGNER
SOPT CONSULTING DESIGN
130 WILMAH STREET, SUITE 400
NEW YORK, NY 10011
TEL: 212.633.3453

COVER AND ACCESSIBILITY CONSULTANT
COEN CONSULTANTS, INC.
165 WEST 30TH STREET, FLOOR 4
NEW YORK, NY 10011
TEL: 212.633.3453

MULTI-MEDIA DISPLAY CASES
CONSTRUCTION SPECIFICATIONS, INC.
25 WILMAH ROAD
ROCKY HILL, CT 06154
TEL: 783.819.2006

GEOTECHNICAL ENGINEER

REV.	DATE	DESCRIPTION
1	05/11/2021	ALLIANCE OF SERVICES
2	06/11/2021	CONTRACT APPLICATION
3	07/11/2021	SITE APPLICATION
4	08/11/2021	SITE APPLICATION
5	09/11/2021	SITE APPLICATION
6	10/11/2021	SITE APPLICATION

09/20/2021

KEY PLAN NTS
2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10027


UTILITY PLAN

SCALE: AS NOTED

DRAWING #
C-700
7 of 10
DOB JOB #


DOB STAMP ZONE

**-PRELIMINARY-
NOT FOR CONSTRUCTION**




1 UTILITY RELOCATION PLAN
Scale: 1" = 10'


LEGEND	
PROPERTY LINE	---
PROPOSED ELECTRIC SERVICE	E E E
PROPOSED SANITARY SERVICE	S
PROPOSED GAS SERVICE	G
PROPOSED SEWER SERVICE	W
PROPOSED WATER SERVICE	W
PROPOSED TELECOM SERVICE	T



1 UTILITY RELOCATION PLAN
SCALE: 1"=10'



2 SANITARY SEWER PROFILE
SCALE: VERTICAL 1"=4', HORIZONTAL 1"=30'



MARVEL
40 HUDSON STREET, FLOOR 3, NEW YORK, NY 10014
212.675.8675

- OWNER:
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10022
TEL: 914.475.8622
- PROJECT ARCHITECTS / LANDSCAPE ARCHITECTS:
MARVEL
40 HUDSON STREET, FLOOR 3
NEW YORK, NY 10014
TEL: 212.675.8675
- GEOTECHNICAL CONSULTANT:
WSP ENGINEERS & SURVEYORS, INC.
2700 WALKER DRIVE, SUITE 200
ROCKY HILL, CT 06151
TEL: 860.422.1422
- STRUCTURAL ENGINEER:
BALMAIN
1212 23RD FLOOR 13
NEW YORK, NY 10013
TEL: 212.633.9710
- BUILDING SYSTEMS ENGINEER:
POLSKIE CONSULTING ENGINEERS, INC.
133 WEST 19TH STREET 7
NEW YORK, NY 10011
TEL: 212.648.3300
- VEGETATION MANAGEMENT CONSULTANT:
VISA
460 WEST 30TH STREET, FLOOR 4
NEW YORK, NY 10018
TEL: 212.688.8800
- ENVIRONMENTAL CONSULTANT:
CORNERSTONE ASSOCIATES, INC.
408 BROADWAY 10TH FLOOR
NEW YORK, NY 10013
TEL: 212.610.3800
- ACQUISITION CONSULTANT:
LITVIN CONSULTANTS
100 W. 40TH STREET
NEW YORK, NY 10018
TEL: 212.762.2810
- ENVIRONMENTAL CONSULTANT:
MMR SCHE
100 W. 40TH STREET, FLOOR 14
NEW YORK, NY 10018
TEL: 212.610.3800
- LANDSCAPE ARCHITECT:
DOTS LANDSCAPE DESIGN
130 MANHATTAN STREET, SUITE 100
NEW YORK, NY 10014
TEL: 212.641.0000
- CEEP AND ACCESSIBILITY CONSULTANT:
CORNERSTONE ASSOCIATES, INC.
408 BROADWAY
NEW YORK, NY 10013
TEL: 212.610.3800
- ARCHITECTURAL SERVICES CONSULTANT:
CONSTRUCTION SPECIFICATIONS, INC.
25 ELLENWAY ROAD
WINGSPANVILLE, NY 14181
TEL: 716.878.2700
- GEOTECHNICAL ENGINEER:

REV.	DATE	DESCRIPTION
1	02/11/2021	ISSUE FOR DOBIS
2	08/10/2021	COMPLETE APPLICATION
3	01/22/2021	SITE APPLICATION SUBMISSION
4	08/31/2021	SITE APPLICATION SUBMISSION
5	08/22/2021	SITE APPLICATION SUBMISSION (S01)

09/20/2021

KEY PLAN NTS
2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10022

-PRELIMINARY-
NOT FOR CONSTRUCTION

UTILITY RELOCATION PLAN
SCALE: AS NOTED

DRAWING #
C-701
8 of 10
DOB JOB #

DOB STAMP ZONE



MARVEL
100 HUNTER STREET, SUITE 200 NEW YORK, NY 10003
212.863.8433

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914.834.8433


PROJECT ARCHITECTS / LANDSCAPE ARCHITECTS
MARVEL
100 HUNTER STREET, SUITE 200
NEW YORK, NY 10003
TEL: 212.863.8433

GENERAL CONTRACTOR
SPECTRUM CIVIL ENGINEERS
500 WEST 10TH STREET
NEW YORK, NY 10014
TEL: 212.863.8433


STRUCTURAL ENGINEER
BLUM
300 WEST 10TH STREET
NEW YORK, NY 10014
TEL: 212.863.8433

ELECTRICAL ENGINEER
POLARIS CONSULTING ENGINEERS INC
125 W 41ST STREET
NEW YORK, NY 10018
TEL: 212.863.8433


Mechanical Engineering
POLARIS CONSULTING ENGINEERS INC
125 W 41ST STREET
NEW YORK, NY 10018
TEL: 212.863.8433




1 STANDARD BELGIAN BLOCK CURB DETAIL
Scale: N.T.S.




2 STANDARD ASPHALT PAVEMENT DETAIL
Scale: N.T.S.



3 STANDARD CURB CUT DETAIL
Scale: N.T.S.




4 HANDICAP STALL MARKINGS DETAIL
Scale: N.T.S.




5 HANDICAP PARKING SIGN w/VAN ACCESSIBLE SIGN
Scale: N.T.S.




6 STANDARD FIRE HYDRANT DETAIL
Scale: N.T.S.




7 STANDARD CHAIN LINKED FENCE DETAIL
Scale: N.T.S.




8 STANDARD AREA DRAIN DETAIL
Scale: N.T.S.




9 STANDARD SILT FENCE DETAIL
Scale: N.T.S.




10 STANDARD SUPER SILT FENCE DETAIL
Scale: N.T.S.



11 PRECAST CONCRETE SANITARY SEWER MANHOLE DETAIL
Scale: N.T.S.




12 STANDARD FILTER FABRIC DROP INLET PROTECTION DETAIL
Scale: N.T.S.




13 STANDARD CONSTRUCTION ENTRANCE DETAIL
Scale: N.T.S.




14 TOPSOIL STOCKPILE DETAIL
Scale: N.T.S.




15 UTILITY TRENCHING DETAIL
Scale: N.T.S.




16 PEDESTRIAN CURB RAMP DETAIL
Scale: N.T.S.



17 CROSSWALK STRIPING DETAIL
Scale: N.T.S.



18 OUTLET CONTROL STRUCTURE DETAIL
Scale: N.T.S.



19 TOPSOIL STOCKPILE DETAIL
Scale: N.T.S.

VERTICAL TRANSPORTATION
NOVA
100 WEST 30TH STREET, SUITE 400
NEW YORK, NY 10001
TEL: 212.863.8433

ARCHITECTURAL CONSULTANTS
CORNER ARCHITECTURE INC
100 WEST 30TH STREET
NEW YORK, NY 10001
TEL: 212.863.8433

ACQUISITION CONSULTANT
LIFE CONSULTANTS
100 WEST 30TH STREET
NEW YORK, NY 10001
TEL: 212.863.8433

LANDSCAPE ARCHITECT
LIFE CONSULTANTS
100 WEST 30TH STREET
NEW YORK, NY 10001
TEL: 212.863.8433


LIGHTING DESIGNER
LIFE CONSULTANTS
100 WEST 30TH STREET
NEW YORK, NY 10001
TEL: 212.863.8433

CODE AND ACCESSIBILITY CONSULTANT
CORNER ARCHITECTURE INC
100 WEST 30TH STREET
NEW YORK, NY 10001
TEL: 212.863.8433

ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION PREPARATION INC
100 WEST 30TH STREET
NEW YORK, NY 10001
TEL: 212.863.8433

GEOTECHNICAL ENGINEER
CONSTRUCTION PREPARATION INC
100 WEST 30TH STREET
NEW YORK, NY 10001
TEL: 212.863.8433

REV	DATE	DESCRIPTION
1	02/14/2021	ISSUE FOR BIDDING
2	02/14/2021	ISSUE FOR BIDDING
3	02/14/2021	ISSUE FOR BIDDING
4	02/14/2021	ISSUE FOR BIDDING
5	02/14/2021	ISSUE FOR BIDDING



KEY PLAN NTS

2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

CONSTRUCTION
DETAILS

SCALE: AS NOTED

DRAWING #
C-900

9 of 10

DOB JOB

DOB STAMP ZONE



MARVEL
146 HUDSON STREET, FLA 2 & NEW YORK, NY 10813
718.818.6820

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10522
TEL: 914.831.8001

PROJECT ARCHITECTS LANDSCAPE ARCHITECTS
MARVEL
146 HUDSON STREET, FLA 2
NEW YORK, NY 10813
TEL: 718.818.6820

GENERAL CONTRACTOR CONSTRUCTION ENGINEERS & ARCHITECTS
CONSTRUCTION ENGINEERS & ARCHITECTS
100 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500

STRUCTURAL ENGINEER
BLUM
30 E 33RD FLOOR 3
NEW YORK, NY 10017
TEL: 212.681.9100

MECHANICAL/ELECTRICAL ENGINEER
FORBES CONSULTING ENGINEERS
100 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500

VEGETATION CONSULTANT
VEGETATION CONSULTANTS
100 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500

AV/IT SECURITY CONSULTANT
CONSENT ARCHITECTS INC.
400 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500


ACQUISITION CONSULTANT
LEVIN CONSULTANTS
100 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500

ENVIRONMENTAL CONSULTANT
ENVIRONMENTAL CONSULTANTS
100 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500


CONCRETE CONSULTANTS INC.
400 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500

MECHANICAL/ELECTRICAL ENGINEER
CONSTRUCTION ENGINEERS & ARCHITECTS
100 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500


VEGETATION ENGINEER
VEGETATION CONSULTANTS
100 WEST 10TH STREET
NEW YORK, NY 10011
TEL: 212.463.1500




1 ADS STORMTECH MC3500 CHAMBER
Scale: N.T.S.



2 BIORETENTION
Scale: N.T.S.




3 4\"/>




4 MC3500 ISOLATOR ROW PLUS
Scale: N.T.S.




5 NOT USED
Scale: N.T.S.




6 POST INDICATOR VALVE
Scale: N.T.S.



7 5\"/>




8 PRECAST CONCRETE ELECTRIC HANDHOLE
Scale: N.T.S.



9 AREA DRAIN
Scale: N.T.S.

REV.	DATE	DESCRIPTION
1	02/11/2021	ISSUE OF DOBSIS
2	06/11/2021	ISSUE SITE APPLICATION
3	01/22/2022	SITE APPLICATION SUBMISSION
4	08/13/2022	SITE APPLICATION SUBMISSION
5	09/20/2022	SITE APPLICATION SUBMISSION

09/20/2021



KEY PLAN NTS
2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

**CONSTRUCTION
DETAILS**

SCALE: AS NOTED



DRAWING #
C-901
10 of 10
DOB JOB

DOB STAMP ZONE

GENERAL NOTES

GENERAL

- 1. DO NOT SCALE DRAWINGS OR CONSULT THE ARCHITECT AND SET FOR ANYHOURS TO ALL DIMENSIONS REGARDING THE WORK. THE CONTRACTOR IS ADVISED THAT ANY INFORMATION IS NECESSARY AND NOT NECESSARY TO COMPLY WITH THE CONTRACTOR'S OBLIGATION TO MAINTAIN THE EXISTING CONDITIONS AND AS AVAILABLE FROM AGENCIES, PRIVATE UTILITIES AND/OR THE OWNER MAY NOT BE COMPLETE.
- 2. ALL SURVEYING INFORMATION AND MEASUREMENTS SHALL BE OBTAINED BY THE OWNER AND SHALL BE FURNISHED TO THE CONTRACTOR IN WRITING BY THE OWNER PRIOR TO THE START OF THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 3. PRIOR TO COMMENCEMENT OF WORK, THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF ALL EXISTING UTILITIES BY THE PROJECT AREA AND RECORD THEM ACCORDING TO ALL APPLICABLE REGULATIONS AND STANDARDS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 18. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 19. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 21. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 22. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 23. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 24. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 25. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 26. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 27. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 28. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.

EXISTING AND REMOVALS

- 1. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATION BETWEEN THE EXISTING CONDITIONS AND THE LANDSCAPE PLAN IN RELATION TO THE EXISTING AND REMOVALS.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.

INSTALLATION MAINTENANCE WORK

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL SURVEYING INFORMATION AND MEASUREMENTS NECESSARY FOR THE WORK.

FINISHES

- 1. ALL FINISHES SHALL BE IN ACCORDANCE WITH THE LATEST SPECIFICATIONS OF THE DEPARTMENT OF BUILDINGS AND ANY OTHER APPLICABLE CODES.
- 2. ALL AREA DRAINS WITHIN THE CONTRACT LIMITS SHALL BE INSTALLED AS NECESSARY, SO THAT THEY WILL BE OPERATIONAL, ACCESSIBLE, AND PROTECTED FROM PROJECTS OCCUPANCY AFTER THE COMPLETION OF THE WORK.
- 3. ANY DAMAGE TO EXISTING AREA DRAINS AND CONNECTIONS CAUSED BY THE CONTRACTOR'S WORK SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO COST TO THE CLIENT, SUBJECT TO THE APPROVAL OF THE LANDSCAPE ARCHITECT AND THE CLIENT.
- 4. ALL EXISTING AREA DRAINAGE AND CONNECTIONS WITHIN THE LIMITS OF THIS CONTRACT AND CONTIGUOUS ARE TO BE CLEANED, OUTFITTED, AND OTHERWISE MADE OPERABLE TO THE SATISFACTION OF THE LANDSCAPE ARCHITECT.

STRUCTURAL

- 1. ALL NEW REINFORCED CONCRETE SHALL BE CONFORM TO ALL APPLICABLE CODES AND SHALL BE IN ACCORDANCE WITH THE LATEST SPECIFICATIONS OF THE DEPARTMENT OF BUILDINGS AND ANY OTHER APPLICABLE CODES.
- 2. ALL REINFORCED CONCRETE SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ALL APPLICABLE CODES AND SHALL BE IN ACCORDANCE WITH THE LATEST SPECIFICATIONS OF THE DEPARTMENT OF BUILDINGS AND ANY OTHER APPLICABLE CODES.
- 3. ALL REINFORCED CONCRETE SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ALL APPLICABLE CODES AND SHALL BE IN ACCORDANCE WITH THE LATEST SPECIFICATIONS OF THE DEPARTMENT OF BUILDINGS AND ANY OTHER APPLICABLE CODES.
- 4. ALL REINFORCED CONCRETE SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ALL APPLICABLE CODES AND SHALL BE IN ACCORDANCE WITH THE LATEST SPECIFICATIONS OF THE DEPARTMENT OF BUILDINGS AND ANY OTHER APPLICABLE CODES.
- 5. ALL REINFORCED CONCRETE SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ALL APPLICABLE CODES AND SHALL BE IN ACCORDANCE WITH THE LATEST SPECIFICATIONS OF THE DEPARTMENT OF BUILDINGS AND ANY OTHER APPLICABLE CODES.



MARVEL

49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

OWNER: THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 212 499 7400

PROJECT ARCHITECTS / LANDSCAPE ARCHITECT: MARVEL
141 DOBBS STREET, FLOOR 9
NEW YORK, NEW YORK 10011
TEL: 212 499 7400

GENERAL CONTRACTOR: W.F. ENGINEERS & BUILDERS, INC.
1075 PARKER STREET, SUITE 100
NEW JERSEY 07003
TEL: 908 409 8900

STRUCTURAL ENGINEER: BLUMER
25 OLD FURN FLOOR 10
NEW YORK, NEW YORK 10011
TEL: 212 468 7700

ELECTRICAL ENGINEER: POLSKY CONSULTING ENGINEERS, INC.
100 WEST 21ST STREET
NEW YORK, NEW YORK 10011
TEL: 212 469 7800

MECHANICAL ENGINEER: VIDA
160 WEST 21ST STREET, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212 469 7800

AV / IT CONSULTANT: AV CONSULTANTS, INC.
100 WEST 21ST STREET, SUITE 100
NEW YORK, NEW YORK 10011
TEL: 212 469 7800

ACQUISITION CONSULTANT: LETA CONSULTANTS
100 WEST 21ST STREET
NEW YORK, NEW YORK 10011
TEL: 212 469 7800

ENVIRONMENTAL CONSULTANT: NEW BONE
140 WEST 21ST STREET, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212 469 7800

DOT DARK LIGHTING DESIGN: DOT DARK LIGHTING DESIGN
100 WEST 21ST STREET, SUITE 100
NEW YORK, NEW YORK 10011
TEL: 212 469 7800

COOR. AND ACCESSIBILITY CONSULTANT: COOR CONSULTANTS, INC.
140 PARK AVENUE 8
NEW YORK, NEW YORK 10011
TEL: 212 497 4033

MECHANICAL, ELECTRICAL, PLUMBING, AND MECHANICAL CONTRACTOR: CONSTRUCTION APPLICATIONS, INC.
100 WEST 21ST STREET, SUITE 100
NEW YORK, NEW YORK 10011
TEL: 212 469 7800

09/20/2021



KEY PLAN NTS

2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

GENERAL NOTES

SCALE: NTS

DRAWING # **L-001**
01 of 10
DOB JOB: -

DOB STAMP ZONE



MARVEL
140 HUDSON STREET, FLR 3 NEW YORK, NY 10013
212.414.4242

OWNER:
THE MASTERS SCHOOL
40 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914.674.8200

PROJECT ARCHITECTS - LANDSCAPE ARCHITECT
MARVEL
100 HUDSON STREET, FLR 3, DOBBS
NEW YORK, NEW YORK 10522
TEL: 212.414.4242

GEOTECHNICAL / CIVIL ENGINEER
MPE ENGINEERS & SURVEYORS, INC.
310 WASHINGTON SQUARE, SUITE 200
SOUTH HAVENFIELD, NEW JERSEY 07088
TEL: 908.522.4452

STRUCTURAL ENGINEER
BLMM
30 OLD SLIP FLOOR, 100
NEW YORK, NEW YORK 10005
TEL: 212.420.7700

BUILDING SYSTEMS ENGINEER
FORRE CONSULTING ENGINEERS & P.C.
100 WEST 30TH STREET
NEW YORK, NEW YORK 10011
TEL: 212.462.1000

VERTICAL TRANSPORTATION
YOR
140 WEST 30TH STREET, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212.662.3000

SECURITY CONSULTANT
COSENTINI ASSOCIATES, INC.
100 WEST 30TH STREET, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212.662.3000

ACOUSTICS CONSULTANT
LEVIN CONSULTANTS
100 WEST 30TH STREET
NEW YORK, NEW YORK 10011
TEL: 212.760.0610

ENVIRONMENTAL CONSULTANT
BLMM
30 OLD SLIP FLOOR, 100
NEW YORK, NEW YORK 10005
TEL: 212.420.7700


DOT DARK LIGHTING DESIGN
DOT DARK LIGHTING DESIGN
100 WEST 30TH STREET, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212.662.3000

CEXIS AND ACCESSIBILITY CONSULTANT
COSENTINI ASSOCIATES, INC.
100 WEST 30TH STREET, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212.662.3000

ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS
117 TENNEY ROAD
MORGANTOWN, NEW JERSEY 07972
TEL: 732.393.0070

LEGEND

- CONCRETE UNIT PAVERS
- ASPHALT PATHWAY
- PLANTING AREA
- COP CONCRETE
- STEEL EDGING
- STONE BENCH
- GRAVEL EDGE
- EXISTING TREE
- PROPOSED TREE



CONTINUE BEHIND AN BLOCK CURBING ALONG SIDEWALK. EXTENT OF CURBING TO BE DETERMINED.

EMERGENCY GENERATOR. REFER TO CIVIL AND MEP DWGS.

A. STONE BENCHES ARE ROUGHLY 5'4" X 2'2" AND THEIR LOCATION AND ORIENTATION IS TO BE VERIFIED BY LANDSCAPE ARCHITECT.

JAM TO BE RESTORED POST CONSTRUCTION. SEE CIVIL DWGS FOR DETAILS.

ADA ACCESSIBLE 18"X14" CONNECTING TO ASPHALT PATH

REV	DATE	DESCRIPTION
1	08/10/2021	ISSUANCE OF PERMITS PER SITE APPLICATION
2	08/10/2021	SITE APPLICATION SUBMISSION
3	07/20/2021	SITE APPLICATION SUBMISSION
4	09/20/2021	SITE APPLICATION SUBMISSION (REV)

09/20/2021

KEY PLAN NTS

2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
40 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

LAYOUT PLAN

SCALE: 1" = 10'



DRAWING #
L-100
02 of 10
DOB JOB -

DOB STAMP ZONE



MARVEL
100 HUDSON STREET, FL 3 NEW YORK, NY 10014
212.648.0488

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 212.478.6888

PHYSICAL ARCHITECTS - LANDSCAPE ARCHITECT
MARVEL
147 MEDICAL STREET, FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 212.648.0488

GEOTECHNICAL / CIVIL ENGINEER
MVE ENGINEERS & DESIGNERS, INC.
270 HAWORTH BOULEVARD
SUITE 200, PLAINFIELD, NEW JERSEY 07041
TEL: 908.322.4422

STRUCTURAL ENGINEER
SJ MAIN
51 WEST 26TH STREET, FLOOR 3
NEW YORK, NEW YORK 10005
TEL: 212.648.7076

BUILDING SYSTEMS ENGINEER
POHNE CONSULTING ENGINEERS, INC.
101 WEST 75TH STREET
NEW YORK, NEW YORK 10023
TEL: 212.648.1922

VERTICAL TRANSPORTATION
NSR
445 WEST 26TH STREET, FLOOR 4
NEW YORK, NEW YORK 10001
TEL: 212.648.8990

AVIATION SECURITY CONSULTANT
COSENTYN ASSOCIATES, INC.
400 RIVER STREET
NEW YORK, NEW YORK 10018
TEL: 212.441.6800

ACQUISITION CONSULTANT
SEY COMPANY PARTNERS
18 BELLEVUE SQUARE
NEW YORK, NEW YORK 10008
TEL: 212.447.8000










ENVIRONMENTAL CONSULTANT
PPP PARTNERS
400 RIVER STREET, FLOOR 14
NEW YORK, NEW YORK 10018
TEL: 212.447.8000


LIGHTING DESIGNER
DOT DASH LIGHTING DESIGN
122 WALL STREET, SUITE 1805
NEW YORK, NEW YORK 10003
TEL: 212.447.9000

CODE AND ACCESSIBILITY CONSULTANT
CODE CONSULTANTS, INC.
145 PARK AVENUE, 3
NEW YORK, NEW YORK 10018
TEL: 212.447.4222

ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS, INC.
117 MARKET STREET
MIDDLETOWN, NEW JERSEY 07940
TEL: 908.684.2500

LEGEND

-  CONCRETE UNIT PAVES (01 15:00)
-  ASPHALT PATH-ARK (02 15:00)
-  PLANTING AREA (03 15:00)
-  C/P CONCRETE (04 15:00)
-  STEEL EDGE (05 15:00)
-  STONE BENCH (06 15:00)
-  GRAVEL EDGE (07 15:00)
-  EXISTING TREE (08 15:00)
-  PROPOSED TREE (09 15:00)



REV	DATE	DESCRIPTION
1	08/14/2021	ISSUANCE OF STOREFRONT SITE APPLICATION
2	08/17/2021	SUB APPLICATION REVISION
3	08/22/2021	SITE APPLICATION REVISION
4	08/26/2021	SITE APPLICATION SUBMISSION - RFP

09/20/2021

KEY PLAN NTS

2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

MATERIALS PLAN

SCALE: 1" = 10'



DRAWING #
L-200
03 of 10
DOB JOB: -

DOB STAMP ZONE

PLANTING PLAN

TREES					
SYM	QTY.	BOTANICAL NAME	COMMON NAME	NATIVE (Y/N)	SIZE
AG	3	<i>Acer griseum</i>	Paperbark maple	(N)	3.5"-4" Caliper
BP	7	<i>Betula populifolia</i>	Grey Birch	(Y)	3.5"-4" Caliper
MS	6	<i>Magnolia x soulangeana</i>	Saucer Magnolia	(Y)	3.5"-4" Caliper
NS	5	<i>Nyssa sylvatica</i>	Black Tupelo	(Y)	3.5"-4" Caliper
TD	9	<i>Thuja occidentalis 'Hetz Wintergreen'</i>	Hetz Wintergreen Arborvitae	(Y)	25 Gal Cont.

IRRIGATION NOTES

1. An irrigation system inclusive of all required components and installation for a fully functional automatic irrigation system at all planted areas shall be included as part of the base bid.
2. System shall be installed by a water sense certified professional and utilize smart irrigation controls and design.
3. Submit shop drawing for approval.

PLANTING NOTES


1. Prior to commencing planting operations the contractor shall stake out the exact location of all trees, shrubs and herbaceous plants for the landscape architect's approval. All planting operations and layout shall proceed under close coordination with the landscape architect. Tree locations may vary as directed by the landscape architect.
2. Plant material will be inspected and approved at place of growth

by landscape architect. However, plant material which has become damaged or diseased or which is unacceptable to the landscape architect may be rejected upon delivery to the site.

3. The actual location of plant materials may vary due to the field conditions. Final placement of plant material shall be approved before the pits are dug. If initial placement is not satisfactory, plants shall be relocated in the field at the direction of the landscape architect at no additional cost to the owner.
4. The contractor is to use care during digging and planting to avoid disturbing or damaging any adjacent or underground utilities and built items. Repair to any damage resulting from this construction will be the contractors responsibility and shall be restored at their expense to the satisfaction of the landscape architect.
5. Should there be any discrepancies between the quantities called for on the plant list and those indicated on the plan, the greater quantity shall govern.
6. All trees shall be "deadheaded" with a minimum of three (3) CMU's per tree as shown on the planting details, unless otherwise noted.
7. At all times the site shall be kept neat, and shall be kept free of debris left from the planting operations.
8. All trees in the same planting area shall be placed and planted at the same time. If because of delivery schedule, any plant on site to maintain their health and vitality. Plants shall be otherwise protected and maintained, including, but not limited to, water and shade. Any plants deemed not in satisfactory health or condition at time of planting shall be replaced at the contractors expense. All shrubs designated for reuse that cannot be replanted immediately after digging shall be heeled-in as noted.

LEGEND

- COURTYARD UNITS (01 of 200)
- ASPHALT PATIWAY (02 of 200)
- PLANTING AREA (01 of 400)
- CIP COVERILE (01 of 200)
- STEEL EDGE (10 of 200)
- STONE BENCH (01 of 200)
- GRAVEL EDGE (01 of 200)
- EXISTING TREES
- PROPOSED TREE



MARVEL

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914 478-6400

PROJECT ARCHITECTS + LANDSCAPE ARCHITECT
MARVEL
140 MEDINA STREET, FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 212 474-1400

GEOTECHNICAL ENGINEER
MPS ENGINEERS & SURVEYORS, INC.
170 W. 10TH STREET, 10TH FLOOR
NEW YORK, NEW YORK 10011
TEL: 212 485-1000

STRUCTURAL ENGINEER
SUNAM
32 OLD 96th FLOOR 4
NEW YORK, NEW YORK 10005
TEL: 212 620-7970

MECHANICAL/ELECTRICAL ENGINEER
POLSKIE CONSULTING ENGINEERS, INC.
110 WEST 87TH STREET
NEW YORK, NEW YORK 10011
TEL: 212 465-7100

VERTICAL TRANSPORTATION
USA
145 WEST 40TH STREET, FLOOR 4
NEW YORK, NEW YORK 10018
TEL: 212 664-9054

AV / IT SECURITY CONSULTANT
CORNING ASSOCIATES, INC.
400 WEST 114TH STREET
NEW YORK, NEW YORK 10018
TEL: 212 875-9900

ACCESSIBILITY CONSULTANT
LETA CONSULTANTS
170 BROADWAY STREET
NEW YORK, NEW YORK 10005
TEL: 212 767-8910

ENVIRONMENTAL CONSULTANT
MVA DESIGN
1 WASHINGTON STREET, FLOOR 14
NEW YORK, NEW YORK 10004
TEL: 212 684-8790

LIGHTING DESIGNER
DOT DASH LIGHTING DESIGN
110 WALKER STREET, SUITE 400
NEW YORK, NEW YORK 10013
TEL: 212 485-1900

CODE AND ACCESSIBILITY CONSULTANT
CODE CONSULTANTS, INC.
440 PARK AVENUE, 5
NEW YORK, NEW YORK 10018
TEL: 212 447-4033

ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS, INC.
22 FERRIS ROAD
ROSELANDVILLE, NEW JERSEY 07068
TEL: 212 370-0700

REV	DATE	DESCRIPTION
1	02/17/2021	ISSUANCE OF DOORS PERNY SITE APPLICATION
2	04/11/2021	SITE APPLICATION SUBMISSION
3	01/22/2021	SITE APPLICATION SUBMISSION
4	09/20/2021	SITE APPLICATION SUBMISSION - RFI

09/20/2021



KEY PLANNING

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

**TREE PLANTING
PLAN**

SCALE: 1" = 10'



DRAWING #
L-400
04 of 10
DOB JOB -

PLANTING PLAN

TREES					
SYM	QTY.	BOTANICAL NAME	COMMON NAME	NATIVE (Y/N)	SIZE
AG	5	<i>Acer griseum</i>	Paperbark maple	(N)	3.5"-4" Caliper
BP	7	<i>Betula populifolia</i>	Grey Birch	(Y)	3.5"-4" Caliper
MS	6	<i>Magnolia x soulangeana</i>	Saucer Magnolia	(Y)	3.5"-4" Caliper
NS	5	<i>Nyssa sylvatica</i>	Black Tupelo	(Y)	3.5"-4" Caliper
TD	2	<i>Thuja occidentalis 'Hetz Wintergreen'</i>	Hetz Wintergreen Arborvitae	(Y)	25 Gal Cont.

PLANTING MIX - ZONE 1 - SHRUBS & PERENNIALS - 913 SF					
SYM	QTY.	BOTANICAL NAME	COMMON NAME	NATIVE (Y/N)	SIZE
CS	16	<i>Cornus sericea 'Flaviramea'</i>	Yellow Twig Dogwood	(Y)	5 gallon
OS	132	<i>Oxoclea sensibilib</i>	Sensitive Fern	(Y)	1 gallon

PLANTING MIX - ZONE 2 - PERENNIALS - 1010 SF					
SYM	QTY.	BOTANICAL NAME	COMMON NAME	NATIVE (Y/N)	SIZE
AS	146	<i>Actaea simplicifolia 'Black Negligee'</i>	Black Negligee Snakeroot	(Y)	1 gallon
AC	146	<i>Asarum canadense</i>	Canadian Wild Ginger	(Y)	1 gallon









PLANTING MIX - ZONE 3 - PERENNIALS - 1636 SF					
SYM	QTY.	BOTANICAL NAME	COMMON NAME	NATIVE (Y/N)	SIZE
EA	236	<i>Euphorbia amygdaloides</i>	Wood Spurge	(Y)	1 gallon
OS	236	<i>Oxoclea sensibilib</i>	Sensitive Fern	(Y)	1 gallon


PLANTING MIX - ZONE 4 - PERENNIALS - 1517 SF					
SYM	QTY.	BOTANICAL NAME	COMMON NAME	NATIVE (Y/N)	SIZE
IV	27	<i>Itea virginica</i>	Virginia sweetspire	(Y)	5 gallon
PV	187	<i>Panicum virgatum 'shenandoah'</i>	Switchgrass	(Y)	1 gallon

PLANTING MIX - ZONE 5 - PERENNIALS - 2080 SF					
SYM	QTY.	BOTANICAL NAME	COMMON NAME	NATIVE (Y/N)	SIZE
PV	300	<i>Panicum virgatum 'shenandoah'</i>	Switchgrass	(Y)	1 gallon
AR	300	<i>Actaea racemosa</i>	Snakeroot	(Y)	1 gallon

PLANTING MIX - ZONE 6 - PERENNIALS - 1018 SF					
SYM	QTY.	BOTANICAL NAME	COMMON NAME	NATIVE (Y/N)	SIZE
DE	24	<i>Myrica pensylvanica</i>	Northern Bayberry	(Y)	5 gallon
OC	147	<i>Osmundastrum cinnamomeum</i>	Cinnamon Fern	(Y)	1 gallon

LEGEND

-  PLANTING MIX 1
-  PLANTING MIX 2
-  PLANTING MIX 3
-  PLANTING MIX 4
-  PLANTING MIX 5
-  PLANTING MIX 6
-  EXISTING TREES
-  PROPOSED TREES



LINK TO BE REVISIONS FOR CONSTRUCTION SEE CIVIL DWGS FOR DETAILS



MARVEL
 49 CLINTON AVENUE, DOBBS FERRY, NEW YORK, NY 10322
 212.818.8020

- OWNER
THE MASTERS SCHOOL
 49 CLINTON AVENUE
 DOBBS FERRY, NEW YORK 10322
 TEL: 914.475.0400
- PROJECT ARCHITECTS + LANDSCAPE ARCHITECTS
MARVEL
 140 WEST 27TH STREET, FLOOR 3
 NEW YORK, NEW YORK 10013
 TEL: 212.818.8020
- GEOTECHNICAL, CIVIL, ENGINEER
PERKINS+WILL
 270 PARK AVENUE, SUITE 2000
 NEW YORK, NEW YORK 10017
 TEL: 212.512.4000
- STRUCTURAL ENGINEER
SL RAIN
 30 OLD 91ST FLOOR 10
 NEW YORK, NEW YORK 10018
 TEL: 212.640.7010
- BUILDING SYSTEMS ENGINEER
PERKINS+WILL
 270 PARK AVENUE, SUITE 2000
 NEW YORK, NEW YORK 10017
 TEL: 212.512.4000
- VERTICAL TRANSPORTATION
VIA
 145 WEST 30TH STREET, FLOOR 4
 NEW YORK, NEW YORK 10011
 TEL: 212.368.8010
- AV / IT SECURITY CONSULTANT
COBERTH ASSOCIATES, INC.
 408 WEST 10TH STREET
 NEW YORK, NEW YORK 10018
 TEL: 212.515.3000
- ACQUISITION CONSULTANT
LETA CONSULTANTS
 78 BROADWAY STREET
 NEW YORK, NEW YORK 10008
 TEL: 212.347.7810
- ENVELOPE CONSULTANT
SL RAIN
 1 WESTERN STREET, FLOOR 14
 NEW YORK, NEW YORK 10011
 TEL: 212.368.8010
- LIGHTING DESIGNER
DOT DASH LIGHTING DESIGN
 127 WILKES STREET, SUITE 100
 NEW YORK, NEW YORK 10013
 TEL: 212.515.0100
- CODE AND ACCESSIBILITY CONSULTANT
CODE CONSULTANTS, INC.
 440 PARK AVENUE, 8
 NEW YORK, NEW YORK 10018
 TEL: 212.447.4033
- ARCHITECTURAL RENDERING
CONSTRUCTION SPECIFICATIONS INC.
 22 TOWNHALL AVENUE
 ROCKY HILL, NEW JERSEY 07871
 TEL: 732.970.0700

REV	DATE	DESCRIPTION
1	09/20/2021	ISSUE OF SCHEMATIC DEVELOPMENT APPLICATION
2	09/15/2021	REVISED APPLICATION
3	09/22/2021	REVISED APPLICATION
4	09/20/2021	REVISED APPLICATION

09/20/2021



KEY PLAN NTS
 2029
**THE MASTERS SCHOOL
 INNOVATION AND
 ENTREPRENEURSHIP
 CENTER**
 49 CLINTON AVENUE
 DOBBS FERRY, NEW YORK 10322

**UNDERSTORY
 PLANTING PLAN**

SCALE: 1" = 10'



DRAWING #
L-410
 05 of 10
 DOB JOB .

GENERAL NOTES


RENDERED PLAN AND ELEVATIONS ARE FOR ILLUSTRATIVE PURPOSES ONLY AND ARE NOT TO BE MEASURED OR EVALUATED FOR CONSTRUCTION AS SCENE ARCHITECTURAL UTILITY OR OTHER ELEMENTS HAVE CHANGED. SEE PREVIOUS LANDSCAPE PLAN OR LANDSCAPE DETAILS FOR REFERENCES



MARVEL

145 HUDSON STREET, FLA 3 NEW YORK, NY 10013
212.638.8888

- OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 212.678.8888
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECT
MARVEL
145 HUDSON STREET, FLA 3
NEW YORK, NEW YORK 10013
TEL: 212.678.8888
- DESIGN CONSULTANT
MPS ENGINEERS & SURVEYORS, P.C.
200 PARKER BOULEVARD
SUITE 1000 FLEET NEW JERSEY 07030
TEL: 908.861.8888
- STRUCTURAL ENGINEER
SEI INC.
3000 10th FLOOR
NEW YORK, NEW YORK 10018
TEL: 212.438.7878
- BUILDING SYSTEMS ENGINEER
POLYEST CONSULTING ENGINEERS, P.C.
110 WEST 57th STREET
NEW YORK, NEW YORK 10019
TEL: 212.463.7888
- VERTICAL TRANSPORTATION
VGA
145 WEST 80th STREET, FLOOR 4
NEW YORK, NEW YORK 10023
TEL: 212.668.8888
- AV / IT SECURITY CONSULTANT
COMBENT ASSOCIATES, INC.
400 W 10th AVE 4th FL
NEW YORK, NEW YORK 10018
TEL: 212.875.8888
- ACoustics CONSULTANT
LTA CONSULTANTS
10 BROADWAY STREET
NEW YORK, NY, NY 10018
TEL: 212.646.8888
- ENCLIPS CONSULTANT
ENI INC.
100 W 10th STREET, FLOOR 4
NEW YORK, NEW YORK 10018
TEL: 212.678.8888
- LANDSCAPE ARCHITECT
DOT LAMP LIGHTING DESIGN
110 WEST 57th STREET, 4th FL
NEW YORK, NEW YORK 10019
TEL: 212.678.8888
- CODE AND ACCESSIBILITY CONSULTANT
COOK CONSULTANTS, INC.
140 PARK AVENUE, 8
NEW YORK, NEW YORK 10017
TEL: 212.447.8888
- ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS, INC.
27 FURNACE ROAD
HIGHLAND, NEW JERSEY 07731
TEL: 732.593.8888



REV.	DATE	DESCRIPTION
1	08/20/21	VILLAGE OF DOBBS FERRY SITE APPLICATION
2	08/20/21	SITE APPLICATION RESUBMISSION
3	07/28/21	SITE APPLICATION RESUBMISSION
4	08/20/21	SITE APPLICATION SUBMISSION NOT

09/20/2021



KEY PLAN NTS

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

SITE PLAN

SCALE: 1" = 10'



DRAWING #
L-600
06 of 10
DOB JOB: -

GENERAL NOTES

RENDERED PLAN AND ELEVATIONS ARE FOR ILLUSTRATIVE PURPOSES ONLY AND ARE NOT TO BE MEASURED OR EVALUATED FOR CONSTRUCTION AS SOME ARCHITECTURAL, UTILITY OR OTHER ELEMENTS HAVE CHANGED. SEE PREVIOUS LANDSCAPE PLANS OR LANDSCAPE DETAILS FOR REFERENCES



MARVEL

140 HUDSON STREET, FLR 3, NEW YORK, NY 10013
212.693.0022

OWNER
THE MASTERS SCHOOL
15 CLINTON AVENUE
DOBSBERRY, NEW YORK 10522
TEL: 914.479.8433

PROJECT ARCHITECTS + LANDSCAPE ARCHITECT
MARVEL
140 HUDSON STREET, FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 212.693.0022

GEOTECHNICAL CONSULTING ENGINEER
WFP ENGINEERS & SURVEYORS, P.C.
ONE WASHINGTON SQUARE, SUITE 100
PLAZA OFFICE, NEW JERSEY 07102
TEL: 908.342.8522

STRUCTURAL ENGINEER
BURNS
315 OLD HEMP HILL ROAD
NEW YORK, NEW YORK 10015
TEL: 212.462.7979

Mechanical/Electrical/Plumbing ENGINEER
POLICE CONSULTING ENGINEERS, P.C.
110 WEST 19TH STREET
NEW YORK, NEW YORK 10011
TEL: 212.462.1100

VERTICAL TRANSPORTATION
VCA
140 WEST 60TH STREET, FLOOR 4
NEW YORK, NEW YORK 10019
TEL: 212.682.8888

AVIATION CONSULTANT
COMPTON ASSOCIATES, INC.
400 WEST 19TH AVENUE
NEW YORK, NEW YORK 10018
TEL: 212.693.3888


ACOUSTICS CONSULTANT
LSTN CONSULTANTS
70 BROADWAY STREET
NEW YORK, NEW YORK 10013
TEL: 212.462.1100

ENVIRONMENTAL CONSULTANT
WFP ENGINEERS
1 WESTERN STREET, FLOOR 14
NEW YORK, NEW YORK 10014
TEL: 212.462.8700


LIGHTING DESIGNER
DOT DASH LIGHTING DESIGN
100 WEST STREET, SUITE 400
NEW YORK, NEW YORK 10013
TEL: 212.462.8700

CODE AND ACCESSIBILITY CONSULTANT
COBE CONSULTANTS, INC.
140 PARK AVENUE, 8
NEW YORK, NEW YORK 10013
TEL: 212.467.4133

ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS, INC.
22 DENNIS ROAD
MORGANVILLE, NEW JERSEY 07971
TEL: 201.376.9700




02 WESTERN FACADE ELEVATION
SCALE: 1/4" = 1'-0"



01 EASTERN FACADE ELEVATION
SCALE: 1/4" = 1'-0"

REV	DATE	DESCRIPTION
1	09/20/2021	ISSUANCE OF DRAWING FOR PERMIT APPLICATION
2	08/12/2021	SITE APPLICATION REVISIONS
3	07/28/2021	SITE APPLICATION REVISIONS
4	06/03/2021	SITE APPLICATION SUBMISSION #02

09/20/2021




KEY PLAN NTS

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
49 CLINTON AVENUE
DOBSBERRY, NEW YORK 10522

SITE SECTIONS I

SCALE: AS NOTED



DRAWING #
L-610
07 of 10
DOB JOB -

GENERAL NOTES

RENDERED PLAN AND ELEVATIONS ARE ILLUSTRATIVE PURPOSES ONLY AND ARE NOT TO BE MEASURED OR EVALUATED FOR CONSTRUCTION AS SOME ARCHITECTURAL UTILITY OR OTHER ELEMENTS HAVE CHANGED. SEE PREVIOUS LANDSCAPE PLANS OR LANDSCAPE DETAILS FOR REFERENCES.



MARVEL


49 HOBSON STREET, FLR 3, NEW YORK, NY 10022
212 414 5402

- OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10022
TEL: 914 478 0402
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECT
MARVEL
87 MADISON STREET, FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 212 678 0402
- GEOTECHNICAL / CIVIL ENGINEER
MPS ENGINEERS & SURVEYORS, SPC
2700 CLINTON ROAD, SUITE 200
ROCKY HILL, NEW JERSEY 07866
TEL: 908 484 0002
- STRUCTURAL ENGINEER
BLM INC
12 OLD SWIP FLOOR 10
NEW YORK, NEW YORK 10005
TEL: 212 463 7470
- BUILDING SYSTEMS ENGINEER
POLICE CONSULTING ENGINEERS, SPC
101 WEST 107TH STREET
NEW YORK, NEW YORK 10019
TEL: 212 465 7802
- VERTICAL TRANSPORTATION
VTA
145 WEST 20TH STREET, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212 898 8900
- NY IT SECURITY CONSULTANT
COSENTINI ASSOCIATES, INC
800 PARK AVENUE, SUITE 1000
NEW YORK, NEW YORK 10018
TEL: 212 610 8800
- ACoustics CONSULTANT
L2M CONSULTANTS
18 BEAVER STREET 7
NEW YORK, NEW YORK 10003
TEL: 212 467 0810
- ENVELOPE CONSULTANT
MPS ENGINEERS
100 WEST 20TH STREET, FLOOR 14
NEW YORK, NEW YORK 10011
TEL: 212 898 8900
- LIGHTING CONSULTANT
DOT DASH LIGHTING DESIGN
102 ANKER STREET, SUITE 100
NEW YORK, NEW YORK 10013
TEL: 212 467 0800
- DOOR AND ACCESSIBILITY CONSULTANT
CORE CONSULTANTS, INC.
400 PARK AVENUE, 5
NEW YORK, NEW YORK 10018
TEL: 212 467 0550
- ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS, INC.
67 TOWNSEND ROAD
MORGANTOWN, NEW JERSEY 07171
TEL: 908 870 0700



- UNIT PAVERS @ 10MM LAYER (02) 1:750
- BOREHOLEMENT BRIDGE (07) 1:750
- CP CONCRETE (01) 1:750

05 NORTHERN FACADE ELEVATION
SCALE: 1/4" = 1'-0"



- UNIT PAVERS @ 10MM LAYER (02) 1:750
- CONCRETE STAIRS (05) 1:750
- ASPHALT PAVING (02) 1:750
- PRESERVE EXISTING LAWN WHERE APPLICABLE

04 SOUTHERN FACADE ELEVATION
SCALE: 1/4" = 1'-0"



- PRUNED TREE PLANTING (01) 1:750
- ASPHALT PAVING (02) 1:750
- CONCRETE STAIRS (05) 1:750
- UNIT PAVING (01) 1:750
- CONCRETE STAIR (05) 1:750
- BOREHOLEMENT PLANTING (04) 1:750
- STONE BENCH RETAINING WALL (08) 1:750

03 SECTION AT BUILDING ROOFLINE
SCALE: 1/4" = 1'-0"

REV	DATE	DESCRIPTION
1	02/17/2021	ISSUE OF DOORS PERMITS APPLICATION
2	06/10/2021	SM & APPLICATION REVISIONS
3	07/23/2021	SITE APPLICATION REVISIONS
4	08/02/2021	SITE APPLICATION REVISIONS

09/20/2021




KEY PLANS

2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10022

SITE SECTIONS II

SCALE: AS NOTED



DRAWING #
L-620
08 of 10
DOB JOB -

DOB STAMP ZONE



MARVEL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914 898 8800

OWNER:
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914 898 8800

PROJECT ARCHITECTS - LANDSCAPE ARCHITECT:
MARVEL
49 CLINTON AVENUE FLOOR 3
DOBBS FERRY, NEW YORK 10522

DESIGN CONSULTANT - CIVIL ENGINEER:
WFS ENGINEERS & SURVEYORS, INC.
200 WASHINGTON SQUARE
SOUTH PLAINFIELD, NEW JERSEY 07080
TEL: 908 882 8800

STRUCTURAL ENGINEER:
BLM INC.
3150 10TH FLOOR
NEW YORK, NEW YORK 10018
TEL: 212 693 7075

PAVING SYSTEMS ENGINEER:
POLAR CONSULTING ENGINEERS, P.C.
110 WEST 57TH STREET
NEW YORK, NEW YORK 10019
TEL: 212 647 6100

VERTICAL TRANSPORTATION
PKA
140 WEST 50TH STREET FLOOR 4
NEW YORK, NEW YORK 10020
TEL: 212 698 9000

AVIATION CONSULTANT:
CONCRETE ASSOCIATES, INC.
400 WEST 11TH STREET
NEW YORK, NEW YORK 10018
TEL: 212 698 8800

ACCESSIBILITY CONSULTANT:
LUNA CONSULTANTS
10 BELLER STREET
NEW YORK, NEW YORK 10008
TEL: 212 698 8800

ENVELOPE CONSULTANT:
BLM INC.
3150 10TH FLOOR
NEW YORK, NEW YORK 10018
TEL: 212 693 7075

INTERIORS DESIGN:
DOT LIGHTING DESIGN
100 WALKER STREET SUITE 400
NEW YORK, NEW YORK 10013
TEL: 212 698 8800

CODE AND ACCESSIBILITY CONSULTANT:
COBE CONSULTANTS, INC.
140 PARK AVENUE, 8
NEW YORK, NEW YORK 10018
TEL: 212 698 8800

ARCHITECTURAL SPECIFICATIONS:
CONSTRUCTION SPECIFICATIONS, INC.
22 THOMPSON ROAD
MORGANTHAU, NEW JERSEY 07975
TEL: 201 529 0000

REV.	DATE	DESCRIPTION
1	09/20/2021	ISSUANCE OF COMPLETION SITE APPLICATION
2	08/10/2021	SITE APPLICATION SUBMISSION
3	07/28/2021	SITE APPLICATION SUBMISSION
4	06/22/2021	SITE APPLICATION SUBMISSION
5	06/02/2021	SITE APPLICATION SUBMISSION

09/20/2021

KEY PLAN NTS

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522


TYPICAL DETAILS I

SCALE: AS NOTED


DRAWING #
L 700
09 of 10

DOB JOB: .


DOB STAMP ZONE



04 GRAVEL PAVING
SCALE: 1 1/2" = 1'-0"




03 DIP CONCRETE
SCALE: 1 1/2" = 1'-0"




02 ASPHALT PAVEMENT
SCALE: 1 1/2" = 1'-0"




01 UNIT PAVERS
SCALE: 1 1/2" = 1'-0"



05 CONCRETE STAIR
SCALE: 3/8" = 1'-0"




07 BIOWALK BOARDWALK
SCALE: 3/4" = 1'-0"




06 STEEL HANDRAIL (NOT IN THIS SUBMISSION)
SCALE: 1 1/2" = 1'-0"

- GENERAL NOTES:**
- REFER TO PLAN FOR STEP TREAD AND RISER QUANTITY AND DIMENSIONS.
 - SLOPE TREAD @ 1% MAX FOR DRAINAGE.
 - UNLESS NOTED OTHERWISE, STAIR FINISH SHALL BE A NON-SLIP HORIZONTAL BROOM FINISH.
 - ALL DIMENSIONS AND MATERIALS FOR STAIRS SHALL COMPLY WITH SECTIONS 504 AND 505 OF THE TRADE ACCESSIBILITY STANDARDS (MARCH 2003).
 - POSTS SHALL BE SURFACE MOUNTED, CORNER, BEEVELED OR SET IN POST FOOTERS. REFERENCE TECHNICAL SPECIFICATIONS AND/OR PROJECT SPECIFIC DETAIL FOR MOUNTING.


05 CONCRETE STAIR
SCALE: 3/8" = 1'-0"




08 STONE BENCH
SCALE: 3/4" = 1'-0"



10 STEEL EDGING
SCALE: 1 1/2" = 1'-0"



09 STONE GRAVEL COURSE
SCALE: 1 1/2" = 1'-0"



07 BIOWALK BOARDWALK
SCALE: 3/4" = 1'-0"


08 STONE BENCH
SCALE: 3/4" = 1'-0"




MARVEL

140 HUDSON STREET, FLA 3, NEW YORK, NY 10013
 822.84.8600


- OWNER
THE MASTERS SCHOOL
 141 EAST 10TH AVENUE
 DOBBS FERRY, NEW YORK 10522
 TEL: 914 478 8400
- PROJECT ARCHITECTS + LANDSCAPE ARCHITECT
MARVEL
 140 HUDSON STREET, FLOOR 3
 NEW YORK, NEW YORK 10013
 TEL: 212 478 8400
- DESIGN CONSULTANT / ENGINEER
MFE ENGINEERS & SURVEYORS, P.C.
 1700 PARK AVENUE, SUITE 100
 ELIZABETH, NEW JERSEY 07208
 TEL: 908 685 8000
- STRUCTURAL ENGINEER
BL/BL
 310 OLD NY 4TH FLOOR 10
 NEW YORK, NEW YORK 10014
 TEL: 212 438 7970
- BUILDING SYSTEMS ENGINEER
POLICE CONSULTING ENGINEERS, P.C.
 22 WEST 87TH STREET, SUITE 100
 NEW YORK, NEW YORK 10019
 TEL: 212 462 7100
- VERTICAL TRANSPORTATION
W&P WEST 40TH STREET, FLOOR 4
 NEW YORK, NEW YORK 10018
 TEL: 212 686 8000
- AV / IT SECURITY CONSULTANT
ESSENTIAL ASSOCIATES, INC.
 400 10TH AVENUE, SUITE 1000
 NEW YORK, NEW YORK 10018
 TEL: 212 475 9800
- ACCESSIBILITY CONSULTANT
L&M CONSULTANTS
 10 BRUCKER STREET
 NEW YORK, NEW YORK 10003
 TEL: 212 785 8900
- ENVELOPE CONSULTANT
BL/BL
 100 WEST 40TH STREET, FLOOR 4
 NEW YORK, NEW YORK 10018
 TEL: 212 686 8000
- LIGHTING DESIGNER
DOT LIGHTING DESIGN
 20 WALL STREET, SUITE 400
 NEW YORK, NEW YORK 10005
 TEL: 212 463 8000
- CODE AND ACCESSIBILITY CONSULTANT
CODE CONSULTANTS, INC.
 140 PARK AVENUE, 8TH
 NEW YORK, NEW YORK 10013
 TEL: 212 447 4033
- ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS, INC.
 27 FINEWOOD ROAD
 HIGHLANDVILLE, NEW JERSEY 07731
 TEL: 732 393 0000




04 SHRUB PLANTING
 SCALE: 3/4" = 1'-0"




02 TREE PROTECTION
 SCALE: 3/8" = 1'-0"



05 PERENNIAL PLANTING
 SCALE: 3/4" = 1'-0"



03 TREE AT GRADE
 SCALE: 3/4" = 1'-0"



01 EVERGREEN TREE PLANTING
 SCALE: 1/2" = 1'-0"

REV	DATE	DESCRIPTION
1	04/23/21	VILLAGE OF DOBBS FERRY SITE APPLICATION
2	06/17/21	SITE APPLICATION - RESUBMISSION
3	07/23/21	SITE APPLICATION - RESUBMISSION
4	08/20/21	SITE APPLICATION - SUBMISSION - NOT

09/20/2021

KEY PLAN NTS
 2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
 49 CLINTON AVENUE
 DOBBS FERRY, NEW YORK 10522

TYPICAL DETAILS II

SCALE: AS NOTED




DRAWING #
L 710
 10 of 10
 DOB JOB: -

DOB STAMP ZONE




MARVEL
145 HUDSON STREET, FLR 3 | NEW YORK, NY 10013
212.415.1010

- OWNER:**
THE MASTERS SCHOOL
45 CLINTON AVENUE
DOBBS FERRY, NY 10522
TEL 914 915 8400
- PROJECT ARCHITECTS + LANDSCAPE ARCHITECTS:**
MARVEL
100 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL 212 415 1010
- CLIENTS/ARCHITECTS/ENGINEERS:**
WFE ENGINEERS & SURVEYORS, SPC
2780 HANCOCK BOULEVARD
SCOTTS PLAZA, SUITE 100
NEW CANY, NY 10951
TEL 845 932 4811
- STRUCTURAL ENGINEER:**
DEKOR
32 GARDEN FLOOR 10
NEW YORK, NY 10003
TEL 212 675 7870
- BUILDING SYSTEMS ENGINEER:**
POL/BC CONSULTING ENGINEERS, SPC
133 AND ST 10 10 1/2 FLOOR
NEW YORK, NY 10011
TEL 212 462 1032
- MECHANICAL ENGINEER:**
VSA
100 WEST 30TH STREET, FLOOR 4
NEW YORK, NY 10001
TEL 212 682 8000
- MECHANICAL ENGINEER:**
AVI / SECURITY CONSULTANTS
600 WEST 42ND STREET, 4TH FLOOR
NEW YORK, NY 10018
TEL 212 675 3000
- MECHANICAL ENGINEER:**
LETA CONSULTANTS
100 WEST 30TH STREET
NEW YORK, NY 10001
TEL 212 675 3000
- MECHANICAL ENGINEER:**
EMWELLS CONSULTANTS
100 WEST 30TH STREET, FLOOR 14
NEW YORK, NY 10001
TEL 212 675 3000
- MECHANICAL ENGINEER:**
LOFT INCORPORATED
805 BANK LEVITT DESIGN
NEW BRUNSWICK, NJ 08851
NEW YORK, NY 10011
TEL 212 675 3000
- MECHANICAL ENGINEER:**
CODE AND ACCESSIBILITY CONSULTANTS
CODE CONSULTANTS, INC.
400 PARK AVENUE
NEW YORK, NY 10017
TEL 212 675 3000
- MECHANICAL ENGINEER:**
ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS, INC.
22 LEXINGTON ROAD
ROCKY HILL, CT 06151
TEL 781 870 0700



REV.	DATE	DESCRIPTION
1	02/11/2021	ISSUE FOR PERMIT
2	03/11/2021	AS APPLICATED
3	03/22/2021	AS APPLICATED
4	03/27/2021	AS APPLICATED
5	03/27/2021	AS APPLICATED
6	03/27/2021	AS APPLICATED

09/20/2021



KEY PLAN NTS

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
45 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

BASEMENT FLOOR PLAN

SCALE: 1/4" = 1'-0"

1 BASEMENT FLOOR PLAN
1/4" = 1'-0"

- LEGEND**
- 1/4" = 1'-0"
 - 1/4" = 1'-0"




DRAWING #:
A-100
of
DOB JOB -




MARVEL
49 CLINTON AVENUE, NEW YORK, NY 10122
212.674.4600

- CONTRACTOR:
- THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 974 474 8400
 - PROFESSIONAL ENGINEERS & ARCHITECTS:
 - MARVEL
100 WALL STREET, FLOOR 3
NEW YORK, NEW YORK 10038
TEL: 212 674 4600
 - GEORGE METCALI, LEAD ENGINEER
100 WALL STREET, FLOOR 3
NEW YORK, NEW YORK 10038
TEL: 212 674 4600
 - WFE ENGINEERS & ARCHITECTS, P.C.
2700 HANCOCK SQUARE
ROCKY HILL, CT 06154
TEL: 860 532 4622
 - STRUCTURAL ENGINEER:
 - REISER
50 WEST 57th STREET, FLOOR 10
NEW YORK, NEW YORK 10019
TEL: 212 633 7700
 - MECHANICAL ENGINEER:
 - POWERS CONSULTING ENGINEERS, P.C.
133 WEST 57th STREET
NEW YORK, NEW YORK 10019
TEL: 212 633 7700
 - ELECTRICAL ENGINEER:
 - VEITZ INC. ENGINEERING
100 WEST 57th STREET, FLOOR 8
NEW YORK, NEW YORK 10019
TEL: 212 633 7700
 - AV / IT CONSULTING CONSULTANT:
 - COMBENTRA ENGINEERS, INC.
400 WEST 111th STREET
NEW YORK, NEW YORK 10019
TEL: 212 633 7700
 - ACoustics CONSULTANT:
 - REISER CONSULTANTS
100 WEST 57th STREET
NEW YORK, NEW YORK 10019
TEL: 212 633 7700
 - ENVIRONMENTAL CONSULTANT:
 - WSP | PARSONS
100 WALL STREET, FLOOR 14
NEW YORK, NEW YORK 10038
TEL: 212 674 4600
 - LABORING CONTRACTOR:
 - BOYD BARRIS LABOR AND DESIGN
THE BRONX, NEW YORK 10460
TEL: 212 674 4600
 - CRANE AND ACCESSORY CONTRACTANT:
 - COOR CONSULTANTS, INC.
400 WEST 111th STREET
NEW YORK, NEW YORK 10019
TEL: 212 633 7700
 - MECHANICAL CONTRACTOR:
 - COMBENTRA ENGINEERS, INC.
400 WEST 111th STREET
NEW YORK, NEW YORK 10019
TEL: 212 633 7700



REV.	DATE	DESCRIPTION
1	07/20/21	ISSUE FOR PERMIT
2	08/20/21	ISSUE FOR PERMIT
3	07/20/21	ISSUE FOR PERMIT
4	08/20/21	ISSUE FOR PERMIT
5	08/20/21	ISSUE FOR PERMIT

09/20/2021



KEY PLAN NTS
2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

FIRST FLOOR PLAN

SCALE: As indicated

1 FIRST FLOOR PLAN
10-11-21

LEGEND

- 1/4" x 1/4" SQUARE
- 1/4" x 1/4" SQUARE

PLAN KEYNOTES

1. HAZARDOUS WASTE SHALL NOT BE DISPOSED OF IN BRUSH CANES, DUMPSTERS, SEPTIC SYSTEMS, DRAINAGE SYSTEMS, STORM DRAINAGE, OR IN ANY MANNER WHICH RESULTS IN POLLUTION OF LAND, BY EXPOSITION, NEUTRALIZATION, OILY, INCARCERATION AND/OR THROUGH ANY OTHER MEANS PROVIDED BY OR UNDER ANY LAW. ALL WASTE SHALL BE PROPERLY FIELD AND DISPOSED OF PER THE DEPARTMENT'S HAZARDOUS WASTE GUIDELINES, FOLLOWING THE VOLUME AND COURTESY GUIDELINES FOR PROPER ON-SITE DISPOSAL.
2. HAZARDOUS PRODUCTS AND WASTE ARE STORED WITHIN THE HAZARDOUS MATERIAL STORAGE CABINET PROVIDED AS PART OF THE CHINESE EQUIPMENT PACKAGE. CABINETS WILL BE LOCATED IN AREAS WHERE HAZARDOUS MATERIALS ARE USED OR WASTE IS GENERATED.
3. HAZARDOUS MATERIALS STORAGE CABINETS SHALL BE INSTALLED BLOCKING WITHIN WALLS REQUIRED TO PREVENT RE-ENTRY INTO VEHICULAR AREAS.



DRAWING #
A-101
of
DOB JOB




MARVEL
100 HUDSON STREET, FLOOR 3, NEW YORK, NY 10013
212.868.8800

- OWNER**
THE MASTERS SCHOOL
48 CLINTON AVENUE
DOBBS FERRY, NY 10522
TEL: 914.873.8400
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS**
MARVEL
100 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 212.868.8800
- CLIENT/OWNER/ CIVIL ENGINEER**
MPI ENGINEERS & SUPERVISOR, INC.
270 HAMILTON ROAD SUITE 400
ROSELAND, NY 10583
TEL: 914.382.4600
- STRUCTURAL ENGINEER**
SKIDMORE OWINGS & MERRILL LLP
30 FLEET STREET, FLOOR 10
NEW YORK, NY 10013
TEL: 212.868.7800
- Mechanical/Electrical/Plumbing**
FORNEY CONSULTING ENGINEERS, INC.
122 HILL ST. SUITE 100
NEW YORK, NY 10013
TEL: 212.868.1000
- MECHANICAL TRANSPORTATION**
VEA
100 HILL ST. SUITE 100 - FLOOR 4
NEW YORK, NY 10013
TEL: 212.868.1000
- SECURITY**
SECURITY CONSULTANT
CONSENT ASSOCIATES, INC.
400 SOUTH STREET
NEW YORK, NY 10013
TEL: 212.868.1000
- MECHANICAL CONSULTANT**
ALLEN CONSULTANTS
100 HILL STREET
NEW YORK, NY 10013
TEL: 212.868.1000
- MECHANICAL CONSULTANT**
MARVEL
100 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 212.868.8800
- MECHANICAL CONSULTANT**
CONSTRUCTION SPECIFICATIONS
22 HUNTINGTON ROAD
ROSELAND, NY 10583
TEL: 914.382.4600

REV.	DATE	DESCRIPTION
1	09/20/21	ISSUE FOR PERMIT
2	09/20/21	REVISED PER PERMIT
3	09/20/21	REVISED PER PERMIT
4	09/20/21	REVISED PER PERMIT
5	09/20/21	REVISED PER PERMIT

09/20/21




KEY PLAN NTS
2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
48 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

SECOND FLOOR PLAN

SCALE: As indicated

DRAWING #
A-102
of
DOB JOB



1 SECOND FLOOR PLAN
09.20.21

LEGEND

[Symbol]	1/2" HX 2" BARRIER
[Symbol]	3/4" HX 2" BARRIER

PLAN KEYNOTES

1. HAZARDOUS WASTE SHALL NOT BE DISPOSED OF IN TRASH CANIS, DUMPSTERS, REFRIG. OR FREEZERS, SHREDDERS, OR OTHER EQUIPMENT. HAZARDOUS WASTE SHALL BE STORED IN A CONTAINER WITH A PROPER LABEL AND DISPOSED OF THROUGH AN APPROPRIATE WASTE MANAGEMENT COMPANY. ALL HAZARDOUS WASTE SHALL BE PROPERLY LABELLED AND DISPOSED OF BY THE 203003 HAZARDOUS WASTE QUANTITIES FOLLOWING THE TOLLAGE AND CONSENTS COLLECTED FOR PROPER ON-SITE DISPOSAL.
2. FLAMMABLE LIQUIDS AND WASTE ARE STORED WITHIN THE FLAMMABLE MATERIAL STORAGE CABINET PROVIDED AS PART OF THE OWNER'S EQUIPMENT PACKAGE. CABINETS WILL BE LOCATED IN AREAS WHERE FLAMMABLE MATERIALS ARE USED OR WASTE IS GENERATED.
3. RACE AND ETHNICITY DATA AND OTHER DATA BLOCKING WITHIN SHALL BE REQUIRED TO BE COLLECTED IN ALL EMPLOYEE RECORDS.



DOB STAMP ZONE




MARVEL
140 HUDSON STREET, FLR 2, NEW YORK, NY 10013
125184202

- OWNER**
THE MASTERS SCHOOL
41 CLINTON AVENUE,
DOUGLASS FERRY, NEW YORK 10522
TEL: 845 348 8400
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS**
MARVEL
140 HUDSON STREET, FLOOR 2
NEW YORK, NEW YORK 10013
TEL: 212 465 1022
- DESIGN CONSULTANTS**
MECHANICAL ENGINEER
MFE ENGINEERS & ARCHITECTS, P.C.
2700 HANCOCK ROAD, SUITE 100
ROCKY HILL, CT 06865
TEL: 860 322 4422
- STRUCTURAL ENGINEER**
SKIDMORE, OWINGS & MERRILL LLP
300 MADISON AVENUE, FLOOR 10
NEW YORK, NEW YORK 10017
TEL: 212 512 2000
- BUILDING PHYSICAL ENGINEER**
POSSIBLE CONSULTING ENGINEERS, P.C.
120 WEST 30TH STREET
NEW YORK, NEW YORK 10011
TEL: 212 465 1022
- MECHANICAL ENGINEER**
180 EAST 90TH STREET, FLOOR 4
NEW YORK, NEW YORK 10011
TEL: 212 465 1022
- SECURITY CONSULTANT**
CORNERMAN ARCHITECTS, INC.
400 WEST 114th STREET
NEW YORK, NEW YORK 10028
TEL: 212 415 3600
- LEED CONSULTANT**
LEED CONSULTANTS, INC.
100 WEST 30TH STREET
NEW YORK, NEW YORK 10011
TEL: 212 465 1022
- ENVELOPE CONSULTANT**
ENVELOPE CONSULTANTS, INC.
100 WEST 30TH STREET, FLOOR 14
NEW YORK, NEW YORK 10011
TEL: 212 465 1022
- MECHANICAL DESIGN**
MECHANICAL DESIGN
100 WEST 30TH STREET, FLOOR 14
NEW YORK, NEW YORK 10011
TEL: 212 465 1022
- CODE AND ACCESSIBILITY CONSULTANT**
CODE CONSULTANTS, INC.
100 WEST 30TH STREET, FLOOR 14
NEW YORK, NEW YORK 10011
TEL: 212 465 1022
- ARCHITECTURAL SPECIFICATIONS**
CONSTRUCTION SPECIFICATIONS, INC.
22 LAMAR ROAD
MIDDLETOWN, NEW JERSEY 07940
TEL: 732 370 0700

REV	DATE	DESCRIPTION
1	02/11/2021	VILLAGE OF DOUGLASS FERRY S.U. APPLICATION
2	06/11/2021	S.U. APPLICATION RE-CORRECTION
3	07/22/2021	S.U. APPLICATION RE-CORRECTION
4	08/19/2021	S.U. APPLICATION RE-CORRECTION
5	09/20/2021	S.U. APPLICATION SUBMISSION REV.

09/20/2021



KEY PLAN INTS

2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER



49 CLINTON AVENUE,
DOUGLASS FERRY, NEW YORK 10522

THIRD FLOOR PLAN

SCALE: 1/4" = 1'-0"

DRAWING #:
A-103
of
DOB JOB: -

DOB STAMP ZONE



1 THIRD FLOOR PLAN
14" x 8"


LEGEND

- THRU WALL SAMPLE
- DRY WALL SAMPLE



MARVEL
140 HUDSON STREET, FLOOR 3, NEW YORK, NY 10013
212.476.8242

- OWNER:**
THE MASTERS SCHOOL
49 CLINTON AVENUE,
DOBBS FERRY, NY 10522
TEL: 914 875 1442
- PROJECT ARCHITECT:**
MARVEL
140 HUDSON STREET, FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 212 476 8242
- ARCHITECTURAL CONSULTANTS:**
MFE ENGINEERS & ARCHITECTS, INC.
270 HAVELock ROAD, LARKSPUR,
NEW YORK, NY 10521
TEL: 914 875 1442
- STRUCTURAL ENGINEER:**
SKIDMORE OWINGS & MERRILL LLP
100 WALL STREET, FLOOR 4
NEW YORK, NY 10038
TEL: 212 904 7000
- Mechanical Engineering:**
POLAR CONSULTING ENGINEERS, INC.
130 HALEY STREET, HELL
NEW YORK, NY 10011
TEL: 212 462 1022
- MECHANICAL ENGINEER:**
VISA
100 WALL STREET, FLOOR 4
NEW YORK, NY 10038
TEL: 212 904 7000
- SECURITY CONSULTANT:**
ECONOMY MANAGEMENT, INC.
400 FLEMING AVENUE
NEW YORK, NY 10018
TEL: 212 475 3000
- CONSULTANT:**
LEVIN CONSULTANTS
70 WALL STREET
NEW YORK, NY 10038
TEL: 212 904 7000
- LANDSCAPE CONSULTANT:**
MFE ENGINEERS & ARCHITECTS, INC.
140 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 212 476 8242
- MECHANICAL DESIGN:**
BOYD ENGINEERING DESIGN
100 HUNTERTON RD, SUITE 101
NEW YORK, NY 10011
TEL: 212 476 1000
- CONSULTANT:**
CODE CONSULTANTS, INC.
400 FLEMING AVENUE
NEW YORK, NY 10018
TEL: 212 476 3000
- ARCHITECTURAL CONSULTANTS:**
CONSTRUCTION OPERATIONS, INC.
23 LINDEN ROAD
MIDDLETOWN, NY 10941
TEL: 845 375 0700



REV	DATE	DESCRIPTION
1	09/20/2021	ISSUE FOR PERMIT
2	09/20/2021	REVISED PER PERMIT
3	07/20/2021	REVISED PER PERMIT
4	08/31/2021	REVISED PER PERMIT
5	09/20/2021	REVISED PER PERMIT

09/20/2021

KEY PLAN INTS

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

ROOF PLAN

SCALE: 1/4" = 1'-0"

1 ROOF PLAN
1/4" = 1'-0"

MATERIALS LEGEND

- CONC-01 ARCHITECTURAL CAST IN PLACE CONCRETE WITH FORMED-FINISH FINISH
- CR-01 BLACK ANODIZED ALUMINUM INSULATED CURTAIN WALL SYSTEM
- CR-02 BLACK ANODIZED ALUMINUM INSULATED PUNCHED WINDOW SYSTEM
- LV-01 ANODIZED ALUMINUM ARCHITECTURAL FINISH LUMBER TO BALCONY CURTAIN WALL SYSTEM
- MF-01 NATURAL FINISH ZINC HANDING SLAN FACADE CLADDING
- MF-02 NATURAL FINISH ZINC TRIM
- MF-03 ANODIZED ALUMINUM CLADDING OVER TOP OF STEEL FRAME STRUCTURE WITH WOOD PLANK MATERIAL UNDESIGNED
- MD-01 TOLUENE POLYMER MEMBRANE



DRAWING #
A-104
of
DOB JOB: -



MARVEL
148 HUDSON STREET, FLOOR 3, NEW YORK, NY 10013
312.874.8929

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914.479.9480

PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS
MARVEL
148 HUDSON STREET, FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 312.874.8929

CLIENTS (GENERAL CONTRACTOR)
MPC ENGINEERS & ARCHITECTS, P.C.
276 HANFORD BOULEVARD
ROCKY HILL, CONNECTICUT 06866
TEL: 860.462.4922

STRUCTURAL ENGINEER
BLUMAN
300 WEST 84th STREET, FLOOR 10
NEW YORK, NEW YORK 10024
TEL: 212.462.7875

MECHANICAL ENGINEER
POLARIS CONSULTING ENGINEERS, P.C.
125 HALEY STREET, SUITE 1
NEW YORK, NEW YORK 10011
TEL: 212.462.1028

ELECTRICAL ENGINEER
VEVA
NEW YORK, NEW YORK 10011, FLOOR 4
NEW YORK, NEW YORK 10021
TEL: 212.462.1028

ARCHITECTS (CONSULTANT)
1818 CONVENT LANE
NEW YORK, NEW YORK 10018
TEL: 212.462.3600


ENVIRONMENTAL ENGINEER
ENVIRONMENTAL ENGINEERS, P.C.
1818 CONVENT LANE
NEW YORK, NEW YORK 10018
TEL: 212.462.3600

MECHANICAL DESIGN
MECHANICAL DESIGN, LLC
NEW YORK, NEW YORK 10018
TEL: 212.462.3600


ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS
22 SUNNYSIDE ROAD
MIDWINTERVILLE, NEW YORK 12544
TEL: 518.476.0700

MATERIALS LEGEND

- (CONC-10)** ARCHITECTURAL CAST IN PLACE CONCRETE WITH BONDIC FORMBILT FINISH
- (CW-01)** BLACK ANODIZED ALUMINUM RIBBLED CURTAIN WALL SYSTEM
- (CW-02)** BLACK ANODIZED ALUMINUM RIBBLED FINANCIAL WINDOW SYSTEM
- (LVT)** ANODIZED ALUMINUM ARCHITECTURAL ELEMENT LOWER TO MATCH CURTAIN WALL SYSTEM
- (MT-01)** NATURAL FINISH ZINC STAINLESS STEEL FINANCE GLAZING
- (MT-02)** NATURAL FINISH ZINC STAINLESS STEEL FINANCE GLAZING
- (MT-03)** ANODIZED ALUMINUM GLAZING OVER TOP OF STEEL FRAME STRUCTURE WITH WOOD PANEL MATERIAL AT LINESHIELD
- (WD-01)** SOLID WOOD PLANK HORIZONTAL
- (W)** WINDOW TYPE




2 WEST ELEVATION
1/8" = 1'-0"



1 SOUTH ELEVATION
1/8" = 1'-0"

REV	DATE	DESCRIPTION
1	09/20/21	ISSUE TO OWNER FOR PERMIT
2	09/20/21	ISSUE TO ARCHITECT FOR PERMIT
3	09/20/21	ISSUE TO ARCHITECT FOR PERMIT
4	09/20/21	ISSUE TO ARCHITECT FOR PERMIT
5	09/20/21	ISSUE TO ARCHITECT FOR PERMIT

09/20/21



KEY PLAN NTS

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

BUILDING ELEVATIONS

SCALE: As indicated



DOB STAMP ZONE

DRAWING #
A-300
of
DOB JOB -



MARVEL
49 CLINTON AVENUE, FLOOR 3 NEW YORK, NY 10013
212.476.7424

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10022
TEL: 914 873.6400

PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS
MARVEL
NEW YORK OFFICE - FLOOR 3
NEW YORK, NY 10013
TEL: 212 476 7424

CLIENT/OWNER'S CIVIL ENGINEER
MFE ENGINEERS & SURVEYORS, EPC
270E HANNA, FORT LEE, NJ 07640
TEL: 201 261 1000

STRUCTURAL ENGINEER
BEAM
30 00 000 000 FLOOR 02
NEW YORK, NY 10022
TEL: 212 487 7000

BUILDING SYSTEMS ENGINEER
PDR INC CONSULTING ENGINEERS, EPC
122 W 45 ST 10TH FLOOR
NEW YORK, NY 10014
TEL: 212 476 1000

VERTICAL TRANSPORTATION
VEVA
140 WEST 81ST STREET - FLOOR 4
NEW YORK, NY 10024
TEL: 212 860 8000

FF+E/MECHANICAL CONSULTANT
CORNER ASSOCIATES, INC.
400 BROADWAY
NEW YORK, NY 10018
TEL: 212 675 8000

ACoustics CONSULTANT
LEVIN CONSULTANTS
70 WEST STREET
NEW YORK, NY 10025
TEL: 212 779 0000

LANDSCAPE CONSULTANT
WV BARK
1 WESTERLY STREET 1 - FLOOR 14
NEW YORK, NY 10024
TEL: 212 487 0000


LEAFY/PLANT DESIGNER
DOTS BARK LANDSCAPE DESIGN
140 HUNTSWAY BLDG 1215
NEW YORK, NY 10038
TEL: 212 261 0000

ENERGY AND WELL-BEING CONSULTANT
COOR CONSULTANTS, INC.
NEW YORK, NY 10014
TEL: 212 476 1000


ARCHITECTURAL SPECIFICATIONS
CONSTRUCTION SPECIFICATIONS, INC.
22 CLAYTON ROAD
MIDDLETOWN, NEW JERSEY 07951
TEL: 732 875 0000

MATERIALS LEGEND

- CONC-01** ARCHITECTURAL CAST IN PLACE CONCRETE WITH BOARD FORMED - FINISH
- CW-01** BLACK ANODIZED ALUMINUM INSULATED CURTAIN WALL SYSTEM
- CW-02** BLACK ANODIZED ALUMINUM INSULATED PLUMBED WINDOW SYSTEM
- LV-01** ANODIZED ALUMINUM ARCHITECTURAL LIGHTSIT LIGATURE FOR CURTAIN WALL SYSTEM
- MT-01** NATURAL FINISH ZINC STAINING SLAM WALL CLADDING
- MT-02** NATURAL FINISH ZINC STAINING
- MT-03** ANODIZED ALUMINUM CLADDING OVER TOP OF STEEL FRAME STRUCTURE WITH WOOD PLANK MATERIAL AT UNDERSE
- HD-01** SOLID WOOD PLANK MEMBERS
- WINDO-TYPE** WINDOW TYPE



2 NORTH ELEVATION
1/8" = 1'-0"



1 EAST ELEVATION
1/8" = 1'-0"

REV	DATE	DESCRIPTION
1	09/20/2021	ISSUANCE
2	09/20/2021	REVISION
3	09/20/2021	REVISION
4	09/20/2021	REVISION
5	09/20/2021	REVISION

09/20/2021

KEY PLAN NTS

2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10022

BUILDING ELEVATIONS

SCALE: As indicated




DRAWING #
A-301
of
DOB JOB -
DOB STAMP ZONE



MARVEL
49 HOBSON STREET, FL 8 | NEW YORK, NY 10013
212 678 4242

- OWNER
THE MASTERS SCHOOL
44 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10022
TEL: 212 473 8400
- PROJECT ARCHITECTS - 11 MANHATTAN ARCHITECTS
MARVEL
100 WOODLAWN STREET, FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 212 678 4242
- ARCHITECTURAL CONSULTANTS
M&E ENGINEERS & SURVEYORS, INC.
270 HAMILTON ROAD, FLOOR 2
DOVER TOWN CENTER, NEW JERSEY 07834
TEL: 908 222 4522
- STRUCTURAL ENGINEER
S&K
32 WEST 37TH STREET, 8TH FLOOR
NEW YORK, NEW YORK 10018
TEL: 212 462 7777
- BUILDING SYSTEMS CONSULTANTS
POLISE CONSULTING ENGINEERS, INC.
111 WOODS TOWN SQUARE
NEW YORK, NEW YORK 10017
TEL: 212 463 1000
- VERTICAL TRANSPORTATION
NSA
100 WEST 30TH STREET, FLOOR 4
NEW YORK, NEW YORK 10001
TEL: 212 368 8000
- MECHANICAL CONSULTANTS
DOUGLASS ASSOCIATES, INC.
400 WEST 42ND STREET
NEW YORK, NEW YORK 10018
TEL: 212 633 8000
- ELECTRICAL CONSULTANTS
L&K
180 WEST 42ND STREET, 10TH FLOOR
NEW YORK, NEW YORK 10018
TEL: 212 676 3811
- MECHANICAL CONSULTANTS
M&E ENGINEERS & SURVEYORS, INC.
270 HAMILTON ROAD, FLOOR 2
DOVER TOWN CENTER, NEW JERSEY 07834
TEL: 908 222 4522
- MECHANICAL CONSULTANTS
DOUGLASS ASSOCIATES, INC.
400 WEST 42ND STREET
NEW YORK, NEW YORK 10018
TEL: 212 633 8000
- MECHANICAL CONSULTANTS
DOUGLASS ASSOCIATES, INC.
400 WEST 42ND STREET
NEW YORK, NEW YORK 10018
TEL: 212 633 8000
- MECHANICAL CONSULTANTS
DOUGLASS ASSOCIATES, INC.
400 WEST 42ND STREET
NEW YORK, NEW YORK 10018
TEL: 212 633 8000



1 BUILDING SECTION - LONGITUDINAL - EAST SIDE

REV.	DATE	DESCRIPTION
1	5/18/2021	10% SCHEMATIC DEVELOPMENT
2	9/07/2021	SITE APPLICATION SUBMISSION
3	10/22/2021	SITE APPLICATION SUBMISSION
4	10/22/2021	SITE APPLICATION SUBMISSION
5	10/22/2021	SITE APPLICATION SUBMISSION

09/20/2021



KEY PLAN NTS
2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10022

BUILDING SECTIONS

SCALE: 1/4" = 1'-0"




DRAWING #
A-320
of _____
DOB JOB - _____
DOB STAMP ZONE



MARVEL
 160 HUDSON STREET, FL 3, NEW YORK, NY 10013
 212 696 8400


- OWNER
 THE MASTERS SCHOOL
 49 CLINTON AVENUE
 DOBBS FERRY, NEW YORK 10022
 TEL: 845 438 4800
- PROJECT ARCHITECTS / LANDSCAPE ARCHITECTS
 MARVEL
 160 HUDSON STREET, FLOOR 3
 NEW YORK, NEW YORK 10013
 TEL: 212 696 8400
- CLIENTS / CIVIL / CIVIL ENGINEER
 W&A ENGINEERS & SURVEYORS, INC.
 2780 HAVEN TOWN SQUARE
 SUITE 100, NEW JERSEY 07091
 TEL: 908 522 4522
- STRUCTURAL ENGINEER
 B&B
 100 SOUTH 111 STREET
 NEW YORK, NEW YORK 10005
 TEL: 212 482 7810
- BUILDING SYSTEMS CONSULTANTS
 POLSKA CONSULTING ENGINEERS, INC.
 100 HILL ST., 10TH FLOOR
 NEW YORK, NY 10002
 TEL: 212 696 8400
- MECHANICAL ENGINEER
 NEW YORK TRANSPORTATION
 100 HILL STREET, FLOOR 4
 NEW YORK, NEW YORK 10002
 TEL: 212 696 8400
- AV. / F. SECURITY CONSULTANT
 SECURITY ASSOCIATES, INC.
 400 WEST 42ND STREET
 NEW YORK, NY 10018
 TEL: 212 696 8400
- ACoustics CONSULTANT
 LEVIN CONSULTANTS
 180 WEST STREET
 NEW YORK, NEW YORK 10005
 TEL: 212 696 8400
- ENVIRONMENTAL CONSULTANT
 W&A ENGINEERS
 100 HILL STREET, FLOOR 4
 NEW YORK, NEW YORK 10002
 TEL: 212 696 8400
- LIGHTING DESIGNER
 SOLO DESIGN LIGHTING DESIGN
 100 HILL STREET, 10TH FLOOR
 NEW YORK, NEW YORK 10002
 TEL: 212 696 8400
- CONSTRUCTION SPECIFICATIONS
 CONSTRUCTION SPECIFICATIONS, INC.
 20 FRANKLIN ROAD
 MIDDLETOWN, NEW JERSEY 07940
 TEL: 908 839 8700



1 BUILDING SECTION - CROSS
 1/4" = 1'-0"

REV.	DATE	DESCRIPTION
1	07/10/21	SUBMIT OF DOBBS FERRY SITE APPLICATION
2	06/10/21	SITE APPLICATION SUBMISSION
3	05/03/21	SITE APPLICATION SUBMISSION
4	04/10/21	SITE APPLICATION SUBMISSION
5	03/02/21	SITE APPLICATION SUBMISSION

09/20/2021



KEY PLAN NTS
 2029
**THE MASTERS SCHOOL
 INNOVATION AND
 ENTREPRENEURSHIP
 CENTER**
 49 CLINTON AVENUE
 DOBBS FERRY, NEW YORK 10022

BUILDING SECTIONS

SCALE: 1/4" = 1'-0"




DRAWING #
A-321

DOB JOB: -



MARVEL
143 HUDSON STREET, FLR 3, NEW YORK, NY 10013
212.818.8423

- OWNER**
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522
TEL: 914.478.8408
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS**
MARVEL
133 HUDSON STREET, FLOOR 3
NEW YORK, NEW YORK 10013
TEL: 212.818.8423
- 2D/3D LOGICAL / CIVIL ENGINEER**
RFB ENGINEERS & SURVEYORS, P.C.
230 PLAZA FOR ECOSYSTEMS
50 JOHN F. LAWFIELD, NEW JERSEY 07960
TEL: 609.387.6027
- STRUCTURAL ENGINEER**
S&B INC.
32 E. 22ND ST., FLOOR 10
NEW YORK, NEW YORK 10005
TEL: 212.870.7810
- MECHANICAL SYSTEMS ENGINEER**
FOLBE CONSULTING ENGINEERS, P.C.
111 WEST 37TH STREET
NEW YORK, NEW YORK 10018
TEL: 212.875.1022
- VERTICAL TRANSPORTATION**
VGA
100 WEST 30TH STREET, FLOOR 4
NEW YORK, NEW YORK 10021
TEL: 212.368.8900
- AV / IT / SECURITY CONSULTANT**
CORRENTIA ASSOCIATES, INC.
481 BROADWAY, 8TH FLOOR
NEW YORK, NEW YORK 10013
TEL: 212.815.3800
- ACoustics CONSULTANT**
LERN CONSULTANTS
19 BROADWAY STREET
NEW YORK, NEW YORK 10005
TEL: 212.788.2410
- ENVIRONMENTAL CONSULTANT**
RFB ENGINEERS
133 HUDSON STREET, FLOOR 14
NEW YORK, NEW YORK 10014
TEL: 212.818.8423
- LIGHTING ENGINEER**
DOE DESIGN LIGHTING DESIGN
100 BROADWAY, SUITE 1715
NEW YORK, NEW YORK 10005
TEL: 212.811.0868
- CODE AND ACCESSIBILITY CONSULTANT**
CODE CONSULTANTS, INC.
481 BROADWAY, SUITE 8
NEW YORK, NEW YORK 10013
TEL: 212.447.4223
- MECHANICAL AND SPECIFICATIONS**
CONSTRUCTION SPECIFICATIONS, INC.
27 EMERSON ROAD
MORRISTOWN, NEW JERSEY 07960
TEL: 908.875.0728



REV	DATE	DESCRIPTION
1	04/10/21	VILLAGE OF DOBBS FERRY SITE APPLICATION
2	06/10/21	SITE APPLICATION REVISIONS
3	07/20/21	SITE APPLICATION REVISIONS
4	09/20/21	SITE APPLICATION SUBMISSION 107

09/20/2021



KEY PLAN: NTS

2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

LANDSCAPE LIGHTING PLAN

SCALE: 3/32" = 1'-0"


DRAWING #
LC-010
of
DOB JOB -

DOB STAMP ZONE



MARVEL
49 CLINTON AVENUE, DOBBS FERRY, NEW YORK, NY 10522


- CONTRACTOR: THE MASTERS SCHOOL, 49 CLINTON AVENUE, DOBBS FERRY, NEW YORK, NY 10522
- DESIGNER: MARVEL, 49 CLINTON AVENUE, DOBBS FERRY, NEW YORK, NY 10522
- DATE: 09/20/2021
- PROJECT: EXTERIOR LIGHTING PLAN (NTS)
- SCALE: 3/32" = 1'-0"
- PROJECT NO: 2021-001
- DATE: 09/20/2021
- PROJECT: EXTERIOR LIGHTING PLAN (NTS)
- SCALE: 3/32" = 1'-0"
- PROJECT NO: 2021-001
- DATE: 09/20/2021




EXTERIOR LIGHTING PLAN (NTS)
ALL EXTERIOR LIGHTING SHALL COMPLY WITH THE GENERAL STANDARDS AND MAXIMUM LIGHT LEVELS PER SECTION 900.41 OF THE ZONING CODE

REV	DATE	DESCRIPTION
1	09/20/2021	ISSUE FOR PERMITTING
2	09/20/2021	ISSUE FOR PERMITTING
3	09/20/2021	ISSUE FOR PERMITTING
4	09/20/2021	ISSUE FOR PERMITTING


09/20/2021




TYPE LJ CANOPY DOWNLIGHT



TYPE XA BOLLARD



TYPE XB AREA LIGHT



TYPE XC TREE STRAP MOONLIGHT



KEY PLANS NTS
2029
THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER
49 CLINTON AVENUE, DOBBS FERRY, NEW YORK, NY 10522

LANDSCAPE LIGHTING PHOTOMETRIC PLAN

SCALE: 3/32" = 1'-0"

DRAWING # **LC-011**
of
DOB JOB



Stormwater Pollution Prevention Plan (SWPPP)

The Masters School
Innovation and Entrepreneurship Center

Dobbs Ferry, New York



Gonzalo M. Trenosky, PE, LEED AP
Associate Engineer

PREPARED FOR:

Ms. Jennifer Olson, AIA, LEED AP
MARVEL
145 Hudson Street
New York, NY 10013

PREPARED BY:

MFS Consulting Engineers & Surveyor, DPC
320 Fifth Avenue, Suite 1102
New York, NY 10001

T: (908) 922-4622

F: (866) 517-7413

Issued for Board of Trustees Sept. 17, 2021 - Last Rev. Sept. 7, 2021
MFS Project No. 1120062

TABLE OF CONTENTS

EXECUTIVE SUMMARY	3
SITE OWNER	3
CONSTRUCTION MANAGER/OPERATOR	3
SWPPP DEVELOPMENT, REVIEW, AND UPDATE	4
SWPPP DEVELOPMENT	4
SWPPP REVIEW	4
SWPPP UPDATE	4
EXISTING CONDITIONS.....	5
PROPERTY INFORMATION.....	5
EXISTING SITE DESCRIPTION	5
EXISTING UTILITIES	6
EXISTING SOIL CONDITIONS.....	6
PROPOSED CONDITIONS.....	6
BUILDING & ACCESS	6
UTILITIES	7
GRADING & DRAINAGE	7
STORMWATER MANAGEMENT	8
TABULAR SUMMARY OF STORMWATER RUNOFF CONDITIONS.....	8
SIX STEP PROCESS FOR STORMWATER SITE PLANNING AND PRACTICES SELECTION	9
CHANNEL PROTECTION VOLUME (CPV)	10
OVERBANK FLOOD CONTROL (QP)	10
EXTREME FLOOD CONTROL (QF).....	11
SOIL EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION.....	11
SOIL EROSION AND SEDIMENT CONTROL PRACTICES.....	11
CONSTRUCTION SCHEDULE.....	12
STAGING AREAS.....	12
VEGETATIVE PLAN	12
MAINTENANCE PROGRAM	14
NON-STORMWATER DISCHARGES	15
STORAGE PRACTICES	16
SPILL PREVENTION PRACTICES	16
SPILL CONTROL PRACTICES	17
INSPECTION DURING CONSTRUCTION	18
SPDES GENERAL REQUIREMENTS AND GUIDELINES.....	18
WINTER CONDITIONS.....	20
CERTIFICATIONS AND FORMS	20

New Jersey

2780 Hamilton Blvd.
 South Plainfield, NJ 07080

Phone 908 922 4622
 Fax 866 517 7413

New York

320 Fifth Avenue, Suite 1102
 New York, NY 10001

Phone 212 943 6576
 Fax 866 517 7413

Puerto Rico

103 C/Isabel Andreu de Aguilar, Suite 3
 San Juan, PR 00918

Phone 787 765 2584
 Fax 787 765 3691

RETENTION OF RECORDS	21
REFERENCES.....	21
APPENDIX A: NOTICE OF INTENT	22
APPENDIX B: SOIL REPORT	23
APPENDIX C: INFILTRATION TESTS SECTION FROM MFS GEOTECHNICAL REPORT	24
APPENDIX D: NYS DEC CRITICAL ENVIRONMENTAL AREAS MAP	25
APPENDIX E: DRAWINGS.....	26
APPENDIX F: POST CONSTRUCTION INSPECTION AND MAINTENANCE CHECKLIST	27
APPENDIX G: SUPPORTING CALCULATIONS	28
APPENDIX H: PRE-CONSTRUCTION DOCUMENTS & CERTIFICATIONS	29
PRE-CONSTRUCTION DOCUMENTS	30
PRE-CONSTRUCTION CERTIFICATIONS.....	32
APPENDIX I: CONSTRUCTION DURATION INSPECTIONS	34
CONSTRUCTION DURATION INSPECTIONS	35
CONSTRUCTION DURATION INSPECTIONS - MODIFICATIONS	41
APPENDIX J: MONTHLY SUMMARY OF SITE INSPECTION ACTIVITIES.....	42
MONTHLY SUMMARY OF SITE INSPECTION ACTIVITIES	43
APPENDIX K: CONTRACTOR’S CERTIFICATIONS AND FORMS.....	44
CONTRACTOR’S CERTIFICATION STATEMENT	45
SUB-CONTRACTOR’S CERTIFICATION STATEMENT	46
CERTIFICATE OF ISSUANCE.....	47
EROSION AND WATER QUALITY CONTROL IDENTIFICATION	48
CONSTRUCTION STABILIZATION	49
CERTIFICATE OF CHANGE BY CONTRACTOR	50
APPENDIX L: END OF CONSTRUCTION DOCUMENTS	51
FINAL STABILIZATION AND RETENTION OF RECORDS	52
CERTIFICATE OF RETURN.....	53
APPENDIX M: EROSION AND SEDIMENT CONTROL MATERIAL SPECS.....	54
ADS STORMTECH MC-3500™ CHAMBER INFORMATION SHEET	54
ADS STORMTECH MC-3500™ CHAMBER DESIGN MANUAL	54
ADS STORMTECH MC-3500™ CHAMBER CONSTRUCTION GUIDE.....	54

EXECUTIVE SUMMARY

This Stormwater Pollution Prevention Plan (SWPPP) has been prepared for the construction of the proposed site development at 49 Clinton Avenue (The Masters School Innovation and Entrepreneurship Center), a 96-acre college preparatory campus in the village of Dobbs Ferry, Westchester County, New York.

As described in Appendix B, Table 2 of the NYSDEC SPDES General Permit for Stormwater Discharges from Construction Activities (Permit No. GP-01-20-001), this SWPPP will include Cost-Construction Stormwater Management Practices.

The SWPPP describes practices and procedures required to prevent pollutants from entering the waters of the United States via stormwater runoff. The stormwater management design and erosion control plan for the project were prepared using criteria established in the New York State Standards and Specifications for Erosion and Sediment Control.

SITE OWNER

Owner

The Masters School
49 Clinton Avenue
Dobbs Ferry, NY 10522

Contact

Seth Marx
Director of Institutional Advancement
The Masters School
49 Clinton Avenue
Dobbs Ferry, NY 10522
+1 (914)-479-6527
seth.marx@mastersny.org

CONSTRUCTION MANAGER/OPERATOR

The construction manager for the construction activities is responsible to install and maintain all stormwater pollution prevention measures proposed in the plan.

Construction Manager

Yorke Construction Corporation
140 West 31st Street, 4th Floor
New York, NY 10001
+1 (212)-564-8467

Contact

Artie Pearsall
Project Manager
Yorke Construction Corporation
140 West 31st Street, 4th Floor
New York, NY 10001
+1 (212)-564-8467 ext. 117 (Office)
+1 (917)-817-5478 (Cell)
artie@yorkeconstruction.com

SWPPP DEVELOPMENT, REVIEW, AND UPDATE

SWPPP DEVELOPMENT

This SWPPP was developed in accordance with accepted engineering practices and provides the following:

- Offers protective measures to minimize sediment transport during construction activities.
- Describes the implementation of control measures that are to be used to reduce pollutant loadings from stormwater runoff during construction activities.
- Identifies potential sources of stormwater pollution from the construction site.

SWPPP REVIEW

This SWPPP will be kept on-site and will be made available for review by the designer, construction manager, subcontractors, and applicable federal, state, and local regulatory agencies that have jurisdiction over the construction site. If necessary, any of these regulatory agencies may notify the owner that the SWPPP is not in compliance with required regulations. If the SWPPP is in need of revision, the construction manager of the project will make the required revisions to the SWPPP within 7 days of notification by the regulatory agency. In addition, the construction manager will submit a written certification that the revisions have been made and will be implemented.

SWPPP UPDATE

When deemed necessary, the owner or construction manager may amend this SWPPP by making a change in design, construction, operations, maintenance, or other item that has an effect on the potential for discharge of pollutants from stormwater runoff associated with the construction activities. Amendment of the SWPPP by the owner or construction manager may also be deemed necessary under the following conditions:

- Field conditions render the erosion and sediment control measures to be ineffective in minimizing pollutants from stormwater discharges.
- To identify a new contractor that will implement any measure of the SWPPP.

The revised SWPPP should be marked as such with the revision date and shall be distributed by the owner or construction manager to the relevant parties.

EXISTING CONDITIONS

PROPERTY INFORMATION

The Masters School campus is presently comprised of several parcels. The proposed improvements (“Project Site”) are located within Dobbs Ferry Parcel ID 3.90-66-1, which is bounded as listed below.

- To the north, by Dobbs Ferry Parcel ID 3.80-47-4.
- To the west, by private property (including Dobbs Ferry Parcel ID 3.80-46-3, 3.80-46-2 and 3.80-46-1) and Clinton Avenue.
- To the south, by Dobbs Ferry Parcel ID 3.120-111-1 and 3.171-153-5.
- To the east, by private property (including Dobbs Ferry Parcel ID 3.90-56-5, 3.90-56-6, 3.90-56-7, 3.90-56-8, 3.90-56-9, 3.90-63-5, 3.90-63-6, 3.90-63-7, 3.90-63-8, 3.90-63-9, 3.90-63-10, 3.90-63-11 and 3.90-63-12) and Estherwood Avenue.

The project site area that will be disturbed by the proposed improvements is approximately 0.83 acres. The site receives minimal tributary waters and is tributary to the Hudson River. It has been determined through site investigations performed by a licensed professional engineer of the State of New York that no surface waters or wetlands are present at the site.

The project site is not located in a Critical Environmental Area (CEA), per the New York State Department of Environmental Conservation Westchester County. A copy of the map is included with this submission for your reference.

EXISTING SITE DESCRIPTION

The project site is primarily grassed lawn, with the following neighboring existing features.

- Athletic Field for Softball, Soccer and Shot-Put
- Athletic Field Accessories (inc. fencing, benches, metal storage containers and net cages)
- Thirty-three (33) parking spaces
- Landscaping

A survey dated January 17, 2021, and prepared by Kenneth B. Salzman, Land Surveyor is included for your reference.

The site topography generally slopes from south to north with a man-made steep-sloped area (20% - 28% grade) to accommodate the softball outfield along the west side of the project site and gentle slopes (4%-7% grade) within the remainder of the project site.

EXISTING UTILITIES

The site has the following existing subsurface utilities.

- Steam & return service lines
- Water valves & service lines (incl. abandoned)
- Electrical manholes & service lines
- Telecommunications manholes & service lines
- Sanitary sewer manholes & service lines
- Gas service lines (incl. abandoned)
- Fire hydrant

EXISTING SOIL CONDITIONS

Based on the Web Soil Survey by the Natural Resources Conservation Society, soils at the site are generally described as Paxton fine sandy loam (± 0.83 acres) encompassing the entire area. The Paxton fine sandy loam (PnB) has a hydrologic soil group designation of 'C.' A 'C' classification is defined as a material with the moderately high runoff potential and low infiltration rates. Infiltration tests performed in the location of proposed stormwater management confirm that the soils have suitable infiltration rates for management practices, see Appendix.

The Soil Survey Map is included with this submission for your reference.

PROPOSED CONDITIONS

Proposed improvements for the project site include construction a new two-story 6,080-sf academic building with two (2) entrance paver patios, site walkways, driveway, and ADA-accessible parking spaces; along with associated utilities including one (1) new transformer with concrete pad, one (1) new emergency generator with concrete pad, condensing units with concrete pad, and necessary relocation and/or realigned of existing utilities; site regrading, landscaping, bioretention, underground stormwater management chambers, and associated structures and piping. Site regrading is proposed where necessary for drainage and aesthetic purposes.

A more detailed explanation of the proposed site improvements is listed below. The work is categorized by the type of site features proposed for the project site within the limits of disturbance: Building & Access, Utilities, and Grading & Drainage.

BUILDING & ACCESS

Innovation & Entrepreneurship Center (IEC)

The proposed two-story building will be bounded by a footprint of approximately 6,080 square feet. Two (2) proposed paver patios will serve as access to the IEC building at the north and south entrances. A proposed asphalt walkway will encompass the perimeter of the IEC building and paver patios in order to provide ADA-compliant pedestrian access from Cochrane Avenue.

UTILITIES

Relocated Utilities

- Steam & Condensate Return – to be rerouted along the western side of the project site, between the proposed IEC Building and the western asphalt walkway.
- Sanitary Sewer – to be rerouted along the western side of the project site, from the existing manhole adjacent to the southern proposed paver patio to the existing manhole within the proposed northern patio area. Two (2) sanitary sewer manhole are proposed at the northern end of the building within the landscaping. Additionally, one (1) existing sanitary sewer service from the eastern side of the property will be relocated around the northeastern area of proposed development and tied into the existing sanitary line to the north.
- Water – to be realigned along the western side of the project site and run north, parallel to the western face of the proposed IEC building. One (1) proposed 3-inch domestic service and one (1) proposed 6-inch fire service lines are to run from the realigned service line to the southwestern corner of the IEC building.
- Electrical – to be realigned along the western side of the project site, from the existing manhole adjacent to the southern proposed paver patio, around the perimeter of the proposed IEC building, to the existing electrical manhole at the northern end of the site. Additionally, one (1) proposed electrical connection will be installed to provide service from the proposed emergency generator at the northern end of the project site to the northern face of the IEC building. Furthermore, one (1) proposed electrical connection will be installed to provide service from the proposed transformer at the southern end of the project site to the eastern face of the IEC building.
- Telecommunications – to be rerouted along the western side of the project site, from the existing manhole adjacent to the southern proposed paver patio to the existing manhole in the landscaped area at the northern end of the project site.
- Gas – to be realigned at a point from the western side of the project site to a point on the existing gas service line at the northern end of the project site.

GRADING & DRAINAGE

Stormwater Chambers

One (1) proposed ADS Stormtech stormwater infiltration chamber system below the northern paver patio will serve as the project site's stormwater detention facility. The chamber system will feature fourteen (14) infiltration chambers, with a mandatory isolation row for maintenance.

Additionally, underdrains are to be installed within the proposed bioretention area at the northern end of the project site. All stormwater from the proposed IEC building and bioretention area will collect via underground pipe to the proposed infiltration chamber system. The chamber system will include two (2) manhole structures; one (1) for all stormwater entering, and one (1) for all stormwater conveyed out to the existing corner curb inlet, east of the project site.

STORMWATER MANAGEMENT

The following information details the stormwater management systems designed to collect and infiltrate stormwater from the proposed impervious areas. Regrading is proposed to promote overland flow and minimize channeling while maintaining existing drainage courses.

Existing drainage patterns convey a tributary area of approximately 1.0 acres to the new building area, and is graded to generally split drainage between two drainage areas. Drainage area one flows overland towards the Carriage House and ultimately splits between flow into the wooded area east of the House, and flow along the circulation road towards the track and Estherwood Avenue. Drainage area two overland to a catch basin in the parking area just north of the Middle School, ultimately being conveyed via pipes to precast drywells in the adjacent lawn. Refer to Existing Drainage Area Map, attached.

Proposed drainage pattern conveys to the extent practicable a tributary area of approximately 1.19 acres, with site drainage being routed to the on-site bioretention basin, and roof drainage routed into the proposed subgrade stormwater chambers. Refer to Proposed Drainage Area Map, attached.

TABULAR SUMMARY OF STORMWATER RUNOFF CONDITIONS

PRE VS POST STORMWATER RUNOFF RATES AND VOLUMES		
	PRE <i>Node: Pre-Existing Composite</i>	POST <i>Node: 7L Composite</i>
1-YR RAINFALL = 2.93 INCHES (Type III 24-hr)		
FLOW	0.99 CFS	0.00 CFS
VOLUME	0.078 AF	0.000 AF
10-YR RAINFALL = 5.53 INCHES (Type III 24-hr)		
FLOW	3.51 CFS	2.66 CFS
VOLUME	0.258 AF	0.153 AF
25-YR RAINFALL = 6.75 INCHES (Type III 24-hr)		
FLOW	4.81 CFS	3.97 CFS
VOLUME	0.355 AF	0.247 AF
100-YR RAINFALL = 8.63 INCHES (Type III 24-hr)		
FLOW	6.88 CFS	6.64 CFS
VOLUME	0.512 AF	0.404 AF

SIX STEP PROCESS FOR STORMWATER SITE PLANNING AND PRACTICES SELECTION

The NYS Stormwater Management Design Manual (SMDM) requires a six-step process to integrated site planning, green infrastructure, and stormwater management practices.

1. Site Planning

Reduction of impervious cover, preservation of natural areas...

Preservation of Natural Resources

- **Locating Development in Less Sensitive Areas**

This project is designed to avoid sensitive resource areas such as nearby mature forests and critical habitats by locating development to fit within unused grass lawn.

- **Reduction of Clearing & Grading**

This project is design within a compact footprint for all necessary foundations, utility relocations, site utilities, and stormwater management design.

Reduction of impervious coverage includes:

- **Roadway Reduction**

This project is designed within an existing campus and requires no new roadway for access, although a small driveway is provided for maintenance access.

- **Building Footprint Reduction**

This project is designed within a compact footprint and low elevation-view exposure by nestling into a slope and incorporating a cellar level.

2. Calculate initial required Water Quality Volume for the site.

$$P = 1.5 \text{ in}$$

$$A = 1.19 \text{ ac}$$

$$A_i = 0.28^* \text{ ac}^* \text{ *This reflects a reduction of 100sf per tree (24 trees proposed)}$$

$$I = 24 \%$$

$$R_v = 0.262$$

$$WQ_v = 0.0389 \text{ af}$$

$$1696 \text{ cf}$$

3. Runoff Reduction Volume (RRv)

Provide Runoff Reduction by incorporating green infrastructure techniques and standard stormwater management practices (SMP) with Runoff Reduction Volume (RRv) capacity.

The full WQv of 1,696-cf is proposed for infiltration through green infrastructure and standard SWPs, which are capable of infiltrating 3,474-cf.

4. Calculate minimum RRv required.

The full WQv of 1,696-cf is proposed for infiltration through green infrastructure and standard SWPs, which are capable of infiltrating 3,474-cf.

5. Provide standard SMPs

Provide standard SMPs to treat remaining portion of water quality volume (WQv) not addressed by green infrastructure and standard SMPs with RRv capacity.

Bioretention infiltration and underground detention chambers are proposed for stormwater infiltration of the WQv.

6. Provide volume and peak rate control practices where required.

Underground detention chambers and restricted-flow outlet control structure are proposed for peak and volume reduction of 1-, 10-, and 100-year storms.

CHANNEL PROTECTION VOLUME (CPV)

The CPv criteria is intended to protect stream banks from erosion, and will be demonstrated by provided 24 hour extended detention of the Type III 1-year, 24-hour storm event. The CPv requirement does not apply in certain conditions, including where Reduction of the entire CPv volume is achieved at a site through green infrastructure or infiltration.

This project proposes infiltration of the entire CPv (3,412-cf) via the bioretention infiltration and the underground infiltration chambers, which are capable of infiltrating 3,474-cf of stormwater.

P = 2.93" Q = 1.32" CN = 81 Tc = 9.1min A = 1.19ac qu = 550csm/in qo/qi = 0.04

OVERBANK FLOOD CONTROL (QP)

The Qp criteria is intended to prevent and increase in frequency and magnitude of out-of-bank flooding generated by new development, and will be demonstrated by attenuating the Type III 10-year, 24-hour peak discharge rate to pre-development conditions.

This project achieves attenuation of the Type III 10-year, 24-hour peak discharge rate to pre-development conditions.

Qpre = 3.51 cfs Qpost = 2.66 cfs

EXTREME FLOOD CONTROL (QF)

The Qf criteria is intended to prevent the increased risk of flood damage from large storm events, maintain the boundaries of pre-development conditions, and protect the physical integrity of stormwater management practices. It will be demonstrated by attenuating the Type III 100-year, 24-hour peak discharge rate to pre-development conditions.

This project achieves attenuation of the Type III 100-year, 24-hour peak discharge rate to pre-development conditions.

Qpre = 6.88 cfs **Qpost = 6.64 cfs**

SOIL EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION

Temporary soil erosion and sediment control measures have been applied to this site to minimize the amount of sediment carried by stormwater runoff and truck hauling during construction activities. The soil erosion and sediment control measures have been designed in accordance with the New York State Standards and Specifications for Erosion and Sediment Control (July 2016). The following summarizes the planned soil erosion and sediment control practices as shown on Sheet C-400.

SOIL EROSION AND SEDIMENT CONTROL PRACTICES

- Silt Fence: Silt fence shall be installed around topsoil stockpile area.
- Surface Stabilization: Surface stabilization will be accomplished with vegetation and mulch. Roadway and building base courses will be installed as soon as finished grade is reached.
- Inlet Protection: Inlet protection shall be installed at all stormwater inlets receiving runoff from disturbed areas of the site.
- Temporary Tree Protection: Where applicable, 6.0-foot-high protective fence will be erected around the dripline of trees that are to remain to prevent damage during construction.
- Stabilized Construction Entrance: A temporary stabilized construction entrance shall be installed for access to and from the construction site. Wash-down water and runoff from the construction entrance shall be directed to the appropriate soil erosion and sediment control measures.
- Staging and Laydown Areas: Staging and laydown areas for vehicles and equipment shall be located on stabilized portions of the site. Vehicles and equipment shall be washed down in stabilized areas prior to exiting the site.
- Dust Control: Should excessive dust be generated; it shall be controlled by sprinkling.

- Erosion Control Blanket: Temporary biodegradable erosion control blankets will be installed along the disturbed steep-slope areas. Install per manufacturer's specification.
- Grading: The maximum created slope is limited to 2' horizontal to 1' vertical. Refer to the Grading Plan (Sheet C-600) for details of design slopes.

CONSTRUCTION SCHEDULE

This construction schedule has been prepared to clearly outline the construction and the implementation of the soil erosion and sediment control measures.

1. Obtain all required village, town, city, county, state, and federal permits, and approvals prior to commencing earthwork.
2. Install erosion and sediment perimeter controls, such as construction fence and stabilized construction entrances, as shown on the Construction Access Plan Sheet C-502 prior to any site disturbances.
3. If required, install excavation support, and begin foundation excavation.
4. Sprinkle areas of exposed soil to control dust, as necessary.
5. Complete excavation, utility installation, and rough grading.
6. Soil erosion features shall remain in place until after construction is completed and final stabilization is reached. Only after the site is stabilized, remove temporary erosion and sediment control structural measures. "Stabilized" shall be defined as a 70% uniform perennial vegetative cover in all unpaved areas and areas not covered by permanent structure.

STAGING AREAS

Locations for contractor stockpiling and staging will be on-site. The approximate limits of these areas are shown on the Construction Access Plan (Sheet C-502).

VEGETATIVE PLAN

The contractor shall initiate surface stabilization measures as soon as practical in portions of the site where construction activities have permanently ceased and in no case more than 14 days after construction activity in that portion of the site has temporarily ceased. Areas to be seeded are referred to as disturbed areas. Refer to Landscape Planting Plan (Sheet L-400) for permanent seeding.

For Temporary Seeding and Mulch:

1. The altered areas that have been final-graded are to be seeded to establish a permanent ground cover with little or no maintenance. A seed mixture of bluegrass (88%) and redtop (12%) or some other species shall be applied at a rate of 40lbs per acre, to a prepared ground surface which includes lime and fertilizer at a rate indicated by soils tests.
2. Rake the seed into the soil and lightly pack to establish good contact.

3. Mulching will be used as an aid in establishing vegetation. Straw or hay mulch will be applied at a rate of 3 tons per acre, in areas where mulching is required. Wood cellulose fiber will be applied at a rate of 1500lbs per acre.
4. Seed and mulch fill slopes in regular vertical increments of 15-feet immediately upon placement.
5. Planting Times
 - a. Sod: May be laid at any time except during the months of June and July, provided that the ground is not frozen.
 - b. Seed: May be laid between March 15 and May 1, and between August 15 and October 1.

Seeding Bed Preparation:

1. Clear the sub-soil upon which topsoil is to be placed of all stones, woody roots, rubbish, and other objectionable matter, scarify the surface thoroughly and loosen to a depth of at least 4"; spread the topsoil to a smooth even surface and to the depth required, then rake or otherwise manipulate to form smooth drainage grades to the levels shown on the Grading Plan (Sheet C-600).
2. Deposit topsoil and spread to a minimum depth of 8" over earth where seeded and sodded areas are indicated, 12" where ground cover areas are indicated, 18" over rock where seeded, sodded or ground cover areas are indicated, and to a minimum depth of 18" over earth, and 36" over rock where planted, garden or shrubbery areas are indicated on the Landscape Planting Plan (Sheet L-400).

For Permanent Seeding:

1. The altered areas that have been final-graded are to be seeded to establish a permanent ground cover with little or no maintenance. A side mixture of bluegrass (88%) and redtop (12%) or some other species shall be applied at a rate of 40 lbs. per acre, to a prepared ground surface which includes lime and fertilizer at a rate indicated by soils tests.
2. Mulching will be used as an aid in establishing vegetation. Straw or hay mulch will be applied at a rate of 3 tons per acre, in areas where mulching is required. Wood cellulose fiber will be applied at a rate of 1500lbs per acre.
3. Lime and fertilizer for all the listed seed mixes shall be applied according to the following rates (per acre) for the development. Fertilizer is to be applied at a rate of 1000 lbs./acre.
 - a. 6 tons agricultural lime
 - b. 100 lbs. N
 - c. 200 lbs. P₂O₅
 - d. 200 lbs. K₂O
4. Planting Times

- a. Sod: May be laid at any time except during the months of June and July, provided that the ground is not frozen.
- b. Seed: May be laid between March 15 and May 1, and between August 15 and October 1.

Maintenance:

1. The contractor may be directed to reseed any areas which, in the opinion of the engineer are unacceptable.
2. The contractor shall adequately maintain the erosion control cover, including watering, as necessary.
3. If the growth is inadequate for erosion control, the contractor shall overseed using half the rate of seed originally applied.
4. If the grass seed growth is over 60% damaged, reseed at the originally specified rate.

SOIL RESTORATION REQUIREMENTS

This project shall comply with NYS DEC requirements for soil restoration, as noted in the Stormwater Management Design Manual Table 5.3 and summarized below.

DEC STORMWATER MANAGEMENT DESIGN MANUAL TABLE 5.3 SOIL RESTORATION REQUIREMENTS		
TYPE OF SOIL DISTURBANCE	SOIL RESTORATION REQUIREMENT	COMMENTS/EXAMPLES
No soil disturbance	Restoration not permitted	Preservation of Natural Features
Minimal soil disturbance	Restoration not required	Clearing and Grubbing
Areas where topsoil is stripped only – no change in grade	HSG C: Aerate and apply 6-in of topsoil	Protect area from ongoing construction activities
Areas of cut or fill	HSG C: Apply full soil restoration (per Deep Ripping and De-compaction, DEC 2008)	
Heavy traffic areas on site (especially in a zone 5-25 feet around buildings but not within a 5-ft perimeter around foundation walls)	Apply full Soil Restoration (per Deep Ripping and De-compaction, DEC 2008)	
Areas where Runoff Reduction and/or Infiltration practices are applied	Restoration not required, but may be applied to enhance the reduction specified for appropriate practices.	Keep construction equipment from crossing these areas. To protect newly installed practice from any ongoing construction activities construct a single phase operation fence area
Redevelopment projects	Soil Restoration is required on redevelopment projects in areas where existing impervious area will be converted to pervious area.	

*Aeration includes the use of machines such as tractor-drawn implements with coulters making a narrow slit in the soil, a roller with many spikes making indentations in the soil, or prongs which function like a mini-subsoiler.

MAINTENANCE PROGRAM

The construction manager shall be responsible for the installation and maintenance of all temporary erosion and sediment control measures. A log shall be kept, documenting the maintenance of the control measures. Inspections shall be done under the supervision of a licensed Professional Engineer or Landscape Architect, or a Certified Professional in Erosion and Sediment Control.

All maintenance methods described below are in direct accordance with the New York State Standards and Specifications for Erosion and Sediment Control (July 2016).

1. The contractor shall be responsible for the proper construction, stabilization, and maintenance of all temporary erosion and sedimentation control measures and related items included within this plan.
2. Soil sediment removed from any temporary soil erosion and sediment control measure during regular maintenance shall be incorporated back into the earthwork as fill on the site. Soil sediment materials shall be distributed on-site without changing drainage patterns during a specific construction stage.
3. All erosion and sediment control practices shall be inspected for stability and operation within 24 hours of every 0.5-inch or greater rainfall, but in no case less than once in a seven-day period. Any needed repairs shall be made immediately to maintain all practices as designed. A Construction Duration Inspections form is included in Appendix B and shall be completed and inserted into this SWPPP after each inspection.
4. Sediment shall be removed from behind the silt fence when it reaches 0.5-feet deep at the silt fence. The silt fence shall be repaired as necessary to maintain a barrier.
5. Debris and litter shall be removed from the site on a monthly basis, or more frequently if necessary.
6. Construction equipment and vehicles within the work area shall be properly maintained and inspected for leaking, particularly for identification of vehicles leaking petroleum products that may enter adjacent stormwater drainage facilities.
7. All seeded areas shall be fertilized, reseeded, and mulched as necessary to maintain a vigorous, dense vegetative cover.

NON-STORMWATER DISCHARGES

Possible sources of non-stormwater discharges associated with the construction activity are identified below. The following are additional stormwater pollution prevention measures for non-stormwater discharges.

- Cleaning water for construction vehicles and equipment shall be diverted to the temporary and approved erosion and sediment control measures. Chemicals and detergents shall not be used.

- The construction manager is to coordinate with the owner for identifying areas on-site for construction vehicle transit (i.e., haul roads, contractor trailers and parking areas, etc.) or equipment staging which shall be monitored and where runoff can be controlled.
- Water used for dust control measures shall be applied using proper quantities and equipment. No chemical additives shall be used.
- Water service flushing, hydrostatic test water, fire test water, and chlorination test water shall be directed to the control measures on the site. Turbid water is to be detained to allow sufficient sedimentation time (minimum of 24 hours). Chlorinated water is to be detained until the water is dechlorinated (minimum of 24 hours).
- Concrete trucks shall be washed out in an area approved of by the owner or owner's representative. All runoff from these activities shall be directed to the on-site control measures.

STORAGE PRACTICES

The following is a description of additional controls and measures that are to be implemented at the site by the general contractor to minimize pollutant transport.

- Solid waste disposal dumpsters and containers are to be covered and emptied regularly. Solid waste is to be disposed of properly in accordance with local regulations.
- Portable toilets are to be installed and cleaned regularly with their contents properly disposed of.
- Building materials are to be properly stored and contained on-site.

SPILL PREVENTION PRACTICES

The following are material management practices that are to be used by the general contractor to reduce the risk of spills or other accidental exposure of materials and substances to storm water runoff during construction. These are a minimum as per the following environmental documents in effect on site: (BUD) - Beneficial Use Determination, (HASP) - Health and Safety Plan, and (RAWP) - Remedial Action Work Plan. The stricter shall govern.

- Materials stored on-site with potential for spillage are to be stored in a neat and orderly manner in their appropriate containers. Materials with a potential for spillage shall be stored under a roof or other enclosure when possible.
- Products are to be kept in their original containers with the original manufacturer's label.
- Substances are not to be mixed with one another unless recommended by the manufacturer.

- Prior to disposal, a product is to be completely used up or its container is to be resealed whenever possible.
- Manufacturers' recommendations for proper use and disposal are to be followed.
- During periodic inspections, the proper use and disposal of materials is to be recorded on the inspection form.
- On-site vehicles are to be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage of petroleum products. Petroleum products are to be stored in closed containers that are clearly labeled. Used oils are to be disposed of properly.
- Materials are to be brought on-site in the minimum quantities required to limit on-site storage.
- Paint containers are to be tightly sealed and properly stored when not required for use.
- Excess paint, solvents, and other similar products shall not be discharged to the storm sewer system. These items are to be properly disposed of according to manufacturers' instructions or state and local regulations.
- Proper precautions are to be taken so materials do not spill onto public thoroughfares. If materials are spilled in these areas, they are to be removed immediately so that they do not enter the surface and subsurface drainage systems.
- Oil containers are to have appropriate secondary containment. If total oil storage on-site exceeds a cumulative total of 1,320 gallons, then a Spill Prevention Control and Countermeasure (SPCC) plan must be prepared by the owner.
- If necessary, the contractor is to prepare a SPCC plan to cover proposed activities.

SPILL CONTROL PRACTICES

The following practices are to be adhered to by the general contractor for spill prevention and cleanup:

- Spills of petroleum, toxins, or hazardous material are to be reported to the owner and appropriate state or local government agencies immediately, regardless of size.
- Manufacturers' recommended methods for spill cleanup are to be clearly posted at the site. Site personnel are to be made aware of the procedures and the location of the information and cleanup supplies.
- Materials and equipment necessary for spill cleanup are to be kept in designated material storage areas on-site. Equipment and materials are to include but not be limited to brooms, dust pans, mops, rags, gloves, goggles, spill control materials, sand, sawdust, and trash containers specifically for this purpose.

- Spills are to be cleaned up immediately after discovery.
- The spill area is to be kept well ventilated and personnel are to wear appropriate protective clothing to prevent injury from contact with hazardous substances.
- A spill report is to be completed and filed in the SWPPP and is to include a description of the spill, the cause of the spill, and the corrective actions taken.

INSPECTION DURING CONSTRUCTION

SPDES GENERAL REQUIREMENTS AND GUIDELINES

The SPDES General Permit for Construction Activity GP-0-20-001 outlines the following requirements and guidelines for inspections during construction:

The owner or operator shall have a qualified professional conduct a site inspection at least once every seven calendar days. Qualified professional means a person that is knowledgeable in the principles and practices of erosion and sediment control, such as a licensed professional engineer, Certified Professional in Erosion and Sediment Control (CPESC), licensed Landscape Architect, or other NYSDEC (Department) endorsed individuals. It also means someone working under the direct supervision of the licensed Professional Engineer or licensed Landscape Architect, provided that person has training in the principles and practices of erosion and sediment control. Training in the principles and practices of erosion and sediment control means that an individual performing a site inspection has received four hours of training, endorsed by the Department, from a Soil and Water Conservation District, CPESP, Inc. or other Department-endorsed entity in proper erosion and sediment control principles no later than two years from date this general permit is issued. After receiving the initial training, an individual working under the direct supervision of the licensed Professional Engineer or licensed Landscape Architect shall receive four hours of training every three years.

At a minimum, the qualified professional shall inspect all soil erosion and sediment control practices to ensure integrity and effectiveness, all post-construction stormwater management practices under construction to ensure that they are constructed in conformance with the SWPPP, all areas of disturbance that have not achieved final stabilization, and all points of discharge from the construction site.

The qualified professional shall prepare an inspection report subsequently to each and every inspection. At a minimum, the inspection report shall include and/or address the following:

1. Date and time of inspection;
2. Name (printed and signed) and title of the person(s) performing inspection;
3. A description of the weather and soil conditions (e.g., dry, wet, saturated) at the time of the inspection;
4. A description of the condition of the runoff at all points of discharge from the construction site. This shall include identification of any discharges of sediment from the

construction site. Include discharges from conveyance systems (i.e., pipes, culverts, ditches, etc.) and overland flow;

5. A description of the condition of all, natural surface waterbodies located within, or immediately adjacent to, the property boundaries of the construction site which receive runoff from disturbed areas. This shall include identification of any discharges of sediment to the surface waterbody;
6. Identification of all erosion and sediment control practices that need repair or maintenance;
7. Identification of all erosion and sediment control practices that were not installed properly or are not functioning as designed and need to be reinstalled or replaced;
8. Description and sketch of areas that are disturbed at the time of the inspection and areas that have been stabilized (temporary and/or final) since the last inspection;
9. Current phase of construction of all post-construction stormwater management practices and identification of all construction that is not in conformance with the SWPPP and technical standards;
10. Corrective action(s) that must be taken to install, repair, replace, or maintain erosion and sediment control practices; and to correct deficiencies identified with the construction of the post-construction stormwater management practice(s); and
11. Digital photographs, with date stamp, that clearly show the condition of all practices that have been identified as needing corrective actions. The qualified inspector shall attach paper color copies of the digital photographs to the inspection report being maintained on site within seven calendar days of the date of the inspection. The qualified inspector shall also take digital photographs, with date stamp, that clearly show the condition of the practice(s) after the corrective action has been completed. The qualified inspector shall attach paper color copies of the digital photographs to the inspection report that documents the completion of the corrective action work within seven (7) calendar days of that inspection.

Within one business day of the completion of an inspection, the qualified professional shall notify the owner or operator and the appropriate contractor (or subcontractor) shall begin implementing the corrective actions within one business day of this notification and shall complete the corrective actions in a reasonable time frame, prior to the next weekly submission.

A typical inspection report form for conducting the inspections is included in Appendix B. If an alternate inspection form is used, it must at least provide the same information as provided on the referenced form. A monthly inspection summary for the inspections of the erosion and sediment control measures shall be prepared by the qualified professional. The general contractor is to post on site a summary of site inspection activities on a monthly basis.

Prior to the completion of work, the general contractor shall have the qualified professional perform a final site inspection. The qualified professional shall certify that the site has undergone

final stabilization using either vegetative or structural stabilization methods and that all temporary erosion and sediment control measures are no longer required.

WINTER CONDITIONS

During winter months, periodic inspections are to occur as described above until construction is completed and the site is stabilized. During winter operation (i.e., suspended soil disturbance, site stabilization), however, the owner may reduce inspection frequencies in accordance with the NYSDEC's Winter Site Stabilization/Site Inspections for Construction Sites. Under winter conditions, inspections are to be performed at least once every 30 days and within 24 hours of the end of a rainfall event of 0.5 inches or greater. Non-winter inspection frequencies are to resume upon resumption of construction activities, but no later than March 15th.

CERTIFICATIONS AND FORMS

The following certifications and forms are to be reviewed, understood, filled out, and signed by the appropriate personnel at the appropriate time:

- The Pre-Construction Documents and Certifications, provided in Appendix A, shall be filled out by the owner, operator, preparer, and qualified professional, as appropriately shown in the section.
- The Construction Duration Inspections form provided in Appendix B is to be filled out and signed by the qualified professional that will perform site inspections and oversee installation of erosion control measures for the project.
- The Monthly Summary of Site Inspection Activities form provided in Appendix C is to be completed by the qualified inspector.
- The Contractor's Certification Statement provided in Appendix D is to be filled out and signed by the operator/general contractor.
- The Sub-Contractor's Certification Statement provided in Appendix D is to be filled out and signed by all sub-contractors.
- The Certificate of Issuance provided in Appendix D is to be filled out and signed by the operator and preparer prior to performing any site work.
- The Erosion and Water Quality Control Identification form provided in Appendix D is to be filled out by the operator.
- Records of site work and site stabilization are to be kept on the Construction Stabilization form provided in Appendix D, to be filled out by the operator, as necessary.
- The Certificate of Change by the Contractor provided in Appendix D is to be filled out and signed by the operator upon implementation of any requested changes to the SWPPP by the owner, preparer, or any local authority having jurisdiction over the project site. Changes to the SWPPP are only to be made when the plan or contractor's implementation

proves to be ineffective in eliminating or significantly minimizing pollutants from the construction activity.

- The Final Stabilization and Retention of Records form provided in Appendix E is to be filled out and signed by the qualified professional that will perform site inspections and oversee installation of erosion control measures for the project.
- The Certificate of Return provided in Appendix E is to be filled out and signed by the operator and owner after final stabilization of the site has been completed.

RETENTION OF RECORDS

The following are to be retained by the owner at the site and for a period of three years from the date the site is finally stabilized.

- SWPPP
- Contract Documents including contract drawings and technical specifications
- Stormwater inspections and maintenance reports
- Contractor Certification
- SWPPP Certification Statement of Satisfactory Completion
- Correspondence regarding stormwater practices

REFERENCES

New York State Standards and Specifications for Erosion and Sediment Control. New York State Department of Environmental Conservation, August 2005.

APPENDIX A:
NOTICE OF INTENT

NOI for coverage under Stormwater General Permit for Construction Activity

version 1.30

(Submission #: HPA-0RM8-X53D2, version 1)

Details

Submission Alias NOI SW General Permit - 49 Clinton Ave (IEC)

Originally Started By Gonzalo Trenosky

Submission ID HPA-0RM8-X53D2

Submission Reason New

Status Draft

Form Input

Owner/Operator Information

Owner/Operator Name (Company/Private Owner/Municipality/Agency/Institution, etc.)

The Masters School

Owner/Operator Contact Person Last Name (NOT CONSULTANT)

Ed

Owner/Operator Contact Person First Name

Biddle

Owner/Operator Mailing Address

49 Clinton Avenue

City

Dobbs Ferry

State

NY

Zip
10522

Phone
9144796431

Email
ed.biddle@mastersny.org

Federal Tax ID
NONE PROVIDED

Project Location

Project/Site Name
The Masters School - Innovation & Entrepreneurship Center

Street Address (Not P.O. Box)
49 Clinton Avenue

Side of Street
East

City/Town/Village (THAT ISSUES BUILDING PERMIT)
Dobbs Ferry

State
NY

Zip
10522

DEC Region
3

County
WESTCHESTER

Name of Nearest Cross Street
NONE PROVIDED

Distance to Nearest Cross Street (Feet)
NONE PROVIDED

Project In Relation to Cross Street
NONE PROVIDED

Tax Map Numbers Section-Block-Parcel
NONE PROVIDED

Tax Map Numbers

NONE PROVIDED

1. Coordinates

Provide the Geographic Coordinates for the project site. The two methods are:

- Navigate to the project location on the map (below) and click to place a marker and obtain the XY coordinates.
- The "Find Me" button will provide the lat/long for the person filling out this form. Then pan the map to the correct location and click the map to place a marker and obtain the XY coordinates.

Navigate to your location and click on the map to get the X,Y coordinates

41.012179586711795,-73.86963084664356

Project Details**2. What is the nature of this project?**

New Construction

3. Select the predominant land use for both pre and post development conditions.**Pre-Development Existing Landuse**

Institutional/School

Post-Development Future Land Use

Institutional/School

3a. If Single Family Subdivision was selected in question 3, enter the number of subdivision lots.NONE PROVIDED

4. In accordance with the larger common plan of development or sale, enter the total project site acreage, the acreage to be disturbed and the future impervious area (acreage)within the disturbed area.

*** ROUND TO THE NEAREST TENTH OF AN ACRE. ***

Total Site Area (acres)

96

Total Area to be Disturbed (acres)

2.2

Existing Impervious Area to be Disturbed (acres)

.1

Future Impervious Area Within Disturbed Area (acres)

.3

5. Do you plan to disturb more than 5 acres of soil at any one time?

No

6. Indicate the percentage (%) of each Hydrologic Soil Group(HSG) at the site.

A (%)

0

B (%)

0

C (%)

100

D (%)

0

7. Is this a phased project?

No

8. Enter the planned start and end dates of the disturbance activities.

Start Date

10/1/2021

End Date

9/30/2023

9. Identify the nearest surface waterbody(ies) to which construction site runoff will discharge.

Hudson River

9a. Type of waterbody identified in question 9?

River Off Site

Other Waterbody Type Off Site Description

NONE PROVIDED

9b. If "wetland" was selected in 9A, how was the wetland identified?

NONE PROVIDED

10. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001?

No

11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001?

No

12. Is the project located in one of the watershed areas associated with AA and AA-S classified waters?

No

If No, skip question 13.

13. Does this construction activity disturb land with no existing impervious cover and where the Soil Slope Phase is identified as an E or F on the USDA Soil Survey?

No

If Yes, what is the acreage to be disturbed?

NONE PROVIDED

14. Will the project disturb soils within a State regulated wetland or the protected 100 foot adjacent area?

No

15. Does the site runoff enter a separate storm sewer system (including roadside drains, swales, ditches, culverts, etc)?

Unknown

16. What is the name of the municipality/entity that owns the separate storm sewer system?

NONE PROVIDED

17. Does any runoff from the site enter a sewer classified as a Combined Sewer?

Unknown

18. Will future use of this site be an agricultural property as defined by the NYS Agriculture and Markets Law?

No

19. Is this property owned by a state authority, state agency, federal government or local government?

No

20. Is this a remediation project being done under a Department approved work plan? (i.e. CERCLA, RCRA, Voluntary Cleanup Agreement, etc.)

No

Required SWPPP Components

21. Has the required Erosion and Sediment Control component of the SWPPP been developed in conformance with the current NYS Standards and Specifications for Erosion and Sediment Control (aka Blue Book)?

Yes

22. Does this construction activity require the development of a SWPPP that includes the post-construction stormwater management practice component (i.e. Runoff Reduction, Water Quality and Quantity Control practices/techniques)?

Yes

If you answered No in question 22, skip question 23 and the Post-construction Criteria and Post-construction SMP Identification sections.

23. Has the post-construction stormwater management practice component of the SWPPP been developed in conformance with the current NYS Stormwater Management Design Manual?

Yes

24. The Stormwater Pollution Prevention Plan (SWPPP) was prepared by:
Professional Engineer (P.E.)

SWPPP Preparer
Gonzalo Trenosky

Contact Name (Last, Space, First)
Trenosky Gonzalo

Mailing Address
2780 Hamilton Boulevard

City
South Plainfield

State
New Jersey

Zip
07080

Phone
9089224625

Email
gmt@mfsengineers.com

Download SWPPP Preparer Certification Form

Please take the following steps to prepare and upload your preparer certification form:

- 1) Click on the link below to download a blank certification form
- 2) The certified SWPPP preparer should sign this form

- 3) Scan the signed form
 - 4) Upload the scanned document
- [Download SWPPP Preparer Certification Form](#)

Please upload the SWPPP Preparer Certification

1120062_SWPPP Preparer Certification Form_signed.pdf - 07/07/2021 01:48 PM

Comment

Please see attached SWPPP Preparer Certification Form. The Owner of the Property is The Masters School.

Erosion & Sediment Control Criteria

25. Has a construction sequence schedule for the planned management practices been prepared?

Yes

26. Select all of the erosion and sediment control practices that will be employed on the project site:

Temporary Structural

Storm Drain Inlet Protection
 Stabilized Construction Entrance
 Silt Fence
 Dust Control
 Construction Road Stabilization

Biotechnical

None

Vegetative Measures

Topsoiling
 Seeding

Permanent Structural

Land Grading

Other

NONE PROVIDED

Post-Construction Criteria

*** IMPORTANT: Completion of Questions 27-39 is not required if response to Question 22 is No.**

27. Identify all site planning practices that were used to prepare the final site plan/layout for the project.

Locating Development in Less Sensitive Areas
 Roadway Reduction

27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).

All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).

28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout). (Acre-feet)

.042

29. Post-construction SMP Identification

Use the Post-construction SMP Identification section to identify the RR techniques (Area Reduction), RR techniques (Volume Reduction) and Standard SMPs with RRv Capacity that were used to reduce the Total WQv Required (#28).

Identify the SMPs to be used by providing the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

Note: Redevelopment projects shall use the Post-Construction SMP Identification section to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

30. Indicate the Total RRv provided by the RR techniques (Area/Volume Reduction) and Standard SMPs with RRv capacity identified in question 29. (acre-feet)

.026

31. Is the Total RRv provided (#30) greater than or equal to the total WQv required (#28)?

No

If Yes, go to question 36. If No, go to question 32.

32. Provide the Minimum RRv required based on HSG. [Minimum RRv Required = (P) (0.95) (Ai) / 12, Ai=(s) (Aic)] (acre-feet)

.012

32a. Is the Total RRv provided (#30) greater than or equal to the Minimum RRv Required (#32)?

Yes

If Yes, go to question 33.

Note: Use the space provided in question #39 to summarize the specific site limitations and justification for not reducing 100% of WQv required (#28). A detailed evaluation of the specific site limitations and justification for not reducing 100% of the WQv required (#28) must also be included in the SWPPP.

If No, sizing criteria has not been met; therefore, NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

33. SMPs

Use the Post-construction SMP Identification section to identify the Standard SMPs and, if applicable, the Alternative SMPs to be used to treat the remaining total WQv (=Total WQv Required in #28 - Total RRv Provided in #30).

Also, provide the total impervious area that contributes runoff to each practice selected.

NOTE: Use the Post-construction SMP Identification section to identify the SMPs used on Redevelopment projects.

33a. Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question #29. (acre-feet)

.026

Note: For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - provided by the practice. (See Table 3.5 in Design Manual)

34. Provide the sum of the Total RRv provided (#30) and the WQv provided (#33a).

.051

35. Is the sum of the RRv provided (#30) and the WQv provided (#33a) greater than or equal to the total WQv required (#28)?

Yes

If Yes, go to question 36.

If No, sizing criteria has not been met; therefore, NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

36. Provide the total Channel Protection Storage Volume (CPv required and provided or select waiver (#36a), if applicable.

CPv Required (acre-feet)

.115

CPv Provided (acre-feet)

.076

36a. The need to provide channel protection has been waived because:

NONE PROVIDED

37. Provide the Overbank Flood (Qp) and Extreme Flood (Qf) control criteria or select waiver (#37a), if applicable.

Overbank Flood Control Criteria (Qp)

Pre-Development (CFS)

3.60

Post-Development (CFS)

3.53

Total Extreme Flood Control Criteria (Qf)**Pre-Development (CFS)**

7.06

Post-Development (CFS)

7.03

37a. The need to meet the Qp and Qf criteria has been waived because:

NONE PROVIDED

38. Has a long term Operation and Maintenance Plan for the post-construction stormwater management practice(s) been developed?

Yes

If Yes, Identify the entity responsible for the long term Operation and Maintenance

The Masters School

39. Use this space to summarize the specific site limitations and justification for not reducing 100% of WQv required (#28). (See question #32a) This space can also be used for other pertinent project information.

Extensive site sloping and poor soil quality conditions.

Post-Construction SMP Identification**Runoff Reduction (RR) Techniques, Standard Stormwater Management Practices (SMPs) and Alternative SMPs**

Identify the Post-construction SMPs to be used by providing the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

RR Techniques (Area Reduction)

Round to the nearest tenth

Total Contributing Acres for Conservation of Natural Area (RR-1)

NONE PROVIDED

Total Contributing Impervious Acres for Conservation of Natural Area (RR-1)

NONE PROVIDED

Total Contributing Acres for Sheetflow to Riparian Buffers/Filter Strips (RR-2)
NONE PROVIDED

Total Contributing Impervious Acres for Sheetflow to Riparian Buffers/Filter Strips (RR-2)
NONE PROVIDED

Total Contributing Acres for Tree Planting/Tree Pit (RR-3)
NONE PROVIDED

Total Contributing Impervious Acres for Tree Planting/Tree Pit (RR-3)
NONE PROVIDED

Total Contributing Acres for Disconnection of Rooftop Runoff (RR-4)
NONE PROVIDED

RR Techniques (Volume Reduction)

Total Contributing Impervious Acres for Disconnection of Rooftop Runoff (RR-4)
NONE PROVIDED

Total Contributing Impervious Acres for Vegetated Swale (RR-5)
NONE PROVIDED

Total Contributing Impervious Acres for Rain Garden (RR-6)
NONE PROVIDED

Total Contributing Impervious Acres for Stormwater Planter (RR-7)
NONE PROVIDED

Total Contributing Impervious Acres for Rain Barrel/Cistern (RR-8)
NONE PROVIDED

Total Contributing Impervious Acres for Porous Pavement (RR-9)
NONE PROVIDED

Total Contributing Impervious Acres for Green Roof (RR-10)
NONE PROVIDED

Standard SMPs with RRv Capacity

Total Contributing Impervious Acres for Infiltration Trench (I-1)
NONE PROVIDED

Total Contributing Impervious Acres for Infiltration Basin (I-2)
NONE PROVIDED

Total Contributing Impervious Acres for Dry Well (I-3)
NONE PROVIDED

Total Contributing Impervious Acres for Underground Infiltration System (I-4)
.29

Total Contributing Impervious Acres for Bioretention (F-5)
.19

Total Contributing Impervious Acres for Dry Swale (O-1)
NONE PROVIDED

Standard SMPs

Total Contributing Impervious Acres for Micropool Extended Detention (P-1)
NONE PROVIDED

Total Contributing Impervious Acres for Wet Pond (P-2)
NONE PROVIDED

Total Contributing Impervious Acres for Wet Extended Detention (P-3)
NONE PROVIDED

Total Contributing Impervious Acres for Multiple Pond System (P-4)
NONE PROVIDED

Total Contributing Impervious Acres for Pocket Pond (P-5)
NONE PROVIDED

Total Contributing Impervious Acres for Surface Sand Filter (F-1)
NONE PROVIDED

Total Contributing Impervious Acres for Underground Sand Filter (F-2)
NONE PROVIDED

Total Contributing Impervious Acres for Perimeter Sand Filter (F-3)
NONE PROVIDED

Total Contributing Impervious Acres for Organic Filter (F-4)
NONE PROVIDED

Total Contributing Impervious Acres for Shallow Wetland (W-1)
NONE PROVIDED

Total Contributing Impervious Acres for Extended Detention Wetland (W-2)
NONE PROVIDED

Total Contributing Impervious Acres for Pond/Wetland System (W-3)
NONE PROVIDED

Total Contributing Impervious Acres for Pocket Wetland (W-4)

NONE PROVIDED

Total Contributing Impervious Acres for Wet Swale (O-2)

NONE PROVIDED

Alternative SMPs (DO NOT INCLUDE PRACTICES BEING USED FOR PRETREATMENT ONLY)

Total Contributing Impervious Area for Hydrodynamic

NONE PROVIDED

Total Contributing Impervious Area for Wet Vault

NONE PROVIDED

Total Contributing Impervious Area for Media Filter

NONE PROVIDED

"Other" Alternative SMP?

NONE PROVIDED

Total Contributing Impervious Area for "Other"

NONE PROVIDED

Provide the name and manufacturer of the alternative SMPs (i.e. proprietary practice(s)) being used for WQv treatment.

Note: Redevelopment projects which do not use RR techniques, shall use questions 28, 29, 33 and 33a to provide SMPs used, total WQv required and total WQv provided for the project.

Manufacturer of Alternative SMP

NONE PROVIDED

Name of Alternative SMP

NONE PROVIDED

Other Permits

40. Identify other DEC permits, existing and new, that are required for this project/facility.

None

If SPDES Multi-Sector GP, then give permit ID

NONE PROVIDED

If Other, then identify

NONE PROVIDED

41. Does this project require a US Army Corps of Engineers Wetland Permit?

No

If "Yes," then indicate Size of Impact, in acres, to the nearest tenth

NONE PROVIDED

42. If this NOI is being submitted for the purpose of continuing or transferring coverage under a general permit for stormwater runoff from construction activities, please indicate the former SPDES number assigned.

NONE PROVIDED

MS4 SWPPP Acceptance

43. Is this project subject to the requirements of a regulated, traditional land use control MS4?

Yes - Please attach the MS4 Acceptance form below

If No, skip question 44

44. Has the "MS4 SWPPP Acceptance" form been signed by the principal executive officer or ranking elected official and submitted along with this NOI?

No

MS4 SWPPP Acceptance Form Download

Download form from the link below. Complete, sign, and upload.

[MS4 SWPPP Acceptance Form](#)

MS4 Acceptance Form Upload

NONE PROVIDED

Comment

NONE PROVIDED

Owner/Operator Certification

Owner/Operator Certification Form Download

Download the certification form by clicking the link below. Complete, sign, scan, and upload the form.

[Owner/Operator Certification Form \(PDF, 45KB\)](#)

Upload Owner/Operator Certification Form

NONE PROVIDED


Comment

NONE PROVIDED





































Attachments

Date	Attachment Name	Context	User
7/7/2021 1:48 PM	1120062_SWPPP Preparer Certification Form_signed.pdf	Attachment	Gonzalo Trenosky

APPENDIX B:
SOIL REPORT



MAP LEGEND

- Area of Interest (AOI)**
 -  Area of Interest (AOI)
- Soils**
 -  Soil Map Unit Polygons
 -  Soil Map Unit Lines
 -  Soil Map Unit Points
- Special Point Features**
 -  Blowout
 -  Borrow Pit
 -  Clay Spot
 -  Closed Depression
 -  Gravel Pit
 -  Gravelly Spot
 -  Landfill
 -  Lava Flow
 -  Marsh or swamp
 -  Mine or Quarry
 -  Miscellaneous Water
 -  Perennial Water
 -  Rock Outcrop
 -  Saline Spot
 -  Sandy Spot
 -  Severely Eroded Spot
 -  Sinkhole
 -  Slide or Slip
 -  Sodic Spot
- Water Features**
 -  Streams and Canals
- Transportation**
 -  Rails
 -  Interstate Highways
 -  US Routes
 -  Major Roads
 -  Local Roads
- Background**
 -  Aerial Photography
- Other Features**
 -  Spoil Area
 -  Stony Spot
 -  Very Stony Spot
 -  Wet Spot
 -  Other
 -  Special Line Features

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Westchester County, New York
 Survey Area Data: Version 16, Jun 11, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 22, 2020—Sep 23, 2020

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
PnB	Paxton fine sandy loam, 3 to 8 percent slopes	12.1	95.6%
PnC	Paxton fine sandy loam, 8 to 15 percent slopes	0.6	4.4%
Totals for Area of Interest		12.6	100.0%

Westchester County, New York

PnB—Paxton fine sandy loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 2t2qp
Elevation: 0 to 1,570 feet
Mean annual precipitation: 36 to 71 inches
Mean annual air temperature: 39 to 55 degrees F
Frost-free period: 140 to 240 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Paxton and similar soils: 80 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Paxton

Setting

Landform: Drumlins, ground moraines, hills
Landform position (two-dimensional): Backslope, summit, shoulder
Landform position (three-dimensional): Side slope, crest, nose slope
Down-slope shape: Linear, convex
Across-slope shape: Convex
Parent material: Coarse-loamy lodgment till derived from gneiss, granite, and/or schist

Typical profile

Ap - 0 to 8 inches: fine sandy loam
Bw1 - 8 to 15 inches: fine sandy loam
Bw2 - 15 to 26 inches: fine sandy loam
Cd - 26 to 65 inches: gravelly fine sandy loam

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: 18 to 39 inches to densic material
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.14 in/hr)
Depth to water table: About 18 to 37 inches
Frequency of flooding: None
Frequency of ponding: None
Maximum salinity: Nonsaline (0.0 to 1.9 mmhos/cm)
Available water capacity: Low (about 3.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2s

Hydrologic Soil Group: C

Ecological site: F144AY007CT - Well Drained Dense Till Uplands

Hydric soil rating: No

Minor Components

Woodbridge

Percent of map unit: 9 percent

Landform: Hills, drumlins, ground moraines

Landform position (two-dimensional): Backslope, footslope, summit

Landform position (three-dimensional): Side slope

Down-slope shape: Concave

Across-slope shape: Linear

Hydric soil rating: No

Ridgebury

Percent of map unit: 6 percent

Landform: Drainageways, hills, ground moraines, depressions

*Landform position (two-dimensional): Backslope, footslope,
toeslope*

Landform position (three-dimensional): Head slope, base slope, dip

Down-slope shape: Concave

Across-slope shape: Concave

Hydric soil rating: Yes

Charlton

Percent of map unit: 5 percent

Landform: Hills

Down-slope shape: Linear

Across-slope shape: Linear

Hydric soil rating: No

Data Source Information

Soil Survey Area: Westchester County, New York

Survey Area Data: Version 16, Jun 11, 2020

APPENDIX C:
INFILTRATION TESTS SECTION FROM MFS GEOTECHNICAL REPORT,
DATED 03 FEBRUARY 2021

engineering software and is provided in Appendix A.

Infiltration Tests

In addition to the borings, MFS completed 12 infiltration tests at three (3) locations, identified as IT-1 through IT-3. Each infiltration test was completed adjacent to a previously completed geotechnical boring in accordance with the NYS SMDM Appendix D (B-1 (IT) corresponds to IT-1, B-2A (IT) and B-2B (IT) corresponds to IT-2, and B-5 corresponds to IT-3). The infiltration test locations are shown in the "As-Drilled Subsurface Investigation Location Plan" located in Figure 2. The depths of the borings and infiltration tests were performed in accordance with Appendix D of the NYS SMDM based on the bottom depths of the proposed stormwater management practice (SMP) as determined by the MFS civil engineering team. The 24-hour presoak period at each infiltration testing location started on 30 December 2020 once the temperature was above freezing point. The ambient temperature remained above the freezing point for the duration of the presoak period and the durations of the infiltration tests performed.

The infiltration tests were performed adjacent to each respective boring in order to determine the permeability coefficient of the soil at the respective depths. Each of the infiltration tests were completed two (2) feet below the proposed SMP depth. The infiltration tests at IT-1 and IT-3 were completed at a depth of 8-feet below grade and the infiltration tests at IT-2 were completed at a depth of 7 feet below grade. The infiltration test logs for each of the three (3) infiltration test locations (12 total infiltration tests performed) are provided in Appendix B.

Temporary Monitoring Well


One (1) temporary monitoring well was installed in boring B-1 (MW) to a depth of 29 feet below grade (EL. +100.3±) upon completion of soil sampling on 30 December 2020. The well construction consisted of 10 feet of 2-inch diameter 0.01-inch slotted PVC screens below 20 feet of 2-inch PVC riser extending to one (1) foot above grade. The annular space between the installed monitoring well and the borehole was backfilled with No. 2 filtration sand over the entire screen length and extending two (2) feet above the screen and riser interface (17 feet below grade). Above the filter sand, a bentonite seal was used to backfill to existing grade.

Due to the drilling methods utilized during the field subsurface investigation, it was not clear if the borings were performed below the groundwater level on site. The purpose of the temporary monitoring well installation was to identify if the groundwater table was present. Upon installation of the temporary monitoring well, the water that was present in the well on the day of drilling (from the drilling operations) had infiltrated out into the existing soils the day following the well installation. As such, it was determined that the groundwater level was not encountered and is expected to be deeper than 29 feet below grade (EL. +100.3±) on site. As no groundwater was observed in the temporary monitoring well, the well was removed and the borehole was backfilled on 31 December 2020. Refer to the Well Construction Log in Appendix C for elevations, and specific well construction information.

Geotechnical Laboratory Testing

Upon completion of the field investigation, all soil samples were transported back to our office for further evaluation and selection of samples for geotechnical laboratory testing. Soil





1 AS-DRILLED SUBSURFACE INVESTIGATION LOCATION PLAN

- NOTE:**
1. ALL AS-DRILLED BORING, INFILTRATION TEST, AND MONITORING WELL LOCATIONS REFERENCE THE FIELD SUBSURFACE INVESTIGATION COMPLETED BY MFS CONSTRUCTION, LLC UNDER THE FULL TIME ENGINEERING INSPECTION OF MFS CONSULTING ENGINEERS AND SURVEYOR, DPC FROM 28 DECEMBER 2020 TO 6 JANUARY 2021.
 2. THE PARTIAL BACKGROUND SURVEY USED FOR THIS PLAN WAS OBTAINED FROM THE 'TOPOGRAPHIC MAP OF THE DEVELOPED PORTION OF THE MASTERS SCHOOL' DATED 9 JANUARY 2017 PROVIDED IN AUTOCAD FORMAT WHICH IS BASED UPON PHOTOGRAMMETRIC MAPPING PREPARED BY GEOMAPS INTERNATIONAL, INC. USING AERIAL PHOTOGRAPHY TAKEN IN APRIL 2008 WITH SUPPLEMENTAL FIELD MEASUREMENTS COMPLETED BETWEEN 4 OCTOBER AND 31 DECEMBER 2016 COMBINED WITH MAPPING OF PORTIONS OF THE CAMPUS PREVIOUSLY PREPARED BY KENNETH B. SALZMANN, LAND SURVEYOR.
 3. ALL AS-DRILLED BORING, MONITORING WELL, AND INFILTRATION TEST LOCATIONS WERE MEASURED IN THE FIELD AT THE TIME OF COMPLETION FROM FIXED OBJECTS AT THE PROJECT SITE AND THE RESPECTIVE LOCATIONS SHALL BE CONSIDERED APPROXIMATE.
 4. ALL ELEVATIONS REFERENCED HEREIN ARE BASED ON THE MASTERS SCHOOL DATUM.



LEGEND	
	B-#/B-#(IT) AS-DRILLED BORING LOCATION
	B-# (MW) MONITORING WELL LOCATION
	IT-# INFILTRATION TEST LOCATION

 <small>MFS CONSULTING ENGINEERS & SURVEYORS, L.P.C. 2019 4TH AVE. # 1008 11/05/19 #703 NEW YORK, NY 10003 212 862 8276 www.mfs-engineers.com 212 862 7413 NY STATEMENT OF AUTHORIZATION: 000722</small>	<small>PROJECT NAME:</small> THE MASTERS SCHOOL INNOVATION AND ENTREPRENEURSHIP CENTER	<small>ISSUANCE TITLE:</small> AS-DRILLED SUBSURFACE INVESTIGATION LOCATION PLAN	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td><small>PROJECT NO.:</small> 10002</td> <td><small>SHEET NO.:</small></td> </tr> <tr> <td><small>DATE:</small> 01/12/21</td> <td></td> </tr> <tr> <td><small>SCALE:</small> AS SHOWN</td> <td style="text-align: center;">FIG. 2</td> </tr> <tr> <td><small>DRAWN BY:</small> JTD</td> <td></td> </tr> <tr> <td><small>CHECKED BY:</small> AM</td> <td style="text-align: right;"><small>#</small> 09 1</td> </tr> </table>	<small>PROJECT NO.:</small> 10002	<small>SHEET NO.:</small>	<small>DATE:</small> 01/12/21		<small>SCALE:</small> AS SHOWN	FIG. 2	<small>DRAWN BY:</small> JTD		<small>CHECKED BY:</small> AM	<small>#</small> 09 1
	<small>PROJECT NO.:</small> 10002	<small>SHEET NO.:</small>											
<small>DATE:</small> 01/12/21													
<small>SCALE:</small> AS SHOWN	FIG. 2												
<small>DRAWN BY:</small> JTD													
<small>CHECKED BY:</small> AM	<small>#</small> 09 1												
<small>BARRE COUNTY: WESTON AND COUNTY NEW YORK</small>													



Prepared for: Marvel Architects, PLLC		PROJECT: Masters School - Innovation and Entrepreneurship Center LOCATION / BOROUGH: Dobbs Ferry, NY	
INSPECTOR: Gilbert Del Orbe	DRILLER: Danny Ninevski	Start Date: 12/31/2020	Weather: 41°F / Light Rain
CONTRACTOR: MFS Construction, LLC	HELPER: Tom Feaser	Start Time: 9:00 AM	
P.E./REP.: Michael Mudalel, PE			
Depth of IT: 8 ft	Drill Bit Type: 3-7/8" TCRB	Weight of Hammer for casing: 140 lbs	
Rig Type: CME 45B	Casing Internal Diameter: 4 in	Type of Hammer: Auto	
	Casing Length: 126 in		


General Formula:
$$K_m = \pi R_t \times \frac{D \left\{ \ln \left(\frac{h_1}{h_2} \right) \right\}}{11 \times (t_2 - t_1)}$$

Formula for 4" internal diameter casing (in/hr):
$$K_m = 1.142 R_t \times \frac{\left\{ \ln \left(\frac{h_1}{h_2} \right) \right\}}{(t_2 - t_1)}$$

where:
$$R_t = 2.2902(0.9842^T) / T^{0.1702}$$

IT-1 @ 8 ft											
TEST 1						TEST 2					
Water temperature (°C), T: 8.2 Rt= 1.40						Water temperature (°C), T: 7.6 Rt= 1.44					
FIELD DATA			CALCULATED DATA			FIELD DATA			CALCULATED DATA		
Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)	Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)
10	12.000	114.000	0.100	0.167	0.9637	10	14.000	112.000	0.118	0.167	1.1600
20	22.500	103.500	0.197	0.167	0.9304	20	22.875	103.125	0.200	0.167	0.8130
30	29.000	97.000	0.262	0.167	0.6246	30	29.000	97.000	0.262	0.167	0.6030
40	34.000	92.000	0.314	0.167	0.5096	40	34.375	91.625	0.319	0.167	0.5614
60	44.500	81.500	0.436	0.333	0.5835	60	43.625	82.375	0.425	0.333	0.5240
TEST 3						TEST 4					
Water temperature (°C), T: 7.5 Rt= 1.44						Water temperature (°C), T: 7.4 Rt= 1.45					
FIELD DATA			CALCULATED DATA			FIELD DATA			CALCULATED DATA		
Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)	Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)
10	11.000	115.000	0.091	0.167	0.9031	10	10.500	115.500	0.087	0.167	0.8636
20	19.000	107.000	0.163	0.167	0.7128	20	18.750	107.250	0.161	0.167	0.7355
30	25.500	100.500	0.226	0.167	0.6196	30	26.063	99.937	0.232	0.167	0.7009
40	31.000	95.000	0.282	0.167	0.5564	40	31.500	94.500	0.288	0.167	0.5552
60	39.625	86.375	0.378	0.333	0.4705	60	40.938	85.063	0.393	0.333	0.5221

IT-1 @ 8 ft



TEST 1 FINAL RESULTS	TEST 2 FINAL RESULTS
Time Weighted Average Permeability Coefficient Km= 0.6992 in/hr	Time Weighted Average Permeability Coefficient Km= 0.6976 in/hr
TEST 3 FINAL RESULTS	TEST 4 FINAL RESULTS
Time Weighted Average Permeability Coefficient Km= 0.6221 in/hr	Time Weighted Average Permeability Coefficient Km= 0.6499 in/hr
AVERAGE IT-1 @ 8 ft	
Time Weighted Average Permeability Coefficient Km= 0.6672 in/hr	

Inspectors Remarks:
24 hour pre-soak started 12/30/2020 at 9:00 AM once the temperature was above freeze point. (Note that the temperature did not drop below freezing point during the pre-soak period)

DEFINITION OF VARIABLES
 *Km= Mean permeability
 T = Temperature of permeant (water), in °C
 Ln = Natural Logarithmic
 t1 = Time at the start of the test in the same units selected for Km
 Rt = Ratio of viscosity of water at test temperature to the viscosity of water at 20°C
 t2= Time at the end of the test in the units selected for Km
 h1= Height of the water above the bottom of the casing at the start of the test in the same units selected for Km
 h2= Height of the water above the bottom of the casing at the end of the test in the same units selected for Km



Prepared for: Marvel Architects, PLLC		PROJECT: Masters School - Innovation and Entrepreneurship Center LOCATION / BOROUGH : Dobbs Ferry, NY	
INSPECTOR: Gilbert Del Orbe	DRILLER: Danny Ninevski	Start Date: 12/31/2020	Weather: 41°F / Light Rain
CONTRACTOR: MFS Construction, LLC	HELPER: Tom Feaser	Start Time: 9:03 AM	
P.E./REP.: Michael Mudalel, PE			
Depth of IT: 7 ft	Drill Bit Type: 3-7/8" TCRB	Weight of Hammer for casing: 140 lbs	
Rig Type: CME 45B	Casing Internal Diameter: 4 in	Type of Hammer: Auto	
	Casing Length: 90 in		

General Formula: Formula for 4" internal diameter casing (in/hr):

ASTM D-6391 – 11 PERMEABILITY COEFFICIENT (Km) FORMULA:

$$K_m = \pi R_t \times \frac{D \left\{ \ln \left(\frac{h_1}{h_2} \right) \right\}}{11 \times (t_2 - t_1)}$$

$$K_m = 1.142 R_t \times \frac{\left[\ln \left(\frac{h_1}{h_2} \right) \right]}{(t_2 - t_1)}$$


where: $R_t = 2.2902(0.9842^T) / T^{0.1702}$

IT-2 @ 7 ft

TEST 1						TEST 2					
Water temperature (°C), T: 7.9			Rt= 1.42			Water temperature (°C), T: 7.5			Rt= 1.44		
FIELD DATA			CALCULATED DATA			FIELD DATA			CALCULATED DATA		
Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)	Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)
10	6.500	83.500	0.075	0.167	0.7299	10	7.000	83.000	0.081	0.167	0.8005
20	13.250	76.750	0.159	0.167	0.8208	20	14.000	76.000	0.169	0.167	0.8711
30	20.000	70.000	0.251	0.167	0.8964	30	20.500	69.500	0.258	0.167	0.8839
40	25.625	64.375	0.335	0.167	0.8157	40	26.500	63.500	0.349	0.167	0.8926
60	35.000	55.000	0.492	0.333	0.7663	60	37.250	52.750	0.534	0.333	0.9168

TEST 3						TEST 4					
Water temperature (°C), T: 7.6			Rt= 1.44			Water temperature (°C), T: 7.4			Rt= 1.45		
FIELD DATA			CALCULATED DATA			FIELD DATA			CALCULATED DATA		
Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)	Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)
10	7.625	82.375	0.089	0.167	0.8718	10	8.000	82.000	0.093	0.167	0.9239
20	14.750	75.250	0.179	0.167	0.8909	20	16.000	74.000	0.196	0.167	1.0188
30	22.125	67.875	0.282	0.167	1.0158	30	23.063	66.937	0.296	0.167	0.9956
40	28.000	62.000	0.373	0.167	0.8916	40	29.625	60.375	0.399	0.167	1.0240
60	39.000	51.000	0.568	0.333	0.9617	60	40.500	49.500	0.598	0.333	0.9855

IT-2 @ 7 ft



TEST 1 FINAL RESULTS	TEST 2 FINAL RESULTS
Time Weighted Average Permeability Coefficient Km= 0.7992 in/hr	Time Weighted Average Permeability Coefficient Km= 0.8803 in/hr
TEST 3 FINAL RESULTS	TEST 4 FINAL RESULTS
Time Weighted Average Permeability Coefficient Km= 0.9323 in/hr	Time Weighted Average Permeability Coefficient Km= 0.9889 in/hr
AVERAGE IT-2 @ 7 ft	
Time Weighted Average Permeability Coefficient Km= 0.9002 in/hr	

Inspectors Remarks:

24 hour pre-soak started 12/30/2020 at 9:00 AM once the temperature was above freeze point. (Note that the temperature did not drop below freezing point during the pre-soak period)

DEFINITION OF VARIABLES

- *Km= Mean permeability
- T = Temperature of permeant (water), in °C
- Ln = Natural Logarithmic
- t1 = Time at the start of the test in the same units selected for Km
- Rt = Ratio of viscosity of water at test temperature to the viscosity of water at 20°C
- t2= Time at the end of the test in the units selected for Km
- h1= Height of the water above the bottom of the casing at the start of the test in the same units selected for Km
- h2= Height of the water above the bottom of the casing at the end of the test in the same units selected for Km



Prepared for: Marvel Architects, PLLC		PROJECT: Masters School - Innovation and Entrepreneurship Center LOCATION / BOROUGH: Dobbs Ferry, NY	
INSPECTOR: Gilbert Del Orbe	DRILLER: Danny Ninevski	Start Date: 12/31/2020	Weather: 41°F / Light Rain
CONTRACTOR: MFS Construction, LLC	HELPER: Tom Feaser	Start Time: 9:05 AM	
P.E./REP.: Michael Mudalel, PE			
Depth of IT: 8 ft	Drill Bit Type: 3-7/8" TCRB	Weight of Hammer for casing: 140 lbs	
Rig Type: CME 45B	Casing Internal Diameter: 4 in	Type of Hammer: Auto	
	Casing Length: 126 in		

General Formula: Formula for 4" internal diameter casing (in/hr):


ASTM D-6391 – 11 PERMEABILITY COEFFICIENT (Km) FORMULA:

$$K_m = \pi R_t \times \frac{D \left\{ \ln \left(\frac{h_1}{h_2} \right) \right\}}{11 \times (t_2 - t_1)}$$

$$K_m = 1.142 R_t \times \frac{\left[\ln \left(\frac{h_1}{h_2} \right) \right]}{(t_2 - t_1)}$$

where: $R_t = 2.2902(0.9842^T) / T^{0.1702}$

IT-3 @ 8 ft						
TEST 1				TEST 2		
Water temperature (°C), T:		8.1	Rt=		1.41	
FIELD DATA		CALCULATED DATA				
Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)	
10	13.000	113.000	0.109	0.167	1.0524	
20	24.875	101.125	0.220	0.167	1.0731	
30	35.000	91.000	0.325	0.167	1.0196	
40	43.875	82.125	0.428	0.167	0.9918	
60	59.000	67.000	0.632	0.333	0.9836	
TEST 3				TEST 4		
Water temperature (°C), T:		7.5	Rt=		1.44	
FIELD DATA		CALCULATED DATA				
Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)	
10	14.750	111.250	0.125	0.167	1.2309	
20	27.063	98.937	0.242	0.167	1.1596	
30	39.625	86.375	0.378	0.167	1.3424	
40	49.500	76.500	0.499	0.167	1.2003	
60	64.875	61.125	0.723	0.333	1.1091	
Water temperature (°C), T:		7.6	Rt=		1.44	
FIELD DATA		CALCULATED DATA				
Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)	
10	14.125	111.875	0.119	0.167	1.1710	
20	26.250	99.750	0.234	0.167	1.1297	
30	37.000	89.000	0.348	0.167	1.1230	
40	47.000	79.000	0.467	0.167	1.1738	
60	63.000	63.000	0.693	0.333	1.1144	
Water temperature (°C), T:		7.5	Rt=		1.44	
FIELD DATA		CALCULATED DATA				
Time (min)	Depth (in)	Height (in)	Ln (H/Ho)	(t ₁ -t ₂)	*Kv (in/hr)	
10	16.000	110.000	0.136	0.167	1.3426	
20	29.000	97.000	0.262	0.167	1.2434	
30	40.250	85.750	0.385	0.167	1.2187	
40	51.000	75.000	0.519	0.167	1.3242	
60	68.250	57.750	0.780	0.333	1.2920	



TEST 1 FINAL RESULTS	TEST 2 FINAL RESULTS
Time Weighted Average Permeability Coefficient Km= 1.0174 in/hr	Time Weighted Average Permeability Coefficient Km= 1.1377 in/hr
TEST 3 FINAL RESULTS	TEST 4 FINAL RESULTS
Time Weighted Average Permeability Coefficient Km= 1.1919 in/hr	Time Weighted Average Permeability Coefficient Km= 1.2855 in/hr

AVERAGE IT-3 @ 8 ft	
Time Weighted Average Permeability Coefficient	Km= 1.1581 in/hr

Inspectors Remarks:
24 hour pre-soak started 12/30/2020 at 9:00 AM once the temperature was above freeze point. (Note that the temperature did not drop below freezing point during the pre-soak period)

DEFINITION OF VARIABLES

*Km= Mean permeability
 T = Temperature of permeant (water), in °C
 Ln = Natural Logarithmic
 t1 = Time at the start of the test in the same units selected for Km
 Rt = Ratio of viscosity of water at test temperature to the viscosity of water at 20°C

t2= Time at the end of the test in the units selected for Km
 h1= Height of the water above the bottom of the casing at the start of the test in the same units selected for Km
 h2= Height of the water above the bottom of the casing at the end of the test in the same units selected for Km

APPENDIX D:
NYS DEC CRITICAL ENVIRONMENTAL AREAS MAP



DECinfo Locator

Base Map: Topographical



Search

Tools

DEC Information Layers

Environmental Quality Outdoor Activity

Permits and Registrations

Environmental Cleanup

Environmental Monitoring

Public Involvement

Environmentally Sensitive Areas


Check / Uncheck all Layer Information

Critical Environmental Areas


Regulatory Tidal Wetlands Areas

Legal Information

Reference Layers



APPENDIX E:
DRAWINGS



51,766 SF (1.19 AC)

EXISTING DRAINAGE AREAS

DRAINAGE AREA	AREA (AC)
EX-01	0.18
EX-02	0.64
EX-03	0.37
TOTAL:	1.19


LEGEND

DRAINAGE AREA BOUNDARY	
FLOW ARROW	
TIME OF CONCENTRATION PATH	

1

EXISTING DRAINAGE AREA PLAN

Scale: 1"=30'




MFS ENGINEERS & SURVEYORS
 MFS CONSULTING ENGINEERS & SURVEYORS, INC.
 110014 ST. SUITE 4001 NEW YORK, NY 10021
 T 212 943 8878 www.MFSengineers.com
 F 212 943 8873
 NY CERTIFICATE OF AUTHORIZATION 002752

PROJECT NAME
 MASTERS SCHOOL OF ENTREPRENEURSHIP
 49 CLINTON AVENUE
 WESTCHESTER COUNTY, NEW YORK

DRAWING FILE
 EXISTING DRAINAGE AREA MAP

PROJECT NO.	122082	SHEET NO.
DATE	7/6/2017	DR-01
SCALE	AS SHOWN	
DRAWN BY	YCM	
CHECKED BY	YEB	1 OF 2



51,766 SF (1.19 AC)

PROPOSED DRAINAGE AREAS

DRAINAGE AREA	AREA (AC)
PR-01	1.05
PR-02	0.14
TOTAL:	1.19


LEGEND

- DRAINAGE AREA BOUNDARY
- FLOW ARROW
- TIME OF CONCENTRATION PATH

1

PROPOSED DRAINAGE AREA PLAN

Scale: 1"=30'



MFS ENGINEERS & SURVEYORS
 MFS CONSULTING ENGINEERS & SURVEYORS, DPC
 31 W 34TH ST SUITE 4071 NEW YORK, NY 10018
 T: 212 943 6576 www.MFSengineers.com
 F: 800-517-2413
 NY CERTIFICATE OF AUTHORIZATION: 0007584



PROJECT NAME
 MASTERS SCHOOL OF ENTREPRENEURSHIP
 49 CLINTON AVENUE
 WESTCHESTER COUNTY
 NEW YORK

DRAWING TITLE
PROPOSED DRAINAGE AREA MAP

PROJECT NO	112092	SHEET NO
DATE	7/6/2021	DR-02
SCALE	AS NOTED	
DRAWN BY	VCM	
CHECKED BY	SEB	2 OF 2




LEGEND	
DEMOLITION & REMOVAL	
EXISTING VEGETATION TO BE REMOVED	[Hatched pattern]
EXISTING ASPHALT TO BE REMOVED	[Dotted pattern]
EXISTING CONCRETE TO BE REMOVED	[Cross-hatched pattern]
EXISTING WELLS TO BE REMOVED	[X symbol]



MARVEL
140 HUDSON STREET, FLOOR 3 NEW YORK, NY 10013
212 478 8400

- OWNER**
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10522
TEL: 914 478 8400
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS**
MARVEL
140 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 212 478 8400
- GEOTECHNICAL CIVIL ENGINEER**
W&B ENGINEERS & SURVEYORS, INC.
200 W. 101st St., 10th Floor
SOUTH PLAINFIELD, NEW JERSEY 07080
TEL: 908 822 4422
- STRUCTURAL ENGINEER**
BULWAK
30 23rd St., FLOOR 10
NEW YORK, NY 10018
TEL: 212 463 7000
- BUILDING SYSTEMS ENGINEER**
PERKINS CORNING ENGINEERS, INC.
133 WEST 91st Street
NEW YORK, NY 10012
TEL: 212 845 1032
- VEHICULAR TRANSPORTATION**
NSA
160 WEST 30th Street, FLOOR 4
NEW YORK, NY 10018
TEL: 212 845 1032
- VEHICULAR TRANSPORTATION**
CONTRIBUTOR ASSOCIATES, INC.
400 W. 10th Street
NEW YORK, NY 10018
TEL: 212 875 3800
- ACADEMIC CONSULTANT**
PERKINS CONSULTANTS
70 BULWER ST. 11th FL.
NEW YORK, NY 10014
TEL: 212 845 1032
- ENVIRONMENTAL CONSULTANT**
W&B ENGINEERS
100 W. 10th St., 11th Floor
NEW YORK, NY 10014
TEL: 212 845 1032
- LIGHTING DESIGNER**
NOT CONSULTING DESIGN
100 W. 10th Street, Suite 400
NEW YORK, NY 10011
TEL: 212 875 3800
- CODE AND ACCESSIBILITY CONSULTANT**
CODE CONSULTANTS, INC.
400 W. 10th Street
NEW YORK, NY 10014
TEL: 212 845 1032
- MECHANICAL, ELECTRICAL, PLUMBING, AND**
CONSTRUCTION SPECIFICATIONS, INC.
22 71st Ave., 10th Fl.
ROCKAWAY, NY 10866
TEL: 718 878 0700
GEOTECHNICAL ENGINEER

REV.	DATE	DESCRIPTION
1	08/11/2021	ISSUANCE OF PERMITS
2	08/11/2021	ISSUANCE OF PERMITS
3	08/22/2021	ISSUANCE OF PERMITS
4	08/31/2021	ISSUANCE OF PERMITS



2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

DEMOLITION & SITE
CLEARING PLAN

SCALE: AS NOTED

DRAWING #
C-300
2 of 10

DOB JOB: -
DOB STAMP ZONE

EXCAVATION & FILL
CUT: 3,600 CY
FILL: 650 CY
NET: 2,950 CY CUT

-PRELIMINARY-
NOT FOR CONSTRUCTION

1 DEMOLITION & SITE CLEARING PLAN
Scale: 1"=10'



MARVEL
140 HUDSON STREET, FLOOR 3, NEW YORK, NY 10013
212.633.8822

- OWNER**
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10522
TEL: 212.434.8822
- PROJECT ARCHITECTS - LANDSCAPE ARCHITECTS**
MARVEL
140 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 212.633.8822
- GEOTECHNICAL / CIVIL ENGINEER**
NEW ENGINEERS & SURVEYORS, P.C.
2100 PARKWAY BOULEVARD, SUITE 200
DOVER, PA 17922
TEL: 717.852.4433
- STRUCTURAL ENGINEER**
BLUMER
30 COLLEGE FLOOR 10
NEW YORK, NY 10003
TEL: 212.633.7979
- BUILDING SYSTEMS ENGINEER**
POKOR CONSTRUCTION ENGINEERS, P.C.
133 WEST 86TH STREET, SUITE 1011
NEW YORK, NY 10024
TEL: 212.465.1300
- VERTICAL TRANSPORTATION**
USA
140 WEST 86TH STREET, FLOOR 4
NEW YORK, NY 10024
TEL: 212.633.8822
- AVIATION SECURITY CONSULTANT**
CONESTOGA ASSOCIATES, INC.
400 SOUTH 9TH AVE, SUITE 100
NEW YORK, NY 10019
TEL: 212.633.8822
- ACQUISITION CONSULTANT**
LETA CONSULTANTS
NEW YORK, NY 10019
TEL: 212.633.8822
- ENVIRONMENTAL CONSULTANT**
ENVIRONMENTAL CONSULTANTS, INC.
140 WEST 86TH STREET, SUITE 1004
NEW YORK, NY 10024
TEL: 212.633.8822
- CONSTRUCTION MANAGEMENT**
CONSTRUCTION MANAGEMENT GROUP, INC.
100 SOUTH STREET, SUITE 400
NEW YORK, NY 10003
TEL: 212.633.8822
- CONSTRUCTION SAFETY CONSULTANT**
COOK CONSULTANTS, INC.
140 WEST 86TH STREET, SUITE 1004
NEW YORK, NY 10024
TEL: 212.633.8822
- ARCHITECTURAL PHOTOGRAPHY**
CONSTRUCTION PHOTOGRAPHY, INC.
22 DEWEY ROAD
MIDWATER, NJ 07045
TEL: 732.975.5100
- GEOTECHNICAL ENGINEER**

REV	DATE	DESCRIPTION
1	08/17/2021	ISSUE FOR PERMIT
2	08/17/2021	REVISED PERMIT APPLICATION
3	01/22/2022	REVISED PERMIT APPLICATION
4	08/31/2021	REVISED PERMIT APPLICATION

08/31/2021

KEY PLAN INTS

2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER

49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10522

CONSTRUCTION
ACCESS PLAN

SCALE: AS NOTED



DRAWING #

C-502

5 of 10


DOB JOB

DOB STAMP ZONE



- NOTES:**
- THE EXISTING SIDEWALK AND CURB WILL ONLY BE DISTURBED AS NECESSARY TO PROVIDE PEDESTRIAN ACCESS TO THE TEMPORARY ENTRANCE SHOULD BE PROVIDED.
 - THE SIDEWALK, CURB AND RIGHT OF WAY SHALL BE RESTORED TO THE SATISFACTION OF THE LOCAL HIGHWAY DEPARTMENT.

(A-A) DRIVEWAY SECTION DETAIL
Scale: NOT TO SCALE



1 CONSTRUCTION ACCESS PLAN
Scale: 1"=20'



DRAWING #

C-502


5 of 10

DOB JOB

DOB STAMP ZONE



LEGEND	
EXISTING CONTOUR	---
PROPOSED HIGH CONTOUR	—+—
PROPOSED MEDIUM CONTOUR	—#—
PROPOSED SPOT ELEVATION	453.7'
SLOPE ARROW	↗ 1.5%
PROPOSED SPOT ELEVATION	300.00'
PROPOSED SPOT WALL ELEVATION	10.10.10.00'



MARVEL
140 HUDSON STREET, FLR 3 NEW YORK, NY 10013
312.674.8100

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NY 10027
TEL: 914 474 8400

PROJECT ARCHITECT'S / LANDSCAPE ARCHITECTS
MARVEL
140 HUDSON STREET, FLOOR 3
NEW YORK, NY 10013
TEL: 312 674 8100

GEOTECHNICAL / CIVIL ENGINEER
MFE ENGINEERS & SURVEYORS, P.C.
210 N. HAVEN, DR. BLDG. 4, 10TH FL.
SOUTH PLAINFIELD, NEW JERSEY 07080
TEL: 908 822 4522

STRUCTURAL ENGINEER
BLMAN
300 CLINTON FLOOR 10
NEW YORK, NEW YORK 10003
TEL: 212 692 9100

BUILDING SYSTEMS ENGINEER
POLISE CONSULTING ENGINEERS, P.C.
103 WEST 96TH STREET
NEW YORK, NEW YORK 10024
TEL: 212 646 1900

MECHANICAL ENGINEER
MVA
40 WEST 86TH STREET, FLOOR 4
NEW YORK, NEW YORK 10024
TEL: 212 698 8800

ARCHITECTURAL SECURITY CONSULTANT
CORRENT ASSOCIATES, INC.
408 BROADWAY, 14TH FL.
NEW YORK, NEW YORK 10018
TEL: 212 693 3600

ACQUISITION CONSULTANT
LBY CONSULTANTS
150 BROADWAY, 15TH FL.
NEW YORK, NEW YORK 10003
TEL: 212 693 8100

ENVIRONMENTAL ENGINEER
LWGLCONS CONSULTANTS
300 WEST 34TH STREET, FLOOR 14
NEW YORK, NEW YORK 10018
TEL: 212 693 8700

LIGHTING DESIGNER
DOT DESIGN LIGHTING DESIGN
105 ANKENY STREET, SUITE 400
NEW YORK, NEW YORK 10013
TEL: 212 693 8100

CODE AND ACCESSIBILITY CONSULTANT
CODE CONSULTANTS, INC.
442 PARK AVENUE, 5TH FL.
NEW YORK, NEW YORK 10017
TEL: 212 693 4500

CONSTRUCTION SUPERVISION
CONSTRUCTION APPLICATIONS, INC.
25 SUMMIT ROAD
MONTICELLO, NEW JERSEY 07075
TEL: 732 978 3100

GEOTECHNICAL ENGINEER

REV	DATE	DESCRIPTION
1	02/11/2024	ISSUE FOR DOCS
2	06/11/2024	COMPLETE SITE ACTION
3	01/22/2025	SITE ACTION SUBMITTAL
4	08/31/2025	SITE ACTION SUBMITTAL

08/31/2025

KEY PLAN NTS

2029
**THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER**

49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10027

PROPOSED GRADING
& DRAINAGE PLAN


SCALE: AS NOTED

DRAWING #
C-600
6 of 10
DOB JOB #

DOB STAMP ZONE


1 GRADING & DRAINAGE PLAN
Scale: 1"=40'

-PRELIMINARY-
NOT FOR CONSTRUCTION





LEGEND	
PROPERTY LINE	---
PROPOSED ELECTRIC SERVICE	—E—E—E—
PROPOSED SANITARY SERVICE	—S—S—S—
PROPOSED GAS SERVICE	—G—G—G—
PROPOSED FIRE WATER SERVICE	—FW—FW—FW—
PROPOSED WATER SERVICE	—W—W—W—
PROPOSED TELECOM SERVICE	—T—T—T—



MARVEL
 140 HANCOCK STREET, FLOOR 3 NEW YORK, NY 10013
 212.678.3400

OWNER
THE MASTERS SCHOOL
 49 CLINTON AVENUE
 DOBBS FERRY, NY 10022
 TEL: 212.678.3400

PROJECT ARCHITECT
LANDSCAPE ARCHITECTS
MARVEL
 140 HANCOCK STREET, FLOOR 3
 NEW YORK, NY 10013
 TEL: 212.678.3400

GEOTECHNICAL / CIVIL ENGINEER
M&E ENGINEERS & SURVEYORS, P.C.
 210 W. 101ST STREET, 10TH FLOOR
 SOUTH PLAZA 10.1 NEW YORK, NY 10024
 TEL: 212.678.3400

STRUCTURAL ENGINEER
BLUM
 32 E. 23RD STREET, FLOOR 10
 NEW YORK, NY 10010
 TEL: 212.678.3400

BUILDING SYSTEMS ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

AV / IT SECURITY CONSULTANT
CONSENTING ASSOCIATES, INC.
 100 W. 42ND STREET, 10TH FLOOR
 NEW YORK, NY 10018
 TEL: 212.678.3400

ACQUISITION CONSULTANT
LETT CONSULTANTS
 16 W. 42ND STREET, 10TH FLOOR
 NEW YORK, NY 10018
 TEL: 212.678.3400

ENVIRONMENTAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500


MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500

MECHANICAL ENGINEER
PCME CONSULTING ENGINEERS, P.C.
 133 WEST 19TH STREET
 NEW YORK, NY 10011
 TEL: 212.641.1500



REV	DATE	DESCRIPTION
1	02/11/2021	ISSUANCE OF DOBISB
2	06/11/2021	COMPLETE APPLICATION
3	07/22/2021	REVISIONS
4	08/31/2021	FINAL APPLICATION

08/31/2021

KEY PLAN NTS

2029
**THE MASTERS SCHOOL
 INNOVATION AND
 ENTREPRENEURSHIP
 CENTER**
 49 CLINTON AVENUE
 DOBBS FERRY, NEW YORK 10022

UTILITY PLAN

SCALE: AS NOTED

-PRELIMINARY-
 NOT FOR CONSTRUCTION

DRAWING #
C-700
 7 of 10

DOB JOB #

DOB STAMP ZONE

1 UTILITY RELOCATION PLAN
 Scale: 1"=10'



DATE PLOTTED: 08/31/2021 10:00:00 AM



MARVEL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10322
TEL: 914 849 9400

OWNER
THE MASTERS SCHOOL
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10322
TEL: 914 849 9400

PROJECT ARCHITECTS / LANDSCAPE ARCHITECTS
MARVEL
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 212 419 4200

MECHANICAL, ELECTRICAL & PLUMBING ENGINEER
WSP | PARSONS
200 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

STRUCTURAL ENGINEER
BLUM
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

BUILDING SYSTEMS ENGINEER
BLUM
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

OPTICAL TRANSPORTATION
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

ACQUISITION CONSULTANT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400


CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400


CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400

CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400


CONSTRUCTION MANAGEMENT
VEA
100 WEST STREET, FLOOR 3
NEW YORK, NEW YORK 10037
TEL: 914 849 9400




1 STANDARD BELGIAN BLOCK CURB DETAIL
Scale: N.T.S.




2 STANDARD ASPHALT PAVEMENT DETAIL
Scale: N.T.S.




3 STANDARD CURB CUT DETAIL
Scale: N.T.S.




4 HANDICAP STALL MARKINGS DETAIL
Scale: N.T.S.




5 HANDICAP PARKING SIGN w/VAN ACCESSIBLE SIGN
Scale: N.T.S.




6 STANDARD FIRE HYDRANT DETAIL
Scale: N.T.S.




7 STANDARD CHAIN LINKED FENCE DETAIL
Scale: N.T.S.




8 STANDARD AREA DRAIN DETAIL
Scale: N.T.S.




9 STANDARD SILT FENCE DETAIL
Scale: N.T.S.




10 STANDARD SUPER SILT FENCE DETAIL
Scale: N.T.S.




11 PRECAST CONCRETE SANITARY SEWER MANHOLE DETAIL
Scale: N.T.S.



12 STANDARD FILTER FABRIC DROP INLET PROTECTION DETAIL
Scale: N.T.S.




13 STANDARD CONSTRUCTION ENTRANCE DETAIL
Scale: N.T.S.




14 TOPSOIL STOCKPILE DETAIL
Scale: N.T.S.




15 UTILITY TRENCHING DETAIL
Scale: N.T.S.




16 PEDESTRIAN CURB RAMP DETAIL
Scale: N.T.S.




17 CROSSWALK STRIPING DETAIL
Scale: N.T.S.




18 OUTLET CONTROL STRUCTURE DETAIL
Scale: N.T.S.




19 STANDARD CONSTRUCTION SPECIFICATION FOR STABILIZED ACCESS
Scale: N.T.S.




20 STANDARD CONSTRUCTION SPECIFICATION FOR STABILIZED ACCESS
Scale: N.T.S.



21 STANDARD CONSTRUCTION SPECIFICATION FOR STABILIZED ACCESS
Scale: N.T.S.



22 STANDARD CONSTRUCTION SPECIFICATION FOR STABILIZED ACCESS
Scale: N.T.S.



23 STANDARD CONSTRUCTION SPECIFICATION FOR STABILIZED ACCESS
Scale: N.T.S.

REV	DATE	DESCRIPTION
1	08/31/2021	REVISIONS TO CORRECT PERMITS APPLICATION SITE APPLICATION REVISIONS
2	08/31/2021	REVISIONS TO CORRECT PERMITS APPLICATION SITE APPLICATION REVISIONS
3	08/31/2021	REVISIONS TO CORRECT PERMITS APPLICATION SITE APPLICATION REVISIONS
4	08/31/2021	REVISIONS TO CORRECT PERMITS APPLICATION SITE APPLICATION REVISIONS

08/31/2021

KEY PLAN NTS

2029
THE MASTERS SCHOOL
INNOVATION AND
ENTREPRENEURSHIP
CENTER
49 CLINTON AVENUE
DOBBS FERRY, NEW YORK 10322

CONSTRUCTION
DETAILS

SCALE: AS NOTED

DRAWING #
C-900
9 of 10
DOB JOB

DOB STAMP ZONE

APPENDIX F:
POST CONSTRUCTION INSPECTION AND MAINTENANCE CHECKLIST
UNDERGROUND INFILTRATION SYSTEM

Post Construction Inspection and Maintenance Checklist Underground Infiltration System

1. Inlet and Outlet Structures (Frequency: Annual)

Yes No NA

- | | | | |
|---|--------------------------|--------------------------|--------------------------|
| a. Concrete structure | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| i. In good condition, no need for repairs. | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| a. Cracks or displacement.
<i>Maintenance: Repair any minor cracks. If minor displacement is observed, re-inspect in 6 months. Replace structure if major cracks or significant displacement is observed.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| b. Minor spalling (<1").
<i>Maintenance: Repair any minor spalling.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| c. Major spalling (rebars exposed).
<i>Maintenance: Replace structure.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| d. Joint failures.
<i>Maintenance: Replace structure.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| e. Water tightness.
<i>Maintenance: Reseal structure for water tightness if minor leaks are observed. Replace structure if significant leaks are observed.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| ii. Clear of sediment.
<i>Maintenance: Remove and properly dispose of any accumulated sediment when at 50% of sump height.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| iii. Clear of debris and trash.
<i>Maintenance: Remove and properly dispose of any debris and trash.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| iv. Pipes free from damage, corrosion, and sediment.
<i>Maintenance: Immediately repair any damaged pipes. If pipes are severely damaged and cannot be repaired, replace the pipes. Remove and properly dispose of any sediment.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

2. Header System

(Frequency: Annual)

Yes No NA

- | | | | |
|--|--------------------------|--------------------------|--------------------------|
| a. Clear of debris and litter.
<i>Maintenance: Use a high pressure nozzle with rear facing jets to wash the sediment and debris into the upstream structure. Remove sediment and debris from the sump of the upstream structure.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| b. Clear of sediment.
<i>Maintenance: Remove and properly dispose of sediment when accumulated over 4 inches. Use a high pressure nozzle with rear facing jets to wash the sediment into the upstream structure. Remove sediment from the sump of the upstream structure.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

3. Isolator/Containment Row
(Frequency: Annual)

Yes No NA

- a. Clear of debris and litter.
Maintenance: Remove and properly dispose of any debris and trash. Use a high pressure nozzle with rear facing jets to wash the debris into the upstream structure. Remove debris from the sump of the upstream structure.
- b. Clear of sediment.
Maintenance: Remove and properly dispose of sediment when accumulated over 4 inches. Use a high pressure nozzle with rear facing jets to wash the sediment into the upstream structure. Remove sediment from the sump of the upstream structure.

4. Underground Chambers
(Frequency: Annual)

Yes No NA

- a. Chambers are in good condition.
Maintenance: Inspect the interior of the chambers using a CCTV or comparable inspection method through the inspection port. If deficiencies are noted immediately contact a NYS licensed Professional Engineer.
- b. Clear of debris and litter.
Maintenance: Remove and properly dispose of any debris and trash. Use a high pressure nozzle with rear facing jets to wash the debris into the upstream structure. Remove debris from the sump of the upstream structure.
- c. Clear of sediment.
Maintenance: Remove and properly dispose of sediment when accumulated over 4 inches. Use a high pressure nozzle with rear facing jets to wash the sediment into the upstream structure. Remove sediment from the sump of the upstream structure.
- d. Dewater between storms.
Maintenance: If standing water during inspection, recheck after 48 hours. If standing water is still present, contact a NYS licensed Professional Engineer.

5. Surrounding Site
(Frequency: Monthly)

Yes No NA

- a. Vegetation and ground cover adequate.
Maintenance: Reseed bare areas. Remove any unauthorized plants or any nuisance weeds and vegetation, including their roots. Do not use any herbicides. Topsoil, rake and seed the disturbed area by their removal.
- b. Area free from depressions.
Maintenance: Immediately repair. Re-grade and compact the soil. Topsoil, rake and seed the area. Re-inspect in 6 months.

Dobbs Ferry, New York

- | | Yes | No | NA |
|---|--------------------------|--------------------------|--------------------------|
| c. Unauthorized plants over system.
<i>Maintenance: Remove any unauthorized plants, including roots. Do not use herbicides. Topsoil, rake and seed the area disturbed by their removal.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| d. Unauthorized structures over system.
<i>Maintenance: Remove any unauthorized structures. Immediately inspect the interior of the chambers using a CCTV or comparable inspection method through the inspection port. If deficiencies are noted immediately contact a NYS licensed Professional Engineer.</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Notes:

1. The site must be returned to the approved conditions when any repairs are made.
2. All seed mixtures shall meet the seed mixture requirements specified on the approved plans.


Comments:

Actions to be taken:

**APPENDIX G:
SUPPORTING CALCULATIONS**



EX-1 (Pre) EX-2 (Pre) EX-3 (Pre)



Pre-Existing
(Composite)



Subcat



Reach



Pond



Link

Project Notes

Defined 10 rainfall events from NY-Westchester IDF

Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
1.193	74	>75% Grass cover, Good, HSG C (1S, 2S, 3S)
1.193	74	TOTAL AREA

Soil Listing (all nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
1.193	HSG C	1S, 2S, 3S
0.000	HSG D	
0.000	Other	
1.193		TOTAL AREA

Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	1.193	0.000	0.000	1.193	>75% Grass cover, Good	1S, 2S, 3S
0.000	0.000	1.193	0.000	0.000	1.193	TOTAL AREA	

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: EX-1 (Pre)

Runoff Area=0.180 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=260' Tc=6.6 min CN=74 Runoff=0.16 cfs 0.012 af

Subcatchment2S: EX-2 (Pre)

Runoff Area=0.640 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=330' Tc=7.2 min CN=74 Runoff=0.57 cfs 0.042 af

Subcatchment3S: EX-3 (Pre)

Runoff Area=0.373 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=280' Tc=10.7 min CN=74 Runoff=0.30 cfs 0.024 af

Link 5L: Pre-Existing (Composite)

Inflow=0.99 cfs 0.078 af
Primary=0.99 cfs 0.078 af

Total Runoff Area = 1.193 ac Runoff Volume = 0.078 af Average Runoff Depth = 0.78"
100.00% Pervious = 1.193 ac 0.00% Impervious = 0.000 ac

Summary for Subcatchment 1S: EX-1 (Pre)

Runoff = 0.16 cfs @ 12.11 hrs, Volume= 0.012 af, Depth> 0.78"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=2.93"

Area (ac)	CN	Description
0.180	74	>75% Grass cover, Good, HSG C
0.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.3	160	0.0812	1.99		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
6.6	260	Total			

Subcatchment 1S: EX-1 (Pre)

Hydrograph



Hydrograph for Subcatchment 1S: EX-1 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.17	0.00	0.00	18.00	2.72	0.74	0.01
5.25	0.18	0.00	0.00	18.25	2.73	0.74	0.01
5.50	0.19	0.00	0.00	18.50	2.74	0.75	0.00
5.75	0.20	0.00	0.00	18.75	2.75	0.76	0.00
6.00	0.21	0.00	0.00	19.00	2.76	0.76	0.00
6.25	0.22	0.00	0.00	19.25	2.77	0.77	0.00
6.50	0.24	0.00	0.00	19.50	2.78	0.77	0.00
6.75	0.25	0.00	0.00	19.75	2.79	0.78	0.00
7.00	0.27	0.00	0.00	20.00	2.80	0.79	0.00
7.25	0.28	0.00	0.00				
7.50	0.30	0.00	0.00				
7.75	0.32	0.00	0.00				
8.00	0.33	0.00	0.00				
8.25	0.35	0.00	0.00				
8.50	0.38	0.00	0.00				
8.75	0.40	0.00	0.00				
9.00	0.43	0.00	0.00				
9.25	0.46	0.00	0.00				
9.50	0.49	0.00	0.00				
9.75	0.52	0.00	0.00				
10.00	0.55	0.00	0.00				
10.25	0.59	0.00	0.00				
10.50	0.63	0.00	0.00				
10.75	0.68	0.00	0.00				
11.00	0.73	0.00	0.00				
11.25	0.79	0.00	0.00				
11.50	0.87	0.01	0.00				
11.75	1.04	0.03	0.02				
12.00	1.46	0.14	0.08				
12.25	1.89	0.30	0.10				
12.50	2.06	0.38	0.05				
12.75	2.14	0.42	0.03				
13.00	2.20	0.45	0.02				
13.25	2.25	0.47	0.02				
13.50	2.30	0.50	0.02				
13.75	2.34	0.52	0.02				
14.00	2.38	0.54	0.01				
14.25	2.41	0.56	0.01				
14.50	2.44	0.58	0.01				
14.75	2.47	0.59	0.01				
15.00	2.50	0.61	0.01				
15.25	2.53	0.62	0.01				
15.50	2.55	0.64	0.01				
15.75	2.58	0.65	0.01				
16.00	2.60	0.66	0.01				
16.25	2.61	0.67	0.01				
16.50	2.63	0.68	0.01				
16.75	2.65	0.69	0.01				
17.00	2.66	0.70	0.01				
17.25	2.68	0.71	0.01				
17.50	2.69	0.72	0.01				
17.75	2.71	0.73	0.01				

Summary for Subcatchment 2S: EX-2 (Pre)

Runoff = 0.57 cfs @ 12.12 hrs, Volume= 0.042 af, Depth> 0.78"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=2.93"

Area (ac)	CN	Description
0.640	74	>75% Grass cover, Good, HSG C
0.640		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.9	230	0.0840	2.03		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
7.2	330	Total			

Subcatchment 2S: EX-2 (Pre)

Hydrograph



Hydrograph for Subcatchment 2S: EX-2 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.17	0.00	0.00	18.00	2.72	0.74	0.02
5.25	0.18	0.00	0.00	18.25	2.73	0.74	0.02
5.50	0.19	0.00	0.00	18.50	2.74	0.75	0.02
5.75	0.20	0.00	0.00	18.75	2.75	0.76	0.02
6.00	0.21	0.00	0.00	19.00	2.76	0.76	0.02
6.25	0.22	0.00	0.00	19.25	2.77	0.77	0.02
6.50	0.24	0.00	0.00	19.50	2.78	0.77	0.02
6.75	0.25	0.00	0.00	19.75	2.79	0.78	0.02
7.00	0.27	0.00	0.00	20.00	2.80	0.79	0.02
7.25	0.28	0.00	0.00				
7.50	0.30	0.00	0.00				
7.75	0.32	0.00	0.00				
8.00	0.33	0.00	0.00				
8.25	0.35	0.00	0.00				
8.50	0.38	0.00	0.00				
8.75	0.40	0.00	0.00				
9.00	0.43	0.00	0.00				
9.25	0.46	0.00	0.00				
9.50	0.49	0.00	0.00				
9.75	0.52	0.00	0.00				
10.00	0.55	0.00	0.00				
10.25	0.59	0.00	0.00				
10.50	0.63	0.00	0.00				
10.75	0.68	0.00	0.00				
11.00	0.73	0.00	0.00				
11.25	0.79	0.00	0.01				
11.50	0.87	0.01	0.01				
11.75	1.04	0.03	0.06				
12.00	1.46	0.14	0.26				
12.25	1.89	0.30	0.36				
12.50	2.06	0.38	0.19				
12.75	2.14	0.42	0.10				
13.00	2.20	0.45	0.08				
13.25	2.25	0.47	0.07				
13.50	2.30	0.50	0.06				
13.75	2.34	0.52	0.06				
14.00	2.38	0.54	0.05				
14.25	2.41	0.56	0.05				
14.50	2.44	0.58	0.05				
14.75	2.47	0.59	0.04				
15.00	2.50	0.61	0.04				
15.25	2.53	0.62	0.04				
15.50	2.55	0.64	0.04				
15.75	2.58	0.65	0.03				
16.00	2.60	0.66	0.03				
16.25	2.61	0.67	0.03				
16.50	2.63	0.68	0.03				
16.75	2.65	0.69	0.03				
17.00	2.66	0.70	0.02				
17.25	2.68	0.71	0.02				
17.50	2.69	0.72	0.02				
17.75	2.71	0.73	0.02				

Summary for Subcatchment 3S: EX-3 (Pre)

Runoff = 0.30 cfs @ 12.17 hrs, Volume= 0.024 af, Depth> 0.78"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=2.93"

Area (ac)	CN	Description
0.373	74	>75% Grass cover, Good, HSG C
0.373		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.3	100	0.0200	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.4	180	0.0972	2.18		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
10.7	280	Total			

Subcatchment 3S: EX-3 (Pre)

Hydrograph



Hydrograph for Subcatchment 3S: EX-3 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.17	0.00	0.00	18.00	2.72	0.74	0.01
5.25	0.18	0.00	0.00	18.25	2.73	0.74	0.01
5.50	0.19	0.00	0.00	18.50	2.74	0.75	0.01
5.75	0.20	0.00	0.00	18.75	2.75	0.76	0.01
6.00	0.21	0.00	0.00	19.00	2.76	0.76	0.01
6.25	0.22	0.00	0.00	19.25	2.77	0.77	0.01
6.50	0.24	0.00	0.00	19.50	2.78	0.77	0.01
6.75	0.25	0.00	0.00	19.75	2.79	0.78	0.01
7.00	0.27	0.00	0.00	20.00	2.80	0.79	0.01
7.25	0.28	0.00	0.00				
7.50	0.30	0.00	0.00				
7.75	0.32	0.00	0.00				
8.00	0.33	0.00	0.00				
8.25	0.35	0.00	0.00				
8.50	0.38	0.00	0.00				
8.75	0.40	0.00	0.00				
9.00	0.43	0.00	0.00				
9.25	0.46	0.00	0.00				
9.50	0.49	0.00	0.00				
9.75	0.52	0.00	0.00				
10.00	0.55	0.00	0.00				
10.25	0.59	0.00	0.00				
10.50	0.63	0.00	0.00				
10.75	0.68	0.00	0.00				
11.00	0.73	0.00	0.00				
11.25	0.79	0.00	0.00				
11.50	0.87	0.01	0.01				
11.75	1.04	0.03	0.03				
12.00	1.46	0.14	0.11				
12.25	1.89	0.30	0.25				
12.50	2.06	0.38	0.13				
12.75	2.14	0.42	0.06				
13.00	2.20	0.45	0.05				
13.25	2.25	0.47	0.04				
13.50	2.30	0.50	0.04				
13.75	2.34	0.52	0.03				
14.00	2.38	0.54	0.03				
14.25	2.41	0.56	0.03				
14.50	2.44	0.58	0.03				
14.75	2.47	0.59	0.03				
15.00	2.50	0.61	0.02				
15.25	2.53	0.62	0.02				
15.50	2.55	0.64	0.02				
15.75	2.58	0.65	0.02				
16.00	2.60	0.66	0.02				
16.25	2.61	0.67	0.02				
16.50	2.63	0.68	0.02				
16.75	2.65	0.69	0.01				
17.00	2.66	0.70	0.01				
17.25	2.68	0.71	0.01				
17.50	2.69	0.72	0.01				
17.75	2.71	0.73	0.01				


Summary for Link 5L: Pre-Existing (Composite)

Inflow Area = 1.193 ac, 0.00% Impervious, Inflow Depth > 0.78" for 1-yr event
 Inflow = 0.99 cfs @ 12.13 hrs, Volume= 0.078 af
 Primary = 0.99 cfs @ 12.13 hrs, Volume= 0.078 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Pre-Existing (Composite)

Hydrograph



Hydrograph for Link 5L: Pre-Existing (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
5.00	0.00	0.00	0.00	18.00	0.03	0.00	0.03
5.25	0.00	0.00	0.00	18.25	0.03	0.00	0.03
5.50	0.00	0.00	0.00	18.50	0.03	0.00	0.03
5.75	0.00	0.00	0.00	18.75	0.03	0.00	0.03
6.00	0.00	0.00	0.00	19.00	0.03	0.00	0.03
6.25	0.00	0.00	0.00	19.25	0.03	0.00	0.03
6.50	0.00	0.00	0.00	19.50	0.03	0.00	0.03
6.75	0.00	0.00	0.00	19.75	0.03	0.00	0.03
7.00	0.00	0.00	0.00	20.00	0.03	0.00	0.03
7.25	0.00	0.00	0.00				
7.50	0.00	0.00	0.00				
7.75	0.00	0.00	0.00				
8.00	0.00	0.00	0.00				
8.25	0.00	0.00	0.00				
8.50	0.00	0.00	0.00				
8.75	0.00	0.00	0.00				
9.00	0.00	0.00	0.00				
9.25	0.00	0.00	0.00				
9.50	0.00	0.00	0.00				
9.75	0.00	0.00	0.00				
10.00	0.00	0.00	0.00				
10.25	0.00	0.00	0.00				
10.50	0.00	0.00	0.00				
10.75	0.00	0.00	0.00				
11.00	0.00	0.00	0.00				
11.25	0.01	0.00	0.01				
11.50	0.03	0.00	0.03				
11.75	0.10	0.00	0.10				
12.00	0.45	0.00	0.45				
12.25	0.71	0.00	0.71				
12.50	0.38	0.00	0.38				
12.75	0.19	0.00	0.19				
13.00	0.15	0.00	0.15				
13.25	0.13	0.00	0.13				
13.50	0.12	0.00	0.12				
13.75	0.11	0.00	0.11				
14.00	0.10	0.00	0.10				
14.25	0.09	0.00	0.09				
14.50	0.09	0.00	0.09				
14.75	0.08	0.00	0.08				
15.00	0.08	0.00	0.08				
15.25	0.07	0.00	0.07				
15.50	0.07	0.00	0.07				
15.75	0.06	0.00	0.06				
16.00	0.06	0.00	0.06				
16.25	0.05	0.00	0.05				
16.50	0.05	0.00	0.05				
16.75	0.05	0.00	0.05				
17.00	0.04	0.00	0.04				
17.25	0.04	0.00	0.04				
17.50	0.04	0.00	0.04				
17.75	0.04	0.00	0.04				

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: EX-1 (Pre)

Runoff Area=0.180 ac 0.00% Impervious Runoff Depth>2.59"
Flow Length=260' Tc=6.6 min CN=74 Runoff=0.57 cfs 0.039 af

Subcatchment2S: EX-2 (Pre)

Runoff Area=0.640 ac 0.00% Impervious Runoff Depth>2.59"
Flow Length=330' Tc=7.2 min CN=74 Runoff=1.98 cfs 0.138 af

Subcatchment3S: EX-3 (Pre)

Runoff Area=0.373 ac 0.00% Impervious Runoff Depth>2.59"
Flow Length=280' Tc=10.7 min CN=74 Runoff=1.03 cfs 0.081 af

Link 5L: Pre-Existing (Composite)

Inflow=3.51 cfs 0.258 af
Primary=3.51 cfs 0.258 af

Total Runoff Area = 1.193 ac Runoff Volume = 0.258 af Average Runoff Depth = 2.59"
100.00% Pervious = 1.193 ac 0.00% Impervious = 0.000 ac

Summary for Subcatchment 1S: EX-1 (Pre)

Runoff = 0.57 cfs @ 12.10 hrs, Volume= 0.039 af, Depth> 2.59"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.53"

Area (ac)	CN	Description
0.180	74	>75% Grass cover, Good, HSG C
0.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.3	160	0.0812	1.99		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
6.6	260	Total			

Subcatchment 1S: EX-1 (Pre)

Hydrograph



Hydrograph for Subcatchment 1S: EX-1 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.31	0.00	0.00	18.00	5.13	2.47	0.01
5.25	0.33	0.00	0.00	18.25	5.15	2.49	0.01
5.50	0.35	0.00	0.00	18.50	5.18	2.50	0.01
5.75	0.38	0.00	0.00	18.75	5.20	2.52	0.01
6.00	0.40	0.00	0.00	19.00	5.22	2.54	0.01
6.25	0.42	0.00	0.00	19.25	5.24	2.55	0.01
6.50	0.45	0.00	0.00	19.50	5.26	2.57	0.01
6.75	0.47	0.00	0.00	19.75	5.27	2.58	0.01
7.00	0.50	0.00	0.00	20.00	5.29	2.60	0.01
7.25	0.53	0.00	0.00				
7.50	0.56	0.00	0.00				
7.75	0.60	0.00	0.00				
8.00	0.63	0.00	0.00				
8.25	0.67	0.00	0.00				
8.50	0.71	0.00	0.00				
8.75	0.76	0.00	0.00				
9.00	0.81	0.00	0.00				
9.25	0.86	0.01	0.00				
9.50	0.92	0.01	0.00				
9.75	0.98	0.02	0.01				
10.00	1.05	0.03	0.01				
10.25	1.12	0.04	0.01				
10.50	1.20	0.06	0.01				
10.75	1.29	0.08	0.02				
11.00	1.38	0.11	0.02				
11.25	1.50	0.15	0.03				
11.50	1.65	0.20	0.04				
11.75	1.96	0.33	0.11				
12.00	2.76	0.76	0.32				
12.25	3.57	1.29	0.31				
12.50	3.88	1.51	0.15				
12.75	4.03	1.62	0.08				
13.00	4.15	1.71	0.06				
13.25	4.24	1.78	0.05				
13.50	4.33	1.84	0.05				
13.75	4.41	1.91	0.04				
14.00	4.48	1.96	0.04				
14.25	4.55	2.01	0.04				
14.50	4.61	2.06	0.03				
14.75	4.67	2.10	0.03				
15.00	4.72	2.15	0.03				
15.25	4.77	2.19	0.03				
15.50	4.82	2.22	0.03				
15.75	4.86	2.25	0.02				
16.00	4.90	2.28	0.02				
16.25	4.93	2.31	0.02				
16.50	4.97	2.34	0.02				
16.75	5.00	2.36	0.02				
17.00	5.03	2.39	0.02				
17.25	5.06	2.41	0.02				
17.50	5.08	2.43	0.02				
17.75	5.11	2.45	0.01				

Summary for Subcatchment 2S: EX-2 (Pre)

Runoff = 1.98 cfs @ 12.11 hrs, Volume= 0.138 af, Depth> 2.59"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.53"

Area (ac)	CN	Description
0.640	74	>75% Grass cover, Good, HSG C
0.640		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.9	230	0.0840	2.03		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
7.2	330	Total			

Subcatchment 2S: EX-2 (Pre)

Hydrograph



Hydrograph for Subcatchment 2S: EX-2 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.31	0.00	0.00	18.00	5.13	2.47	0.05
5.25	0.33	0.00	0.00	18.25	5.15	2.49	0.05
5.50	0.35	0.00	0.00	18.50	5.18	2.50	0.04
5.75	0.38	0.00	0.00	18.75	5.20	2.52	0.04
6.00	0.40	0.00	0.00	19.00	5.22	2.54	0.04
6.25	0.42	0.00	0.00	19.25	5.24	2.55	0.04
6.50	0.45	0.00	0.00	19.50	5.26	2.57	0.04
6.75	0.47	0.00	0.00	19.75	5.27	2.58	0.04
7.00	0.50	0.00	0.00	20.00	5.29	2.60	0.04
7.25	0.53	0.00	0.00				
7.50	0.56	0.00	0.00				
7.75	0.60	0.00	0.00				
8.00	0.63	0.00	0.00				
8.25	0.67	0.00	0.00				
8.50	0.71	0.00	0.00				
8.75	0.76	0.00	0.00				
9.00	0.81	0.00	0.01				
9.25	0.86	0.01	0.01				
9.50	0.92	0.01	0.01				
9.75	0.98	0.02	0.02				
10.00	1.05	0.03	0.03				
10.25	1.12	0.04	0.03				
10.50	1.20	0.06	0.05				
10.75	1.29	0.08	0.06				
11.00	1.38	0.11	0.07				
11.25	1.50	0.15	0.10				
11.50	1.65	0.20	0.14				
11.75	1.96	0.33	0.36				
12.00	2.76	0.76	1.06				
12.25	3.57	1.29	1.14				
12.50	3.88	1.51	0.55				
12.75	4.03	1.62	0.28				
13.00	4.15	1.71	0.22				
13.25	4.24	1.78	0.19				
13.50	4.33	1.84	0.17				
13.75	4.41	1.91	0.16				
14.00	4.48	1.96	0.14				
14.25	4.55	2.01	0.13				
14.50	4.61	2.06	0.12				
14.75	4.67	2.10	0.12				
15.00	4.72	2.15	0.11				
15.25	4.77	2.19	0.10				
15.50	4.82	2.22	0.09				
15.75	4.86	2.25	0.08				
16.00	4.90	2.28	0.08				
16.25	4.93	2.31	0.07				
16.50	4.97	2.34	0.07				
16.75	5.00	2.36	0.06				
17.00	5.03	2.39	0.06				
17.25	5.06	2.41	0.06				
17.50	5.08	2.43	0.05				
17.75	5.11	2.45	0.05				

Summary for Subcatchment 3S: EX-3 (Pre)

Runoff = 1.03 cfs @ 12.15 hrs, Volume= 0.081 af, Depth> 2.59"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.53"

Area (ac)	CN	Description
0.373	74	>75% Grass cover, Good, HSG C
0.373		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.3	100	0.0200	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.4	180	0.0972	2.18		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
10.7	280	Total			

Subcatchment 3S: EX-3 (Pre)

Hydrograph



Hydrograph for Subcatchment 3S: EX-3 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.31	0.00	0.00	18.00	5.13	2.47	0.03
5.25	0.33	0.00	0.00	18.25	5.15	2.49	0.03
5.50	0.35	0.00	0.00	18.50	5.18	2.50	0.03
5.75	0.38	0.00	0.00	18.75	5.20	2.52	0.03
6.00	0.40	0.00	0.00	19.00	5.22	2.54	0.02
6.25	0.42	0.00	0.00	19.25	5.24	2.55	0.02
6.50	0.45	0.00	0.00	19.50	5.26	2.57	0.02
6.75	0.47	0.00	0.00	19.75	5.27	2.58	0.02
7.00	0.50	0.00	0.00	20.00	5.29	2.60	0.02
7.25	0.53	0.00	0.00				
7.50	0.56	0.00	0.00				
7.75	0.60	0.00	0.00				
8.00	0.63	0.00	0.00				
8.25	0.67	0.00	0.00				
8.50	0.71	0.00	0.00				
8.75	0.76	0.00	0.00				
9.00	0.81	0.00	0.00				
9.25	0.86	0.01	0.01				
9.50	0.92	0.01	0.01				
9.75	0.98	0.02	0.01				
10.00	1.05	0.03	0.01				
10.25	1.12	0.04	0.02				
10.50	1.20	0.06	0.03				
10.75	1.29	0.08	0.03				
11.00	1.38	0.11	0.04				
11.25	1.50	0.15	0.05				
11.50	1.65	0.20	0.08				
11.75	1.96	0.33	0.17				
12.00	2.76	0.76	0.47				
12.25	3.57	1.29	0.81				
12.50	3.88	1.51	0.39				
12.75	4.03	1.62	0.18				
13.00	4.15	1.71	0.14				
13.25	4.24	1.78	0.11				
13.50	4.33	1.84	0.10				
13.75	4.41	1.91	0.09				
14.00	4.48	1.96	0.08				
14.25	4.55	2.01	0.08				
14.50	4.61	2.06	0.07				
14.75	4.67	2.10	0.07				
15.00	4.72	2.15	0.06				
15.25	4.77	2.19	0.06				
15.50	4.82	2.22	0.06				
15.75	4.86	2.25	0.05				
16.00	4.90	2.28	0.05				
16.25	4.93	2.31	0.04				
16.50	4.97	2.34	0.04				
16.75	5.00	2.36	0.04				
17.00	5.03	2.39	0.04				
17.25	5.06	2.41	0.03				
17.50	5.08	2.43	0.03				
17.75	5.11	2.45	0.03				


Summary for Link 5L: Pre-Existing (Composite)

Inflow Area = 1.193 ac, 0.00% Impervious, Inflow Depth > 2.59" for 10-yr event
 Inflow = 3.51 cfs @ 12.12 hrs, Volume= 0.258 af
 Primary = 3.51 cfs @ 12.12 hrs, Volume= 0.258 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Pre-Existing (Composite)

Hydrograph



Hydrograph for Link 5L: Pre-Existing (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
5.00	0.00	0.00	0.00	18.00	0.09	0.00	0.09
5.25	0.00	0.00	0.00	18.25	0.08	0.00	0.08
5.50	0.00	0.00	0.00	18.50	0.08	0.00	0.08
5.75	0.00	0.00	0.00	18.75	0.08	0.00	0.08
6.00	0.00	0.00	0.00	19.00	0.08	0.00	0.08
6.25	0.00	0.00	0.00	19.25	0.08	0.00	0.08
6.50	0.00	0.00	0.00	19.50	0.08	0.00	0.08
6.75	0.00	0.00	0.00	19.75	0.07	0.00	0.07
7.00	0.00	0.00	0.00	20.00	0.07	0.00	0.07
7.25	0.00	0.00	0.00				
7.50	0.00	0.00	0.00				
7.75	0.00	0.00	0.00				
8.00	0.00	0.00	0.00				
8.25	0.00	0.00	0.00				
8.50	0.00	0.00	0.00				
8.75	0.00	0.00	0.00				
9.00	0.01	0.00	0.01				
9.25	0.02	0.00	0.02				
9.50	0.03	0.00	0.03				
9.75	0.04	0.00	0.04				
10.00	0.05	0.00	0.05				
10.25	0.06	0.00	0.06				
10.50	0.08	0.00	0.08				
10.75	0.11	0.00	0.11				
11.00	0.13	0.00	0.13				
11.25	0.18	0.00	0.18				
11.50	0.26	0.00	0.26				
11.75	0.64	0.00	0.64				
12.00	1.85	0.00	1.85				
12.25	2.26	0.00	2.26				
12.50	1.09	0.00	1.09				
12.75	0.54	0.00	0.54				
13.00	0.42	0.00	0.42				
13.25	0.35	0.00	0.35				
13.50	0.32	0.00	0.32				
13.75	0.29	0.00	0.29				
14.00	0.27	0.00	0.27				
14.25	0.24	0.00	0.24				
14.50	0.23	0.00	0.23				
14.75	0.22	0.00	0.22				
15.00	0.20	0.00	0.20				
15.25	0.19	0.00	0.19				
15.50	0.17	0.00	0.17				
15.75	0.16	0.00	0.16				
16.00	0.14	0.00	0.14				
16.25	0.13	0.00	0.13				
16.50	0.13	0.00	0.13				
16.75	0.12	0.00	0.12				
17.00	0.11	0.00	0.11				
17.25	0.11	0.00	0.11				
17.50	0.10	0.00	0.10				
17.75	0.10	0.00	0.10				

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: EX-1 (Pre)

Runoff Area=0.180 ac 0.00% Impervious Runoff Depth>3.57"
Flow Length=260' Tc=6.6 min CN=74 Runoff=0.78 cfs 0.054 af

Subcatchment2S: EX-2 (Pre)

Runoff Area=0.640 ac 0.00% Impervious Runoff Depth>3.57"
Flow Length=330' Tc=7.2 min CN=74 Runoff=2.72 cfs 0.190 af

Subcatchment3S: EX-3 (Pre)

Runoff Area=0.373 ac 0.00% Impervious Runoff Depth>3.56"
Flow Length=280' Tc=10.7 min CN=74 Runoff=1.42 cfs 0.111 af

Link 5L: Pre-Existing (Composite)

Inflow=4.81 cfs 0.355 af
Primary=4.81 cfs 0.355 af

Total Runoff Area = 1.193 ac Runoff Volume = 0.355 af Average Runoff Depth = 3.57"
100.00% Pervious = 1.193 ac 0.00% Impervious = 0.000 ac

Summary for Subcatchment 1S: EX-1 (Pre)

Runoff = 0.78 cfs @ 12.10 hrs, Volume= 0.054 af, Depth> 3.57"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.75"

Area (ac)	CN	Description
0.180	74	>75% Grass cover, Good, HSG C
0.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.3	160	0.0812	1.99		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
6.6	260	Total			

Subcatchment 1S: EX-1 (Pre)

Hydrograph



Hydrograph for Subcatchment 1S: EX-1 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.38	0.00	0.00	18.00	6.26	3.41	0.02
5.25	0.41	0.00	0.00	18.25	6.29	3.43	0.02
5.50	0.43	0.00	0.00	18.50	6.32	3.45	0.02
5.75	0.46	0.00	0.00	18.75	6.34	3.47	0.02
6.00	0.49	0.00	0.00	19.00	6.37	3.50	0.02
6.25	0.51	0.00	0.00	19.25	6.39	3.52	0.01
6.50	0.54	0.00	0.00	19.50	6.41	3.54	0.01
6.75	0.58	0.00	0.00	19.75	6.44	3.56	0.01
7.00	0.61	0.00	0.00	20.00	6.46	3.58	0.01
7.25	0.65	0.00	0.00				
7.50	0.69	0.00	0.00				
7.75	0.73	0.00	0.00				
8.00	0.77	0.00	0.00				
8.25	0.82	0.00	0.00				
8.50	0.87	0.01	0.00				
8.75	0.92	0.01	0.00				
9.00	0.98	0.02	0.01				
9.25	1.05	0.03	0.01				
9.50	1.12	0.04	0.01				
9.75	1.20	0.06	0.01				
10.00	1.28	0.08	0.01				
10.25	1.36	0.10	0.02				
10.50	1.46	0.13	0.02				
10.75	1.57	0.17	0.03				
11.00	1.69	0.22	0.03				
11.25	1.83	0.27	0.04				
11.50	2.01	0.36	0.06				
11.75	2.40	0.55	0.16				
12.00	3.37	1.15	0.44				
12.25	4.35	1.86	0.42				
12.50	4.74	2.16	0.20				
12.75	4.92	2.30	0.10				
13.00	5.06	2.41	0.08				
13.25	5.18	2.51	0.07				
13.50	5.29	2.60	0.06				
13.75	5.39	2.68	0.06				
14.00	5.47	2.75	0.05				
14.25	5.55	2.81	0.05				
14.50	5.63	2.88	0.04				
14.75	5.70	2.93	0.04				
15.00	5.77	2.99	0.04				
15.25	5.83	3.04	0.04				
15.50	5.88	3.09	0.03				
15.75	5.93	3.13	0.03				
16.00	5.98	3.17	0.03				
16.25	6.02	3.20	0.03				
16.50	6.06	3.24	0.02				
16.75	6.10	3.27	0.02				
17.00	6.14	3.30	0.02				
17.25	6.17	3.33	0.02				
17.50	6.21	3.36	0.02				
17.75	6.24	3.38	0.02				

Summary for Subcatchment 2S: EX-2 (Pre)

Runoff = 2.72 cfs @ 12.11 hrs, Volume= 0.190 af, Depth> 3.57"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.75"

Area (ac)	CN	Description
0.640	74	>75% Grass cover, Good, HSG C
0.640		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.9	230	0.0840	2.03		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
7.2	330	Total			

Subcatchment 2S: EX-2 (Pre)

Hydrograph



Hydrograph for Subcatchment 2S: EX-2 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.38	0.00	0.00	18.00	6.26	3.41	0.06
5.25	0.41	0.00	0.00	18.25	6.29	3.43	0.06
5.50	0.43	0.00	0.00	18.50	6.32	3.45	0.06
5.75	0.46	0.00	0.00	18.75	6.34	3.47	0.06
6.00	0.49	0.00	0.00	19.00	6.37	3.50	0.05
6.25	0.51	0.00	0.00	19.25	6.39	3.52	0.05
6.50	0.54	0.00	0.00	19.50	6.41	3.54	0.05
6.75	0.58	0.00	0.00	19.75	6.44	3.56	0.05
7.00	0.61	0.00	0.00	20.00	6.46	3.58	0.05
7.25	0.65	0.00	0.00				
7.50	0.69	0.00	0.00				
7.75	0.73	0.00	0.00				
8.00	0.77	0.00	0.00				
8.25	0.82	0.00	0.01				
8.50	0.87	0.01	0.01				
8.75	0.92	0.01	0.01				
9.00	0.98	0.02	0.02				
9.25	1.05	0.03	0.03				
9.50	1.12	0.04	0.03				
9.75	1.20	0.06	0.04				
10.00	1.28	0.08	0.05				
10.25	1.36	0.10	0.06				
10.50	1.46	0.13	0.08				
10.75	1.57	0.17	0.10				
11.00	1.69	0.22	0.11				
11.25	1.83	0.27	0.15				
11.50	2.01	0.36	0.21				
11.75	2.40	0.55	0.54				
12.00	3.37	1.15	1.49				
12.25	4.35	1.86	1.54				
12.50	4.74	2.16	0.73				
12.75	4.92	2.30	0.37				
13.00	5.06	2.41	0.29				
13.25	5.18	2.51	0.24				
13.50	5.29	2.60	0.22				
13.75	5.39	2.68	0.20				
14.00	5.47	2.75	0.18				
14.25	5.55	2.81	0.17				
14.50	5.63	2.88	0.16				
14.75	5.70	2.93	0.15				
15.00	5.77	2.99	0.14				
15.25	5.83	3.04	0.13				
15.50	5.88	3.09	0.12				
15.75	5.93	3.13	0.11				
16.00	5.98	3.17	0.10				
16.25	6.02	3.20	0.09				
16.50	6.06	3.24	0.09				
16.75	6.10	3.27	0.08				
17.00	6.14	3.30	0.08				
17.25	6.17	3.33	0.07				
17.50	6.21	3.36	0.07				
17.75	6.24	3.38	0.07				

Summary for Subcatchment 3S: EX-3 (Pre)

Runoff = 1.42 cfs @ 12.15 hrs, Volume= 0.111 af, Depth> 3.56"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.75"

Area (ac)	CN	Description
0.373	74	>75% Grass cover, Good, HSG C
0.373		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.3	100	0.0200	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.4	180	0.0972	2.18		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
10.7	280	Total			

Subcatchment 3S: EX-3 (Pre)

Hydrograph



Hydrograph for Subcatchment 3S: EX-3 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.38	0.00	0.00	18.00	6.26	3.41	0.04
5.25	0.41	0.00	0.00	18.25	6.29	3.43	0.03
5.50	0.43	0.00	0.00	18.50	6.32	3.45	0.03
5.75	0.46	0.00	0.00	18.75	6.34	3.47	0.03
6.00	0.49	0.00	0.00	19.00	6.37	3.50	0.03
6.25	0.51	0.00	0.00	19.25	6.39	3.52	0.03
6.50	0.54	0.00	0.00	19.50	6.41	3.54	0.03
6.75	0.58	0.00	0.00	19.75	6.44	3.56	0.03
7.00	0.61	0.00	0.00	20.00	6.46	3.58	0.03
7.25	0.65	0.00	0.00				
7.50	0.69	0.00	0.00				
7.75	0.73	0.00	0.00				
8.00	0.77	0.00	0.00				
8.25	0.82	0.00	0.00				
8.50	0.87	0.01	0.01				
8.75	0.92	0.01	0.01				
9.00	0.98	0.02	0.01				
9.25	1.05	0.03	0.01				
9.50	1.12	0.04	0.02				
9.75	1.20	0.06	0.02				
10.00	1.28	0.08	0.03				
10.25	1.36	0.10	0.04				
10.50	1.46	0.13	0.04				
10.75	1.57	0.17	0.05				
11.00	1.69	0.22	0.06				
11.25	1.83	0.27	0.08				
11.50	2.01	0.36	0.12				
11.75	2.40	0.55	0.25				
12.00	3.37	1.15	0.67				
12.25	4.35	1.86	1.09				
12.50	4.74	2.16	0.52				
12.75	4.92	2.30	0.24				
13.00	5.06	2.41	0.18				
13.25	5.18	2.51	0.15				
13.50	5.29	2.60	0.13				
13.75	5.39	2.68	0.12				
14.00	5.47	2.75	0.11				
14.25	5.55	2.81	0.10				
14.50	5.63	2.88	0.09				
14.75	5.70	2.93	0.09				
15.00	5.77	2.99	0.08				
15.25	5.83	3.04	0.08				
15.50	5.88	3.09	0.07				
15.75	5.93	3.13	0.07				
16.00	5.98	3.17	0.06				
16.25	6.02	3.20	0.05				
16.50	6.06	3.24	0.05				
16.75	6.10	3.27	0.05				
17.00	6.14	3.30	0.05				
17.25	6.17	3.33	0.04				
17.50	6.21	3.36	0.04				
17.75	6.24	3.38	0.04				


Summary for Link 5L: Pre-Existing (Composite)

Inflow Area = 1.193 ac, 0.00% Impervious, Inflow Depth > 3.57" for 25-yr event
 Inflow = 4.81 cfs @ 12.11 hrs, Volume= 0.355 af
 Primary = 4.81 cfs @ 12.11 hrs, Volume= 0.355 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Pre-Existing (Composite)

Hydrograph



Hydrograph for Link 5L: Pre-Existing (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
5.00	0.00	0.00	0.00	18.00	0.11	0.00	0.11
5.25	0.00	0.00	0.00	18.25	0.11	0.00	0.11
5.50	0.00	0.00	0.00	18.50	0.11	0.00	0.11
5.75	0.00	0.00	0.00	18.75	0.10	0.00	0.10
6.00	0.00	0.00	0.00	19.00	0.10	0.00	0.10
6.25	0.00	0.00	0.00	19.25	0.10	0.00	0.10
6.50	0.00	0.00	0.00	19.50	0.10	0.00	0.10
6.75	0.00	0.00	0.00	19.75	0.09	0.00	0.09
7.00	0.00	0.00	0.00	20.00	0.09	0.00	0.09
7.25	0.00	0.00	0.00				
7.50	0.00	0.00	0.00				
7.75	0.00	0.00	0.00				
8.00	0.01	0.00	0.01				
8.25	0.01	0.00	0.01				
8.50	0.02	0.00	0.02				
8.75	0.03	0.00	0.03				
9.00	0.04	0.00	0.04				
9.25	0.05	0.00	0.05				
9.50	0.06	0.00	0.06				
9.75	0.08	0.00	0.08				
10.00	0.09	0.00	0.09				
10.25	0.12	0.00	0.12				
10.50	0.14	0.00	0.14				
10.75	0.18	0.00	0.18				
11.00	0.21	0.00	0.21				
11.25	0.28	0.00	0.28				
11.50	0.39	0.00	0.39				
11.75	0.95	0.00	0.95				
12.00	2.61	0.00	2.61				
12.25	3.04	0.00	3.04				
12.50	1.45	0.00	1.45				
12.75	0.71	0.00	0.71				
13.00	0.55	0.00	0.55				
13.25	0.46	0.00	0.46				
13.50	0.42	0.00	0.42				
13.75	0.38	0.00	0.38				
14.00	0.35	0.00	0.35				
14.25	0.32	0.00	0.32				
14.50	0.30	0.00	0.30				
14.75	0.28	0.00	0.28				
15.00	0.26	0.00	0.26				
15.25	0.24	0.00	0.24				
15.50	0.23	0.00	0.23				
15.75	0.21	0.00	0.21				
16.00	0.19	0.00	0.19				
16.25	0.17	0.00	0.17				
16.50	0.17	0.00	0.17				
16.75	0.16	0.00	0.16				
17.00	0.15	0.00	0.15				
17.25	0.14	0.00	0.14				
17.50	0.13	0.00	0.13				
17.75	0.12	0.00	0.12				

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: EX-1 (Pre)

Runoff Area=0.180 ac 0.00% Impervious Runoff Depth>5.15"
Flow Length=260' Tc=6.6 min CN=74 Runoff=1.11 cfs 0.077 af

Subcatchment2S: EX-2 (Pre)

Runoff Area=0.640 ac 0.00% Impervious Runoff Depth>5.15"
Flow Length=330' Tc=7.2 min CN=74 Runoff=3.89 cfs 0.275 af

Subcatchment3S: EX-3 (Pre)

Runoff Area=0.373 ac 0.00% Impervious Runoff Depth>5.14"
Flow Length=280' Tc=10.7 min CN=74 Runoff=2.03 cfs 0.160 af

Link 5L: Pre-Existing (Composite)

Inflow=6.88 cfs 0.512 af
Primary=6.88 cfs 0.512 af

Total Runoff Area = 1.193 ac Runoff Volume = 0.512 af Average Runoff Depth = 5.15"
100.00% Pervious = 1.193 ac 0.00% Impervious = 0.000 ac

Summary for Subcatchment 1S: EX-1 (Pre)

Runoff = 1.11 cfs @ 12.10 hrs, Volume= 0.077 af, Depth> 5.15"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.63"

Area (ac)	CN	Description
0.180	74	>75% Grass cover, Good, HSG C
0.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.3	160	0.0812	1.99		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
6.6	260	Total			

Subcatchment 1S: EX-1 (Pre)

Hydrograph



Hydrograph for Subcatchment 1S: EX-1 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.49	0.00	0.00	18.00	8.01	4.93	0.02
5.25	0.52	0.00	0.00	18.25	8.04	4.96	0.02
5.50	0.55	0.00	0.00	18.50	8.08	4.99	0.02
5.75	0.59	0.00	0.00	18.75	8.11	5.02	0.02
6.00	0.62	0.00	0.00	19.00	8.14	5.05	0.02
6.25	0.66	0.00	0.00	19.25	8.17	5.08	0.02
6.50	0.70	0.00	0.00	19.50	8.20	5.11	0.02
6.75	0.74	0.00	0.00	19.75	8.23	5.13	0.02
7.00	0.78	0.00	0.00	20.00	8.26	5.16	0.02
7.25	0.83	0.00	0.00				
7.50	0.88	0.01	0.00				
7.75	0.93	0.01	0.00				
8.00	0.98	0.02	0.01				
8.25	1.04	0.03	0.01				
8.50	1.11	0.04	0.01				
8.75	1.18	0.06	0.01				
9.00	1.26	0.08	0.01				
9.25	1.34	0.10	0.02				
9.50	1.43	0.13	0.02				
9.75	1.53	0.16	0.02				
10.00	1.63	0.19	0.03				
10.25	1.74	0.24	0.03				
10.50	1.87	0.29	0.04				
10.75	2.01	0.35	0.05				
11.00	2.16	0.43	0.05				
11.25	2.34	0.52	0.07				
11.50	2.57	0.65	0.10				
11.75	3.07	0.95	0.24				
12.00	4.31	1.83	0.65				
12.25	5.56	2.82	0.58				
12.50	6.06	3.23	0.27				
12.75	6.29	3.43	0.14				
13.00	6.47	3.59	0.11				
13.25	6.62	3.72	0.09				
13.50	6.76	3.84	0.09				
13.75	6.89	3.94	0.08				
14.00	7.00	4.04	0.07				
14.25	7.10	4.13	0.06				
14.50	7.20	4.22	0.06				
14.75	7.29	4.29	0.06				
15.00	7.37	4.37	0.05				
15.25	7.45	4.44	0.05				
15.50	7.52	4.50	0.05				
15.75	7.59	4.56	0.04				
16.00	7.65	4.61	0.04				
16.25	7.70	4.66	0.04				
16.50	7.75	4.71	0.03				
16.75	7.80	4.75	0.03				
17.00	7.85	4.79	0.03				
17.25	7.89	4.83	0.03				
17.50	7.93	4.87	0.03				
17.75	7.97	4.90	0.02				

Summary for Subcatchment 2S: EX-2 (Pre)

Runoff = 3.89 cfs @ 12.10 hrs, Volume= 0.275 af, Depth> 5.15"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.63"

Area (ac)	CN	Description
0.640	74	>75% Grass cover, Good, HSG C
0.640		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.9	230	0.0840	2.03		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
7.2	330	Total			

Subcatchment 2S: EX-2 (Pre)

Hydrograph



Hydrograph for Subcatchment 2S: EX-2 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.49	0.00	0.00	18.00	8.01	4.93	0.08
5.25	0.52	0.00	0.00	18.25	8.04	4.96	0.08
5.50	0.55	0.00	0.00	18.50	8.08	4.99	0.08
5.75	0.59	0.00	0.00	18.75	8.11	5.02	0.08
6.00	0.62	0.00	0.00	19.00	8.14	5.05	0.07
6.25	0.66	0.00	0.00	19.25	8.17	5.08	0.07
6.50	0.70	0.00	0.00	19.50	8.20	5.11	0.07
6.75	0.74	0.00	0.00	19.75	8.23	5.13	0.07
7.00	0.78	0.00	0.00	20.00	8.26	5.16	0.07
7.25	0.83	0.00	0.01				
7.50	0.88	0.01	0.01				
7.75	0.93	0.01	0.01				
8.00	0.98	0.02	0.02				
8.25	1.04	0.03	0.02				
8.50	1.11	0.04	0.03				
8.75	1.18	0.06	0.04				
9.00	1.26	0.08	0.05				
9.25	1.34	0.10	0.06				
9.50	1.43	0.13	0.07				
9.75	1.53	0.16	0.08				
10.00	1.63	0.19	0.10				
10.25	1.74	0.24	0.11				
10.50	1.87	0.29	0.14				
10.75	2.01	0.35	0.16				
11.00	2.16	0.43	0.19				
11.25	2.34	0.52	0.25				
11.50	2.57	0.65	0.34				
11.75	3.07	0.95	0.82				
12.00	4.31	1.83	2.19				
12.25	5.56	2.82	2.15				
12.50	6.06	3.23	1.01				
12.75	6.29	3.43	0.51				
13.00	6.47	3.59	0.40				
13.25	6.62	3.72	0.33				
13.50	6.76	3.84	0.31				
13.75	6.89	3.94	0.28				
14.00	7.00	4.04	0.25				
14.25	7.10	4.13	0.23				
14.50	7.20	4.22	0.22				
14.75	7.29	4.29	0.20				
15.00	7.37	4.37	0.19				
15.25	7.45	4.44	0.18				
15.50	7.52	4.50	0.16				
15.75	7.59	4.56	0.15				
16.00	7.65	4.61	0.13				
16.25	7.70	4.66	0.13				
16.50	7.75	4.71	0.12				
16.75	7.80	4.75	0.11				
17.00	7.85	4.79	0.11				
17.25	7.89	4.83	0.10				
17.50	7.93	4.87	0.09				
17.75	7.97	4.90	0.09				

Summary for Subcatchment 3S: EX-3 (Pre)

Runoff = 2.03 cfs @ 12.15 hrs, Volume= 0.160 af, Depth> 5.14"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.63"

Area (ac)	CN	Description
0.373	74	>75% Grass cover, Good, HSG C
0.373		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.3	100	0.0200	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.4	180	0.0972	2.18		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
10.7	280	Total			

Subcatchment 3S: EX-3 (Pre)

Hydrograph



Hydrograph for Subcatchment 3S: EX-3 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.49	0.00	0.00	18.00	8.01	4.93	0.05
5.25	0.52	0.00	0.00	18.25	8.04	4.96	0.05
5.50	0.55	0.00	0.00	18.50	8.08	4.99	0.05
5.75	0.59	0.00	0.00	18.75	8.11	5.02	0.04
6.00	0.62	0.00	0.00	19.00	8.14	5.05	0.04
6.25	0.66	0.00	0.00	19.25	8.17	5.08	0.04
6.50	0.70	0.00	0.00	19.50	8.20	5.11	0.04
6.75	0.74	0.00	0.00	19.75	8.23	5.13	0.04
7.00	0.78	0.00	0.00	20.00	8.26	5.16	0.04
7.25	0.83	0.00	0.00				
7.50	0.88	0.01	0.01				
7.75	0.93	0.01	0.01				
8.00	0.98	0.02	0.01				
8.25	1.04	0.03	0.01				
8.50	1.11	0.04	0.02				
8.75	1.18	0.06	0.02				
9.00	1.26	0.08	0.03				
9.25	1.34	0.10	0.03				
9.50	1.43	0.13	0.04				
9.75	1.53	0.16	0.05				
10.00	1.63	0.19	0.05				
10.25	1.74	0.24	0.06				
10.50	1.87	0.29	0.08				
10.75	2.01	0.35	0.09				
11.00	2.16	0.43	0.11				
11.25	2.34	0.52	0.14				
11.50	2.57	0.65	0.18				
11.75	3.07	0.95	0.39				
12.00	4.31	1.83	0.99				
12.25	5.56	2.82	1.54				
12.50	6.06	3.23	0.72				
12.75	6.29	3.43	0.32				
13.00	6.47	3.59	0.24				
13.25	6.62	3.72	0.20				
13.50	6.76	3.84	0.18				
13.75	6.89	3.94	0.17				
14.00	7.00	4.04	0.15				
14.25	7.10	4.13	0.14				
14.50	7.20	4.22	0.13				
14.75	7.29	4.29	0.12				
15.00	7.37	4.37	0.11				
15.25	7.45	4.44	0.10				
15.50	7.52	4.50	0.10				
15.75	7.59	4.56	0.09				
16.00	7.65	4.61	0.08				
16.25	7.70	4.66	0.07				
16.50	7.75	4.71	0.07				
16.75	7.80	4.75	0.07				
17.00	7.85	4.79	0.06				
17.25	7.89	4.83	0.06				
17.50	7.93	4.87	0.06				
17.75	7.97	4.90	0.05				


Summary for Link 5L: Pre-Existing (Composite)

Inflow Area = 1.193 ac, 0.00% Impervious, Inflow Depth > 5.15" for 100-yr event
 Inflow = 6.88 cfs @ 12.11 hrs, Volume= 0.512 af
 Primary = 6.88 cfs @ 12.11 hrs, Volume= 0.512 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Pre-Existing (Composite)

Hydrograph



Hydrograph for Link 5L: Pre-Existing (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
5.00	0.00	0.00	0.00	18.00	0.15	0.00	0.15
5.25	0.00	0.00	0.00	18.25	0.15	0.00	0.15
5.50	0.00	0.00	0.00	18.50	0.14	0.00	0.14
5.75	0.00	0.00	0.00	18.75	0.14	0.00	0.14
6.00	0.00	0.00	0.00	19.00	0.14	0.00	0.14
6.25	0.00	0.00	0.00	19.25	0.13	0.00	0.13
6.50	0.00	0.00	0.00	19.50	0.13	0.00	0.13
6.75	0.00	0.00	0.00	19.75	0.13	0.00	0.13
7.00	0.01	0.00	0.01	20.00	0.12	0.00	0.12
7.25	0.01	0.00	0.01				
7.50	0.02	0.00	0.02				
7.75	0.03	0.00	0.03				
8.00	0.03	0.00	0.03				
8.25	0.04	0.00	0.04				
8.50	0.06	0.00	0.06				
8.75	0.07	0.00	0.07				
9.00	0.09	0.00	0.09				
9.25	0.11	0.00	0.11				
9.50	0.13	0.00	0.13				
9.75	0.15	0.00	0.15				
10.00	0.18	0.00	0.18				
10.25	0.21	0.00	0.21				
10.50	0.25	0.00	0.25				
10.75	0.30	0.00	0.30				
11.00	0.35	0.00	0.35				
11.25	0.45	0.00	0.45				
11.50	0.62	0.00	0.62				
11.75	1.45	0.00	1.45				
12.00	3.83	0.00	3.83				
12.25	4.28	0.00	4.28				
12.50	2.01	0.00	2.01				
12.75	0.97	0.00	0.97				
13.00	0.75	0.00	0.75				
13.25	0.63	0.00	0.63				
13.50	0.57	0.00	0.57				
13.75	0.52	0.00	0.52				
14.00	0.47	0.00	0.47				
14.25	0.43	0.00	0.43				
14.50	0.41	0.00	0.41				
14.75	0.38	0.00	0.38				
15.00	0.36	0.00	0.36				
15.25	0.33	0.00	0.33				
15.50	0.30	0.00	0.30				
15.75	0.28	0.00	0.28				
16.00	0.25	0.00	0.25				
16.25	0.23	0.00	0.23				
16.50	0.22	0.00	0.22				
16.75	0.21	0.00	0.21				
17.00	0.20	0.00	0.20				
17.25	0.19	0.00	0.19				
17.50	0.18	0.00	0.18				
17.75	0.17	0.00	0.17				

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: EX-1 (Pre)

Runoff Area=0.180 ac 0.00% Impervious Runoff Depth>0.13"
Flow Length=260' Tc=6.6 min CN=74 Runoff=0.01 cfs 0.002 af

Subcatchment2S: EX-2 (Pre)

Runoff Area=0.640 ac 0.00% Impervious Runoff Depth>0.13"
Flow Length=330' Tc=7.2 min CN=74 Runoff=0.04 cfs 0.007 af

Subcatchment3S: EX-3 (Pre)

Runoff Area=0.373 ac 0.00% Impervious Runoff Depth>0.13"
Flow Length=280' Tc=10.7 min CN=74 Runoff=0.03 cfs 0.004 af

Link 5L: Pre-Existing (Composite)

Inflow=0.08 cfs 0.013 af
Primary=0.08 cfs 0.013 af

Total Runoff Area = 1.193 ac Runoff Volume = 0.013 af Average Runoff Depth = 0.13"
100.00% Pervious = 1.193 ac 0.00% Impervious = 0.000 ac

Summary for Subcatchment 1S: EX-1 (Pre)

Runoff = 0.01 cfs @ 12.28 hrs, Volume= 0.002 af, Depth> 0.13"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr Custom Rainfall=1.50"

Area (ac)	CN	Description
0.180	74	>75% Grass cover, Good, HSG C
0.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.3	160	0.0812	1.99		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
6.6	260	Total			

Subcatchment 1S: EX-1 (Pre)

Hydrograph



Hydrograph for Subcatchment 1S: EX-1 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.09	0.00	0.00	18.00	1.39	0.11	0.00
5.25	0.09	0.00	0.00	18.25	1.40	0.11	0.00
5.50	0.10	0.00	0.00	18.50	1.40	0.12	0.00
5.75	0.10	0.00	0.00	18.75	1.41	0.12	0.00
6.00	0.11	0.00	0.00	19.00	1.41	0.12	0.00
6.25	0.11	0.00	0.00	19.25	1.42	0.12	0.00
6.50	0.12	0.00	0.00	19.50	1.43	0.12	0.00
6.75	0.13	0.00	0.00	19.75	1.43	0.12	0.00
7.00	0.14	0.00	0.00	20.00	1.44	0.13	0.00
7.25	0.14	0.00	0.00				
7.50	0.15	0.00	0.00				
7.75	0.16	0.00	0.00				
8.00	0.17	0.00	0.00				
8.25	0.18	0.00	0.00				
8.50	0.19	0.00	0.00				
8.75	0.21	0.00	0.00				
9.00	0.22	0.00	0.00				
9.25	0.23	0.00	0.00				
9.50	0.25	0.00	0.00				
9.75	0.27	0.00	0.00				
10.00	0.28	0.00	0.00				
10.25	0.30	0.00	0.00				
10.50	0.32	0.00	0.00				
10.75	0.35	0.00	0.00				
11.00	0.38	0.00	0.00				
11.25	0.41	0.00	0.00				
11.50	0.45	0.00	0.00				
11.75	0.53	0.00	0.00				
12.00	0.75	0.00	0.00				
12.25	0.97	0.02	0.01				
12.50	1.05	0.03	0.01				
12.75	1.09	0.04	0.01				
13.00	1.12	0.05	0.00				
13.25	1.15	0.05	0.00				
13.50	1.18	0.06	0.00				
13.75	1.20	0.06	0.00				
14.00	1.22	0.07	0.00				
14.25	1.23	0.07	0.00				
14.50	1.25	0.07	0.00				
14.75	1.27	0.08	0.00				
15.00	1.28	0.08	0.00				
15.25	1.29	0.09	0.00				
15.50	1.31	0.09	0.00				
15.75	1.32	0.09	0.00				
16.00	1.33	0.09	0.00				
16.25	1.34	0.10	0.00				
16.50	1.35	0.10	0.00				
16.75	1.36	0.10	0.00				
17.00	1.36	0.10	0.00				
17.25	1.37	0.11	0.00				
17.50	1.38	0.11	0.00				
17.75	1.39	0.11	0.00				

Summary for Subcatchment 2S: EX-2 (Pre)

Runoff = 0.04 cfs @ 12.29 hrs, Volume= 0.007 af, Depth> 0.13"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr Custom Rainfall=1.50"

Area (ac)	CN	Description
0.640	74	>75% Grass cover, Good, HSG C
0.640		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	100	0.0800	0.31		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.9	230	0.0840	2.03		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
7.2	330	Total			

Subcatchment 2S: EX-2 (Pre)

Hydrograph



Hydrograph for Subcatchment 2S: EX-2 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.09	0.00	0.00	18.00	1.39	0.11	0.00
5.25	0.09	0.00	0.00	18.25	1.40	0.11	0.00
5.50	0.10	0.00	0.00	18.50	1.40	0.12	0.00
5.75	0.10	0.00	0.00	18.75	1.41	0.12	0.00
6.00	0.11	0.00	0.00	19.00	1.41	0.12	0.00
6.25	0.11	0.00	0.00	19.25	1.42	0.12	0.00
6.50	0.12	0.00	0.00	19.50	1.43	0.12	0.00
6.75	0.13	0.00	0.00	19.75	1.43	0.12	0.00
7.00	0.14	0.00	0.00	20.00	1.44	0.13	0.00
7.25	0.14	0.00	0.00				
7.50	0.15	0.00	0.00				
7.75	0.16	0.00	0.00				
8.00	0.17	0.00	0.00				
8.25	0.18	0.00	0.00				
8.50	0.19	0.00	0.00				
8.75	0.21	0.00	0.00				
9.00	0.22	0.00	0.00				
9.25	0.23	0.00	0.00				
9.50	0.25	0.00	0.00				
9.75	0.27	0.00	0.00				
10.00	0.28	0.00	0.00				
10.25	0.30	0.00	0.00				
10.50	0.32	0.00	0.00				
10.75	0.35	0.00	0.00				
11.00	0.38	0.00	0.00				
11.25	0.41	0.00	0.00				
11.50	0.45	0.00	0.00				
11.75	0.53	0.00	0.00				
12.00	0.75	0.00	0.00				
12.25	0.97	0.02	0.04				
12.50	1.05	0.03	0.03				
12.75	1.09	0.04	0.02				
13.00	1.12	0.05	0.02				
13.25	1.15	0.05	0.01				
13.50	1.18	0.06	0.01				
13.75	1.20	0.06	0.01				
14.00	1.22	0.07	0.01				
14.25	1.23	0.07	0.01				
14.50	1.25	0.07	0.01				
14.75	1.27	0.08	0.01				
15.00	1.28	0.08	0.01				
15.25	1.29	0.09	0.01				
15.50	1.31	0.09	0.01				
15.75	1.32	0.09	0.01				
16.00	1.33	0.09	0.01				
16.25	1.34	0.10	0.01				
16.50	1.35	0.10	0.01				
16.75	1.36	0.10	0.01				
17.00	1.36	0.10	0.01				
17.25	1.37	0.11	0.01				
17.50	1.38	0.11	0.01				
17.75	1.39	0.11	0.01				

Summary for Subcatchment 3S: EX-3 (Pre)

Runoff = 0.03 cfs @ 12.35 hrs, Volume= 0.004 af, Depth> 0.13"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr Custom Rainfall=1.50"

Area (ac)	CN	Description
0.373	74	>75% Grass cover, Good, HSG C
0.373		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.3	100	0.0200	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.4	180	0.0972	2.18		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
10.7	280	Total			

Subcatchment 3S: EX-3 (Pre)

Hydrograph



Hydrograph for Subcatchment 3S: EX-3 (Pre)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
5.00	0.09	0.00	0.00	18.00	1.39	0.11	0.00
5.25	0.09	0.00	0.00	18.25	1.40	0.11	0.00
5.50	0.10	0.00	0.00	18.50	1.40	0.12	0.00
5.75	0.10	0.00	0.00	18.75	1.41	0.12	0.00
6.00	0.11	0.00	0.00	19.00	1.41	0.12	0.00
6.25	0.11	0.00	0.00	19.25	1.42	0.12	0.00
6.50	0.12	0.00	0.00	19.50	1.43	0.12	0.00
6.75	0.13	0.00	0.00	19.75	1.43	0.12	0.00
7.00	0.14	0.00	0.00	20.00	1.44	0.13	0.00
7.25	0.14	0.00	0.00				
7.50	0.15	0.00	0.00				
7.75	0.16	0.00	0.00				
8.00	0.17	0.00	0.00				
8.25	0.18	0.00	0.00				
8.50	0.19	0.00	0.00				
8.75	0.21	0.00	0.00				
9.00	0.22	0.00	0.00				
9.25	0.23	0.00	0.00				
9.50	0.25	0.00	0.00				
9.75	0.27	0.00	0.00				
10.00	0.28	0.00	0.00				
10.25	0.30	0.00	0.00				
10.50	0.32	0.00	0.00				
10.75	0.35	0.00	0.00				
11.00	0.38	0.00	0.00				
11.25	0.41	0.00	0.00				
11.50	0.45	0.00	0.00				
11.75	0.53	0.00	0.00				
12.00	0.75	0.00	0.00				
12.25	0.97	0.02	0.02				
12.50	1.05	0.03	0.02				
12.75	1.09	0.04	0.01				
13.00	1.12	0.05	0.01				
13.25	1.15	0.05	0.01				
13.50	1.18	0.06	0.01				
13.75	1.20	0.06	0.01				
14.00	1.22	0.07	0.01				
14.25	1.23	0.07	0.01				
14.50	1.25	0.07	0.01				
14.75	1.27	0.08	0.01				
15.00	1.28	0.08	0.01				
15.25	1.29	0.09	0.01				
15.50	1.31	0.09	0.01				
15.75	1.32	0.09	0.00				
16.00	1.33	0.09	0.00				
16.25	1.34	0.10	0.00				
16.50	1.35	0.10	0.00				
16.75	1.36	0.10	0.00				
17.00	1.36	0.10	0.00				
17.25	1.37	0.11	0.00				
17.50	1.38	0.11	0.00				
17.75	1.39	0.11	0.00				


Summary for Link 5L: Pre-Existing (Composite)

Inflow Area = 1.193 ac, 0.00% Impervious, Inflow Depth > 0.13" for Custom event
 Inflow = 0.08 cfs @ 12.31 hrs, Volume= 0.013 af
 Primary = 0.08 cfs @ 12.31 hrs, Volume= 0.013 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs


Link 5L: Pre-Existing (Composite)

Hydrograph



Hydrograph for Link 5L: Pre-Existing (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
5.00	0.00	0.00	0.00	18.00	0.01	0.00	0.01
5.25	0.00	0.00	0.00	18.25	0.01	0.00	0.01
5.50	0.00	0.00	0.00	18.50	0.01	0.00	0.01
5.75	0.00	0.00	0.00	18.75	0.01	0.00	0.01
6.00	0.00	0.00	0.00	19.00	0.01	0.00	0.01
6.25	0.00	0.00	0.00	19.25	0.01	0.00	0.01
6.50	0.00	0.00	0.00	19.50	0.01	0.00	0.01
6.75	0.00	0.00	0.00	19.75	0.01	0.00	0.01
7.00	0.00	0.00	0.00	20.00	0.01	0.00	0.01
7.25	0.00	0.00	0.00				
7.50	0.00	0.00	0.00				
7.75	0.00	0.00	0.00				
8.00	0.00	0.00	0.00				
8.25	0.00	0.00	0.00				
8.50	0.00	0.00	0.00				
8.75	0.00	0.00	0.00				
9.00	0.00	0.00	0.00				
9.25	0.00	0.00	0.00				
9.50	0.00	0.00	0.00				
9.75	0.00	0.00	0.00				
10.00	0.00	0.00	0.00				
10.25	0.00	0.00	0.00				
10.50	0.00	0.00	0.00				
10.75	0.00	0.00	0.00				
11.00	0.00	0.00	0.00				
11.25	0.00	0.00	0.00				
11.50	0.00	0.00	0.00				
11.75	0.00	0.00	0.00				
12.00	0.00	0.00	0.00				
12.25	0.08	0.00	0.08				
12.50	0.06	0.00	0.06				
12.75	0.04	0.00	0.04				
13.00	0.03	0.00	0.03				
13.25	0.03	0.00	0.03				
13.50	0.03	0.00	0.03				
13.75	0.02	0.00	0.02				
14.00	0.02	0.00	0.02				
14.25	0.02	0.00	0.02				
14.50	0.02	0.00	0.02				
14.75	0.02	0.00	0.02				
15.00	0.02	0.00	0.02				
15.25	0.02	0.00	0.02				
15.50	0.02	0.00	0.02				
15.75	0.02	0.00	0.02				
16.00	0.01	0.00	0.01				
16.25	0.01	0.00	0.01				
16.50	0.01	0.00	0.01				
16.75	0.01	0.00	0.01				
17.00	0.01	0.00	0.01				
17.25	0.01	0.00	0.01				
17.50	0.01	0.00	0.01				
17.75	0.01	0.00	0.01				



Project Notes

Defined 10 rainfall events from NY-Westchester IDF

Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.850	74	>75% Grass cover, Good, HSG C (4S)
0.200	98	Paved parking, HSG C (4S)
0.140	98	Roofs, HSG C (5S)
1.190	81	TOTAL AREA

Soil Listing (all nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
1.190	HSG C	4S, 5S
0.000	HSG D	
0.000	Other	
1.190		TOTAL AREA

Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.850	0.000	0.000	0.850	>75% Grass cover, Good	4S
0.000	0.000	0.200	0.000	0.000	0.200	Paved parking	4S
0.000	0.000	0.140	0.000	0.000	0.140	Roofs	5S
0.000	0.000	1.190	0.000	0.000	1.190	TOTAL AREA	

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment4S: PR-01 (Site)

Runoff Area=1.050 ac 19.05% Impervious Runoff Depth>1.14"
Flow Length=310' Tc=9.1 min CN=79 Runoff=1.21 cfs 0.099 af

Subcatchment5S: PR-02 (Roof)

Runoff Area=0.140 ac 100.00% Impervious Runoff Depth>2.70"
Tc=6.0 min CN=98 Runoff=0.39 cfs 0.031 af

Pond 7P: Chambers

Peak Elev=122.83' Storage=0.015 af Inflow=0.39 cfs 0.031 af
Discarded=0.02 cfs 0.028 af Primary=0.00 cfs 0.000 af Outflow=0.02 cfs 0.028 af

Pond 8P: Bioretention

Peak Elev=129.58' Storage=0.051 af Inflow=1.21 cfs 0.099 af
Discarded=0.09 cfs 0.073 af Primary=0.00 cfs 0.000 af Outflow=0.09 cfs 0.073 af

Link 7L: Post (Composite)

Inflow=0.00 cfs 0.000 af
Primary=0.00 cfs 0.000 af

Total Runoff Area = 1.190 ac Runoff Volume = 0.131 af Average Runoff Depth = 1.32"
71.43% Pervious = 0.850 ac 28.57% Impervious = 0.340 ac

Summary for Subcatchment 4S: PR-01 (Site)

Runoff = 1.21 cfs @ 12.14 hrs, Volume= 0.099 af, Depth> 1.14"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 1-yr Rainfall=2.93"

Area (ac)	CN	Description
0.200	98	Paved parking, HSG C
0.850	74	>75% Grass cover, Good, HSG C
1.050	79	Weighted Average
0.850		80.95% Pervious Area
0.200		19.05% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	35	0.0700	0.24		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.7	28	0.1070	0.27		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
3.4	37	0.0340	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.0	78	0.0350	1.31		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
0.1	30	0.0500	4.54		Shallow Concentrated Flow, Pathway Paved Kv= 20.3 fps
0.3	52	0.0290	2.55		Shallow Concentrated Flow, Shallow Concentrated Grassed Waterway Kv= 15.0 fps
0.2	50	0.2000	4.47		Shallow Concentrated Flow, Shallow Concentrated Nearly Bare & Untilled Kv= 10.0 fps
9.1	310	Total			

Subcatchment 4S: PR-01 (Site)

Hydrograph



Hydrograph for Subcatchment 4S: PR-01 (Site)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	2.20	0.64	0.16
0.25	0.01	0.00	0.00	13.25	2.25	0.67	0.14
0.50	0.01	0.00	0.00	13.50	2.30	0.70	0.13
0.75	0.02	0.00	0.00	13.75	2.34	0.73	0.12
1.00	0.03	0.00	0.00	14.00	2.38	0.76	0.11
1.25	0.04	0.00	0.00	14.25	2.41	0.78	0.10
1.50	0.04	0.00	0.00	14.50	2.44	0.80	0.09
1.75	0.05	0.00	0.00	14.75	2.47	0.82	0.09
2.00	0.06	0.00	0.00	15.00	2.50	0.84	0.08
2.25	0.07	0.00	0.00	15.25	2.53	0.86	0.08
2.50	0.07	0.00	0.00	15.50	2.55	0.87	0.07
2.75	0.08	0.00	0.00	15.75	2.58	0.89	0.06
3.00	0.09	0.00	0.00	16.00	2.60	0.90	0.06
3.25	0.10	0.00	0.00	16.25	2.61	0.92	0.05
3.50	0.11	0.00	0.00	16.50	2.63	0.93	0.05
3.75	0.12	0.00	0.00	16.75	2.65	0.94	0.05
4.00	0.13	0.00	0.00	17.00	2.66	0.95	0.05
4.25	0.14	0.00	0.00	17.25	2.68	0.96	0.04
4.50	0.15	0.00	0.00	17.50	2.69	0.97	0.04
4.75	0.16	0.00	0.00	17.75	2.71	0.98	0.04
5.00	0.17	0.00	0.00	18.00	2.72	0.99	0.04
5.25	0.18	0.00	0.00	18.25	2.73	1.00	0.03
5.50	0.19	0.00	0.00	18.50	2.74	1.00	0.03
5.75	0.20	0.00	0.00	18.75	2.75	1.01	0.03
6.00	0.21	0.00	0.00	19.00	2.76	1.02	0.03
6.25	0.22	0.00	0.00	19.25	2.77	1.03	0.03
6.50	0.24	0.00	0.00	19.50	2.78	1.03	0.03
6.75	0.25	0.00	0.00	19.75	2.79	1.04	0.03
7.00	0.27	0.00	0.00	20.00	2.80	1.05	0.03
7.25	0.28	0.00	0.00	20.25	2.81	1.05	0.03
7.50	0.30	0.00	0.00	20.50	2.82	1.06	0.03
7.75	0.32	0.00	0.00	20.75	2.83	1.07	0.03
8.00	0.33	0.00	0.00	21.00	2.84	1.07	0.03
8.25	0.35	0.00	0.00	21.25	2.85	1.08	0.03
8.50	0.38	0.00	0.00	21.50	2.86	1.09	0.03
8.75	0.40	0.00	0.00	21.75	2.87	1.09	0.02
9.00	0.43	0.00	0.00	22.00	2.87	1.10	0.02
9.25	0.46	0.00	0.00	22.25	2.88	1.10	0.02
9.50	0.49	0.00	0.00	22.50	2.89	1.11	0.02
9.75	0.52	0.00	0.00	22.75	2.90	1.11	0.02
10.00	0.55	0.00	0.00	23.00	2.90	1.12	0.02
10.25	0.59	0.00	0.00	23.25	2.91	1.12	0.02
10.50	0.63	0.00	0.01	23.50	2.92	1.13	0.02
10.75	0.68	0.01	0.02	23.75	2.92	1.13	0.02
11.00	0.73	0.01	0.03	24.00	2.93	1.14	0.02
11.25	0.79	0.02	0.04				
11.50	0.87	0.04	0.06				
11.75	1.04	0.08	0.17				
12.00	1.46	0.24	0.55				
12.25	1.89	0.46	0.87				
12.50	2.06	0.56	0.44				
12.75	2.14	0.60	0.21				

Summary for Subcatchment 5S: PR-02 (Roof)

Runoff = 0.39 cfs @ 12.09 hrs, Volume= 0.031 af, Depth> 2.70"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=2.93"

Area (ac)	CN	Description
0.140	98	Roofs, HSG C
0.140		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Roof

Subcatchment 5S: PR-02 (Roof)

Hydrograph



Hydrograph for Subcatchment 5S: PR-02 (Roof)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	2.20	1.97	0.03
0.25	0.01	0.00	0.00	13.25	2.25	2.02	0.03
0.50	0.01	0.00	0.00	13.50	2.30	2.07	0.03
0.75	0.02	0.00	0.00	13.75	2.34	2.11	0.02
1.00	0.03	0.00	0.00	14.00	2.38	2.15	0.02
1.25	0.04	0.00	0.00	14.25	2.41	2.18	0.02
1.50	0.04	0.00	0.00	14.50	2.44	2.21	0.02
1.75	0.05	0.00	0.00	14.75	2.47	2.25	0.02
2.00	0.06	0.00	0.00	15.00	2.50	2.27	0.02
2.25	0.07	0.00	0.00	15.25	2.53	2.30	0.01
2.50	0.07	0.00	0.00	15.50	2.55	2.32	0.01
2.75	0.08	0.01	0.00	15.75	2.58	2.35	0.01
3.00	0.09	0.01	0.00	16.00	2.60	2.37	0.01
3.25	0.10	0.01	0.00	16.25	2.61	2.38	0.01
3.50	0.11	0.02	0.00	16.50	2.63	2.40	0.01
3.75	0.12	0.02	0.00	16.75	2.65	2.42	0.01
4.00	0.13	0.03	0.00	17.00	2.66	2.43	0.01
4.25	0.14	0.03	0.00	17.25	2.68	2.45	0.01
4.50	0.15	0.04	0.00	17.50	2.69	2.46	0.01
4.75	0.16	0.04	0.00	17.75	2.71	2.48	0.01
5.00	0.17	0.05	0.00	18.00	2.72	2.49	0.01
5.25	0.18	0.05	0.00	18.25	2.73	2.50	0.01
5.50	0.19	0.06	0.00	18.50	2.74	2.51	0.01
5.75	0.20	0.07	0.00	18.75	2.75	2.52	0.01
6.00	0.21	0.08	0.00	19.00	2.76	2.53	0.01
6.25	0.22	0.09	0.00	19.25	2.77	2.54	0.01
6.50	0.24	0.10	0.01	19.50	2.78	2.55	0.01
6.75	0.25	0.11	0.01	19.75	2.79	2.56	0.01
7.00	0.27	0.12	0.01	20.00	2.80	2.57	0.01
7.25	0.28	0.13	0.01	20.25	2.81	2.58	0.01
7.50	0.30	0.14	0.01	20.50	2.82	2.59	0.01
7.75	0.32	0.16	0.01	20.75	2.83	2.60	0.01
8.00	0.33	0.17	0.01	21.00	2.84	2.61	0.00
8.25	0.35	0.19	0.01	21.25	2.85	2.62	0.00
8.50	0.38	0.21	0.01	21.50	2.86	2.63	0.00
8.75	0.40	0.23	0.01	21.75	2.87	2.63	0.00
9.00	0.43	0.25	0.01	22.00	2.87	2.64	0.00
9.25	0.46	0.28	0.01	22.25	2.88	2.65	0.00
9.50	0.49	0.31	0.02	22.50	2.89	2.66	0.00
9.75	0.52	0.34	0.02	22.75	2.90	2.67	0.00
10.00	0.55	0.37	0.02	23.00	2.90	2.67	0.00
10.25	0.59	0.40	0.02	23.25	2.91	2.68	0.00
10.50	0.63	0.44	0.02	23.50	2.92	2.69	0.00
10.75	0.68	0.49	0.03	23.75	2.92	2.69	0.00
11.00	0.73	0.53	0.03	24.00	2.93	2.70	0.00
11.25	0.79	0.59	0.03				
11.50	0.87	0.67	0.04				
11.75	1.04	0.83	0.10				
12.00	1.46	1.25	0.25				
12.25	1.89	1.66	0.18				
12.50	2.06	1.83	0.08				
12.75	2.14	1.91	0.04				

Summary for Pond 7P: Chambers

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth > 0.32" for 1-yr event
 Inflow = 0.39 cfs @ 12.09 hrs, Volume= 0.031 af
 Outflow = 0.02 cfs @ 13.84 hrs, Volume= 0.028 af, Atten= 94%, Lag= 105.2 min
 Discarded = 0.02 cfs @ 13.84 hrs, Volume= 0.028 af
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 122.83' @ 13.84 hrs Surf.Area= 0.024 ac Storage= 0.015 af

Plug-Flow detention time= 243.3 min calculated for 0.028 af (89% of inflow)
 Center-of-Mass det. time= 189.8 min (947.6 - 757.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	121.33'	0.031 af	17.33'W x 41.55'L x 6.25'H Field A 0.103 af Overall - 0.027 af Embedded = 0.077 af x 40.0% Voids
#2A	122.83'	0.027 af	ADS_StormTech MC-3500 d +Capx 10 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 10 Chambers in 2 Rows Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf
#3B	121.33'	0.015 af	9.42'W x 35.38'L x 6.25'H Field B 0.048 af Overall - 0.011 af Embedded = 0.037 af x 40.0% Voids
#4B	122.83'	0.011 af	ADS_StormTech MC-3500 d +Capx 4 Inside #3 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf
		0.083 af	Total Available Storage

Storage Group A created with Chamber Wizard
 Storage Group B created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	121.33'	0.750 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 115.00'
#2	Primary	122.95'	4.0" Vert. Orifice/Grate C= 0.600
#3	Primary	123.50'	10.0" Vert. Orifice/Grate C= 0.600
#4	Primary	126.50'	1.5' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Discarded OutFlow Max=0.02 cfs @ 13.84 hrs HW=122.83' (Free Discharge)

↑1=Exfiltration (Controls 0.02 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=121.33' (Free Discharge)

↑2=Orifice/Grate (Controls 0.00 cfs)

↑3=Orifice/Grate (Controls 0.00 cfs)

↑4=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 7P: Chambers - Chamber Wizard Field A

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech@MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf

77.0" Wide + 18.0" Spacing = 95.0" C-C Row Spacing

5 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 39.55' Row Length +12.0" End Stone x 2 = 41.55' Base Length

2 Rows x 77.0" Wide + 18.0" Spacing x 1 + 18.0" Side Stone x 2 = 17.33' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

10 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 2 Rows = 1,159.1 cf Chamber Storage

4,501.2 cf Field - 1,159.1 cf Chambers = 3,342.1 cf Stone x 40.0% Voids = 1,336.9 cf Stone Storage

Chamber Storage + Stone Storage = 2,496.0 cf = 0.057 af


Overall Storage Efficiency = 55.5%

Overall System Size = 41.55' x 17.33' x 6.25'

10 Chambers

166.7 cy Field

123.8 cy Stone



Pond 7P: Chambers - Chamber Wizard Field B

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf

4 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 32.38' Row Length +18.0" End Stone x 2 = 35.38' Base Length

1 Rows x 77.0" Wide + 18.0" Side Stone x 2 = 9.42' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

4 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 1 Rows = 469.6 cf Chamber Storage

2,082.3 cf Field - 469.6 cf Chambers = 1,612.7 cf Stone x 40.0% Voids = 645.1 cf Stone Storage

Chamber Storage + Stone Storage = 1,114.7 cf = 0.026 af



Overall Storage Efficiency = 53.5%

Overall System Size = 35.38' x 9.42' x 6.25'

4 Chambers


77.1 cy Field

59.7 cy Stone




Pond 7P: Chambers

Hydrograph




Pond 7P: Chambers

Stage-Discharge



Pond 7P: Chambers

Stage-Area-Storage



Hydrograph for Pond 7P: Chambers

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	121.33	0.00	0.00	0.00
0.50	0.00	0.000	121.33	0.00	0.00	0.00
1.00	0.00	0.000	121.33	0.00	0.00	0.00
1.50	0.00	0.000	121.33	0.00	0.00	0.00
2.00	0.00	0.000	121.33	0.00	0.00	0.00
2.50	0.00	0.000	121.33	0.00	0.00	0.00
3.00	0.00	0.000	121.33	0.00	0.00	0.00
3.50	0.00	0.000	121.34	0.00	0.00	0.00
4.00	0.00	0.000	121.34	0.00	0.00	0.00
4.50	0.00	0.000	121.34	0.00	0.00	0.00
5.00	0.00	0.000	121.34	0.00	0.00	0.00
5.50	0.00	0.000	121.34	0.00	0.00	0.00
6.00	0.00	0.000	121.34	0.00	0.00	0.00
6.50	0.01	0.000	121.35	0.00	0.00	0.00
7.00	0.01	0.000	121.35	0.01	0.01	0.00
7.50	0.01	0.000	121.35	0.01	0.01	0.00
8.00	0.01	0.000	121.36	0.01	0.01	0.00
8.50	0.01	0.000	121.36	0.01	0.01	0.00
9.00	0.01	0.000	121.37	0.01	0.01	0.00
9.50	0.02	0.000	121.38	0.01	0.01	0.00
10.00	0.02	0.001	121.38	0.02	0.02	0.00
10.50	0.02	0.001	121.40	0.02	0.02	0.00
11.00	0.03	0.001	121.42	0.02	0.02	0.00
11.50	0.04	0.002	121.49	0.02	0.02	0.00
12.00	0.25	0.005	121.88	0.02	0.02	0.00
12.50	0.08	0.013	122.70	0.02	0.02	0.00
13.00	0.03	0.014	122.80	0.02	0.02	0.00
13.50	0.03	0.015	122.83	0.02	0.02	0.00
14.00	0.02	0.015	122.83	0.02	0.02	0.00
14.50	0.02	0.014	122.82	0.02	0.02	0.00
15.00	0.02	0.014	122.80	0.02	0.02	0.00
15.50	0.01	0.014	122.76	0.02	0.02	0.00
16.00	0.01	0.013	122.72	0.02	0.02	0.00
16.50	0.01	0.013	122.67	0.02	0.02	0.00
17.00	0.01	0.012	122.62	0.02	0.02	0.00
17.50	0.01	0.012	122.56	0.02	0.02	0.00
18.00	0.01	0.011	122.50	0.02	0.02	0.00
18.50	0.01	0.011	122.43	0.02	0.02	0.00
19.00	0.01	0.010	122.37	0.02	0.02	0.00
19.50	0.01	0.009	122.30	0.02	0.02	0.00
20.00	0.01	0.009	122.24	0.02	0.02	0.00
20.50	0.01	0.008	122.17	0.02	0.02	0.00
21.00	0.00	0.007	122.10	0.02	0.02	0.00
21.50	0.00	0.007	122.04	0.02	0.02	0.00
22.00	0.00	0.006	121.97	0.02	0.02	0.00
22.50	0.00	0.006	121.90	0.02	0.02	0.00
23.00	0.00	0.005	121.84	0.02	0.02	0.00
23.50	0.00	0.004	121.77	0.02	0.02	0.00
24.00	0.00	0.004	121.70	0.02	0.02	0.00

Stage-Discharge for Pond 7P: Chambers

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
121.33	0.00	0.00	0.00	126.53	5.08	0.03	5.04
121.43	0.02	0.02	0.00	126.63	5.34	0.03	5.31
121.53	0.02	0.02	0.00	126.73	5.70	0.03	5.67
121.63	0.02	0.02	0.00	126.83	6.14	0.03	6.11
121.73	0.02	0.02	0.00	126.93	6.66	0.03	6.62
121.83	0.02	0.02	0.00	127.03	7.25	0.03	7.22
121.93	0.02	0.02	0.00	127.13	7.92	0.04	7.88
122.03	0.02	0.02	0.00	127.23	8.68	0.04	8.65
122.13	0.02	0.02	0.00	127.33	9.50	0.04	9.46
122.23	0.02	0.02	0.00	127.43	10.29	0.04	10.25
122.33	0.02	0.02	0.00	127.53	11.12	0.04	11.08
122.43	0.02	0.02	0.00				
122.53	0.02	0.02	0.00				
122.63	0.02	0.02	0.00				
122.73	0.02	0.02	0.00				
122.83	0.02	0.02	0.00				
122.93	0.02	0.02	0.00				
123.03	0.04	0.02	0.02				
123.13	0.09	0.02	0.07				
123.23	0.16	0.02	0.14				
123.33	0.22	0.02	0.19				
123.43	0.26	0.02	0.24				
123.53	0.30	0.02	0.27				
123.63	0.39	0.02	0.37				
123.73	0.55	0.03	0.53				
123.83	0.77	0.03	0.75				
123.93	1.04	0.03	1.01				
124.03	1.33	0.03	1.31				
124.13	1.64	0.03	1.62				
124.23	1.94	0.03	1.92				
124.33	2.18	0.03	2.15				
124.43	2.39	0.03	2.36				
124.53	2.58	0.03	2.56				
124.63	2.76	0.03	2.73				
124.73	2.93	0.03	2.90				
124.83	3.09	0.03	3.06				
124.93	3.24	0.03	3.21				
125.03	3.38	0.03	3.35				
125.13	3.52	0.03	3.49				
125.23	3.65	0.03	3.62				
125.33	3.78	0.03	3.75				
125.43	3.90	0.03	3.87				
125.53	4.02	0.03	3.99				
125.63	4.13	0.03	4.10				
125.73	4.25	0.03	4.22				
125.83	4.36	0.03	4.32				
125.93	4.46	0.03	4.43				
126.03	4.57	0.03	4.53				
126.13	4.67	0.03	4.64				
126.23	4.77	0.03	4.74				
126.33	4.87	0.03	4.83				
126.43	4.96	0.03	4.93				

Stage-Area-Storage for Pond 7P: Chambers

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
121.33	0.024	0.000	126.53	0.024	0.073
121.43	0.024	0.001	126.63	0.024	0.074
121.53	0.024	0.002	126.73	0.024	0.075
121.63	0.024	0.003	126.83	0.024	0.076
121.73	0.024	0.004	126.93	0.024	0.077
121.83	0.024	0.005	127.03	0.024	0.078
121.93	0.024	0.006	127.13	0.024	0.079
122.03	0.024	0.007	127.23	0.024	0.080
122.13	0.024	0.008	127.33	0.024	0.080
122.23	0.024	0.009	127.43	0.024	0.081
122.33	0.024	0.010	127.53	0.024	0.082
122.43	0.024	0.011			
122.53	0.024	0.012			
122.63	0.024	0.013			
122.73	0.024	0.014			
122.83	0.024	0.015			
122.93	0.024	0.016			
123.03	0.024	0.018			
123.13	0.024	0.020			
123.23	0.024	0.022			
123.33	0.024	0.024			
123.43	0.024	0.025			
123.53	0.024	0.027			
123.63	0.024	0.029			
123.73	0.024	0.031			
123.83	0.024	0.032			
123.93	0.024	0.034			
124.03	0.024	0.036			
124.13	0.024	0.038			
124.23	0.024	0.039			
124.33	0.024	0.041			
124.43	0.024	0.043			
124.53	0.024	0.044			
124.63	0.024	0.046			
124.73	0.024	0.048			
124.83	0.024	0.049			
124.93	0.024	0.051			
125.03	0.024	0.053			
125.13	0.024	0.054			
125.23	0.024	0.056			
125.33	0.024	0.057			
125.43	0.024	0.059			
125.53	0.024	0.060			
125.63	0.024	0.062			
125.73	0.024	0.063			
125.83	0.024	0.065			
125.93	0.024	0.066			
126.03	0.024	0.067			
126.13	0.024	0.068			
126.23	0.024	0.070			
126.33	0.024	0.071			
126.43	0.024	0.072			

Summary for Pond 8P: Bioretention

Inflow Area = 1.050 ac, 19.05% Impervious, Inflow Depth > 1.14" for 1-yr event
 Inflow = 1.21 cfs @ 12.14 hrs, Volume= 0.099 af
 Outflow = 0.09 cfs @ 14.62 hrs, Volume= 0.073 af, Atten= 93%, Lag= 148.9 min
 Discarded = 0.09 cfs @ 14.62 hrs, Volume= 0.073 af
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 129.58' @ 14.62 hrs Surf.Area= 0.090 ac Storage= 0.051 af

Plug-Flow detention time= 291.9 min calculated for 0.073 af (74% of inflow)
 Center-of-Mass det. time= 197.7 min (1,050.3 - 852.5)

Volume	Invert	Avail.Storage	Storage Description
#1	125.50'	0.020 af	Gravel (Prismatic) Listed below 0.050 af Overall x 40.0% Voids
#2	127.00'	0.029 af	Soil (Prismatic) Listed below (Recalc) 0.082 af Overall x 35.0% Voids
#3	129.50'	0.028 af	Custom Stage Data (Prismatic) Listed below (Recalc)
		0.077 af	Total Available Storage

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
125.50	0.033	0.000	0.000
127.00	0.033	0.050	0.050

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
127.00	0.033	0.000	0.000
129.50	0.033	0.082	0.082

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
129.50	0.023	0.000	0.000
130.00	0.028	0.013	0.013
130.50	0.033	0.015	0.028


Device	Routing	Invert	Outlet Devices
#1	Primary	130.00'	12.0" Horiz. Orifice/Grate X 4 rows C= 0.600 Limited to weir flow at low heads
#2	Discarded	125.50'	0.900 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 100.00'

Discarded OutFlow Max=0.09 cfs @ 14.62 hrs HW=129.58' (Free Discharge)
 ↑2=Exfiltration (Controls 0.09 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=125.50' (Free Discharge)
 ↑1=Orifice/Grate (Controls 0.00 cfs)


Pond 8P: Bioretention

Hydrograph




Pond 8P: Bioretention

Stage-Discharge



Pond 8P: Bioretention

Stage-Area-Storage



Hydrograph for Pond 8P: Bioretention

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	125.50	0.00	0.00	0.00
0.50	0.00	0.000	125.50	0.00	0.00	0.00
1.00	0.00	0.000	125.50	0.00	0.00	0.00
1.50	0.00	0.000	125.50	0.00	0.00	0.00
2.00	0.00	0.000	125.50	0.00	0.00	0.00
2.50	0.00	0.000	125.50	0.00	0.00	0.00
3.00	0.00	0.000	125.50	0.00	0.00	0.00
3.50	0.00	0.000	125.50	0.00	0.00	0.00
4.00	0.00	0.000	125.50	0.00	0.00	0.00
4.50	0.00	0.000	125.50	0.00	0.00	0.00
5.00	0.00	0.000	125.50	0.00	0.00	0.00
5.50	0.00	0.000	125.50	0.00	0.00	0.00
6.00	0.00	0.000	125.50	0.00	0.00	0.00
6.50	0.00	0.000	125.50	0.00	0.00	0.00
7.00	0.00	0.000	125.50	0.00	0.00	0.00
7.50	0.00	0.000	125.50	0.00	0.00	0.00
8.00	0.00	0.000	125.50	0.00	0.00	0.00
8.50	0.00	0.000	125.50	0.00	0.00	0.00
9.00	0.00	0.000	125.50	0.00	0.00	0.00
9.50	0.00	0.000	125.50	0.00	0.00	0.00
10.00	0.00	0.000	125.50	0.00	0.00	0.00
10.50	0.01	0.000	125.51	0.01	0.01	0.00
11.00	0.03	0.000	125.53	0.02	0.02	0.00
11.50	0.06	0.001	125.58	0.03	0.03	0.00
12.00	0.55	0.008	126.13	0.03	0.03	0.00
12.50	0.44	0.039	128.70	0.07	0.07	0.00
13.00	0.16	0.047	129.31	0.07	0.07	0.00
13.50	0.13	0.049	129.52	0.09	0.09	0.00
14.00	0.11	0.050	129.57	0.09	0.09	0.00
14.50	0.09	0.051	129.58	0.09	0.09	0.00
15.00	0.08	0.051	129.58	0.09	0.09	0.00
15.50	0.07	0.050	129.55	0.09	0.09	0.00
16.00	0.06	0.049	129.51	0.09	0.09	0.00
16.50	0.05	0.048	129.44	0.07	0.07	0.00
17.00	0.05	0.047	129.38	0.07	0.07	0.00
17.50	0.04	0.046	129.29	0.07	0.07	0.00
18.00	0.04	0.045	129.19	0.07	0.07	0.00
18.50	0.03	0.044	129.08	0.07	0.07	0.00
19.00	0.03	0.042	128.96	0.07	0.07	0.00
19.50	0.03	0.041	128.84	0.07	0.07	0.00
20.00	0.03	0.040	128.71	0.07	0.07	0.00
20.50	0.03	0.038	128.58	0.07	0.07	0.00
21.00	0.03	0.036	128.44	0.06	0.06	0.00
21.50	0.03	0.035	128.30	0.06	0.06	0.00
22.00	0.02	0.033	128.16	0.06	0.06	0.00
22.50	0.02	0.032	128.02	0.06	0.06	0.00
23.00	0.02	0.030	127.87	0.06	0.06	0.00
23.50	0.02	0.028	127.72	0.06	0.06	0.00
24.00	0.02	0.026	127.56	0.06	0.06	0.00

Stage-Discharge for Pond 8P: Bioretention

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
125.50	0.00	0.00	0.00	128.10	0.06	0.06	0.00
125.55	0.03	0.03	0.00	128.15	0.06	0.06	0.00
125.60	0.03	0.03	0.00	128.20	0.06	0.06	0.00
125.65	0.03	0.03	0.00	128.25	0.06	0.06	0.00
125.70	0.03	0.03	0.00	128.30	0.06	0.06	0.00
125.75	0.03	0.03	0.00	128.35	0.06	0.06	0.00
125.80	0.03	0.03	0.00	128.40	0.06	0.06	0.00
125.85	0.03	0.03	0.00	128.45	0.06	0.06	0.00
125.90	0.03	0.03	0.00	128.50	0.07	0.07	0.00
125.95	0.03	0.03	0.00	128.55	0.07	0.07	0.00
126.00	0.03	0.03	0.00	128.60	0.07	0.07	0.00
126.05	0.03	0.03	0.00	128.65	0.07	0.07	0.00
126.10	0.03	0.03	0.00	128.70	0.07	0.07	0.00
126.15	0.03	0.03	0.00	128.75	0.07	0.07	0.00
126.20	0.03	0.03	0.00	128.80	0.07	0.07	0.00
126.25	0.03	0.03	0.00	128.85	0.07	0.07	0.00
126.30	0.03	0.03	0.00	128.90	0.07	0.07	0.00
126.35	0.03	0.03	0.00	128.95	0.07	0.07	0.00
126.40	0.03	0.03	0.00	129.00	0.07	0.07	0.00
126.45	0.03	0.03	0.00	129.05	0.07	0.07	0.00
126.50	0.03	0.03	0.00	129.10	0.07	0.07	0.00
126.55	0.03	0.03	0.00	129.15	0.07	0.07	0.00
126.60	0.03	0.03	0.00	129.20	0.07	0.07	0.00
126.65	0.03	0.03	0.00	129.25	0.07	0.07	0.00
126.70	0.03	0.03	0.00	129.30	0.07	0.07	0.00
126.75	0.03	0.03	0.00	129.35	0.07	0.07	0.00
126.80	0.03	0.03	0.00	129.40	0.07	0.07	0.00
126.85	0.03	0.03	0.00	129.45	0.07	0.07	0.00
126.90	0.03	0.03	0.00	129.50	0.09	0.09	0.00
126.95	0.03	0.03	0.00	129.55	0.09	0.09	0.00
127.00	0.06	0.06	0.00	129.60	0.09	0.09	0.00
127.05	0.06	0.06	0.00	129.65	0.09	0.09	0.00
127.10	0.06	0.06	0.00	129.70	0.09	0.09	0.00
127.15	0.06	0.06	0.00	129.75	0.09	0.09	0.00
127.20	0.06	0.06	0.00	129.80	0.09	0.09	0.00
127.25	0.06	0.06	0.00	129.85	0.09	0.09	0.00
127.30	0.06	0.06	0.00	129.90	0.09	0.09	0.00
127.35	0.06	0.06	0.00	129.95	0.09	0.09	0.00
127.40	0.06	0.06	0.00	130.00	0.09	0.09	0.00
127.45	0.06	0.06	0.00	130.05	0.55	0.09	0.46
127.50	0.06	0.06	0.00	130.10	1.39	0.10	1.30
127.55	0.06	0.06	0.00	130.15	2.48	0.10	2.39
127.60	0.06	0.06	0.00	130.20	3.77	0.10	3.68
127.65	0.06	0.06	0.00	130.25	5.23	0.10	5.14
127.70	0.06	0.06	0.00	130.30	6.85	0.10	6.75
127.75	0.06	0.06	0.00	130.35	8.61	0.10	8.51
127.80	0.06	0.06	0.00	130.40	9.67	0.10	9.57
127.85	0.06	0.06	0.00	130.45	10.25	0.10	10.15
127.90	0.06	0.06	0.00	130.50	10.80	0.10	10.70
127.95	0.06	0.06	0.00				
128.00	0.06	0.06	0.00				
128.05	0.06	0.06	0.00				

Stage-Area-Storage for Pond 8P: Bioretention

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
125.50	0.033	0.000	128.10	0.066	0.033
125.55	0.033	0.001	128.15	0.066	0.033
125.60	0.033	0.001	128.20	0.066	0.034
125.65	0.033	0.002	128.25	0.066	0.034
125.70	0.033	0.003	128.30	0.066	0.035
125.75	0.033	0.003	128.35	0.066	0.035
125.80	0.033	0.004	128.40	0.066	0.036
125.85	0.033	0.005	128.45	0.066	0.037
125.90	0.033	0.005	128.50	0.066	0.037
125.95	0.033	0.006	128.55	0.066	0.038
126.00	0.033	0.007	128.60	0.066	0.038
126.05	0.033	0.007	128.65	0.066	0.039
126.10	0.033	0.008	128.70	0.066	0.039
126.15	0.033	0.009	128.75	0.066	0.040
126.20	0.033	0.009	128.80	0.066	0.041
126.25	0.033	0.010	128.85	0.066	0.041
126.30	0.033	0.011	128.90	0.066	0.042
126.35	0.033	0.011	128.95	0.066	0.042
126.40	0.033	0.012	129.00	0.066	0.043
126.45	0.033	0.013	129.05	0.066	0.043
126.50	0.033	0.013	129.10	0.066	0.044
126.55	0.033	0.014	129.15	0.066	0.045
126.60	0.033	0.015	129.20	0.066	0.045
126.65	0.033	0.015	129.25	0.066	0.046
126.70	0.033	0.016	129.30	0.066	0.046
126.75	0.033	0.017	129.35	0.066	0.047
126.80	0.033	0.017	129.40	0.066	0.048
126.85	0.033	0.018	129.45	0.066	0.048
126.90	0.033	0.018	129.50	0.089	0.049
126.95	0.033	0.019	129.55	0.090	0.050
127.00	0.066	0.020	129.60	0.090	0.051
127.05	0.066	0.020	129.65	0.091	0.052
127.10	0.066	0.021	129.70	0.091	0.053
127.15	0.066	0.022	129.75	0.091	0.055
127.20	0.066	0.022	129.80	0.092	0.056
127.25	0.066	0.023	129.85	0.092	0.057
127.30	0.066	0.023	129.90	0.093	0.059
127.35	0.066	0.024	129.95	0.093	0.060
127.40	0.066	0.024	130.00	0.094	0.061
127.45	0.066	0.025	130.05	0.095	0.063
127.50	0.066	0.026	130.10	0.095	0.064
127.55	0.066	0.026	130.15	0.096	0.066
127.60	0.066	0.027	130.20	0.096	0.067
127.65	0.066	0.027	130.25	0.096	0.069
127.70	0.066	0.028	130.30	0.097	0.070
127.75	0.066	0.028	130.35	0.097	0.072
127.80	0.066	0.029	130.40	0.098	0.073
127.85	0.066	0.030	130.45	0.098	0.075
127.90	0.066	0.030	130.50	0.099	0.077
127.95	0.066	0.031			
128.00	0.066	0.031			
128.05	0.066	0.032			


Summary for Link 7L: Post (Composite)

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth = 0.00" for 1-yr event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: Post (Composite)

Hydrograph



Hydrograph for Link 7L: Post (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
0.00	0.00	0.00	0.00	13.00	0.00	0.00	0.00
0.25	0.00	0.00	0.00	13.25	0.00	0.00	0.00
0.50	0.00	0.00	0.00	13.50	0.00	0.00	0.00
0.75	0.00	0.00	0.00	13.75	0.00	0.00	0.00
1.00	0.00	0.00	0.00	14.00	0.00	0.00	0.00
1.25	0.00	0.00	0.00	14.25	0.00	0.00	0.00
1.50	0.00	0.00	0.00	14.50	0.00	0.00	0.00
1.75	0.00	0.00	0.00	14.75	0.00	0.00	0.00
2.00	0.00	0.00	0.00	15.00	0.00	0.00	0.00
2.25	0.00	0.00	0.00	15.25	0.00	0.00	0.00
2.50	0.00	0.00	0.00	15.50	0.00	0.00	0.00
2.75	0.00	0.00	0.00	15.75	0.00	0.00	0.00
3.00	0.00	0.00	0.00	16.00	0.00	0.00	0.00
3.25	0.00	0.00	0.00	16.25	0.00	0.00	0.00
3.50	0.00	0.00	0.00	16.50	0.00	0.00	0.00
3.75	0.00	0.00	0.00	16.75	0.00	0.00	0.00
4.00	0.00	0.00	0.00	17.00	0.00	0.00	0.00
4.25	0.00	0.00	0.00	17.25	0.00	0.00	0.00
4.50	0.00	0.00	0.00	17.50	0.00	0.00	0.00
4.75	0.00	0.00	0.00	17.75	0.00	0.00	0.00
5.00	0.00	0.00	0.00	18.00	0.00	0.00	0.00
5.25	0.00	0.00	0.00	18.25	0.00	0.00	0.00
5.50	0.00	0.00	0.00	18.50	0.00	0.00	0.00
5.75	0.00	0.00	0.00	18.75	0.00	0.00	0.00
6.00	0.00	0.00	0.00	19.00	0.00	0.00	0.00
6.25	0.00	0.00	0.00	19.25	0.00	0.00	0.00
6.50	0.00	0.00	0.00	19.50	0.00	0.00	0.00
6.75	0.00	0.00	0.00	19.75	0.00	0.00	0.00
7.00	0.00	0.00	0.00	20.00	0.00	0.00	0.00
7.25	0.00	0.00	0.00	20.25	0.00	0.00	0.00
7.50	0.00	0.00	0.00	20.50	0.00	0.00	0.00
7.75	0.00	0.00	0.00	20.75	0.00	0.00	0.00
8.00	0.00	0.00	0.00	21.00	0.00	0.00	0.00
8.25	0.00	0.00	0.00	21.25	0.00	0.00	0.00
8.50	0.00	0.00	0.00	21.50	0.00	0.00	0.00
8.75	0.00	0.00	0.00	21.75	0.00	0.00	0.00
9.00	0.00	0.00	0.00	22.00	0.00	0.00	0.00
9.25	0.00	0.00	0.00	22.25	0.00	0.00	0.00
9.50	0.00	0.00	0.00	22.50	0.00	0.00	0.00
9.75	0.00	0.00	0.00	22.75	0.00	0.00	0.00
10.00	0.00	0.00	0.00	23.00	0.00	0.00	0.00
10.25	0.00	0.00	0.00	23.25	0.00	0.00	0.00
10.50	0.00	0.00	0.00	23.50	0.00	0.00	0.00
10.75	0.00	0.00	0.00	23.75	0.00	0.00	0.00
11.00	0.00	0.00	0.00	24.00	0.00	0.00	0.00
11.25	0.00	0.00	0.00				
11.50	0.00	0.00	0.00				
11.75	0.00	0.00	0.00				
12.00	0.00	0.00	0.00				
12.25	0.00	0.00	0.00				
12.50	0.00	0.00	0.00				
12.75	0.00	0.00	0.00				

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment4S: PR-01 (Site)

Runoff Area=1.050 ac 19.05% Impervious Runoff Depth>3.26"
Flow Length=310' Tc=9.1 min CN=79 Runoff=3.54 cfs 0.285 af

Subcatchment5S: PR-02 (Roof)

Runoff Area=0.140 ac 100.00% Impervious Runoff Depth>5.29"
Tc=6.0 min CN=98 Runoff=0.74 cfs 0.062 af

Pond 7P: Chambers

Peak Elev=124.59' Storage=0.045 af Inflow=4.39 cfs 0.198 af
Discarded=0.03 cfs 0.034 af Primary=2.66 cfs 0.153 af Outflow=2.69 cfs 0.187 af

Pond 8P: Bioretention

Peak Elev=130.21' Storage=0.067 af Inflow=3.54 cfs 0.285 af
Discarded=0.10 cfs 0.101 af Primary=3.84 cfs 0.136 af Outflow=3.94 cfs 0.238 af

Link 7L: Post (Composite)

Inflow=2.66 cfs 0.153 af
Primary=2.66 cfs 0.153 af

Total Runoff Area = 1.190 ac Runoff Volume = 0.347 af Average Runoff Depth = 3.50"
71.43% Pervious = 0.850 ac 28.57% Impervious = 0.340 ac

Summary for Subcatchment 4S: PR-01 (Site)

Runoff = 3.54 cfs @ 12.13 hrs, Volume= 0.285 af, Depth> 3.26"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.53"

Area (ac)	CN	Description
0.200	98	Paved parking, HSG C
0.850	74	>75% Grass cover, Good, HSG C
1.050	79	Weighted Average
0.850		80.95% Pervious Area
0.200		19.05% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	35	0.0700	0.24		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.7	28	0.1070	0.27		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
3.4	37	0.0340	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.0	78	0.0350	1.31		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
0.1	30	0.0500	4.54		Shallow Concentrated Flow, Pathway Paved Kv= 20.3 fps
0.3	52	0.0290	2.55		Shallow Concentrated Flow, Shallow Concentrated Grassed Waterway Kv= 15.0 fps
0.2	50	0.2000	4.47		Shallow Concentrated Flow, Shallow Concentrated Nearly Bare & Untilled Kv= 10.0 fps
9.1	310	Total			

Subcatchment 4S: PR-01 (Site)

Hydrograph



Hydrograph for Subcatchment 4S: PR-01 (Site)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	4.15	2.08	0.41
0.25	0.01	0.00	0.00	13.25	4.24	2.16	0.34
0.50	0.03	0.00	0.00	13.50	4.33	2.24	0.31
0.75	0.04	0.00	0.00	13.75	4.41	2.30	0.28
1.00	0.06	0.00	0.00	14.00	4.48	2.36	0.26
1.25	0.07	0.00	0.00	14.25	4.55	2.42	0.23
1.50	0.08	0.00	0.00	14.50	4.61	2.47	0.22
1.75	0.10	0.00	0.00	14.75	4.67	2.52	0.21
2.00	0.11	0.00	0.00	15.00	4.72	2.57	0.19
2.25	0.12	0.00	0.00	15.25	4.77	2.61	0.18
2.50	0.14	0.00	0.00	15.50	4.82	2.65	0.17
2.75	0.15	0.00	0.00	15.75	4.86	2.68	0.15
3.00	0.17	0.00	0.00	16.00	4.90	2.72	0.14
3.25	0.19	0.00	0.00	16.25	4.93	2.75	0.13
3.50	0.20	0.00	0.00	16.50	4.97	2.77	0.12
3.75	0.22	0.00	0.00	16.75	5.00	2.80	0.12
4.00	0.24	0.00	0.00	17.00	5.03	2.83	0.11
4.25	0.26	0.00	0.00	17.25	5.06	2.85	0.10
4.50	0.27	0.00	0.00	17.50	5.08	2.87	0.10
4.75	0.29	0.00	0.00	17.75	5.11	2.90	0.09
5.00	0.31	0.00	0.00	18.00	5.13	2.92	0.08
5.25	0.33	0.00	0.00	18.25	5.15	2.93	0.08
5.50	0.35	0.00	0.00	18.50	5.18	2.95	0.08
5.75	0.38	0.00	0.00	18.75	5.20	2.97	0.08
6.00	0.40	0.00	0.00	19.00	5.22	2.99	0.07
6.25	0.42	0.00	0.00	19.25	5.24	3.01	0.07
6.50	0.45	0.00	0.00	19.50	5.26	3.02	0.07
6.75	0.47	0.00	0.00	19.75	5.27	3.04	0.07
7.00	0.50	0.00	0.00	20.00	5.29	3.05	0.07
7.25	0.53	0.00	0.00	20.25	5.31	3.07	0.07
7.50	0.56	0.00	0.00	20.50	5.33	3.09	0.06
7.75	0.60	0.00	0.00	20.75	5.34	3.10	0.06
8.00	0.63	0.00	0.01	21.00	5.36	3.11	0.06
8.25	0.67	0.01	0.01	21.25	5.38	3.13	0.06
8.50	0.71	0.01	0.02	21.50	5.39	3.14	0.06
8.75	0.76	0.02	0.03	21.75	5.41	3.16	0.06
9.00	0.81	0.03	0.03	22.00	5.42	3.17	0.06
9.25	0.86	0.04	0.04	22.25	5.44	3.18	0.05
9.50	0.92	0.05	0.05	22.50	5.45	3.19	0.05
9.75	0.98	0.06	0.07	22.75	5.47	3.21	0.05
10.00	1.05	0.08	0.08	23.00	5.48	3.22	0.05
10.25	1.12	0.11	0.09	23.25	5.49	3.23	0.05
10.50	1.20	0.13	0.12	23.50	5.51	3.24	0.05
10.75	1.29	0.17	0.14	23.75	5.52	3.25	0.05
11.00	1.38	0.21	0.17	24.00	5.53	3.26	0.04
11.25	1.50	0.26	0.22				
11.50	1.65	0.33	0.30				
11.75	1.96	0.50	0.69				
12.00	2.76	1.02	1.81				
12.25	3.57	1.62	2.40				
12.50	3.88	1.87	1.13				
12.75	4.03	1.99	0.53				

Summary for Subcatchment 5S: PR-02 (Roof)

Runoff = 0.74 cfs @ 12.09 hrs, Volume= 0.062 af, Depth> 5.29"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.53"

Area (ac)	CN	Description
0.140	98	Roofs, HSG C
0.140		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Roof

Subcatchment 5S: PR-02 (Roof)

Hydrograph



Hydrograph for Subcatchment 5S: PR-02 (Roof)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	4.15	3.91	0.06
0.25	0.01	0.00	0.00	13.25	4.24	4.01	0.05
0.50	0.03	0.00	0.00	13.50	4.33	4.10	0.05
0.75	0.04	0.00	0.00	13.75	4.41	4.18	0.04
1.00	0.06	0.00	0.00	14.00	4.48	4.25	0.04
1.25	0.07	0.00	0.00	14.25	4.55	4.31	0.04
1.50	0.08	0.01	0.00	14.50	4.61	4.38	0.03
1.75	0.10	0.01	0.00	14.75	4.67	4.43	0.03
2.00	0.11	0.02	0.00	15.00	4.72	4.49	0.03
2.25	0.12	0.02	0.00	15.25	4.77	4.54	0.03
2.50	0.14	0.03	0.00	15.50	4.82	4.58	0.03
2.75	0.15	0.04	0.00	15.75	4.86	4.63	0.02
3.00	0.17	0.05	0.01	16.00	4.90	4.66	0.02
3.25	0.19	0.06	0.01	16.25	4.93	4.70	0.02
3.50	0.20	0.07	0.01	16.50	4.97	4.73	0.02
3.75	0.22	0.08	0.01	16.75	5.00	4.76	0.02
4.00	0.24	0.10	0.01	17.00	5.03	4.79	0.02
4.25	0.26	0.11	0.01	17.25	5.06	4.82	0.02
4.50	0.27	0.12	0.01	17.50	5.08	4.85	0.01
4.75	0.29	0.14	0.01	17.75	5.11	4.87	0.01
5.00	0.31	0.16	0.01	18.00	5.13	4.89	0.01
5.25	0.33	0.17	0.01	18.25	5.15	4.92	0.01
5.50	0.35	0.19	0.01	18.50	5.18	4.94	0.01
5.75	0.38	0.21	0.01	18.75	5.20	4.96	0.01
6.00	0.40	0.23	0.01	19.00	5.22	4.98	0.01
6.25	0.42	0.25	0.01	19.25	5.24	5.00	0.01
6.50	0.45	0.27	0.01	19.50	5.26	5.02	0.01
6.75	0.47	0.29	0.01	19.75	5.27	5.04	0.01
7.00	0.50	0.32	0.01	20.00	5.29	5.05	0.01
7.25	0.53	0.35	0.02	20.25	5.31	5.07	0.01
7.50	0.56	0.37	0.02	20.50	5.33	5.09	0.01
7.75	0.60	0.41	0.02	20.75	5.34	5.11	0.01
8.00	0.63	0.44	0.02	21.00	5.36	5.12	0.01
8.25	0.67	0.47	0.02	21.25	5.38	5.14	0.01
8.50	0.71	0.51	0.02	21.50	5.39	5.16	0.01
8.75	0.76	0.56	0.02	21.75	5.41	5.17	0.01
9.00	0.81	0.60	0.03	22.00	5.42	5.19	0.01
9.25	0.86	0.66	0.03	22.25	5.44	5.20	0.01
9.50	0.92	0.71	0.03	22.50	5.45	5.22	0.01
9.75	0.98	0.77	0.03	22.75	5.47	5.23	0.01
10.00	1.05	0.83	0.04	23.00	5.48	5.24	0.01
10.25	1.12	0.90	0.04	23.25	5.49	5.26	0.01
10.50	1.20	0.98	0.04	23.50	5.51	5.27	0.01
10.75	1.29	1.07	0.05	23.75	5.52	5.28	0.01
11.00	1.38	1.16	0.05	24.00	5.53	5.29	0.01
11.25	1.50	1.28	0.07				
11.50	1.65	1.43	0.09				
11.75	1.96	1.74	0.20				
12.00	2.76	2.53	0.48				
12.25	3.57	3.33	0.35				
12.50	3.88	3.65	0.16				
12.75	4.03	3.80	0.08				

Summary for Pond 7P: Chambers

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth > 1.99" for 10-yr event
 Inflow = 4.39 cfs @ 12.16 hrs, Volume= 0.198 af
 Outflow = 2.69 cfs @ 12.27 hrs, Volume= 0.187 af, Atten= 39%, Lag= 6.7 min
 Discarded = 0.03 cfs @ 12.27 hrs, Volume= 0.034 af
 Primary = 2.66 cfs @ 12.27 hrs, Volume= 0.153 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 124.59' @ 12.27 hrs Surf.Area= 0.024 ac Storage= 0.045 af

Plug-Flow detention time= 58.2 min calculated for 0.187 af (95% of inflow)
 Center-of-Mass det. time= 38.7 min (804.0 - 765.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	121.33'	0.031 af	17.33'W x 41.55'L x 6.25'H Field A 0.103 af Overall - 0.027 af Embedded = 0.077 af x 40.0% Voids
#2A	122.83'	0.027 af	ADS StormTech MC-3500 d +Cap x 10 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 10 Chambers in 2 Rows Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf
#3B	121.33'	0.015 af	9.42'W x 35.38'L x 6.25'H Field B 0.048 af Overall - 0.011 af Embedded = 0.037 af x 40.0% Voids
#4B	122.83'	0.011 af	ADS StormTech MC-3500 d +Cap x 4 Inside #3 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf
		0.083 af	Total Available Storage

Storage Group A created with Chamber Wizard
 Storage Group B created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	121.33'	0.750 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 115.00'
#2	Primary	122.95'	4.0" Vert. Orifice/Grate C= 0.600
#3	Primary	123.50'	10.0" Vert. Orifice/Grate C= 0.600
#4	Primary	126.50'	1.5' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Discarded OutFlow Max=0.03 cfs @ 12.27 hrs HW=124.57' (Free Discharge)
 ↑1=Exfiltration (Controls 0.03 cfs)

Primary OutFlow Max=2.63 cfs @ 12.27 hrs HW=124.57' (Free Discharge)
 ↑2=Orifice/Grate (Orifice Controls 0.51 cfs @ 5.80 fps)
 ↑3=Orifice/Grate (Orifice Controls 2.12 cfs @ 3.89 fps)
 ↑4=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 7P: Chambers - Chamber Wizard Field A

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf

77.0" Wide + 18.0" Spacing = 95.0" C-C Row Spacing

5 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 39.55' Row Length +12.0" End Stone x 2 = 41.55' Base Length

2 Rows x 77.0" Wide + 18.0" Spacing x 1 + 18.0" Side Stone x 2 = 17.33' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

10 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 2 Rows = 1,159.1 cf Chamber Storage

4,501.2 cf Field - 1,159.1 cf Chambers = 3,342.1 cf Stone x 40.0% Voids = 1,336.9 cf Stone Storage

Chamber Storage + Stone Storage = 2,496.0 cf = 0.057 af



Overall Storage Efficiency = 55.5%

Overall System Size = 41.55' x 17.33' x 6.25'

10 Chambers

166.7 cy Field

123.8 cy Stone



Pond 7P: Chambers - Chamber Wizard Field B

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf

4 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 32.38' Row Length +18.0" End Stone x 2 = 35.38' Base Length

1 Rows x 77.0" Wide + 18.0" Side Stone x 2 = 9.42' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

4 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 1 Rows = 469.6 cf Chamber Storage

2,082.3 cf Field - 469.6 cf Chambers = 1,612.7 cf Stone x 40.0% Voids = 645.1 cf Stone Storage

Chamber Storage + Stone Storage = 1,114.7 cf = 0.026 af


Overall Storage Efficiency = 53.5%

Overall System Size = 35.38' x 9.42' x 6.25'

4 Chambers


77.1 cy Field

59.7 cy Stone




Pond 7P: Chambers

Hydrograph




Pond 7P: Chambers

Stage-Discharge



Pond 7P: Chambers

Stage-Area-Storage



Hydrograph for Pond 7P: Chambers

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	121.33	0.00	0.00	0.00
0.50	0.00	0.000	121.33	0.00	0.00	0.00
1.00	0.00	0.000	121.33	0.00	0.00	0.00
1.50	0.00	0.000	121.33	0.00	0.00	0.00
2.00	0.00	0.000	121.34	0.00	0.00	0.00
2.50	0.00	0.000	121.34	0.00	0.00	0.00
3.00	0.01	0.000	121.35	0.00	0.00	0.00
3.50	0.01	0.000	121.35	0.01	0.01	0.00
4.00	0.01	0.000	121.35	0.01	0.01	0.00
4.50	0.01	0.000	121.36	0.01	0.01	0.00
5.00	0.01	0.000	121.36	0.01	0.01	0.00
5.50	0.01	0.000	121.36	0.01	0.01	0.00
6.00	0.01	0.000	121.36	0.01	0.01	0.00
6.50	0.01	0.000	121.37	0.01	0.01	0.00
7.00	0.01	0.000	121.37	0.01	0.01	0.00
7.50	0.02	0.000	121.38	0.01	0.01	0.00
8.00	0.02	0.001	121.39	0.02	0.02	0.00
8.50	0.02	0.001	121.40	0.02	0.02	0.00
9.00	0.03	0.001	121.42	0.02	0.02	0.00
9.50	0.03	0.001	121.47	0.02	0.02	0.00
10.00	0.04	0.002	121.54	0.02	0.02	0.00
10.50	0.04	0.003	121.63	0.02	0.02	0.00
11.00	0.05	0.004	121.76	0.02	0.02	0.00
11.50	0.09	0.006	121.96	0.02	0.02	0.00
12.00	0.48	0.014	122.78	0.02	0.02	0.00
12.50	1.28	0.038	124.14	1.66	0.03	1.63
13.00	0.40	0.030	123.68	0.47	0.03	0.44
13.50	0.27	0.027	123.55	0.31	0.02	0.29
14.00	0.21	0.026	123.44	0.26	0.02	0.24
14.50	0.16	0.023	123.31	0.21	0.02	0.19
15.00	0.13	0.022	123.23	0.16	0.02	0.14
15.50	0.10	0.021	123.17	0.12	0.02	0.10
16.00	0.07	0.020	123.12	0.09	0.02	0.07
16.50	0.05	0.019	123.08	0.06	0.02	0.04
17.00	0.03	0.018	123.05	0.05	0.02	0.02
17.50	0.02	0.018	123.01	0.03	0.02	0.01
18.00	0.01	0.017	122.98	0.03	0.02	0.00
18.50	0.01	0.017	122.95	0.02	0.02	0.00
19.00	0.01	0.016	122.93	0.02	0.02	0.00
19.50	0.01	0.016	122.90	0.02	0.02	0.00
20.00	0.01	0.015	122.87	0.02	0.02	0.00
20.50	0.01	0.015	122.84	0.02	0.02	0.00
21.00	0.01	0.014	122.80	0.02	0.02	0.00
21.50	0.01	0.014	122.74	0.02	0.02	0.00
22.00	0.01	0.013	122.69	0.02	0.02	0.00
22.50	0.01	0.013	122.63	0.02	0.02	0.00
23.00	0.01	0.012	122.57	0.02	0.02	0.00
23.50	0.01	0.011	122.50	0.02	0.02	0.00
24.00	0.01	0.011	122.44	0.02	0.02	0.00

Stage-Discharge for Pond 7P: Chambers

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
121.33	0.00	0.00	0.00	126.53	5.08	0.03	5.04
121.43	0.02	0.02	0.00	126.63	5.34	0.03	5.31
121.53	0.02	0.02	0.00	126.73	5.70	0.03	5.67
121.63	0.02	0.02	0.00	126.83	6.14	0.03	6.11
121.73	0.02	0.02	0.00	126.93	6.66	0.03	6.62
121.83	0.02	0.02	0.00	127.03	7.25	0.03	7.22
121.93	0.02	0.02	0.00	127.13	7.92	0.04	7.88
122.03	0.02	0.02	0.00	127.23	8.68	0.04	8.65
122.13	0.02	0.02	0.00	127.33	9.50	0.04	9.46
122.23	0.02	0.02	0.00	127.43	10.29	0.04	10.25
122.33	0.02	0.02	0.00	127.53	11.12	0.04	11.08
122.43	0.02	0.02	0.00				
122.53	0.02	0.02	0.00				
122.63	0.02	0.02	0.00				
122.73	0.02	0.02	0.00				
122.83	0.02	0.02	0.00				
122.93	0.02	0.02	0.00				
123.03	0.04	0.02	0.02				
123.13	0.09	0.02	0.07				
123.23	0.16	0.02	0.14				
123.33	0.22	0.02	0.19				
123.43	0.26	0.02	0.24				
123.53	0.30	0.02	0.27				
123.63	0.39	0.02	0.37				
123.73	0.55	0.03	0.53				
123.83	0.77	0.03	0.75				
123.93	1.04	0.03	1.01				
124.03	1.33	0.03	1.31				
124.13	1.64	0.03	1.62				
124.23	1.94	0.03	1.92				
124.33	2.18	0.03	2.15				
124.43	2.39	0.03	2.36				
124.53	2.58	0.03	2.56				
124.63	2.76	0.03	2.73				
124.73	2.93	0.03	2.90				
124.83	3.09	0.03	3.06				
124.93	3.24	0.03	3.21				
125.03	3.38	0.03	3.35				
125.13	3.52	0.03	3.49				
125.23	3.65	0.03	3.62				
125.33	3.78	0.03	3.75				
125.43	3.90	0.03	3.87				
125.53	4.02	0.03	3.99				
125.63	4.13	0.03	4.10				
125.73	4.25	0.03	4.22				
125.83	4.36	0.03	4.32				
125.93	4.46	0.03	4.43				
126.03	4.57	0.03	4.53				
126.13	4.67	0.03	4.64				
126.23	4.77	0.03	4.74				
126.33	4.87	0.03	4.83				
126.43	4.96	0.03	4.93				

Stage-Area-Storage for Pond 7P: Chambers

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
121.33	0.024	0.000	126.53	0.024	0.073
121.43	0.024	0.001	126.63	0.024	0.074
121.53	0.024	0.002	126.73	0.024	0.075
121.63	0.024	0.003	126.83	0.024	0.076
121.73	0.024	0.004	126.93	0.024	0.077
121.83	0.024	0.005	127.03	0.024	0.078
121.93	0.024	0.006	127.13	0.024	0.079
122.03	0.024	0.007	127.23	0.024	0.080
122.13	0.024	0.008	127.33	0.024	0.080
122.23	0.024	0.009	127.43	0.024	0.081
122.33	0.024	0.010	127.53	0.024	0.082
122.43	0.024	0.011			
122.53	0.024	0.012			
122.63	0.024	0.013			
122.73	0.024	0.014			
122.83	0.024	0.015			
122.93	0.024	0.016			
123.03	0.024	0.018			
123.13	0.024	0.020			
123.23	0.024	0.022			
123.33	0.024	0.024			
123.43	0.024	0.025			
123.53	0.024	0.027			
123.63	0.024	0.029			
123.73	0.024	0.031			
123.83	0.024	0.032			
123.93	0.024	0.034			
124.03	0.024	0.036			
124.13	0.024	0.038			
124.23	0.024	0.039			
124.33	0.024	0.041			
124.43	0.024	0.043			
124.53	0.024	0.044			
124.63	0.024	0.046			
124.73	0.024	0.048			
124.83	0.024	0.049			
124.93	0.024	0.051			
125.03	0.024	0.053			
125.13	0.024	0.054			
125.23	0.024	0.056			
125.33	0.024	0.057			
125.43	0.024	0.059			
125.53	0.024	0.060			
125.63	0.024	0.062			
125.73	0.024	0.063			
125.83	0.024	0.065			
125.93	0.024	0.066			
126.03	0.024	0.067			
126.13	0.024	0.068			
126.23	0.024	0.070			
126.33	0.024	0.071			
126.43	0.024	0.072			

Summary for Pond 8P: Bioretention

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 1.050 ac, 19.05% Impervious, Inflow Depth > 3.26" for 10-yr event
 Inflow = 3.54 cfs @ 12.13 hrs, Volume= 0.285 af
 Outflow = 3.94 cfs @ 12.16 hrs, Volume= 0.238 af, Atten= 0%, Lag= 1.8 min
 Discarded = 0.10 cfs @ 12.16 hrs, Volume= 0.101 af
 Primary = 3.84 cfs @ 12.16 hrs, Volume= 0.136 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 130.21' @ 12.16 hrs Surf.Area= 0.096 ac Storage= 0.067 af

Plug-Flow detention time= 129.1 min calculated for 0.237 af (83% of inflow)
 Center-of-Mass det. time= 61.2 min (883.2 - 822.0)

Volume	Invert	Avail.Storage	Storage Description
#1	125.50'	0.020 af	Gravel (Prismatic) Listed below 0.050 af Overall x 40.0% Voids
#2	127.00'	0.029 af	Soil (Prismatic) Listed below (Recalc) 0.082 af Overall x 35.0% Voids
#3	129.50'	0.028 af	Custom Stage Data (Prismatic) Listed below (Recalc)
		0.077 af	Total Available Storage

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
125.50	0.033	0.000	0.000
127.00	0.033	0.050	0.050

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
127.00	0.033	0.000	0.000
129.50	0.033	0.082	0.082

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
129.50	0.023	0.000	0.000
130.00	0.028	0.013	0.013
130.50	0.033	0.015	0.028


Device	Routing	Invert	Outlet Devices
#1	Primary	130.00'	12.0" Horiz. Orifice/Grate X 4 rows C= 0.600 Limited to weir flow at low heads
#2	Discarded	125.50'	0.900 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 100.00'

Discarded OutFlow Max=0.10 cfs @ 12.16 hrs HW=130.20' (Free Discharge)
 ↑2=Exfiltration (Controls 0.10 cfs)

Primary OutFlow Max=3.60 cfs @ 12.16 hrs HW=130.20' (Free Discharge)
 ↑1=Orifice/Grate (Weir Controls 3.60 cfs @ 1.45 fps)


Pond 8P: Bioretention

Hydrograph



Pond 8P: Bioretention


Stage-Discharge



Pond 8P: Bioretention

Stage-Area-Storage

Surface/Horizontal/Wetted Area (acres)



Hydrograph for Pond 8P: Bioretention

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	125.50	0.00	0.00	0.00
0.50	0.00	0.000	125.50	0.00	0.00	0.00
1.00	0.00	0.000	125.50	0.00	0.00	0.00
1.50	0.00	0.000	125.50	0.00	0.00	0.00
2.00	0.00	0.000	125.50	0.00	0.00	0.00
2.50	0.00	0.000	125.50	0.00	0.00	0.00
3.00	0.00	0.000	125.50	0.00	0.00	0.00
3.50	0.00	0.000	125.50	0.00	0.00	0.00
4.00	0.00	0.000	125.50	0.00	0.00	0.00
4.50	0.00	0.000	125.50	0.00	0.00	0.00
5.00	0.00	0.000	125.50	0.00	0.00	0.00
5.50	0.00	0.000	125.50	0.00	0.00	0.00
6.00	0.00	0.000	125.50	0.00	0.00	0.00
6.50	0.00	0.000	125.50	0.00	0.00	0.00
7.00	0.00	0.000	125.50	0.00	0.00	0.00
7.50	0.00	0.000	125.50	0.00	0.00	0.00
8.00	0.01	0.000	125.51	0.00	0.00	0.00
8.50	0.02	0.000	125.52	0.01	0.01	0.00
9.00	0.03	0.001	125.54	0.03	0.03	0.00
9.50	0.05	0.001	125.59	0.03	0.03	0.00
10.00	0.08	0.003	125.70	0.03	0.03	0.00
10.50	0.12	0.005	125.90	0.03	0.03	0.00
11.00	0.17	0.010	126.24	0.03	0.03	0.00
11.50	0.30	0.018	126.84	0.03	0.03	0.00
12.00	1.81	0.048	129.41	0.07	0.07	0.00
12.50	1.13	0.064	130.09	1.22	0.10	1.12
13.00	0.41	0.062	130.04	0.43	0.09	0.33
13.50	0.31	0.062	130.02	0.32	0.09	0.22
14.00	0.26	0.062	130.02	0.26	0.09	0.17
14.50	0.22	0.062	130.01	0.22	0.09	0.13
15.00	0.19	0.062	130.01	0.20	0.09	0.10
15.50	0.17	0.062	130.01	0.17	0.09	0.07
16.00	0.14	0.062	130.01	0.14	0.09	0.05
16.50	0.12	0.062	130.00	0.12	0.09	0.03
17.00	0.11	0.061	130.00	0.11	0.09	0.02
17.50	0.10	0.061	130.00	0.10	0.09	0.00
18.00	0.08	0.061	129.99	0.09	0.09	0.00
18.50	0.08	0.061	129.97	0.09	0.09	0.00
19.00	0.07	0.060	129.95	0.09	0.09	0.00
19.50	0.07	0.059	129.92	0.09	0.09	0.00
20.00	0.07	0.058	129.88	0.09	0.09	0.00
20.50	0.06	0.057	129.84	0.09	0.09	0.00
21.00	0.06	0.056	129.79	0.09	0.09	0.00
21.50	0.06	0.055	129.74	0.09	0.09	0.00
22.00	0.06	0.053	129.69	0.09	0.09	0.00
22.50	0.05	0.052	129.63	0.09	0.09	0.00
23.00	0.05	0.050	129.56	0.09	0.09	0.00
23.50	0.05	0.049	129.49	0.08	0.08	0.00
24.00	0.04	0.048	129.40	0.07	0.07	0.00

Stage-Discharge for Pond 8P: Bioretention

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
125.50	0.00	0.00	0.00	128.10	0.06	0.06	0.00
125.55	0.03	0.03	0.00	128.15	0.06	0.06	0.00
125.60	0.03	0.03	0.00	128.20	0.06	0.06	0.00
125.65	0.03	0.03	0.00	128.25	0.06	0.06	0.00
125.70	0.03	0.03	0.00	128.30	0.06	0.06	0.00
125.75	0.03	0.03	0.00	128.35	0.06	0.06	0.00
125.80	0.03	0.03	0.00	128.40	0.06	0.06	0.00
125.85	0.03	0.03	0.00	128.45	0.06	0.06	0.00
125.90	0.03	0.03	0.00	128.50	0.07	0.07	0.00
125.95	0.03	0.03	0.00	128.55	0.07	0.07	0.00
126.00	0.03	0.03	0.00	128.60	0.07	0.07	0.00
126.05	0.03	0.03	0.00	128.65	0.07	0.07	0.00
126.10	0.03	0.03	0.00	128.70	0.07	0.07	0.00
126.15	0.03	0.03	0.00	128.75	0.07	0.07	0.00
126.20	0.03	0.03	0.00	128.80	0.07	0.07	0.00
126.25	0.03	0.03	0.00	128.85	0.07	0.07	0.00
126.30	0.03	0.03	0.00	128.90	0.07	0.07	0.00
126.35	0.03	0.03	0.00	128.95	0.07	0.07	0.00
126.40	0.03	0.03	0.00	129.00	0.07	0.07	0.00
126.45	0.03	0.03	0.00	129.05	0.07	0.07	0.00
126.50	0.03	0.03	0.00	129.10	0.07	0.07	0.00
126.55	0.03	0.03	0.00	129.15	0.07	0.07	0.00
126.60	0.03	0.03	0.00	129.20	0.07	0.07	0.00
126.65	0.03	0.03	0.00	129.25	0.07	0.07	0.00
126.70	0.03	0.03	0.00	129.30	0.07	0.07	0.00
126.75	0.03	0.03	0.00	129.35	0.07	0.07	0.00
126.80	0.03	0.03	0.00	129.40	0.07	0.07	0.00
126.85	0.03	0.03	0.00	129.45	0.07	0.07	0.00
126.90	0.03	0.03	0.00	129.50	0.09	0.09	0.00
126.95	0.03	0.03	0.00	129.55	0.09	0.09	0.00
127.00	0.06	0.06	0.00	129.60	0.09	0.09	0.00
127.05	0.06	0.06	0.00	129.65	0.09	0.09	0.00
127.10	0.06	0.06	0.00	129.70	0.09	0.09	0.00
127.15	0.06	0.06	0.00	129.75	0.09	0.09	0.00
127.20	0.06	0.06	0.00	129.80	0.09	0.09	0.00
127.25	0.06	0.06	0.00	129.85	0.09	0.09	0.00
127.30	0.06	0.06	0.00	129.90	0.09	0.09	0.00
127.35	0.06	0.06	0.00	129.95	0.09	0.09	0.00
127.40	0.06	0.06	0.00	130.00	0.09	0.09	0.00
127.45	0.06	0.06	0.00	130.05	0.55	0.09	0.46
127.50	0.06	0.06	0.00	130.10	1.39	0.10	1.30
127.55	0.06	0.06	0.00	130.15	2.48	0.10	2.39
127.60	0.06	0.06	0.00	130.20	3.77	0.10	3.68
127.65	0.06	0.06	0.00	130.25	5.23	0.10	5.14
127.70	0.06	0.06	0.00	130.30	6.85	0.10	6.75
127.75	0.06	0.06	0.00	130.35	8.61	0.10	8.51
127.80	0.06	0.06	0.00	130.40	9.67	0.10	9.57
127.85	0.06	0.06	0.00	130.45	10.25	0.10	10.15
127.90	0.06	0.06	0.00	130.50	10.80	0.10	10.70
127.95	0.06	0.06	0.00				
128.00	0.06	0.06	0.00				
128.05	0.06	0.06	0.00				

Stage-Area-Storage for Pond 8P: Bioretention

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
125.50	0.033	0.000	128.10	0.066	0.033
125.55	0.033	0.001	128.15	0.066	0.033
125.60	0.033	0.001	128.20	0.066	0.034
125.65	0.033	0.002	128.25	0.066	0.034
125.70	0.033	0.003	128.30	0.066	0.035
125.75	0.033	0.003	128.35	0.066	0.035
125.80	0.033	0.004	128.40	0.066	0.036
125.85	0.033	0.005	128.45	0.066	0.037
125.90	0.033	0.005	128.50	0.066	0.037
125.95	0.033	0.006	128.55	0.066	0.038
126.00	0.033	0.007	128.60	0.066	0.038
126.05	0.033	0.007	128.65	0.066	0.039
126.10	0.033	0.008	128.70	0.066	0.039
126.15	0.033	0.009	128.75	0.066	0.040
126.20	0.033	0.009	128.80	0.066	0.041
126.25	0.033	0.010	128.85	0.066	0.041
126.30	0.033	0.011	128.90	0.066	0.042
126.35	0.033	0.011	128.95	0.066	0.042
126.40	0.033	0.012	129.00	0.066	0.043
126.45	0.033	0.013	129.05	0.066	0.043
126.50	0.033	0.013	129.10	0.066	0.044
126.55	0.033	0.014	129.15	0.066	0.045
126.60	0.033	0.015	129.20	0.066	0.045
126.65	0.033	0.015	129.25	0.066	0.046
126.70	0.033	0.016	129.30	0.066	0.046
126.75	0.033	0.017	129.35	0.066	0.047
126.80	0.033	0.017	129.40	0.066	0.048
126.85	0.033	0.018	129.45	0.066	0.048
126.90	0.033	0.018	129.50	0.089	0.049
126.95	0.033	0.019	129.55	0.090	0.050
127.00	0.066	0.020	129.60	0.090	0.051
127.05	0.066	0.020	129.65	0.091	0.052
127.10	0.066	0.021	129.70	0.091	0.053
127.15	0.066	0.022	129.75	0.091	0.055
127.20	0.066	0.022	129.80	0.092	0.056
127.25	0.066	0.023	129.85	0.092	0.057
127.30	0.066	0.023	129.90	0.093	0.059
127.35	0.066	0.024	129.95	0.093	0.060
127.40	0.066	0.024	130.00	0.094	0.061
127.45	0.066	0.025	130.05	0.095	0.063
127.50	0.066	0.026	130.10	0.095	0.064
127.55	0.066	0.026	130.15	0.096	0.066
127.60	0.066	0.027	130.20	0.096	0.067
127.65	0.066	0.027	130.25	0.096	0.069
127.70	0.066	0.028	130.30	0.097	0.070
127.75	0.066	0.028	130.35	0.097	0.072
127.80	0.066	0.029	130.40	0.098	0.073
127.85	0.066	0.030	130.45	0.098	0.075
127.90	0.066	0.030	130.50	0.099	0.077
127.95	0.066	0.031			
128.00	0.066	0.031			
128.05	0.066	0.032			


Summary for Link 7L: Post (Composite)

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth = 1.55" for 10-yr event
 Inflow = 2.66 cfs @ 12.27 hrs, Volume= 0.153 af
 Primary = 2.66 cfs @ 12.27 hrs, Volume= 0.153 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: Post (Composite)

Hydrograph



Hydrograph for Link 7L: Post (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
0.00	0.00	0.00	0.00	13.00	0.44	0.00	0.44
0.25	0.00	0.00	0.00	13.25	0.34	0.00	0.34
0.50	0.00	0.00	0.00	13.50	0.29	0.00	0.29
0.75	0.00	0.00	0.00	13.75	0.26	0.00	0.26
1.00	0.00	0.00	0.00	14.00	0.24	0.00	0.24
1.25	0.00	0.00	0.00	14.25	0.21	0.00	0.21
1.50	0.00	0.00	0.00	14.50	0.19	0.00	0.19
1.75	0.00	0.00	0.00	14.75	0.16	0.00	0.16
2.00	0.00	0.00	0.00	15.00	0.14	0.00	0.14
2.25	0.00	0.00	0.00	15.25	0.12	0.00	0.12
2.50	0.00	0.00	0.00	15.50	0.10	0.00	0.10
2.75	0.00	0.00	0.00	15.75	0.08	0.00	0.08
3.00	0.00	0.00	0.00	16.00	0.07	0.00	0.07
3.25	0.00	0.00	0.00	16.25	0.05	0.00	0.05
3.50	0.00	0.00	0.00	16.50	0.04	0.00	0.04
3.75	0.00	0.00	0.00	16.75	0.03	0.00	0.03
4.00	0.00	0.00	0.00	17.00	0.02	0.00	0.02
4.25	0.00	0.00	0.00	17.25	0.02	0.00	0.02
4.50	0.00	0.00	0.00	17.50	0.01	0.00	0.01
4.75	0.00	0.00	0.00	17.75	0.01	0.00	0.01
5.00	0.00	0.00	0.00	18.00	0.00	0.00	0.00
5.25	0.00	0.00	0.00	18.25	0.00	0.00	0.00
5.50	0.00	0.00	0.00	18.50	0.00	0.00	0.00
5.75	0.00	0.00	0.00	18.75	0.00	0.00	0.00
6.00	0.00	0.00	0.00	19.00	0.00	0.00	0.00
6.25	0.00	0.00	0.00	19.25	0.00	0.00	0.00
6.50	0.00	0.00	0.00	19.50	0.00	0.00	0.00
6.75	0.00	0.00	0.00	19.75	0.00	0.00	0.00
7.00	0.00	0.00	0.00	20.00	0.00	0.00	0.00
7.25	0.00	0.00	0.00	20.25	0.00	0.00	0.00
7.50	0.00	0.00	0.00	20.50	0.00	0.00	0.00
7.75	0.00	0.00	0.00	20.75	0.00	0.00	0.00
8.00	0.00	0.00	0.00	21.00	0.00	0.00	0.00
8.25	0.00	0.00	0.00	21.25	0.00	0.00	0.00
8.50	0.00	0.00	0.00	21.50	0.00	0.00	0.00
8.75	0.00	0.00	0.00	21.75	0.00	0.00	0.00
9.00	0.00	0.00	0.00	22.00	0.00	0.00	0.00
9.25	0.00	0.00	0.00	22.25	0.00	0.00	0.00
9.50	0.00	0.00	0.00	22.50	0.00	0.00	0.00
9.75	0.00	0.00	0.00	22.75	0.00	0.00	0.00
10.00	0.00	0.00	0.00	23.00	0.00	0.00	0.00
10.25	0.00	0.00	0.00	23.25	0.00	0.00	0.00
10.50	0.00	0.00	0.00	23.50	0.00	0.00	0.00
10.75	0.00	0.00	0.00	23.75	0.00	0.00	0.00
11.00	0.00	0.00	0.00	24.00	0.00	0.00	0.00
11.25	0.00	0.00	0.00				
11.50	0.00	0.00	0.00				
11.75	0.00	0.00	0.00				
12.00	0.00	0.00	0.00				
12.25	2.64	0.00	2.64				
12.50	1.63	0.00	1.63				
12.75	0.67	0.00	0.67				

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment4S: PR-01 (Site)

Runoff Area=1.050 ac 19.05% Impervious Runoff Depth>4.35"
Flow Length=310' Tc=9.1 min CN=79 Runoff=4.71 cfs 0.381 af

Subcatchment5S: PR-02 (Roof)

Runoff Area=0.140 ac 100.00% Impervious Runoff Depth>6.51"
Tc=6.0 min CN=98 Runoff=0.91 cfs 0.076 af

Pond 7P: Chambers

Peak Elev=125.51' Storage=0.060 af Inflow=5.35 cfs 0.295 af
Discarded=0.03 cfs 0.036 af Primary=3.97 cfs 0.247 af Outflow=4.00 cfs 0.283 af

Pond 8P: Bioretention

Peak Elev=130.23' Storage=0.068 af Inflow=4.71 cfs 0.381 af
Discarded=0.10 cfs 0.107 af Primary=4.60 cfs 0.220 af Outflow=4.70 cfs 0.327 af

Link 7L: Post (Composite)

Inflow=3.97 cfs 0.247 af
Primary=3.97 cfs 0.247 af

Total Runoff Area = 1.190 ac Runoff Volume = 0.457 af Average Runoff Depth = 4.60"
71.43% Pervious = 0.850 ac 28.57% Impervious = 0.340 ac

Summary for Subcatchment 4S: PR-01 (Site)

Runoff = 4.71 cfs @ 12.13 hrs, Volume= 0.381 af, Depth> 4.35"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.75"

Area (ac)	CN	Description
0.200	98	Paved parking, HSG C
0.850	74	>75% Grass cover, Good, HSG C
1.050	79	Weighted Average
0.850		80.95% Pervious Area
0.200		19.05% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	35	0.0700	0.24		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.7	28	0.1070	0.27		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
3.4	37	0.0340	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.0	78	0.0350	1.31		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
0.1	30	0.0500	4.54		Shallow Concentrated Flow, Pathway Paved Kv= 20.3 fps
0.3	52	0.0290	2.55		Shallow Concentrated Flow, Shallow Concentrated Grassed Waterway Kv= 15.0 fps
0.2	50	0.2000	4.47		Shallow Concentrated Flow, Shallow Concentrated Nearly Bare & Untilled Kv= 10.0 fps
9.1	310	Total			

Subcatchment 4S: PR-01 (Site)

Hydrograph



Hydrograph for Subcatchment 4S: PR-01 (Site)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	5.06	2.86	0.53
0.25	0.02	0.00	0.00	13.25	5.18	2.96	0.44
0.50	0.03	0.00	0.00	13.50	5.29	3.05	0.40
0.75	0.05	0.00	0.00	13.75	5.39	3.14	0.36
1.00	0.07	0.00	0.00	14.00	5.47	3.21	0.33
1.25	0.08	0.00	0.00	14.25	5.55	3.28	0.30
1.50	0.10	0.00	0.00	14.50	5.63	3.35	0.28
1.75	0.12	0.00	0.00	14.75	5.70	3.41	0.27
2.00	0.14	0.00	0.00	15.00	5.77	3.47	0.25
2.25	0.15	0.00	0.00	15.25	5.83	3.53	0.23
2.50	0.17	0.00	0.00	15.50	5.88	3.58	0.21
2.75	0.19	0.00	0.00	15.75	5.93	3.62	0.19
3.00	0.21	0.00	0.00	16.00	5.98	3.66	0.18
3.25	0.23	0.00	0.00	16.25	6.02	3.70	0.16
3.50	0.25	0.00	0.00	16.50	6.06	3.74	0.15
3.75	0.27	0.00	0.00	16.75	6.10	3.77	0.15
4.00	0.29	0.00	0.00	17.00	6.14	3.80	0.14
4.25	0.31	0.00	0.00	17.25	6.17	3.83	0.13
4.50	0.34	0.00	0.00	17.50	6.21	3.86	0.12
4.75	0.36	0.00	0.00	17.75	6.24	3.89	0.12
5.00	0.38	0.00	0.00	18.00	6.26	3.92	0.11
5.25	0.41	0.00	0.00	18.25	6.29	3.94	0.10
5.50	0.43	0.00	0.00	18.50	6.32	3.96	0.10
5.75	0.46	0.00	0.00	18.75	6.34	3.99	0.10
6.00	0.49	0.00	0.00	19.00	6.37	4.01	0.09
6.25	0.51	0.00	0.00	19.25	6.39	4.03	0.09
6.50	0.54	0.00	0.00	19.50	6.41	4.05	0.09
6.75	0.58	0.00	0.00	19.75	6.44	4.07	0.09
7.00	0.61	0.00	0.01	20.00	6.46	4.09	0.09
7.25	0.65	0.00	0.01	20.25	6.48	4.11	0.08
7.50	0.69	0.01	0.02	20.50	6.50	4.13	0.08
7.75	0.73	0.01	0.02	20.75	6.52	4.15	0.08
8.00	0.77	0.02	0.03	21.00	6.54	4.17	0.08
8.25	0.82	0.03	0.03	21.25	6.56	4.19	0.08
8.50	0.87	0.04	0.04	21.50	6.58	4.20	0.07
8.75	0.92	0.05	0.05	21.75	6.60	4.22	0.07
9.00	0.98	0.07	0.06	22.00	6.62	4.24	0.07
9.25	1.05	0.08	0.08	22.25	6.64	4.25	0.07
9.50	1.12	0.11	0.09	22.50	6.66	4.27	0.07
9.75	1.20	0.13	0.11	22.75	6.67	4.29	0.07
10.00	1.28	0.16	0.13	23.00	6.69	4.30	0.06
10.25	1.36	0.20	0.15	23.25	6.70	4.32	0.06
10.50	1.46	0.24	0.18	23.50	6.72	4.33	0.06
10.75	1.57	0.29	0.21	23.75	6.74	4.34	0.06
11.00	1.69	0.35	0.25	24.00	6.75	4.36	0.06
11.25	1.83	0.43	0.32				
11.50	2.01	0.53	0.43				
11.75	2.40	0.77	0.96				
12.00	3.37	1.47	2.46				
12.25	4.35	2.25	3.15				
12.50	4.74	2.58	1.46				
12.75	4.92	2.73	0.68				

Summary for Subcatchment 5S: PR-02 (Roof)

Runoff = 0.91 cfs @ 12.09 hrs, Volume= 0.076 af, Depth> 6.51"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.75"

Area (ac)	CN	Description
0.140	98	Roofs, HSG C
0.140		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Roof

Subcatchment 5S: PR-02 (Roof)

Hydrograph



Hydrograph for Subcatchment 5S: PR-02 (Roof)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	5.06	4.83	0.08
0.25	0.02	0.00	0.00	13.25	5.18	4.94	0.07
0.50	0.03	0.00	0.00	13.50	5.29	5.05	0.06
0.75	0.05	0.00	0.00	13.75	5.39	5.15	0.05
1.00	0.07	0.00	0.00	14.00	5.47	5.24	0.05
1.25	0.08	0.01	0.00	14.25	5.55	5.32	0.04
1.50	0.10	0.01	0.00	14.50	5.63	5.39	0.04
1.75	0.12	0.02	0.00	14.75	5.70	5.46	0.04
2.00	0.14	0.03	0.00	15.00	5.77	5.53	0.04
2.25	0.15	0.04	0.01	15.25	5.83	5.59	0.03
2.50	0.17	0.05	0.01	15.50	5.88	5.65	0.03
2.75	0.19	0.06	0.01	15.75	5.93	5.70	0.03
3.00	0.21	0.07	0.01	16.00	5.98	5.74	0.03
3.25	0.23	0.09	0.01	16.25	6.02	5.79	0.02
3.50	0.25	0.10	0.01	16.50	6.06	5.83	0.02
3.75	0.27	0.12	0.01	16.75	6.10	5.86	0.02
4.00	0.29	0.14	0.01	17.00	6.14	5.90	0.02
4.25	0.31	0.16	0.01	17.25	6.17	5.94	0.02
4.50	0.34	0.17	0.01	17.50	6.21	5.97	0.02
4.75	0.36	0.19	0.01	17.75	6.24	6.00	0.02
5.00	0.38	0.21	0.01	18.00	6.26	6.03	0.02
5.25	0.41	0.24	0.01	18.25	6.29	6.05	0.02
5.50	0.43	0.26	0.01	18.50	6.32	6.08	0.01
5.75	0.46	0.28	0.01	18.75	6.34	6.10	0.01
6.00	0.49	0.31	0.01	19.00	6.37	6.13	0.01
6.25	0.51	0.33	0.01	19.25	6.39	6.15	0.01
6.50	0.54	0.36	0.02	19.50	6.41	6.18	0.01
6.75	0.58	0.39	0.02	19.75	6.44	6.20	0.01
7.00	0.61	0.42	0.02	20.00	6.46	6.22	0.01
7.25	0.65	0.45	0.02	20.25	6.48	6.24	0.01
7.50	0.69	0.49	0.02	20.50	6.50	6.26	0.01
7.75	0.73	0.53	0.02	20.75	6.52	6.28	0.01
8.00	0.77	0.57	0.02	21.00	6.54	6.31	0.01
8.25	0.82	0.61	0.03	21.25	6.56	6.32	0.01
8.50	0.87	0.66	0.03	21.50	6.58	6.34	0.01
8.75	0.92	0.72	0.03	21.75	6.60	6.36	0.01
9.00	0.98	0.78	0.03	22.00	6.62	6.38	0.01
9.25	1.05	0.84	0.04	22.25	6.64	6.40	0.01
9.50	1.12	0.91	0.04	22.50	6.66	6.42	0.01
9.75	1.20	0.98	0.04	22.75	6.67	6.43	0.01
10.00	1.28	1.06	0.04	23.00	6.69	6.45	0.01
10.25	1.36	1.15	0.05	23.25	6.70	6.47	0.01
10.50	1.46	1.24	0.06	23.50	6.72	6.48	0.01
10.75	1.57	1.35	0.06	23.75	6.74	6.50	0.01
11.00	1.69	1.47	0.07	24.00	6.75	6.51	0.01
11.25	1.83	1.61	0.08				
11.50	2.01	1.79	0.10				
11.75	2.40	2.17	0.24				
12.00	3.37	3.14	0.59				
12.25	4.35	4.12	0.42				
12.50	4.74	4.50	0.19				
12.75	4.92	4.68	0.10				

Summary for Pond 7P: Chambers

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth > 2.98" for 25-yr event
 Inflow = 5.35 cfs @ 12.13 hrs, Volume= 0.295 af
 Outflow = 4.00 cfs @ 12.23 hrs, Volume= 0.283 af, Atten= 25%, Lag= 6.0 min
 Discarded = 0.03 cfs @ 12.24 hrs, Volume= 0.036 af
 Primary = 3.97 cfs @ 12.23 hrs, Volume= 0.247 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 125.51' @ 12.24 hrs Surf.Area= 0.024 ac Storage= 0.060 af

Plug-Flow detention time= 44.2 min calculated for 0.283 af (96% of inflow)
 Center-of-Mass det. time= 28.2 min (794.5 - 766.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	121.33'	0.031 af	17.33'W x 41.55'L x 6.25'H Field A 0.103 af Overall - 0.027 af Embedded = 0.077 af x 40.0% Voids
#2A	122.83'	0.027 af	ADS StormTech MC-3500 d +Cap x 10 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 10 Chambers in 2 Rows Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf
#3B	121.33'	0.015 af	9.42'W x 35.38'L x 6.25'H Field B 0.048 af Overall - 0.011 af Embedded = 0.037 af x 40.0% Voids
#4B	122.83'	0.011 af	ADS StormTech MC-3500 d +Cap x 4 Inside #3 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf
		0.083 af	Total Available Storage

Storage Group A created with Chamber Wizard
 Storage Group B created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	121.33'	0.750 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 115.00'
#2	Primary	122.95'	4.0" Vert. Orifice/Grate C= 0.600
#3	Primary	123.50'	10.0" Vert. Orifice/Grate C= 0.600
#4	Primary	126.50'	1.5' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Discarded OutFlow Max=0.03 cfs @ 12.24 hrs HW=125.49' (Free Discharge)

↑1=Exfiltration (Controls 0.03 cfs)

Primary OutFlow Max=3.94 cfs @ 12.23 hrs HW=125.49' (Free Discharge)

↑2=Orifice/Grate (Orifice Controls 0.65 cfs @ 7.42 fps)
 ↑3=Orifice/Grate (Orifice Controls 3.29 cfs @ 6.04 fps)
 ↑4=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 7P: Chambers - Chamber Wizard Field A

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf

77.0" Wide + 18.0" Spacing = 95.0" C-C Row Spacing

5 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 39.55' Row Length +12.0" End Stone x 2 = 41.55' Base Length

2 Rows x 77.0" Wide + 18.0" Spacing x 1 + 18.0" Side Stone x 2 = 17.33' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

10 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 2 Rows = 1,159.1 cf Chamber Storage

4,501.2 cf Field - 1,159.1 cf Chambers = 3,342.1 cf Stone x 40.0% Voids = 1,336.9 cf Stone Storage

Chamber Storage + Stone Storage = 2,496.0 cf = 0.057 af



Overall Storage Efficiency = 55.5%

Overall System Size = 41.55' x 17.33' x 6.25'

10 Chambers

166.7 cy Field

123.8 cy Stone



Pond 7P: Chambers - Chamber Wizard Field B

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf

4 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 32.38' Row Length +18.0" End Stone x 2 = 35.38' Base Length

1 Rows x 77.0" Wide + 18.0" Side Stone x 2 = 9.42' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

4 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 1 Rows = 469.6 cf Chamber Storage

2,082.3 cf Field - 469.6 cf Chambers = 1,612.7 cf Stone x 40.0% Voids = 645.1 cf Stone Storage

Chamber Storage + Stone Storage = 1,114.7 cf = 0.026 af


Overall Storage Efficiency = 53.5%

Overall System Size = 35.38' x 9.42' x 6.25'

4 Chambers


77.1 cy Field

59.7 cy Stone




Pond 7P: Chambers

Hydrograph




Pond 7P: Chambers

Stage-Discharge



Pond 7P: Chambers

Stage-Area-Storage



Hydrograph for Pond 7P: Chambers

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	121.33	0.00	0.00	0.00
0.50	0.00	0.000	121.33	0.00	0.00	0.00
1.00	0.00	0.000	121.33	0.00	0.00	0.00
1.50	0.00	0.000	121.34	0.00	0.00	0.00
2.00	0.00	0.000	121.34	0.00	0.00	0.00
2.50	0.01	0.000	121.35	0.01	0.01	0.00
3.00	0.01	0.000	121.35	0.01	0.01	0.00
3.50	0.01	0.000	121.36	0.01	0.01	0.00
4.00	0.01	0.000	121.36	0.01	0.01	0.00
4.50	0.01	0.000	121.36	0.01	0.01	0.00
5.00	0.01	0.000	121.37	0.01	0.01	0.00
5.50	0.01	0.000	121.37	0.01	0.01	0.00
6.00	0.01	0.000	121.37	0.01	0.01	0.00
6.50	0.02	0.000	121.38	0.01	0.01	0.00
7.00	0.02	0.001	121.39	0.02	0.02	0.00
7.50	0.02	0.001	121.39	0.02	0.02	0.00
8.00	0.02	0.001	121.41	0.02	0.02	0.00
8.50	0.03	0.001	121.44	0.02	0.02	0.00
9.00	0.03	0.002	121.49	0.02	0.02	0.00
9.50	0.04	0.002	121.56	0.02	0.02	0.00
10.00	0.04	0.003	121.66	0.02	0.02	0.00
10.50	0.06	0.004	121.79	0.02	0.02	0.00
11.00	0.07	0.006	121.96	0.02	0.02	0.00
11.50	0.10	0.009	122.23	0.02	0.02	0.00
12.00	2.92	0.025	123.39	0.24	0.02	0.22
12.50	1.65	0.043	124.46	2.45	0.03	2.43
13.00	0.53	0.031	123.75	0.60	0.03	0.57
13.50	0.37	0.029	123.64	0.40	0.02	0.38
14.00	0.29	0.028	123.56	0.32	0.02	0.30
14.50	0.23	0.026	123.47	0.27	0.02	0.25
15.00	0.19	0.024	123.37	0.24	0.02	0.21
15.50	0.15	0.023	123.27	0.19	0.02	0.17
16.00	0.11	0.021	123.19	0.14	0.02	0.12
16.50	0.08	0.020	123.14	0.10	0.02	0.08
17.00	0.07	0.020	123.11	0.08	0.02	0.06
17.50	0.05	0.019	123.08	0.06	0.02	0.04
18.00	0.03	0.018	123.04	0.05	0.02	0.02
18.50	0.02	0.018	123.01	0.03	0.02	0.01
19.00	0.01	0.017	122.98	0.03	0.02	0.00
19.50	0.01	0.017	122.96	0.02	0.02	0.00
20.00	0.01	0.016	122.94	0.02	0.02	0.00
20.50	0.01	0.016	122.91	0.02	0.02	0.00
21.00	0.01	0.016	122.89	0.02	0.02	0.00
21.50	0.01	0.015	122.86	0.02	0.02	0.00
22.00	0.01	0.015	122.83	0.02	0.02	0.00
22.50	0.01	0.014	122.78	0.02	0.02	0.00
23.00	0.01	0.013	122.73	0.02	0.02	0.00
23.50	0.01	0.013	122.67	0.02	0.02	0.00
24.00	0.01	0.012	122.61	0.02	0.02	0.00

Stage-Discharge for Pond 7P: Chambers

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
121.33	0.00	0.00	0.00	126.53	5.08	0.03	5.04
121.43	0.02	0.02	0.00	126.63	5.34	0.03	5.31
121.53	0.02	0.02	0.00	126.73	5.70	0.03	5.67
121.63	0.02	0.02	0.00	126.83	6.14	0.03	6.11
121.73	0.02	0.02	0.00	126.93	6.66	0.03	6.62
121.83	0.02	0.02	0.00	127.03	7.25	0.03	7.22
121.93	0.02	0.02	0.00	127.13	7.92	0.04	7.88
122.03	0.02	0.02	0.00	127.23	8.68	0.04	8.65
122.13	0.02	0.02	0.00	127.33	9.50	0.04	9.46
122.23	0.02	0.02	0.00	127.43	10.29	0.04	10.25
122.33	0.02	0.02	0.00	127.53	11.12	0.04	11.08
122.43	0.02	0.02	0.00				
122.53	0.02	0.02	0.00				
122.63	0.02	0.02	0.00				
122.73	0.02	0.02	0.00				
122.83	0.02	0.02	0.00				
122.93	0.02	0.02	0.00				
123.03	0.04	0.02	0.02				
123.13	0.09	0.02	0.07				
123.23	0.16	0.02	0.14				
123.33	0.22	0.02	0.19				
123.43	0.26	0.02	0.24				
123.53	0.30	0.02	0.27				
123.63	0.39	0.02	0.37				
123.73	0.55	0.03	0.53				
123.83	0.77	0.03	0.75				
123.93	1.04	0.03	1.01				
124.03	1.33	0.03	1.31				
124.13	1.64	0.03	1.62				
124.23	1.94	0.03	1.92				
124.33	2.18	0.03	2.15				
124.43	2.39	0.03	2.36				
124.53	2.58	0.03	2.56				
124.63	2.76	0.03	2.73				
124.73	2.93	0.03	2.90				
124.83	3.09	0.03	3.06				
124.93	3.24	0.03	3.21				
125.03	3.38	0.03	3.35				
125.13	3.52	0.03	3.49				
125.23	3.65	0.03	3.62				
125.33	3.78	0.03	3.75				
125.43	3.90	0.03	3.87				
125.53	4.02	0.03	3.99				
125.63	4.13	0.03	4.10				
125.73	4.25	0.03	4.22				
125.83	4.36	0.03	4.32				
125.93	4.46	0.03	4.43				
126.03	4.57	0.03	4.53				
126.13	4.67	0.03	4.64				
126.23	4.77	0.03	4.74				
126.33	4.87	0.03	4.83				
126.43	4.96	0.03	4.93				

Stage-Area-Storage for Pond 7P: Chambers

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
121.33	0.024	0.000	126.53	0.024	0.073
121.43	0.024	0.001	126.63	0.024	0.074
121.53	0.024	0.002	126.73	0.024	0.075
121.63	0.024	0.003	126.83	0.024	0.076
121.73	0.024	0.004	126.93	0.024	0.077
121.83	0.024	0.005	127.03	0.024	0.078
121.93	0.024	0.006	127.13	0.024	0.079
122.03	0.024	0.007	127.23	0.024	0.080
122.13	0.024	0.008	127.33	0.024	0.080
122.23	0.024	0.009	127.43	0.024	0.081
122.33	0.024	0.010	127.53	0.024	0.082
122.43	0.024	0.011			
122.53	0.024	0.012			
122.63	0.024	0.013			
122.73	0.024	0.014			
122.83	0.024	0.015			
122.93	0.024	0.016			
123.03	0.024	0.018			
123.13	0.024	0.020			
123.23	0.024	0.022			
123.33	0.024	0.024			
123.43	0.024	0.025			
123.53	0.024	0.027			
123.63	0.024	0.029			
123.73	0.024	0.031			
123.83	0.024	0.032			
123.93	0.024	0.034			
124.03	0.024	0.036			
124.13	0.024	0.038			
124.23	0.024	0.039			
124.33	0.024	0.041			
124.43	0.024	0.043			
124.53	0.024	0.044			
124.63	0.024	0.046			
124.73	0.024	0.048			
124.83	0.024	0.049			
124.93	0.024	0.051			
125.03	0.024	0.053			
125.13	0.024	0.054			
125.23	0.024	0.056			
125.33	0.024	0.057			
125.43	0.024	0.059			
125.53	0.024	0.060			
125.63	0.024	0.062			
125.73	0.024	0.063			
125.83	0.024	0.065			
125.93	0.024	0.066			
126.03	0.024	0.067			
126.13	0.024	0.068			
126.23	0.024	0.070			
126.33	0.024	0.071			
126.43	0.024	0.072			

Summary for Pond 8P: Bioretention

Inflow Area = 1.050 ac, 19.05% Impervious, Inflow Depth > 4.35" for 25-yr event
 Inflow = 4.71 cfs @ 12.13 hrs, Volume= 0.381 af
 Outflow = 4.70 cfs @ 12.14 hrs, Volume= 0.327 af, Atten= 0%, Lag= 0.9 min
 Discarded = 0.10 cfs @ 12.14 hrs, Volume= 0.107 af
 Primary = 4.60 cfs @ 12.14 hrs, Volume= 0.220 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 130.23' @ 12.14 hrs Surf.Area= 0.096 ac Storage= 0.068 af

Plug-Flow detention time= 101.0 min calculated for 0.326 af (86% of inflow)
 Center-of-Mass det. time= 40.5 min (854.3 - 813.8)

Volume	Invert	Avail.Storage	Storage Description
#1	125.50'	0.020 af	Gravel (Prismatic) Listed below 0.050 af Overall x 40.0% Voids
#2	127.00'	0.029 af	Soil (Prismatic) Listed below (Recalc) 0.082 af Overall x 35.0% Voids
#3	129.50'	0.028 af	Custom Stage Data (Prismatic) Listed below (Recalc)
		0.077 af	Total Available Storage

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
125.50	0.033	0.000	0.000
127.00	0.033	0.050	0.050

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
127.00	0.033	0.000	0.000
129.50	0.033	0.082	0.082

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
129.50	0.023	0.000	0.000
130.00	0.028	0.013	0.013
130.50	0.033	0.015	0.028


Device	Routing	Invert	Outlet Devices
#1	Primary	130.00'	12.0" Horiz. Orifice/Grate X 4 rows C= 0.600 Limited to weir flow at low heads
#2	Discarded	125.50'	0.900 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 100.00'

Discarded OutFlow Max=0.10 cfs @ 12.14 hrs HW=130.23' (Free Discharge)
 ↑2=Exfiltration (Controls 0.10 cfs)

Primary OutFlow Max=4.54 cfs @ 12.14 hrs HW=130.23' (Free Discharge)
 ↑1=Orifice/Grate (Weir Controls 4.54 cfs @ 1.57 fps)


Pond 8P: Bioretention

Hydrograph




Pond 8P: Bioretention

Stage-Discharge



Pond 8P: Bioretention

Stage-Area-Storage



Hydrograph for Pond 8P: Bioretention

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	125.50	0.00	0.00	0.00
0.50	0.00	0.000	125.50	0.00	0.00	0.00
1.00	0.00	0.000	125.50	0.00	0.00	0.00
1.50	0.00	0.000	125.50	0.00	0.00	0.00
2.00	0.00	0.000	125.50	0.00	0.00	0.00
2.50	0.00	0.000	125.50	0.00	0.00	0.00
3.00	0.00	0.000	125.50	0.00	0.00	0.00
3.50	0.00	0.000	125.50	0.00	0.00	0.00
4.00	0.00	0.000	125.50	0.00	0.00	0.00
4.50	0.00	0.000	125.50	0.00	0.00	0.00
5.00	0.00	0.000	125.50	0.00	0.00	0.00
5.50	0.00	0.000	125.50	0.00	0.00	0.00
6.00	0.00	0.000	125.50	0.00	0.00	0.00
6.50	0.00	0.000	125.50	0.00	0.00	0.00
7.00	0.01	0.000	125.51	0.00	0.00	0.00
7.50	0.02	0.000	125.52	0.01	0.01	0.00
8.00	0.03	0.000	125.53	0.02	0.02	0.00
8.50	0.04	0.001	125.56	0.03	0.03	0.00
9.00	0.06	0.002	125.63	0.03	0.03	0.00
9.50	0.09	0.004	125.78	0.03	0.03	0.00
10.00	0.13	0.007	126.03	0.03	0.03	0.00
10.50	0.18	0.012	126.40	0.03	0.03	0.00
11.00	0.25	0.019	126.96	0.04	0.04	0.00
11.50	0.43	0.030	127.89	0.06	0.06	0.00
12.00	2.46	0.066	130.15	2.43	0.10	2.33
12.50	1.46	0.064	130.11	1.55	0.10	1.46
13.00	0.53	0.063	130.05	0.54	0.09	0.45
13.50	0.40	0.062	130.03	0.41	0.09	0.31
14.00	0.33	0.062	130.03	0.33	0.09	0.24
14.50	0.28	0.062	130.02	0.29	0.09	0.19
15.00	0.25	0.062	130.02	0.25	0.09	0.16
15.50	0.21	0.062	130.01	0.21	0.09	0.12
16.00	0.18	0.062	130.01	0.18	0.09	0.08
16.50	0.15	0.062	130.01	0.16	0.09	0.06
17.00	0.14	0.062	130.00	0.14	0.09	0.05
17.50	0.12	0.062	130.00	0.12	0.09	0.03
18.00	0.11	0.061	130.00	0.11	0.09	0.01
18.50	0.10	0.061	130.00	0.10	0.09	0.01
19.00	0.09	0.061	130.00	0.10	0.09	0.00
19.50	0.09	0.061	130.00	0.09	0.09	0.00
20.00	0.09	0.061	129.99	0.09	0.09	0.00
20.50	0.08	0.061	129.97	0.09	0.09	0.00
21.00	0.08	0.060	129.95	0.09	0.09	0.00
21.50	0.07	0.059	129.92	0.09	0.09	0.00
22.00	0.07	0.058	129.89	0.09	0.09	0.00
22.50	0.07	0.058	129.86	0.09	0.09	0.00
23.00	0.06	0.056	129.81	0.09	0.09	0.00
23.50	0.06	0.055	129.77	0.09	0.09	0.00
24.00	0.06	0.054	129.71	0.09	0.09	0.00

Stage-Discharge for Pond 8P: Bioretention

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
125.50	0.00	0.00	0.00	128.10	0.06	0.06	0.00
125.55	0.03	0.03	0.00	128.15	0.06	0.06	0.00
125.60	0.03	0.03	0.00	128.20	0.06	0.06	0.00
125.65	0.03	0.03	0.00	128.25	0.06	0.06	0.00
125.70	0.03	0.03	0.00	128.30	0.06	0.06	0.00
125.75	0.03	0.03	0.00	128.35	0.06	0.06	0.00
125.80	0.03	0.03	0.00	128.40	0.06	0.06	0.00
125.85	0.03	0.03	0.00	128.45	0.06	0.06	0.00
125.90	0.03	0.03	0.00	128.50	0.07	0.07	0.00
125.95	0.03	0.03	0.00	128.55	0.07	0.07	0.00
126.00	0.03	0.03	0.00	128.60	0.07	0.07	0.00
126.05	0.03	0.03	0.00	128.65	0.07	0.07	0.00
126.10	0.03	0.03	0.00	128.70	0.07	0.07	0.00
126.15	0.03	0.03	0.00	128.75	0.07	0.07	0.00
126.20	0.03	0.03	0.00	128.80	0.07	0.07	0.00
126.25	0.03	0.03	0.00	128.85	0.07	0.07	0.00
126.30	0.03	0.03	0.00	128.90	0.07	0.07	0.00
126.35	0.03	0.03	0.00	128.95	0.07	0.07	0.00
126.40	0.03	0.03	0.00	129.00	0.07	0.07	0.00
126.45	0.03	0.03	0.00	129.05	0.07	0.07	0.00
126.50	0.03	0.03	0.00	129.10	0.07	0.07	0.00
126.55	0.03	0.03	0.00	129.15	0.07	0.07	0.00
126.60	0.03	0.03	0.00	129.20	0.07	0.07	0.00
126.65	0.03	0.03	0.00	129.25	0.07	0.07	0.00
126.70	0.03	0.03	0.00	129.30	0.07	0.07	0.00
126.75	0.03	0.03	0.00	129.35	0.07	0.07	0.00
126.80	0.03	0.03	0.00	129.40	0.07	0.07	0.00
126.85	0.03	0.03	0.00	129.45	0.07	0.07	0.00
126.90	0.03	0.03	0.00	129.50	0.09	0.09	0.00
126.95	0.03	0.03	0.00	129.55	0.09	0.09	0.00
127.00	0.06	0.06	0.00	129.60	0.09	0.09	0.00
127.05	0.06	0.06	0.00	129.65	0.09	0.09	0.00
127.10	0.06	0.06	0.00	129.70	0.09	0.09	0.00
127.15	0.06	0.06	0.00	129.75	0.09	0.09	0.00
127.20	0.06	0.06	0.00	129.80	0.09	0.09	0.00
127.25	0.06	0.06	0.00	129.85	0.09	0.09	0.00
127.30	0.06	0.06	0.00	129.90	0.09	0.09	0.00
127.35	0.06	0.06	0.00	129.95	0.09	0.09	0.00
127.40	0.06	0.06	0.00	130.00	0.09	0.09	0.00
127.45	0.06	0.06	0.00	130.05	0.55	0.09	0.46
127.50	0.06	0.06	0.00	130.10	1.39	0.10	1.30
127.55	0.06	0.06	0.00	130.15	2.48	0.10	2.39
127.60	0.06	0.06	0.00	130.20	3.77	0.10	3.68
127.65	0.06	0.06	0.00	130.25	5.23	0.10	5.14
127.70	0.06	0.06	0.00	130.30	6.85	0.10	6.75
127.75	0.06	0.06	0.00	130.35	8.61	0.10	8.51
127.80	0.06	0.06	0.00	130.40	9.67	0.10	9.57
127.85	0.06	0.06	0.00	130.45	10.25	0.10	10.15
127.90	0.06	0.06	0.00	130.50	10.80	0.10	10.70
127.95	0.06	0.06	0.00				
128.00	0.06	0.06	0.00				
128.05	0.06	0.06	0.00				

Stage-Area-Storage for Pond 8P: Bioretention

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
125.50	0.033	0.000	128.10	0.066	0.033
125.55	0.033	0.001	128.15	0.066	0.033
125.60	0.033	0.001	128.20	0.066	0.034
125.65	0.033	0.002	128.25	0.066	0.034
125.70	0.033	0.003	128.30	0.066	0.035
125.75	0.033	0.003	128.35	0.066	0.035
125.80	0.033	0.004	128.40	0.066	0.036
125.85	0.033	0.005	128.45	0.066	0.037
125.90	0.033	0.005	128.50	0.066	0.037
125.95	0.033	0.006	128.55	0.066	0.038
126.00	0.033	0.007	128.60	0.066	0.038
126.05	0.033	0.007	128.65	0.066	0.039
126.10	0.033	0.008	128.70	0.066	0.039
126.15	0.033	0.009	128.75	0.066	0.040
126.20	0.033	0.009	128.80	0.066	0.041
126.25	0.033	0.010	128.85	0.066	0.041
126.30	0.033	0.011	128.90	0.066	0.042
126.35	0.033	0.011	128.95	0.066	0.042
126.40	0.033	0.012	129.00	0.066	0.043
126.45	0.033	0.013	129.05	0.066	0.043
126.50	0.033	0.013	129.10	0.066	0.044
126.55	0.033	0.014	129.15	0.066	0.045
126.60	0.033	0.015	129.20	0.066	0.045
126.65	0.033	0.015	129.25	0.066	0.046
126.70	0.033	0.016	129.30	0.066	0.046
126.75	0.033	0.017	129.35	0.066	0.047
126.80	0.033	0.017	129.40	0.066	0.048
126.85	0.033	0.018	129.45	0.066	0.048
126.90	0.033	0.018	129.50	0.089	0.049
126.95	0.033	0.019	129.55	0.090	0.050
127.00	0.066	0.020	129.60	0.090	0.051
127.05	0.066	0.020	129.65	0.091	0.052
127.10	0.066	0.021	129.70	0.091	0.053
127.15	0.066	0.022	129.75	0.091	0.055
127.20	0.066	0.022	129.80	0.092	0.056
127.25	0.066	0.023	129.85	0.092	0.057
127.30	0.066	0.023	129.90	0.093	0.059
127.35	0.066	0.024	129.95	0.093	0.060
127.40	0.066	0.024	130.00	0.094	0.061
127.45	0.066	0.025	130.05	0.095	0.063
127.50	0.066	0.026	130.10	0.095	0.064
127.55	0.066	0.026	130.15	0.096	0.066
127.60	0.066	0.027	130.20	0.096	0.067
127.65	0.066	0.027	130.25	0.096	0.069
127.70	0.066	0.028	130.30	0.097	0.070
127.75	0.066	0.028	130.35	0.097	0.072
127.80	0.066	0.029	130.40	0.098	0.073
127.85	0.066	0.030	130.45	0.098	0.075
127.90	0.066	0.030	130.50	0.099	0.077
127.95	0.066	0.031			
128.00	0.066	0.031			
128.05	0.066	0.032			


Summary for Link 7L: Post (Composite)

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth = 2.50" for 25-yr event
 Inflow = 3.97 cfs @ 12.23 hrs, Volume= 0.247 af
 Primary = 3.97 cfs @ 12.23 hrs, Volume= 0.247 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: Post (Composite)

Hydrograph



Hydrograph for Link 7L: Post (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
0.00	0.00	0.00	0.00	13.00	0.57	0.00	0.57
0.25	0.00	0.00	0.00	13.25	0.44	0.00	0.44
0.50	0.00	0.00	0.00	13.50	0.38	0.00	0.38
0.75	0.00	0.00	0.00	13.75	0.34	0.00	0.34
1.00	0.00	0.00	0.00	14.00	0.30	0.00	0.30
1.25	0.00	0.00	0.00	14.25	0.27	0.00	0.27
1.50	0.00	0.00	0.00	14.50	0.25	0.00	0.25
1.75	0.00	0.00	0.00	14.75	0.23	0.00	0.23
2.00	0.00	0.00	0.00	15.00	0.21	0.00	0.21
2.25	0.00	0.00	0.00	15.25	0.19	0.00	0.19
2.50	0.00	0.00	0.00	15.50	0.17	0.00	0.17
2.75	0.00	0.00	0.00	15.75	0.14	0.00	0.14
3.00	0.00	0.00	0.00	16.00	0.12	0.00	0.12
3.25	0.00	0.00	0.00	16.25	0.09	0.00	0.09
3.50	0.00	0.00	0.00	16.50	0.08	0.00	0.08
3.75	0.00	0.00	0.00	16.75	0.07	0.00	0.07
4.00	0.00	0.00	0.00	17.00	0.06	0.00	0.06
4.25	0.00	0.00	0.00	17.25	0.05	0.00	0.05
4.50	0.00	0.00	0.00	17.50	0.04	0.00	0.04
4.75	0.00	0.00	0.00	17.75	0.03	0.00	0.03
5.00	0.00	0.00	0.00	18.00	0.02	0.00	0.02
5.25	0.00	0.00	0.00	18.25	0.01	0.00	0.01
5.50	0.00	0.00	0.00	18.50	0.01	0.00	0.01
5.75	0.00	0.00	0.00	18.75	0.01	0.00	0.01
6.00	0.00	0.00	0.00	19.00	0.00	0.00	0.00
6.25	0.00	0.00	0.00	19.25	0.00	0.00	0.00
6.50	0.00	0.00	0.00	19.50	0.00	0.00	0.00
6.75	0.00	0.00	0.00	19.75	0.00	0.00	0.00
7.00	0.00	0.00	0.00	20.00	0.00	0.00	0.00
7.25	0.00	0.00	0.00	20.25	0.00	0.00	0.00
7.50	0.00	0.00	0.00	20.50	0.00	0.00	0.00
7.75	0.00	0.00	0.00	20.75	0.00	0.00	0.00
8.00	0.00	0.00	0.00	21.00	0.00	0.00	0.00
8.25	0.00	0.00	0.00	21.25	0.00	0.00	0.00
8.50	0.00	0.00	0.00	21.50	0.00	0.00	0.00
8.75	0.00	0.00	0.00	21.75	0.00	0.00	0.00
9.00	0.00	0.00	0.00	22.00	0.00	0.00	0.00
9.25	0.00	0.00	0.00	22.25	0.00	0.00	0.00
9.50	0.00	0.00	0.00	22.50	0.00	0.00	0.00
9.75	0.00	0.00	0.00	22.75	0.00	0.00	0.00
10.00	0.00	0.00	0.00	23.00	0.00	0.00	0.00
10.25	0.00	0.00	0.00	23.25	0.00	0.00	0.00
10.50	0.00	0.00	0.00	23.50	0.00	0.00	0.00
10.75	0.00	0.00	0.00	23.75	0.00	0.00	0.00
11.00	0.00	0.00	0.00	24.00	0.00	0.00	0.00
11.25	0.00	0.00	0.00				
11.50	0.00	0.00	0.00				
11.75	0.00	0.00	0.00				
12.00	0.22	0.00	0.22				
12.25	3.96	0.00	3.96				
12.50	2.43	0.00	2.43				
12.75	0.88	0.00	0.88				

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment4S: PR-01 (Site)

Runoff Area=1.050 ac 19.05% Impervious Runoff Depth>6.09"
Flow Length=310' Tc=9.1 min CN=79 Runoff=6.52 cfs 0.533 af

Subcatchment5S: PR-02 (Roof)

Runoff Area=0.140 ac 100.00% Impervious Runoff Depth>8.38"
Tc=6.0 min CN=98 Runoff=1.16 cfs 0.098 af

Pond 7P: Chambers

Peak Elev=126.93' Storage=0.077 af Inflow=7.38 cfs 0.457 af
Discarded=0.03 cfs 0.038 af Primary=6.64 cfs 0.404 af Outflow=6.67 cfs 0.442 af

Pond 8P: Bioretention

Peak Elev=130.29' Storage=0.070 af Inflow=6.52 cfs 0.533 af
Discarded=0.10 cfs 0.114 af Primary=6.42 cfs 0.359 af Outflow=6.52 cfs 0.473 af

Link 7L: Post (Composite)

Inflow=6.64 cfs 0.404 af
Primary=6.64 cfs 0.404 af

Total Runoff Area = 1.190 ac Runoff Volume = 0.631 af Average Runoff Depth = 6.36"
71.43% Pervious = 0.850 ac 28.57% Impervious = 0.340 ac

Summary for Subcatchment 4S: PR-01 (Site)

Runoff = 6.52 cfs @ 12.13 hrs, Volume= 0.533 af, Depth> 6.09"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.63"

Area (ac)	CN	Description
0.200	98	Paved parking, HSG C
0.850	74	>75% Grass cover, Good, HSG C
1.050	79	Weighted Average
0.850		80.95% Pervious Area
0.200		19.05% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	35	0.0700	0.24		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.7	28	0.1070	0.27		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
3.4	37	0.0340	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.0	78	0.0350	1.31		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
0.1	30	0.0500	4.54		Shallow Concentrated Flow, Pathway Paved Kv= 20.3 fps
0.3	52	0.0290	2.55		Shallow Concentrated Flow, Shallow Concentrated Grassed Waterway Kv= 15.0 fps
0.2	50	0.2000	4.47		Shallow Concentrated Flow, Shallow Concentrated Nearly Bare & Untilled Kv= 10.0 fps
9.1	310	Total			

Subcatchment 4S: PR-01 (Site)

Hydrograph



Hydrograph for Subcatchment 4S: PR-01 (Site)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	6.47	4.10	0.71
0.25	0.02	0.00	0.00	13.25	6.62	4.24	0.58
0.50	0.04	0.00	0.00	13.50	6.76	4.37	0.53
0.75	0.06	0.00	0.00	13.75	6.89	4.48	0.49
1.00	0.09	0.00	0.00	14.00	7.00	4.58	0.44
1.25	0.11	0.00	0.00	14.25	7.10	4.68	0.40
1.50	0.13	0.00	0.00	14.50	7.20	4.77	0.38
1.75	0.15	0.00	0.00	14.75	7.29	4.85	0.35
2.00	0.17	0.00	0.00	15.00	7.37	4.93	0.33
2.25	0.19	0.00	0.00	15.25	7.45	5.00	0.31
2.50	0.22	0.00	0.00	15.50	7.52	5.06	0.28
2.75	0.24	0.00	0.00	15.75	7.59	5.12	0.26
3.00	0.27	0.00	0.00	16.00	7.65	5.18	0.23
3.25	0.29	0.00	0.00	16.25	7.70	5.23	0.22
3.50	0.32	0.00	0.00	16.50	7.75	5.28	0.21
3.75	0.34	0.00	0.00	16.75	7.80	5.32	0.19
4.00	0.37	0.00	0.00	17.00	7.85	5.37	0.18
4.25	0.40	0.00	0.00	17.25	7.89	5.41	0.17
4.50	0.43	0.00	0.00	17.50	7.93	5.45	0.16
4.75	0.46	0.00	0.00	17.75	7.97	5.48	0.15
5.00	0.49	0.00	0.00	18.00	8.01	5.52	0.14
5.25	0.52	0.00	0.00	18.25	8.04	5.55	0.13
5.50	0.55	0.00	0.00	18.50	8.08	5.58	0.13
5.75	0.59	0.00	0.00	18.75	8.11	5.61	0.13
6.00	0.62	0.00	0.01	19.00	8.14	5.64	0.13
6.25	0.66	0.01	0.01	19.25	8.17	5.67	0.12
6.50	0.70	0.01	0.02	19.50	8.20	5.70	0.12
6.75	0.74	0.01	0.02	19.75	8.23	5.72	0.12
7.00	0.78	0.02	0.03	20.00	8.26	5.75	0.11
7.25	0.83	0.03	0.03	20.25	8.29	5.78	0.11
7.50	0.88	0.04	0.04	20.50	8.31	5.80	0.11
7.75	0.93	0.05	0.05	20.75	8.34	5.83	0.11
8.00	0.98	0.07	0.06	21.00	8.37	5.85	0.10
8.25	1.04	0.08	0.07	21.25	8.39	5.87	0.10
8.50	1.11	0.10	0.09	21.50	8.42	5.90	0.10
8.75	1.18	0.13	0.10	21.75	8.44	5.92	0.10
9.00	1.26	0.16	0.12	22.00	8.46	5.94	0.09
9.25	1.34	0.19	0.14	22.25	8.49	5.96	0.09
9.50	1.43	0.23	0.16	22.50	8.51	5.98	0.09
9.75	1.53	0.27	0.18	22.75	8.53	6.00	0.09
10.00	1.63	0.32	0.21	23.00	8.55	6.02	0.08
10.25	1.74	0.38	0.24	23.25	8.57	6.04	0.08
10.50	1.87	0.45	0.28	23.50	8.59	6.06	0.08
10.75	2.01	0.53	0.33	23.75	8.61	6.08	0.08
11.00	2.16	0.62	0.38	24.00	8.63	6.10	0.07
11.25	2.34	0.73	0.48				
11.50	2.57	0.89	0.64				
11.75	3.07	1.24	1.41				
12.00	4.31	2.22	3.48				
12.25	5.56	3.29	4.30				
12.50	6.06	3.73	1.98				
12.75	6.29	3.94	0.92				

Summary for Subcatchment 5S: PR-02 (Roof)

Runoff = 1.16 cfs @ 12.09 hrs, Volume= 0.098 af, Depth> 8.38"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.63"

Area (ac)	CN	Description
0.140	98	Roofs, HSG C
0.140		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Roof

Subcatchment 5S: PR-02 (Roof)

Hydrograph



Hydrograph for Subcatchment 5S: PR-02 (Roof)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	6.47	6.23	0.10
0.25	0.02	0.00	0.00	13.25	6.62	6.38	0.08
0.50	0.04	0.00	0.00	13.50	6.76	6.52	0.08
0.75	0.06	0.00	0.00	13.75	6.89	6.65	0.07
1.00	0.09	0.01	0.00	14.00	7.00	6.76	0.06
1.25	0.11	0.02	0.00	14.25	7.10	6.86	0.06
1.50	0.13	0.03	0.01	14.50	7.20	6.96	0.05
1.75	0.15	0.04	0.01	14.75	7.29	7.05	0.05
2.00	0.17	0.05	0.01	15.00	7.37	7.13	0.05
2.25	0.19	0.07	0.01	15.25	7.45	7.21	0.04
2.50	0.22	0.08	0.01	15.50	7.52	7.28	0.04
2.75	0.24	0.10	0.01	15.75	7.59	7.35	0.04
3.00	0.27	0.12	0.01	16.00	7.65	7.41	0.03
3.25	0.29	0.14	0.01	16.25	7.70	7.46	0.03
3.50	0.32	0.16	0.01	16.50	7.75	7.51	0.03
3.75	0.34	0.18	0.01	16.75	7.80	7.56	0.03
4.00	0.37	0.20	0.01	17.00	7.85	7.61	0.03
4.25	0.40	0.23	0.01	17.25	7.89	7.65	0.02
4.50	0.43	0.25	0.01	17.50	7.93	7.69	0.02
4.75	0.46	0.28	0.02	17.75	7.97	7.73	0.02
5.00	0.49	0.31	0.02	18.00	8.01	7.77	0.02
5.25	0.52	0.34	0.02	18.25	8.04	7.80	0.02
5.50	0.55	0.37	0.02	18.50	8.08	7.84	0.02
5.75	0.59	0.40	0.02	18.75	8.11	7.87	0.02
6.00	0.62	0.43	0.02	19.00	8.14	7.90	0.02
6.25	0.66	0.46	0.02	19.25	8.17	7.93	0.02
6.50	0.70	0.50	0.02	19.50	8.20	7.96	0.02
6.75	0.74	0.54	0.02	19.75	8.23	7.99	0.02
7.00	0.78	0.58	0.02	20.00	8.26	8.02	0.02
7.25	0.83	0.62	0.03	20.25	8.29	8.05	0.02
7.50	0.88	0.67	0.03	20.50	8.31	8.07	0.02
7.75	0.93	0.72	0.03	20.75	8.34	8.10	0.01
8.00	0.98	0.78	0.03	21.00	8.37	8.13	0.01
8.25	1.04	0.83	0.03	21.25	8.39	8.15	0.01
8.50	1.11	0.90	0.04	21.50	8.42	8.18	0.01
8.75	1.18	0.97	0.04	21.75	8.44	8.20	0.01
9.00	1.26	1.04	0.04	22.00	8.46	8.22	0.01
9.25	1.34	1.12	0.05	22.25	8.49	8.25	0.01
9.50	1.43	1.21	0.05	22.50	8.51	8.27	0.01
9.75	1.53	1.31	0.05	22.75	8.53	8.29	0.01
10.00	1.63	1.41	0.06	23.00	8.55	8.31	0.01
10.25	1.74	1.52	0.06	23.25	8.57	8.33	0.01
10.50	1.87	1.64	0.07	23.50	8.59	8.35	0.01
10.75	2.01	1.78	0.08	23.75	8.61	8.37	0.01
11.00	2.16	1.93	0.09	24.00	8.63	8.39	0.01
11.25	2.34	2.11	0.11				
11.50	2.57	2.34	0.13				
11.75	3.07	2.83	0.31				
12.00	4.31	4.08	0.75				
12.25	5.56	5.33	0.54				
12.50	6.06	5.82	0.24				
12.75	6.29	6.05	0.13				

Summary for Pond 7P: Chambers

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth > 4.61" for 100-yr event
 Inflow = 7.38 cfs @ 12.13 hrs, Volume= 0.457 af
 Outflow = 6.67 cfs @ 12.20 hrs, Volume= 0.442 af, Atten= 10%, Lag= 4.3 min
 Discarded = 0.03 cfs @ 12.21 hrs, Volume= 0.038 af
 Primary = 6.64 cfs @ 12.20 hrs, Volume= 0.404 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 126.93' @ 12.21 hrs Surf.Area= 0.024 ac Storage= 0.077 af

Plug-Flow detention time= 34.3 min calculated for 0.441 af (96% of inflow)
 Center-of-Mass det. time= 20.6 min (790.8 - 770.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	121.33'	0.031 af	17.33'W x 41.55'L x 6.25'H Field A 0.103 af Overall - 0.027 af Embedded = 0.077 af x 40.0% Voids
#2A	122.83'	0.027 af	ADS_StormTech MC-3500 d +Capx 10 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 10 Chambers in 2 Rows Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf
#3B	121.33'	0.015 af	9.42'W x 35.38'L x 6.25'H Field B 0.048 af Overall - 0.011 af Embedded = 0.037 af x 40.0% Voids
#4B	122.83'	0.011 af	ADS_StormTech MC-3500 d +Capx 4 Inside #3 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf
		0.083 af	Total Available Storage

Storage Group A created with Chamber Wizard
 Storage Group B created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	121.33'	0.750 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 115.00'
#2	Primary	122.95'	4.0" Vert. Orifice/Grate C= 0.600
#3	Primary	123.50'	10.0" Vert. Orifice/Grate C= 0.600
#4	Primary	126.50'	1.5' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Discarded OutFlow Max=0.03 cfs @ 12.21 hrs HW=126.91' (Free Discharge)
 ↑1=Exfiltration (Controls 0.03 cfs)

Primary OutFlow Max=6.53 cfs @ 12.20 hrs HW=126.91' (Free Discharge)
 ↑2=Orifice/Grate (Orifice Controls 0.82 cfs @ 9.38 fps)
 ↑3=Orifice/Grate (Orifice Controls 4.55 cfs @ 8.33 fps)
 ↑4=Broad-Crested Rectangular Weir(Weir Controls 1.17 cfs @ 1.88 fps)

Pond 7P: Chambers - Chamber Wizard Field A

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech@MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf

77.0" Wide + 18.0" Spacing = 95.0" C-C Row Spacing

5 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 39.55' Row Length +12.0" End Stone x 2 = 41.55' Base Length

2 Rows x 77.0" Wide + 18.0" Spacing x 1 + 18.0" Side Stone x 2 = 17.33' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

10 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 2 Rows = 1,159.1 cf Chamber Storage

4,501.2 cf Field - 1,159.1 cf Chambers = 3,342.1 cf Stone x 40.0% Voids = 1,336.9 cf Stone Storage

Chamber Storage + Stone Storage = 2,496.0 cf = 0.057 af



Overall Storage Efficiency = 55.5%

Overall System Size = 41.55' x 17.33' x 6.25'

10 Chambers

166.7 cy Field

123.8 cy Stone



Pond 7P: Chambers - Chamber Wizard Field B

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf

4 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 32.38' Row Length +18.0" End Stone x 2 = 35.38'

Base Length

1 Rows x 77.0" Wide + 18.0" Side Stone x 2 = 9.42' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

4 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 1 Rows = 469.6 cf Chamber Storage

2,082.3 cf Field - 469.6 cf Chambers = 1,612.7 cf Stone x 40.0% Voids = 645.1 cf Stone Storage

Chamber Storage + Stone Storage = 1,114.7 cf = 0.026 af


Overall Storage Efficiency = 53.5%

Overall System Size = 35.38' x 9.42' x 6.25'

4 Chambers


77.1 cy Field

59.7 cy Stone




Pond 7P: Chambers

Hydrograph




Pond 7P: Chambers

Stage-Discharge



Pond 7P: Chambers

Stage-Area-Storage



Hydrograph for Pond 7P: Chambers

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	121.33	0.00	0.00	0.00
0.50	0.00	0.000	121.33	0.00	0.00	0.00
1.00	0.00	0.000	121.33	0.00	0.00	0.00
1.50	0.01	0.000	121.34	0.00	0.00	0.00
2.00	0.01	0.000	121.35	0.01	0.01	0.00
2.50	0.01	0.000	121.36	0.01	0.01	0.00
3.00	0.01	0.000	121.36	0.01	0.01	0.00
3.50	0.01	0.000	121.37	0.01	0.01	0.00
4.00	0.01	0.000	121.37	0.01	0.01	0.00
4.50	0.01	0.000	121.38	0.01	0.01	0.00
5.00	0.02	0.000	121.38	0.01	0.01	0.00
5.50	0.02	0.001	121.38	0.02	0.02	0.00
6.00	0.02	0.001	121.39	0.02	0.02	0.00
6.50	0.02	0.001	121.39	0.02	0.02	0.00
7.00	0.02	0.001	121.41	0.02	0.02	0.00
7.50	0.03	0.001	121.44	0.02	0.02	0.00
8.00	0.03	0.001	121.48	0.02	0.02	0.00
8.50	0.04	0.002	121.54	0.02	0.02	0.00
9.00	0.04	0.003	121.63	0.02	0.02	0.00
9.50	0.05	0.004	121.75	0.02	0.02	0.00
10.00	0.06	0.005	121.90	0.02	0.02	0.00
10.50	0.07	0.007	122.08	0.02	0.02	0.00
11.00	0.09	0.010	122.33	0.02	0.02	0.00
11.50	0.13	0.013	122.69	0.02	0.02	0.00
12.00	3.91	0.046	124.62	2.74	0.03	2.71
12.50	2.25	0.053	125.07	3.44	0.03	3.41
13.00	0.73	0.033	123.84	0.81	0.03	0.78
13.50	0.52	0.031	123.73	0.55	0.03	0.52
14.00	0.41	0.030	123.66	0.44	0.03	0.42
14.50	0.34	0.028	123.60	0.36	0.02	0.34
15.00	0.29	0.027	123.55	0.31	0.02	0.29
15.50	0.23	0.026	123.47	0.27	0.02	0.25
16.00	0.18	0.024	123.35	0.23	0.02	0.20
16.50	0.14	0.022	123.25	0.18	0.02	0.15
17.00	0.12	0.021	123.19	0.14	0.02	0.11
17.50	0.09	0.020	123.15	0.11	0.02	0.09
18.00	0.07	0.020	123.12	0.09	0.02	0.06
18.50	0.06	0.019	123.09	0.07	0.02	0.04
19.00	0.05	0.019	123.07	0.06	0.02	0.03
19.50	0.04	0.019	123.05	0.05	0.02	0.03
20.00	0.03	0.018	123.04	0.04	0.02	0.02
20.50	0.03	0.018	123.02	0.04	0.02	0.01
21.00	0.02	0.018	123.00	0.03	0.02	0.01
21.50	0.02	0.017	122.99	0.03	0.02	0.00
22.00	0.01	0.017	122.96	0.02	0.02	0.00
22.50	0.01	0.017	122.94	0.02	0.02	0.00
23.00	0.01	0.016	122.92	0.02	0.02	0.00
23.50	0.01	0.016	122.89	0.02	0.02	0.00
24.00	0.01	0.015	122.86	0.02	0.02	0.00

Stage-Discharge for Pond 7P: Chambers

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
121.33	0.00	0.00	0.00	126.53	5.08	0.03	5.04
121.43	0.02	0.02	0.00	126.63	5.34	0.03	5.31
121.53	0.02	0.02	0.00	126.73	5.70	0.03	5.67
121.63	0.02	0.02	0.00	126.83	6.14	0.03	6.11
121.73	0.02	0.02	0.00	126.93	6.66	0.03	6.62
121.83	0.02	0.02	0.00	127.03	7.25	0.03	7.22
121.93	0.02	0.02	0.00	127.13	7.92	0.04	7.88
122.03	0.02	0.02	0.00	127.23	8.68	0.04	8.65
122.13	0.02	0.02	0.00	127.33	9.50	0.04	9.46
122.23	0.02	0.02	0.00	127.43	10.29	0.04	10.25
122.33	0.02	0.02	0.00	127.53	11.12	0.04	11.08
122.43	0.02	0.02	0.00				
122.53	0.02	0.02	0.00				
122.63	0.02	0.02	0.00				
122.73	0.02	0.02	0.00				
122.83	0.02	0.02	0.00				
122.93	0.02	0.02	0.00				
123.03	0.04	0.02	0.02				
123.13	0.09	0.02	0.07				
123.23	0.16	0.02	0.14				
123.33	0.22	0.02	0.19				
123.43	0.26	0.02	0.24				
123.53	0.30	0.02	0.27				
123.63	0.39	0.02	0.37				
123.73	0.55	0.03	0.53				
123.83	0.77	0.03	0.75				
123.93	1.04	0.03	1.01				
124.03	1.33	0.03	1.31				
124.13	1.64	0.03	1.62				
124.23	1.94	0.03	1.92				
124.33	2.18	0.03	2.15				
124.43	2.39	0.03	2.36				
124.53	2.58	0.03	2.56				
124.63	2.76	0.03	2.73				
124.73	2.93	0.03	2.90				
124.83	3.09	0.03	3.06				
124.93	3.24	0.03	3.21				
125.03	3.38	0.03	3.35				
125.13	3.52	0.03	3.49				
125.23	3.65	0.03	3.62				
125.33	3.78	0.03	3.75				
125.43	3.90	0.03	3.87				
125.53	4.02	0.03	3.99				
125.63	4.13	0.03	4.10				
125.73	4.25	0.03	4.22				
125.83	4.36	0.03	4.32				
125.93	4.46	0.03	4.43				
126.03	4.57	0.03	4.53				
126.13	4.67	0.03	4.64				
126.23	4.77	0.03	4.74				
126.33	4.87	0.03	4.83				
126.43	4.96	0.03	4.93				

Stage-Area-Storage for Pond 7P: Chambers

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
121.33	0.024	0.000	126.53	0.024	0.073
121.43	0.024	0.001	126.63	0.024	0.074
121.53	0.024	0.002	126.73	0.024	0.075
121.63	0.024	0.003	126.83	0.024	0.076
121.73	0.024	0.004	126.93	0.024	0.077
121.83	0.024	0.005	127.03	0.024	0.078
121.93	0.024	0.006	127.13	0.024	0.079
122.03	0.024	0.007	127.23	0.024	0.080
122.13	0.024	0.008	127.33	0.024	0.080
122.23	0.024	0.009	127.43	0.024	0.081
122.33	0.024	0.010	127.53	0.024	0.082
122.43	0.024	0.011			
122.53	0.024	0.012			
122.63	0.024	0.013			
122.73	0.024	0.014			
122.83	0.024	0.015			
122.93	0.024	0.016			
123.03	0.024	0.018			
123.13	0.024	0.020			
123.23	0.024	0.022			
123.33	0.024	0.024			
123.43	0.024	0.025			
123.53	0.024	0.027			
123.63	0.024	0.029			
123.73	0.024	0.031			
123.83	0.024	0.032			
123.93	0.024	0.034			
124.03	0.024	0.036			
124.13	0.024	0.038			
124.23	0.024	0.039			
124.33	0.024	0.041			
124.43	0.024	0.043			
124.53	0.024	0.044			
124.63	0.024	0.046			
124.73	0.024	0.048			
124.83	0.024	0.049			
124.93	0.024	0.051			
125.03	0.024	0.053			
125.13	0.024	0.054			
125.23	0.024	0.056			
125.33	0.024	0.057			
125.43	0.024	0.059			
125.53	0.024	0.060			
125.63	0.024	0.062			
125.73	0.024	0.063			
125.83	0.024	0.065			
125.93	0.024	0.066			
126.03	0.024	0.067			
126.13	0.024	0.068			
126.23	0.024	0.070			
126.33	0.024	0.071			
126.43	0.024	0.072			

Summary for Pond 8P: Bioretention

Inflow Area = 1.050 ac, 19.05% Impervious, Inflow Depth > 6.09" for 100-yr event
 Inflow = 6.52 cfs @ 12.13 hrs, Volume= 0.533 af
 Outflow = 6.52 cfs @ 12.14 hrs, Volume= 0.473 af, Atten= 0%, Lag= 0.9 min
 Discarded = 0.10 cfs @ 12.14 hrs, Volume= 0.114 af
 Primary = 6.42 cfs @ 12.14 hrs, Volume= 0.359 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 130.29' @ 12.14 hrs Surf.Area= 0.097 ac Storage= 0.070 af

Plug-Flow detention time= 78.4 min calculated for 0.473 af (89% of inflow)
 Center-of-Mass det. time= 26.1 min (830.5 - 804.4)

Volume	Invert	Avail.Storage	Storage Description
#1	125.50'	0.020 af	Gravel (Prismatic) Listed below 0.050 af Overall x 40.0% Voids
#2	127.00'	0.029 af	Soil (Prismatic) Listed below (Recalc) 0.082 af Overall x 35.0% Voids
#3	129.50'	0.028 af	Custom Stage Data (Prismatic) Listed below (Recalc)
		0.077 af	Total Available Storage

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
125.50	0.033	0.000	0.000
127.00	0.033	0.050	0.050

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
127.00	0.033	0.000	0.000
129.50	0.033	0.082	0.082

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
129.50	0.023	0.000	0.000
130.00	0.028	0.013	0.013
130.50	0.033	0.015	0.028


Device	Routing	Invert	Outlet Devices
#1	Primary	130.00'	12.0" Horiz. Orifice/Grate X 4 rows C= 0.600 Limited to weir flow at low heads
#2	Discarded	125.50'	0.900 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 100.00'

Discarded OutFlow Max=0.10 cfs @ 12.14 hrs HW=130.29' (Free Discharge)
 ↑2=Exfiltration (Controls 0.10 cfs)

Primary OutFlow Max=6.32 cfs @ 12.14 hrs HW=130.29' (Free Discharge)
 ↑1=Orifice/Grate (Weir Controls 6.32 cfs @ 1.75 fps)


Pond 8P: Bioretention

Hydrograph




Pond 8P: Bioretention

Stage-Discharge



Pond 8P: Bioretention

Stage-Area-Storage



Hydrograph for Pond 8P: Bioretention

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	125.50	0.00	0.00	0.00
0.50	0.00	0.000	125.50	0.00	0.00	0.00
1.00	0.00	0.000	125.50	0.00	0.00	0.00
1.50	0.00	0.000	125.50	0.00	0.00	0.00
2.00	0.00	0.000	125.50	0.00	0.00	0.00
2.50	0.00	0.000	125.50	0.00	0.00	0.00
3.00	0.00	0.000	125.50	0.00	0.00	0.00
3.50	0.00	0.000	125.50	0.00	0.00	0.00
4.00	0.00	0.000	125.50	0.00	0.00	0.00
4.50	0.00	0.000	125.50	0.00	0.00	0.00
5.00	0.00	0.000	125.50	0.00	0.00	0.00
5.50	0.00	0.000	125.50	0.00	0.00	0.00
6.00	0.01	0.000	125.51	0.00	0.00	0.00
6.50	0.02	0.000	125.52	0.01	0.01	0.00
7.00	0.03	0.000	125.54	0.02	0.02	0.00
7.50	0.04	0.001	125.56	0.03	0.03	0.00
8.00	0.06	0.002	125.62	0.03	0.03	0.00
8.50	0.09	0.003	125.75	0.03	0.03	0.00
9.00	0.12	0.006	125.97	0.03	0.03	0.00
9.50	0.16	0.011	126.32	0.03	0.03	0.00
10.00	0.21	0.017	126.80	0.03	0.03	0.00
10.50	0.28	0.025	127.46	0.06	0.06	0.00
11.00	0.38	0.036	128.42	0.06	0.06	0.00
11.50	0.64	0.053	129.70	0.09	0.09	0.00
12.00	3.48	0.067	130.18	3.25	0.10	3.15
12.50	1.98	0.065	130.13	2.10	0.10	2.00
13.00	0.71	0.063	130.06	0.72	0.09	0.63
13.50	0.53	0.063	130.05	0.54	0.09	0.45
14.00	0.44	0.063	130.04	0.44	0.09	0.35
14.50	0.38	0.062	130.03	0.38	0.09	0.29
15.00	0.33	0.062	130.03	0.33	0.09	0.24
15.50	0.28	0.062	130.02	0.29	0.09	0.19
16.00	0.23	0.062	130.02	0.24	0.09	0.14
16.50	0.21	0.062	130.01	0.21	0.09	0.11
17.00	0.18	0.062	130.01	0.19	0.09	0.09
17.50	0.16	0.062	130.01	0.16	0.09	0.07
18.00	0.14	0.062	130.01	0.14	0.09	0.05
18.50	0.13	0.062	130.00	0.13	0.09	0.04
19.00	0.13	0.062	130.00	0.13	0.09	0.03
19.50	0.12	0.062	130.00	0.12	0.09	0.03
20.00	0.11	0.061	130.00	0.11	0.09	0.02
20.50	0.11	0.061	130.00	0.11	0.09	0.01
21.00	0.10	0.061	130.00	0.10	0.09	0.01
21.50	0.10	0.061	130.00	0.10	0.09	0.00
22.00	0.09	0.061	130.00	0.09	0.09	0.00
22.50	0.09	0.061	130.00	0.09	0.09	0.00
23.00	0.08	0.061	129.98	0.09	0.09	0.00
23.50	0.08	0.060	129.96	0.09	0.09	0.00
24.00	0.07	0.060	129.94	0.09	0.09	0.00

Stage-Discharge for Pond 8P: Bioretention

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
125.50	0.00	0.00	0.00	128.10	0.06	0.06	0.00
125.55	0.03	0.03	0.00	128.15	0.06	0.06	0.00
125.60	0.03	0.03	0.00	128.20	0.06	0.06	0.00
125.65	0.03	0.03	0.00	128.25	0.06	0.06	0.00
125.70	0.03	0.03	0.00	128.30	0.06	0.06	0.00
125.75	0.03	0.03	0.00	128.35	0.06	0.06	0.00
125.80	0.03	0.03	0.00	128.40	0.06	0.06	0.00
125.85	0.03	0.03	0.00	128.45	0.06	0.06	0.00
125.90	0.03	0.03	0.00	128.50	0.07	0.07	0.00
125.95	0.03	0.03	0.00	128.55	0.07	0.07	0.00
126.00	0.03	0.03	0.00	128.60	0.07	0.07	0.00
126.05	0.03	0.03	0.00	128.65	0.07	0.07	0.00
126.10	0.03	0.03	0.00	128.70	0.07	0.07	0.00
126.15	0.03	0.03	0.00	128.75	0.07	0.07	0.00
126.20	0.03	0.03	0.00	128.80	0.07	0.07	0.00
126.25	0.03	0.03	0.00	128.85	0.07	0.07	0.00
126.30	0.03	0.03	0.00	128.90	0.07	0.07	0.00
126.35	0.03	0.03	0.00	128.95	0.07	0.07	0.00
126.40	0.03	0.03	0.00	129.00	0.07	0.07	0.00
126.45	0.03	0.03	0.00	129.05	0.07	0.07	0.00
126.50	0.03	0.03	0.00	129.10	0.07	0.07	0.00
126.55	0.03	0.03	0.00	129.15	0.07	0.07	0.00
126.60	0.03	0.03	0.00	129.20	0.07	0.07	0.00
126.65	0.03	0.03	0.00	129.25	0.07	0.07	0.00
126.70	0.03	0.03	0.00	129.30	0.07	0.07	0.00
126.75	0.03	0.03	0.00	129.35	0.07	0.07	0.00
126.80	0.03	0.03	0.00	129.40	0.07	0.07	0.00
126.85	0.03	0.03	0.00	129.45	0.07	0.07	0.00
126.90	0.03	0.03	0.00	129.50	0.09	0.09	0.00
126.95	0.03	0.03	0.00	129.55	0.09	0.09	0.00
127.00	0.06	0.06	0.00	129.60	0.09	0.09	0.00
127.05	0.06	0.06	0.00	129.65	0.09	0.09	0.00
127.10	0.06	0.06	0.00	129.70	0.09	0.09	0.00
127.15	0.06	0.06	0.00	129.75	0.09	0.09	0.00
127.20	0.06	0.06	0.00	129.80	0.09	0.09	0.00
127.25	0.06	0.06	0.00	129.85	0.09	0.09	0.00
127.30	0.06	0.06	0.00	129.90	0.09	0.09	0.00
127.35	0.06	0.06	0.00	129.95	0.09	0.09	0.00
127.40	0.06	0.06	0.00	130.00	0.09	0.09	0.00
127.45	0.06	0.06	0.00	130.05	0.55	0.09	0.46
127.50	0.06	0.06	0.00	130.10	1.39	0.10	1.30
127.55	0.06	0.06	0.00	130.15	2.48	0.10	2.39
127.60	0.06	0.06	0.00	130.20	3.77	0.10	3.68
127.65	0.06	0.06	0.00	130.25	5.23	0.10	5.14
127.70	0.06	0.06	0.00	130.30	6.85	0.10	6.75
127.75	0.06	0.06	0.00	130.35	8.61	0.10	8.51
127.80	0.06	0.06	0.00	130.40	9.67	0.10	9.57
127.85	0.06	0.06	0.00	130.45	10.25	0.10	10.15
127.90	0.06	0.06	0.00	130.50	10.80	0.10	10.70
127.95	0.06	0.06	0.00				
128.00	0.06	0.06	0.00				
128.05	0.06	0.06	0.00				

Stage-Area-Storage for Pond 8P: Bioretention

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
125.50	0.033	0.000	128.10	0.066	0.033
125.55	0.033	0.001	128.15	0.066	0.033
125.60	0.033	0.001	128.20	0.066	0.034
125.65	0.033	0.002	128.25	0.066	0.034
125.70	0.033	0.003	128.30	0.066	0.035
125.75	0.033	0.003	128.35	0.066	0.035
125.80	0.033	0.004	128.40	0.066	0.036
125.85	0.033	0.005	128.45	0.066	0.037
125.90	0.033	0.005	128.50	0.066	0.037
125.95	0.033	0.006	128.55	0.066	0.038
126.00	0.033	0.007	128.60	0.066	0.038
126.05	0.033	0.007	128.65	0.066	0.039
126.10	0.033	0.008	128.70	0.066	0.039
126.15	0.033	0.009	128.75	0.066	0.040
126.20	0.033	0.009	128.80	0.066	0.041
126.25	0.033	0.010	128.85	0.066	0.041
126.30	0.033	0.011	128.90	0.066	0.042
126.35	0.033	0.011	128.95	0.066	0.042
126.40	0.033	0.012	129.00	0.066	0.043
126.45	0.033	0.013	129.05	0.066	0.043
126.50	0.033	0.013	129.10	0.066	0.044
126.55	0.033	0.014	129.15	0.066	0.045
126.60	0.033	0.015	129.20	0.066	0.045
126.65	0.033	0.015	129.25	0.066	0.046
126.70	0.033	0.016	129.30	0.066	0.046
126.75	0.033	0.017	129.35	0.066	0.047
126.80	0.033	0.017	129.40	0.066	0.048
126.85	0.033	0.018	129.45	0.066	0.048
126.90	0.033	0.018	129.50	0.089	0.049
126.95	0.033	0.019	129.55	0.090	0.050
127.00	0.066	0.020	129.60	0.090	0.051
127.05	0.066	0.020	129.65	0.091	0.052
127.10	0.066	0.021	129.70	0.091	0.053
127.15	0.066	0.022	129.75	0.091	0.055
127.20	0.066	0.022	129.80	0.092	0.056
127.25	0.066	0.023	129.85	0.092	0.057
127.30	0.066	0.023	129.90	0.093	0.059
127.35	0.066	0.024	129.95	0.093	0.060
127.40	0.066	0.024	130.00	0.094	0.061
127.45	0.066	0.025	130.05	0.095	0.063
127.50	0.066	0.026	130.10	0.095	0.064
127.55	0.066	0.026	130.15	0.096	0.066
127.60	0.066	0.027	130.20	0.096	0.067
127.65	0.066	0.027	130.25	0.096	0.069
127.70	0.066	0.028	130.30	0.097	0.070
127.75	0.066	0.028	130.35	0.097	0.072
127.80	0.066	0.029	130.40	0.098	0.073
127.85	0.066	0.030	130.45	0.098	0.075
127.90	0.066	0.030	130.50	0.099	0.077
127.95	0.066	0.031			
128.00	0.066	0.031			
128.05	0.066	0.032			


Summary for Link 7L: Post (Composite)

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth = 4.07" for 100-yr event
 Inflow = 6.64 cfs @ 12.20 hrs, Volume= 0.404 af
 Primary = 6.64 cfs @ 12.20 hrs, Volume= 0.404 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: Post (Composite)

Hydrograph



Hydrograph for Link 7L: Post (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
0.00	0.00	0.00	0.00	13.00	0.78	0.00	0.78
0.25	0.00	0.00	0.00	13.25	0.60	0.00	0.60
0.50	0.00	0.00	0.00	13.50	0.52	0.00	0.52
0.75	0.00	0.00	0.00	13.75	0.47	0.00	0.47
1.00	0.00	0.00	0.00	14.00	0.42	0.00	0.42
1.25	0.00	0.00	0.00	14.25	0.37	0.00	0.37
1.50	0.00	0.00	0.00	14.50	0.34	0.00	0.34
1.75	0.00	0.00	0.00	14.75	0.31	0.00	0.31
2.00	0.00	0.00	0.00	15.00	0.29	0.00	0.29
2.25	0.00	0.00	0.00	15.25	0.27	0.00	0.27
2.50	0.00	0.00	0.00	15.50	0.25	0.00	0.25
2.75	0.00	0.00	0.00	15.75	0.23	0.00	0.23
3.00	0.00	0.00	0.00	16.00	0.20	0.00	0.20
3.25	0.00	0.00	0.00	16.25	0.18	0.00	0.18
3.50	0.00	0.00	0.00	16.50	0.15	0.00	0.15
3.75	0.00	0.00	0.00	16.75	0.13	0.00	0.13
4.00	0.00	0.00	0.00	17.00	0.11	0.00	0.11
4.25	0.00	0.00	0.00	17.25	0.10	0.00	0.10
4.50	0.00	0.00	0.00	17.50	0.09	0.00	0.09
4.75	0.00	0.00	0.00	17.75	0.07	0.00	0.07
5.00	0.00	0.00	0.00	18.00	0.06	0.00	0.06
5.25	0.00	0.00	0.00	18.25	0.05	0.00	0.05
5.50	0.00	0.00	0.00	18.50	0.04	0.00	0.04
5.75	0.00	0.00	0.00	18.75	0.04	0.00	0.04
6.00	0.00	0.00	0.00	19.00	0.03	0.00	0.03
6.25	0.00	0.00	0.00	19.25	0.03	0.00	0.03
6.50	0.00	0.00	0.00	19.50	0.03	0.00	0.03
6.75	0.00	0.00	0.00	19.75	0.02	0.00	0.02
7.00	0.00	0.00	0.00	20.00	0.02	0.00	0.02
7.25	0.00	0.00	0.00	20.25	0.02	0.00	0.02
7.50	0.00	0.00	0.00	20.50	0.01	0.00	0.01
7.75	0.00	0.00	0.00	20.75	0.01	0.00	0.01
8.00	0.00	0.00	0.00	21.00	0.01	0.00	0.01
8.25	0.00	0.00	0.00	21.25	0.01	0.00	0.01
8.50	0.00	0.00	0.00	21.50	0.00	0.00	0.00
8.75	0.00	0.00	0.00	21.75	0.00	0.00	0.00
9.00	0.00	0.00	0.00	22.00	0.00	0.00	0.00
9.25	0.00	0.00	0.00	22.25	0.00	0.00	0.00
9.50	0.00	0.00	0.00	22.50	0.00	0.00	0.00
9.75	0.00	0.00	0.00	22.75	0.00	0.00	0.00
10.00	0.00	0.00	0.00	23.00	0.00	0.00	0.00
10.25	0.00	0.00	0.00	23.25	0.00	0.00	0.00
10.50	0.00	0.00	0.00	23.50	0.00	0.00	0.00
10.75	0.00	0.00	0.00	23.75	0.00	0.00	0.00
11.00	0.00	0.00	0.00	24.00	0.00	0.00	0.00
11.25	0.00	0.00	0.00				
11.50	0.00	0.00	0.00				
11.75	0.16	0.00	0.16				
12.00	2.71	0.00	2.71				
12.25	5.56	0.00	5.56				
12.50	3.41	0.00	3.41				
12.75	1.26	0.00	1.26				

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment4S: PR-01 (Site)

Runoff Area=1.050 ac 19.05% Impervious Runoff Depth>0.26"
Flow Length=310' Tc=9.1 min CN=79 Runoff=0.21 cfs 0.023 af

Subcatchment5S: PR-02 (Roof)

Runoff Area=0.140 ac 100.00% Impervious Runoff Depth>1.28"
Tc=6.0 min CN=98 Runoff=0.19 cfs 0.015 af

Pond 7P: Chambers

Peak Elev=121.92' Storage=0.006 af Inflow=0.19 cfs 0.015 af
Discarded=0.02 cfs 0.015 af Primary=0.00 cfs 0.000 af Outflow=0.02 cfs 0.015 af

Pond 8P: Bioretention

Peak Elev=126.03' Storage=0.007 af Inflow=0.21 cfs 0.023 af
Discarded=0.03 cfs 0.022 af Primary=0.00 cfs 0.000 af Outflow=0.03 cfs 0.022 af

Link 7L: Post (Composite)

Inflow=0.00 cfs 0.000 af
Primary=0.00 cfs 0.000 af

Total Runoff Area = 1.190 ac Runoff Volume = 0.037 af Average Runoff Depth = 0.38"
71.43% Pervious = 0.850 ac 28.57% Impervious = 0.340 ac

Summary for Subcatchment 4S: PR-01 (Site)

Runoff = 0.21 cfs @ 12.16 hrs, Volume= 0.023 af, Depth> 0.26"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr Custom Rainfall=1.50"

Area (ac)	CN	Description
0.200	98	Paved parking, HSG C
0.850	74	>75% Grass cover, Good, HSG C
1.050	79	Weighted Average
0.850		80.95% Pervious Area
0.200		19.05% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	35	0.0700	0.24		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.7	28	0.1070	0.27		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
3.4	37	0.0340	0.18		Sheet Flow, Sheet Flow Grass: Short n= 0.150 P2= 3.58"
1.0	78	0.0350	1.31		Shallow Concentrated Flow, Shallow Concentrated Short Grass Pasture Kv= 7.0 fps
0.1	30	0.0500	4.54		Shallow Concentrated Flow, Pathway Paved Kv= 20.3 fps
0.3	52	0.0290	2.55		Shallow Concentrated Flow, Shallow Concentrated Grassed Waterway Kv= 15.0 fps
0.2	50	0.2000	4.47		Shallow Concentrated Flow, Shallow Concentrated Nearly Bare & Untilled Kv= 10.0 fps
9.1	310	Total			

Subcatchment 4S: PR-01 (Site)

Hydrograph



Hydrograph for Subcatchment 4S: PR-01 (Site)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	1.12	0.11	0.04
0.25	0.00	0.00	0.00	13.25	1.15	0.12	0.04
0.50	0.01	0.00	0.00	13.50	1.18	0.13	0.04
0.75	0.01	0.00	0.00	13.75	1.20	0.13	0.03
1.00	0.02	0.00	0.00	14.00	1.22	0.14	0.03
1.25	0.02	0.00	0.00	14.25	1.23	0.15	0.03
1.50	0.02	0.00	0.00	14.50	1.25	0.15	0.03
1.75	0.03	0.00	0.00	14.75	1.27	0.16	0.03
2.00	0.03	0.00	0.00	15.00	1.28	0.16	0.02
2.25	0.03	0.00	0.00	15.25	1.29	0.17	0.02
2.50	0.04	0.00	0.00	15.50	1.31	0.18	0.02
2.75	0.04	0.00	0.00	15.75	1.32	0.18	0.02
3.00	0.05	0.00	0.00	16.00	1.33	0.18	0.02
3.25	0.05	0.00	0.00	16.25	1.34	0.19	0.02
3.50	0.06	0.00	0.00	16.50	1.35	0.19	0.02
3.75	0.06	0.00	0.00	16.75	1.36	0.20	0.02
4.00	0.06	0.00	0.00	17.00	1.36	0.20	0.01
4.25	0.07	0.00	0.00	17.25	1.37	0.20	0.01
4.50	0.07	0.00	0.00	17.50	1.38	0.20	0.01
4.75	0.08	0.00	0.00	17.75	1.39	0.21	0.01
5.00	0.09	0.00	0.00	18.00	1.39	0.21	0.01
5.25	0.09	0.00	0.00	18.25	1.40	0.21	0.01
5.50	0.10	0.00	0.00	18.50	1.40	0.22	0.01
5.75	0.10	0.00	0.00	18.75	1.41	0.22	0.01
6.00	0.11	0.00	0.00	19.00	1.41	0.22	0.01
6.25	0.11	0.00	0.00	19.25	1.42	0.22	0.01
6.50	0.12	0.00	0.00	19.50	1.43	0.22	0.01
6.75	0.13	0.00	0.00	19.75	1.43	0.23	0.01
7.00	0.14	0.00	0.00	20.00	1.44	0.23	0.01
7.25	0.14	0.00	0.00	20.25	1.44	0.23	0.01
7.50	0.15	0.00	0.00	20.50	1.45	0.23	0.01
7.75	0.16	0.00	0.00	20.75	1.45	0.24	0.01
8.00	0.17	0.00	0.00	21.00	1.45	0.24	0.01
8.25	0.18	0.00	0.00	21.25	1.46	0.24	0.01
8.50	0.19	0.00	0.00	21.50	1.46	0.24	0.01
8.75	0.21	0.00	0.00	21.75	1.47	0.24	0.01
9.00	0.22	0.00	0.00	22.00	1.47	0.25	0.01
9.25	0.23	0.00	0.00	22.25	1.48	0.25	0.01
9.50	0.25	0.00	0.00	22.50	1.48	0.25	0.01
9.75	0.27	0.00	0.00	22.75	1.48	0.25	0.01
10.00	0.28	0.00	0.00	23.00	1.49	0.25	0.01
10.25	0.30	0.00	0.00	23.25	1.49	0.25	0.01
10.50	0.32	0.00	0.00	23.50	1.49	0.26	0.01
10.75	0.35	0.00	0.00	23.75	1.50	0.26	0.01
11.00	0.38	0.00	0.00	24.00	1.50	0.26	0.01
11.25	0.41	0.00	0.00				
11.50	0.45	0.00	0.00				
11.75	0.53	0.00	0.00				
12.00	0.75	0.02	0.05				
12.25	0.97	0.06	0.18				
12.50	1.05	0.09	0.11				
12.75	1.09	0.10	0.05				

Summary for Subcatchment 5S: PR-02 (Roof)

Runoff = 0.19 cfs @ 12.09 hrs, Volume= 0.015 af, Depth> 1.28"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr Custom Rainfall=1.50"

Area (ac)	CN	Description
0.140	98	Roofs, HSG C
0.140		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Roof

Subcatchment 5S: PR-02 (Roof)

Hydrograph



Hydrograph for Subcatchment 5S: PR-02 (Roof)

Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)	Time (hours)	Precip. (inches)	Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	13.00	1.12	0.91	0.02
0.25	0.00	0.00	0.00	13.25	1.15	0.94	0.01
0.50	0.01	0.00	0.00	13.50	1.18	0.96	0.01
0.75	0.01	0.00	0.00	13.75	1.20	0.98	0.01
1.00	0.02	0.00	0.00	14.00	1.22	1.00	0.01
1.25	0.02	0.00	0.00	14.25	1.23	1.02	0.01
1.50	0.02	0.00	0.00	14.50	1.25	1.04	0.01
1.75	0.03	0.00	0.00	14.75	1.27	1.05	0.01
2.00	0.03	0.00	0.00	15.00	1.28	1.07	0.01
2.25	0.03	0.00	0.00	15.25	1.29	1.08	0.01
2.50	0.04	0.00	0.00	15.50	1.31	1.09	0.01
2.75	0.04	0.00	0.00	15.75	1.32	1.10	0.01
3.00	0.05	0.00	0.00	16.00	1.33	1.11	0.01
3.25	0.05	0.00	0.00	16.25	1.34	1.12	0.01
3.50	0.06	0.00	0.00	16.50	1.35	1.13	0.00
3.75	0.06	0.00	0.00	16.75	1.36	1.14	0.00
4.00	0.06	0.00	0.00	17.00	1.36	1.15	0.00
4.25	0.07	0.00	0.00	17.25	1.37	1.15	0.00
4.50	0.07	0.00	0.00	17.50	1.38	1.16	0.00
4.75	0.08	0.01	0.00	17.75	1.39	1.17	0.00
5.00	0.09	0.01	0.00	18.00	1.39	1.17	0.00
5.25	0.09	0.01	0.00	18.25	1.40	1.18	0.00
5.50	0.10	0.01	0.00	18.50	1.40	1.19	0.00
5.75	0.10	0.01	0.00	18.75	1.41	1.19	0.00
6.00	0.11	0.02	0.00	19.00	1.41	1.20	0.00
6.25	0.11	0.02	0.00	19.25	1.42	1.20	0.00
6.50	0.12	0.02	0.00	19.50	1.43	1.21	0.00
6.75	0.13	0.03	0.00	19.75	1.43	1.21	0.00
7.00	0.14	0.03	0.00	20.00	1.44	1.22	0.00
7.25	0.14	0.03	0.00	20.25	1.44	1.22	0.00
7.50	0.15	0.04	0.00	20.50	1.45	1.23	0.00
7.75	0.16	0.04	0.00	20.75	1.45	1.23	0.00
8.00	0.17	0.05	0.00	21.00	1.45	1.24	0.00
8.25	0.18	0.06	0.00	21.25	1.46	1.24	0.00
8.50	0.19	0.06	0.00	21.50	1.46	1.24	0.00
8.75	0.21	0.07	0.00	21.75	1.47	1.25	0.00
9.00	0.22	0.08	0.01	22.00	1.47	1.25	0.00
9.25	0.23	0.09	0.01	22.25	1.48	1.26	0.00
9.50	0.25	0.11	0.01	22.50	1.48	1.26	0.00
9.75	0.27	0.12	0.01	22.75	1.48	1.26	0.00
10.00	0.28	0.13	0.01	23.00	1.49	1.27	0.00
10.25	0.30	0.15	0.01	23.25	1.49	1.27	0.00
10.50	0.32	0.17	0.01	23.50	1.49	1.27	0.00
10.75	0.35	0.19	0.01	23.75	1.50	1.28	0.00
11.00	0.38	0.21	0.01	24.00	1.50	1.28	0.00
11.25	0.41	0.23	0.02				
11.50	0.45	0.27	0.02				
11.75	0.53	0.35	0.05				
12.00	0.75	0.55	0.12				
12.25	0.97	0.76	0.09				
12.50	1.05	0.84	0.04				
12.75	1.09	0.88	0.02				

Summary for Pond 7P: Chambers

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth > 0.15" for Custom event
 Inflow = 0.19 cfs @ 12.09 hrs, Volume= 0.015 af
 Outflow = 0.02 cfs @ 12.83 hrs, Volume= 0.015 af, Atten= 90%, Lag= 44.7 min
 Discarded = 0.02 cfs @ 12.83 hrs, Volume= 0.015 af
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 121.92' @ 12.83 hrs Surf.Area= 0.024 ac Storage= 0.006 af

Plug-Flow detention time= 101.1 min calculated for 0.015 af (100% of inflow)
 Center-of-Mass det. time= 98.4 min (873.2 - 774.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	121.33'	0.031 af	17.33'W x 41.55'L x 6.25'H Field A 0.103 af Overall - 0.027 af Embedded = 0.077 af x 40.0% Voids
#2A	122.83'	0.027 af	ADS_StormTech MC-3500 d +Capx 10 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 10 Chambers in 2 Rows Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf
#3B	121.33'	0.015 af	9.42'W x 35.38'L x 6.25'H Field B 0.048 af Overall - 0.011 af Embedded = 0.037 af x 40.0% Voids
#4B	122.83'	0.011 af	ADS_StormTech MC-3500 d +Capx 4 Inside #3 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf
		0.083 af	Total Available Storage

Storage Group A created with Chamber Wizard
 Storage Group B created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	121.33'	0.750 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 115.00'
#2	Primary	122.95'	4.0" Vert. Orifice/Grate C= 0.600
#3	Primary	123.50'	10.0" Vert. Orifice/Grate C= 0.600
#4	Primary	126.50'	1.5' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Discarded OutFlow Max=0.02 cfs @ 12.83 hrs HW=121.92' (Free Discharge)
 ↳1=Exfiltration (Controls 0.02 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=121.33' (Free Discharge)
 ↳2=Orifice/Grate (Controls 0.00 cfs)
 ↳3=Orifice/Grate (Controls 0.00 cfs)
 ↳4=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 7P: Chambers - Chamber Wizard Field A

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 2 rows = 59.6 cf

77.0" Wide + 18.0" Spacing = 95.0" C-C Row Spacing

5 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 39.55' Row Length +12.0" End Stone x 2 = 41.55' Base Length

2 Rows x 77.0" Wide + 18.0" Spacing x 1 + 18.0" Side Stone x 2 = 17.33' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

10 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 2 Rows = 1,159.1 cf Chamber Storage

4,501.2 cf Field - 1,159.1 cf Chambers = 3,342.1 cf Stone x 40.0% Voids = 1,336.9 cf Stone Storage

Chamber Storage + Stone Storage = 2,496.0 cf = 0.057 af


Overall Storage Efficiency = 55.5%

Overall System Size = 41.55' x 17.33' x 6.25'

10 Chambers

166.7 cy Field

123.8 cy Stone



Pond 7P: Chambers - Chamber Wizard Field B

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 1 rows = 29.8 cf

4 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 32.38' Row Length +18.0" End Stone x 2 = 35.38' Base Length

1 Rows x 77.0" Wide + 18.0" Side Stone x 2 = 9.42' Base Width

18.0" Base + 45.0" Chamber Height + 12.0" Cover = 6.25' Field Height

4 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 1 Rows = 469.6 cf Chamber Storage

2,082.3 cf Field - 469.6 cf Chambers = 1,612.7 cf Stone x 40.0% Voids = 645.1 cf Stone Storage

Chamber Storage + Stone Storage = 1,114.7 cf = 0.026 af



Overall Storage Efficiency = 53.5%

Overall System Size = 35.38' x 9.42' x 6.25'

4 Chambers


77.1 cy Field

59.7 cy Stone




Pond 7P: Chambers

Hydrograph




Pond 7P: Chambers

Stage-Discharge



Pond 7P: Chambers

Stage-Area-Storage



Hydrograph for Pond 7P: Chambers

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	121.33	0.00	0.00	0.00
0.50	0.00	0.000	121.33	0.00	0.00	0.00
1.00	0.00	0.000	121.33	0.00	0.00	0.00
1.50	0.00	0.000	121.33	0.00	0.00	0.00
2.00	0.00	0.000	121.33	0.00	0.00	0.00
2.50	0.00	0.000	121.33	0.00	0.00	0.00
3.00	0.00	0.000	121.33	0.00	0.00	0.00
3.50	0.00	0.000	121.33	0.00	0.00	0.00
4.00	0.00	0.000	121.33	0.00	0.00	0.00
4.50	0.00	0.000	121.33	0.00	0.00	0.00
5.00	0.00	0.000	121.33	0.00	0.00	0.00
5.50	0.00	0.000	121.33	0.00	0.00	0.00
6.00	0.00	0.000	121.33	0.00	0.00	0.00
6.50	0.00	0.000	121.34	0.00	0.00	0.00
7.00	0.00	0.000	121.34	0.00	0.00	0.00
7.50	0.00	0.000	121.34	0.00	0.00	0.00
8.00	0.00	0.000	121.34	0.00	0.00	0.00
8.50	0.00	0.000	121.34	0.00	0.00	0.00
9.00	0.01	0.000	121.35	0.00	0.00	0.00
9.50	0.01	0.000	121.35	0.01	0.01	0.00
10.00	0.01	0.000	121.35	0.01	0.01	0.00
10.50	0.01	0.000	121.36	0.01	0.01	0.00
11.00	0.01	0.000	121.37	0.01	0.01	0.00
11.50	0.02	0.001	121.38	0.02	0.02	0.00
12.00	0.12	0.002	121.53	0.02	0.02	0.00
12.50	0.04	0.006	121.90	0.02	0.02	0.00
13.00	0.02	0.006	121.91	0.02	0.02	0.00
13.50	0.01	0.005	121.89	0.02	0.02	0.00
14.00	0.01	0.005	121.86	0.02	0.02	0.00
14.50	0.01	0.005	121.81	0.02	0.02	0.00
15.00	0.01	0.004	121.77	0.02	0.02	0.00
15.50	0.01	0.004	121.72	0.02	0.02	0.00
16.00	0.01	0.003	121.66	0.02	0.02	0.00
16.50	0.00	0.003	121.60	0.02	0.02	0.00
17.00	0.00	0.002	121.54	0.02	0.02	0.00
17.50	0.00	0.001	121.48	0.02	0.02	0.00
18.00	0.00	0.001	121.41	0.02	0.02	0.00
18.50	0.00	0.000	121.36	0.01	0.01	0.00
19.00	0.00	0.000	121.35	0.00	0.00	0.00
19.50	0.00	0.000	121.34	0.00	0.00	0.00
20.00	0.00	0.000	121.34	0.00	0.00	0.00
20.50	0.00	0.000	121.34	0.00	0.00	0.00
21.00	0.00	0.000	121.34	0.00	0.00	0.00
21.50	0.00	0.000	121.34	0.00	0.00	0.00
22.00	0.00	0.000	121.34	0.00	0.00	0.00
22.50	0.00	0.000	121.34	0.00	0.00	0.00
23.00	0.00	0.000	121.34	0.00	0.00	0.00
23.50	0.00	0.000	121.34	0.00	0.00	0.00
24.00	0.00	0.000	121.34	0.00	0.00	0.00

Stage-Discharge for Pond 7P: Chambers

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
121.33	0.00	0.00	0.00	126.53	5.08	0.03	5.04
121.43	0.02	0.02	0.00	126.63	5.34	0.03	5.31
121.53	0.02	0.02	0.00	126.73	5.70	0.03	5.67
121.63	0.02	0.02	0.00	126.83	6.14	0.03	6.11
121.73	0.02	0.02	0.00	126.93	6.66	0.03	6.62
121.83	0.02	0.02	0.00	127.03	7.25	0.03	7.22
121.93	0.02	0.02	0.00	127.13	7.92	0.04	7.88
122.03	0.02	0.02	0.00	127.23	8.68	0.04	8.65
122.13	0.02	0.02	0.00	127.33	9.50	0.04	9.46
122.23	0.02	0.02	0.00	127.43	10.29	0.04	10.25
122.33	0.02	0.02	0.00	127.53	11.12	0.04	11.08
122.43	0.02	0.02	0.00				
122.53	0.02	0.02	0.00				
122.63	0.02	0.02	0.00				
122.73	0.02	0.02	0.00				
122.83	0.02	0.02	0.00				
122.93	0.02	0.02	0.00				
123.03	0.04	0.02	0.02				
123.13	0.09	0.02	0.07				
123.23	0.16	0.02	0.14				
123.33	0.22	0.02	0.19				
123.43	0.26	0.02	0.24				
123.53	0.30	0.02	0.27				
123.63	0.39	0.02	0.37				
123.73	0.55	0.03	0.53				
123.83	0.77	0.03	0.75				
123.93	1.04	0.03	1.01				
124.03	1.33	0.03	1.31				
124.13	1.64	0.03	1.62				
124.23	1.94	0.03	1.92				
124.33	2.18	0.03	2.15				
124.43	2.39	0.03	2.36				
124.53	2.58	0.03	2.56				
124.63	2.76	0.03	2.73				
124.73	2.93	0.03	2.90				
124.83	3.09	0.03	3.06				
124.93	3.24	0.03	3.21				
125.03	3.38	0.03	3.35				
125.13	3.52	0.03	3.49				
125.23	3.65	0.03	3.62				
125.33	3.78	0.03	3.75				
125.43	3.90	0.03	3.87				
125.53	4.02	0.03	3.99				
125.63	4.13	0.03	4.10				
125.73	4.25	0.03	4.22				
125.83	4.36	0.03	4.32				
125.93	4.46	0.03	4.43				
126.03	4.57	0.03	4.53				
126.13	4.67	0.03	4.64				
126.23	4.77	0.03	4.74				
126.33	4.87	0.03	4.83				
126.43	4.96	0.03	4.93				

Stage-Area-Storage for Pond 7P: Chambers

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
121.33	0.024	0.000	126.53	0.024	0.073
121.43	0.024	0.001	126.63	0.024	0.074
121.53	0.024	0.002	126.73	0.024	0.075
121.63	0.024	0.003	126.83	0.024	0.076
121.73	0.024	0.004	126.93	0.024	0.077
121.83	0.024	0.005	127.03	0.024	0.078
121.93	0.024	0.006	127.13	0.024	0.079
122.03	0.024	0.007	127.23	0.024	0.080
122.13	0.024	0.008	127.33	0.024	0.080
122.23	0.024	0.009	127.43	0.024	0.081
122.33	0.024	0.010	127.53	0.024	0.082
122.43	0.024	0.011			
122.53	0.024	0.012			
122.63	0.024	0.013			
122.73	0.024	0.014			
122.83	0.024	0.015			
122.93	0.024	0.016			
123.03	0.024	0.018			
123.13	0.024	0.020			
123.23	0.024	0.022			
123.33	0.024	0.024			
123.43	0.024	0.025			
123.53	0.024	0.027			
123.63	0.024	0.029			
123.73	0.024	0.031			
123.83	0.024	0.032			
123.93	0.024	0.034			
124.03	0.024	0.036			
124.13	0.024	0.038			
124.23	0.024	0.039			
124.33	0.024	0.041			
124.43	0.024	0.043			
124.53	0.024	0.044			
124.63	0.024	0.046			
124.73	0.024	0.048			
124.83	0.024	0.049			
124.93	0.024	0.051			
125.03	0.024	0.053			
125.13	0.024	0.054			
125.23	0.024	0.056			
125.33	0.024	0.057			
125.43	0.024	0.059			
125.53	0.024	0.060			
125.63	0.024	0.062			
125.73	0.024	0.063			
125.83	0.024	0.065			
125.93	0.024	0.066			
126.03	0.024	0.067			
126.13	0.024	0.068			
126.23	0.024	0.070			
126.33	0.024	0.071			
126.43	0.024	0.072			

Summary for Pond 8P: Bioretention

Inflow Area = 1.050 ac, 19.05% Impervious, Inflow Depth > 0.26" for Custom event
 Inflow = 0.21 cfs @ 12.16 hrs, Volume= 0.023 af
 Outflow = 0.03 cfs @ 13.97 hrs, Volume= 0.022 af, Atten= 85%, Lag= 108.4 min
 Discarded = 0.03 cfs @ 13.97 hrs, Volume= 0.022 af
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 126.03' @ 13.97 hrs Surf.Area= 0.033 ac Storage= 0.007 af

Plug-Flow detention time= 100.6 min calculated for 0.022 af (99% of inflow)
 Center-of-Mass det. time= 97.2 min (999.4 - 902.1)

Volume	Invert	Avail.Storage	Storage Description
#1	125.50'	0.020 af	Gravel (Prismatic) Listed below 0.050 af Overall x 40.0% Voids
#2	127.00'	0.029 af	Soil (Prismatic) Listed below (Recalc) 0.082 af Overall x 35.0% Voids
#3	129.50'	0.028 af	Custom Stage Data (Prismatic) Listed below (Recalc)
		0.077 af	Total Available Storage

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
125.50	0.033	0.000	0.000
127.00	0.033	0.050	0.050

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
127.00	0.033	0.000	0.000
129.50	0.033	0.082	0.082

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
129.50	0.023	0.000	0.000
130.00	0.028	0.013	0.013
130.50	0.033	0.015	0.028


Device	Routing	Invert	Outlet Devices
#1	Primary	130.00'	12.0" Horiz. Orifice/Grate X 4 rows C= 0.600 Limited to weir flow at low heads
#2	Discarded	125.50'	0.900 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 100.00'

Discarded OutFlow Max=0.03 cfs @ 13.97 hrs HW=126.03' (Free Discharge)
 ↑2=Exfiltration (Controls 0.03 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=125.50' (Free Discharge)
 ↑1=Orifice/Grate (Controls 0.00 cfs)


Pond 8P: Bioretention

Hydrograph




Pond 8P: Bioretention

Stage-Discharge



Pond 8P: Bioretention

Stage-Area-Storage



Hydrograph for Pond 8P: Bioretention

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Outflow (cfs)	Discarded (cfs)	Primary (cfs)
0.00	0.00	0.000	125.50	0.00	0.00	0.00
0.50	0.00	0.000	125.50	0.00	0.00	0.00
1.00	0.00	0.000	125.50	0.00	0.00	0.00
1.50	0.00	0.000	125.50	0.00	0.00	0.00
2.00	0.00	0.000	125.50	0.00	0.00	0.00
2.50	0.00	0.000	125.50	0.00	0.00	0.00
3.00	0.00	0.000	125.50	0.00	0.00	0.00
3.50	0.00	0.000	125.50	0.00	0.00	0.00
4.00	0.00	0.000	125.50	0.00	0.00	0.00
4.50	0.00	0.000	125.50	0.00	0.00	0.00
5.00	0.00	0.000	125.50	0.00	0.00	0.00
5.50	0.00	0.000	125.50	0.00	0.00	0.00
6.00	0.00	0.000	125.50	0.00	0.00	0.00
6.50	0.00	0.000	125.50	0.00	0.00	0.00
7.00	0.00	0.000	125.50	0.00	0.00	0.00
7.50	0.00	0.000	125.50	0.00	0.00	0.00
8.00	0.00	0.000	125.50	0.00	0.00	0.00
8.50	0.00	0.000	125.50	0.00	0.00	0.00
9.00	0.00	0.000	125.50	0.00	0.00	0.00
9.50	0.00	0.000	125.50	0.00	0.00	0.00
10.00	0.00	0.000	125.50	0.00	0.00	0.00
10.50	0.00	0.000	125.50	0.00	0.00	0.00
11.00	0.00	0.000	125.50	0.00	0.00	0.00
11.50	0.00	0.000	125.50	0.00	0.00	0.00
12.00	0.05	0.000	125.51	0.01	0.01	0.00
12.50	0.11	0.005	125.90	0.03	0.03	0.00
13.00	0.04	0.007	125.99	0.03	0.03	0.00
13.50	0.04	0.007	126.02	0.03	0.03	0.00
14.00	0.03	0.007	126.03	0.03	0.03	0.00
14.50	0.03	0.007	126.02	0.03	0.03	0.00
15.00	0.02	0.007	126.00	0.03	0.03	0.00
15.50	0.02	0.006	125.98	0.03	0.03	0.00
16.00	0.02	0.006	125.94	0.03	0.03	0.00
16.50	0.02	0.005	125.90	0.03	0.03	0.00
17.00	0.01	0.005	125.85	0.03	0.03	0.00
17.50	0.01	0.004	125.80	0.03	0.03	0.00
18.00	0.01	0.003	125.74	0.03	0.03	0.00
18.50	0.01	0.002	125.68	0.03	0.03	0.00
19.00	0.01	0.002	125.62	0.03	0.03	0.00
19.50	0.01	0.001	125.56	0.03	0.03	0.00
20.00	0.01	0.000	125.52	0.01	0.01	0.00
20.50	0.01	0.000	125.52	0.01	0.01	0.00
21.00	0.01	0.000	125.51	0.01	0.01	0.00
21.50	0.01	0.000	125.51	0.01	0.01	0.00
22.00	0.01	0.000	125.51	0.01	0.01	0.00
22.50	0.01	0.000	125.51	0.01	0.01	0.00
23.00	0.01	0.000	125.51	0.01	0.01	0.00
23.50	0.01	0.000	125.51	0.01	0.01	0.00
24.00	0.01	0.000	125.51	0.01	0.01	0.00

Stage-Discharge for Pond 8P: Bioretention

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)	Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
125.50	0.00	0.00	0.00	128.10	0.06	0.06	0.00
125.55	0.03	0.03	0.00	128.15	0.06	0.06	0.00
125.60	0.03	0.03	0.00	128.20	0.06	0.06	0.00
125.65	0.03	0.03	0.00	128.25	0.06	0.06	0.00
125.70	0.03	0.03	0.00	128.30	0.06	0.06	0.00
125.75	0.03	0.03	0.00	128.35	0.06	0.06	0.00
125.80	0.03	0.03	0.00	128.40	0.06	0.06	0.00
125.85	0.03	0.03	0.00	128.45	0.06	0.06	0.00
125.90	0.03	0.03	0.00	128.50	0.07	0.07	0.00
125.95	0.03	0.03	0.00	128.55	0.07	0.07	0.00
126.00	0.03	0.03	0.00	128.60	0.07	0.07	0.00
126.05	0.03	0.03	0.00	128.65	0.07	0.07	0.00
126.10	0.03	0.03	0.00	128.70	0.07	0.07	0.00
126.15	0.03	0.03	0.00	128.75	0.07	0.07	0.00
126.20	0.03	0.03	0.00	128.80	0.07	0.07	0.00
126.25	0.03	0.03	0.00	128.85	0.07	0.07	0.00
126.30	0.03	0.03	0.00	128.90	0.07	0.07	0.00
126.35	0.03	0.03	0.00	128.95	0.07	0.07	0.00
126.40	0.03	0.03	0.00	129.00	0.07	0.07	0.00
126.45	0.03	0.03	0.00	129.05	0.07	0.07	0.00
126.50	0.03	0.03	0.00	129.10	0.07	0.07	0.00
126.55	0.03	0.03	0.00	129.15	0.07	0.07	0.00
126.60	0.03	0.03	0.00	129.20	0.07	0.07	0.00
126.65	0.03	0.03	0.00	129.25	0.07	0.07	0.00
126.70	0.03	0.03	0.00	129.30	0.07	0.07	0.00
126.75	0.03	0.03	0.00	129.35	0.07	0.07	0.00
126.80	0.03	0.03	0.00	129.40	0.07	0.07	0.00
126.85	0.03	0.03	0.00	129.45	0.07	0.07	0.00
126.90	0.03	0.03	0.00	129.50	0.09	0.09	0.00
126.95	0.03	0.03	0.00	129.55	0.09	0.09	0.00
127.00	0.06	0.06	0.00	129.60	0.09	0.09	0.00
127.05	0.06	0.06	0.00	129.65	0.09	0.09	0.00
127.10	0.06	0.06	0.00	129.70	0.09	0.09	0.00
127.15	0.06	0.06	0.00	129.75	0.09	0.09	0.00
127.20	0.06	0.06	0.00	129.80	0.09	0.09	0.00
127.25	0.06	0.06	0.00	129.85	0.09	0.09	0.00
127.30	0.06	0.06	0.00	129.90	0.09	0.09	0.00
127.35	0.06	0.06	0.00	129.95	0.09	0.09	0.00
127.40	0.06	0.06	0.00	130.00	0.09	0.09	0.00
127.45	0.06	0.06	0.00	130.05	0.55	0.09	0.46
127.50	0.06	0.06	0.00	130.10	1.39	0.10	1.30
127.55	0.06	0.06	0.00	130.15	2.48	0.10	2.39
127.60	0.06	0.06	0.00	130.20	3.77	0.10	3.68
127.65	0.06	0.06	0.00	130.25	5.23	0.10	5.14
127.70	0.06	0.06	0.00	130.30	6.85	0.10	6.75
127.75	0.06	0.06	0.00	130.35	8.61	0.10	8.51
127.80	0.06	0.06	0.00	130.40	9.67	0.10	9.57
127.85	0.06	0.06	0.00	130.45	10.25	0.10	10.15
127.90	0.06	0.06	0.00	130.50	10.80	0.10	10.70
127.95	0.06	0.06	0.00				
128.00	0.06	0.06	0.00				
128.05	0.06	0.06	0.00				

Stage-Area-Storage for Pond 8P: Bioretention

Elevation (feet)	Surface (acres)	Storage (acre-feet)	Elevation (feet)	Surface (acres)	Storage (acre-feet)
125.50	0.033	0.000	128.10	0.066	0.033
125.55	0.033	0.001	128.15	0.066	0.033
125.60	0.033	0.001	128.20	0.066	0.034
125.65	0.033	0.002	128.25	0.066	0.034
125.70	0.033	0.003	128.30	0.066	0.035
125.75	0.033	0.003	128.35	0.066	0.035
125.80	0.033	0.004	128.40	0.066	0.036
125.85	0.033	0.005	128.45	0.066	0.037
125.90	0.033	0.005	128.50	0.066	0.037
125.95	0.033	0.006	128.55	0.066	0.038
126.00	0.033	0.007	128.60	0.066	0.038
126.05	0.033	0.007	128.65	0.066	0.039
126.10	0.033	0.008	128.70	0.066	0.039
126.15	0.033	0.009	128.75	0.066	0.040
126.20	0.033	0.009	128.80	0.066	0.041
126.25	0.033	0.010	128.85	0.066	0.041
126.30	0.033	0.011	128.90	0.066	0.042
126.35	0.033	0.011	128.95	0.066	0.042
126.40	0.033	0.012	129.00	0.066	0.043
126.45	0.033	0.013	129.05	0.066	0.043
126.50	0.033	0.013	129.10	0.066	0.044
126.55	0.033	0.014	129.15	0.066	0.045
126.60	0.033	0.015	129.20	0.066	0.045
126.65	0.033	0.015	129.25	0.066	0.046
126.70	0.033	0.016	129.30	0.066	0.046
126.75	0.033	0.017	129.35	0.066	0.047
126.80	0.033	0.017	129.40	0.066	0.048
126.85	0.033	0.018	129.45	0.066	0.048
126.90	0.033	0.018	129.50	0.089	0.049
126.95	0.033	0.019	129.55	0.090	0.050
127.00	0.066	0.020	129.60	0.090	0.051
127.05	0.066	0.020	129.65	0.091	0.052
127.10	0.066	0.021	129.70	0.091	0.053
127.15	0.066	0.022	129.75	0.091	0.055
127.20	0.066	0.022	129.80	0.092	0.056
127.25	0.066	0.023	129.85	0.092	0.057
127.30	0.066	0.023	129.90	0.093	0.059
127.35	0.066	0.024	129.95	0.093	0.060
127.40	0.066	0.024	130.00	0.094	0.061
127.45	0.066	0.025	130.05	0.095	0.063
127.50	0.066	0.026	130.10	0.095	0.064
127.55	0.066	0.026	130.15	0.096	0.066
127.60	0.066	0.027	130.20	0.096	0.067
127.65	0.066	0.027	130.25	0.096	0.069
127.70	0.066	0.028	130.30	0.097	0.070
127.75	0.066	0.028	130.35	0.097	0.072
127.80	0.066	0.029	130.40	0.098	0.073
127.85	0.066	0.030	130.45	0.098	0.075
127.90	0.066	0.030	130.50	0.099	0.077
127.95	0.066	0.031			
128.00	0.066	0.031			
128.05	0.066	0.032			


Summary for Link 7L: Post (Composite)

Inflow Area = 1.190 ac, 28.57% Impervious, Inflow Depth = 0.00" for Custom event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: Post (Composite)

Hydrograph



Hydrograph for Link 7L: Post (Composite)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
0.00	0.00	0.00	0.00	13.00	0.00	0.00	0.00
0.25	0.00	0.00	0.00	13.25	0.00	0.00	0.00
0.50	0.00	0.00	0.00	13.50	0.00	0.00	0.00
0.75	0.00	0.00	0.00	13.75	0.00	0.00	0.00
1.00	0.00	0.00	0.00	14.00	0.00	0.00	0.00
1.25	0.00	0.00	0.00	14.25	0.00	0.00	0.00
1.50	0.00	0.00	0.00	14.50	0.00	0.00	0.00
1.75	0.00	0.00	0.00	14.75	0.00	0.00	0.00
2.00	0.00	0.00	0.00	15.00	0.00	0.00	0.00
2.25	0.00	0.00	0.00	15.25	0.00	0.00	0.00
2.50	0.00	0.00	0.00	15.50	0.00	0.00	0.00
2.75	0.00	0.00	0.00	15.75	0.00	0.00	0.00
3.00	0.00	0.00	0.00	16.00	0.00	0.00	0.00
3.25	0.00	0.00	0.00	16.25	0.00	0.00	0.00
3.50	0.00	0.00	0.00	16.50	0.00	0.00	0.00
3.75	0.00	0.00	0.00	16.75	0.00	0.00	0.00
4.00	0.00	0.00	0.00	17.00	0.00	0.00	0.00
4.25	0.00	0.00	0.00	17.25	0.00	0.00	0.00
4.50	0.00	0.00	0.00	17.50	0.00	0.00	0.00
4.75	0.00	0.00	0.00	17.75	0.00	0.00	0.00
5.00	0.00	0.00	0.00	18.00	0.00	0.00	0.00
5.25	0.00	0.00	0.00	18.25	0.00	0.00	0.00
5.50	0.00	0.00	0.00	18.50	0.00	0.00	0.00
5.75	0.00	0.00	0.00	18.75	0.00	0.00	0.00
6.00	0.00	0.00	0.00	19.00	0.00	0.00	0.00
6.25	0.00	0.00	0.00	19.25	0.00	0.00	0.00
6.50	0.00	0.00	0.00	19.50	0.00	0.00	0.00
6.75	0.00	0.00	0.00	19.75	0.00	0.00	0.00
7.00	0.00	0.00	0.00	20.00	0.00	0.00	0.00
7.25	0.00	0.00	0.00	20.25	0.00	0.00	0.00
7.50	0.00	0.00	0.00	20.50	0.00	0.00	0.00
7.75	0.00	0.00	0.00	20.75	0.00	0.00	0.00
8.00	0.00	0.00	0.00	21.00	0.00	0.00	0.00
8.25	0.00	0.00	0.00	21.25	0.00	0.00	0.00
8.50	0.00	0.00	0.00	21.50	0.00	0.00	0.00
8.75	0.00	0.00	0.00	21.75	0.00	0.00	0.00
9.00	0.00	0.00	0.00	22.00	0.00	0.00	0.00
9.25	0.00	0.00	0.00	22.25	0.00	0.00	0.00
9.50	0.00	0.00	0.00	22.50	0.00	0.00	0.00
9.75	0.00	0.00	0.00	22.75	0.00	0.00	0.00
10.00	0.00	0.00	0.00	23.00	0.00	0.00	0.00
10.25	0.00	0.00	0.00	23.25	0.00	0.00	0.00
10.50	0.00	0.00	0.00	23.50	0.00	0.00	0.00
10.75	0.00	0.00	0.00	23.75	0.00	0.00	0.00
11.00	0.00	0.00	0.00	24.00	0.00	0.00	0.00
11.25	0.00	0.00	0.00				
11.50	0.00	0.00	0.00				
11.75	0.00	0.00	0.00				
12.00	0.00	0.00	0.00				
12.25	0.00	0.00	0.00				
12.50	0.00	0.00	0.00				
12.75	0.00	0.00	0.00				

**APPENDIX H:
PRE-CONSTRUCTION DOCUMENTS & CERTIFICATIONS**

PRE-CONSTRUCTION DOCUMENTS

Project Name: The Masters School Innovation and Entrepreneurship Center

Name of Owner: The Masters School

Name of Operator: Yorke Construction Corporation

Name of Preparer: Gonzalo Trenosky, P.E.

Name of Qualified Professional: Gonzalo Trenosky, P.E.

PREAMBLE TO SITE ASSESSMENT AND INSPECTIONS

The Following Information to Be Read by All Person's Involved in The Construction of Stormwater Related Activities:

A qualified professional¹ shall conduct an assessment of the site prior to the commencement of construction activities^{2,3} and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP have been adequately installed or implemented to ensure overall preparedness of the site for the commencement of construction.

Prior to the commencement of construction, the Preparer shall certify in this site logbook that the SWPPP has been prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements.

When construction starts, site inspections shall be conducted by the qualified professional at least every seven (7) calendar days (Construction Duration Inspections), except as otherwise

¹ "Qualified Professional" means a person that is knowledgeable in the principles and practices of erosion and sediment control, such as a licensed Professional Engineer, Certified Professional in Erosion and Sediment Control (CPESC), licensed Landscape Architect, or other NYSDEC (Department) endorsed individual(s). It also means someone working under the direct supervision of the licensed Professional Engineer or licensed Landscape Architect, if person has training in the principles and practices of erosion and sediment control. Training in that principles and practices of erosion and sediment control means that an individual performing a site inspection has received four (4) hours of training, endorsed by the Department, from a Soil and Water Conservation District, CPESC, Inc. or other Department endorsed entity in proper erosion and sediment control principles no later than two (2) years from date this general permit is issued. After receiving the initial training, an individual working under the direct supervision of the licensed Professional Engineer or licensed Landscape Architect shall receive four (4) hours of training every three (3) years.

² "Commencement of Construction Activities" means the initial disturbance of soils associated with clearing, grading or excavation activities; or other construction related activities that disturb or expose soils such as demolition, stockpiling of fill material, and the initial installation of erosion and sediment control practices required in the SWPPP. See definition for "Construction Activity(ies)" also.

³ "Construction Activity(ies)" means any clearing, grading, excavation, filling, demolition or stockpiling activities that result in soil disturbance. Clearing activities can include, but are not limited to, logging equipment operation, the cutting and skidding of trees, stump removal and/or brush root removal. Construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of a facility.

required during “winter frequency”. The Operator shall maintain a record of all inspection reports in this site logbook. The site logbook shall be maintained on site and be made available to the permitting authorities upon request. The Operator shall post at the site, in a publicly accessible location, a summary of the site inspection activities on a monthly basis (Monthly Summary Report).

A qualified professional shall perform a final site inspection. The qualified professional shall certify that the site had undergone final stabilization⁴ using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. In addition, the Preparer must identify and certify that all permanent structures described in the SWPPP have been constructed and provide the owner(s) with an operation and maintenance plan that ensures the structure(s) continuously functions as designed.

⁴ “Final stabilization” means that all soil-disturbing activities have ceased and a uniform, perennial vegetative cover with a density of eighty (80) percent over the entire pervious surface has been established; or other equivalent stabilization measures, such as permanent landscape mulches, rock rip-rap or washed/crushed stone have been applied on all disturbed areas that are not covered by permanent structures, concrete or pavement.

PRE-CONSTRUCTION CERTIFICATIONS

PREPARER'S CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Name (please print): Gonzalo Trenosky, P.E.

Title: Associate Engineer \ MFS

Date: _____

Address: 320 Fifth Avenue, Suite 1102 New York, NY 10001

Phone: (212)-943-6576

Email: gmt@mfsengineers.com

Signature:

OWNER'S CERTIFICATION

"I certify under penalty of law that I understand and agree to comply with the terms and conditions of the SWPPP for the construction site identified in such SWPPP as a condition of authorization to discharge storm water. I also understand that the operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System (SPDES) general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards.

I certify that the storm water control measures as shown in the SWPPP will be in place before commencement of construction of any segment of the project that requires each measure."

Name (please print): Mr. Seth Marx

Title: Director of Institutional Advancement

Date: _____

Address: 49 Clinton Avenue, Dobbs Ferry, NY 10522

Phone: +1 (914)-479-6527

Email: seth.marx@mastersny.org

Signature:



OPERATOR'S CERTIFICATION

"I certify under penalty of law that I understand and agree to comply with the terms and conditions of the SWPPP for the construction site identified in such SWPPP as a condition of authorization to discharge stormwater. I also understand that the operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System (SPDES) general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards.

I certify that the stormwater control measure as shown in the SWPPP will be in place before commencement of construction of any segment of the project that requires each measure."

Name (please print): Yorke Construction Corporation

Title: _____ **Date:** _____

Address: _____

Phone: _____ **Email:** _____

Signature:

PREPARER'S CERTIFICATION

"I hereby certify that I meet the criteria set forth in the SWPPP to conduct site inspections for this project and that appropriate erosion and sediment controls described in the SWPPP and as described in the following Pre-Construction site assessment Checklist have been adequately installed or implemented, ensuring the overall preparedness of this site for the commencement of construction."

Name (please print): Gonzalo Trenosky, P.E.

Title: Associate Engineer \ MFS **Date:** _____

Address: 320 Fifth Avenue, Suite 1102 New York, NY 10001

Phone: (212)-943-6576 **Email:** gmt@mfsengineers.com

Signature:



APPENDIX I:
CONSTRUCTION DURATION INSPECTIONS

CONSTRUCTION DURATION INSPECTIONS

Directions:

Inspection Forms will be filled out during the entire construction phase of the project. Required Elements:

On a site map, indicate the extent of all disturbed site areas and drainage pathways. Indicate site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period;

Indicate on a site map all areas of the site that have undergone temporary or permanent stabilization;

Indicate all disturbed site areas that have not undergone active site work during the previous 14-day period;

Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of sediment storage volume (for example, 10 percent, 20 percent, 50 percent);

Inspect all erosion and sediment control practices and record all maintenance requirements such as verifying the integrity of barrier or diversion systems (earthen berms or silt fencing) and containment systems (sediment basins and sediment traps). Identify any evidence of rill or gully erosion occurring on slopes and any loss of stabilizing vegetation or seeding/mulching. Document any excessive deposition of sediment or ponding water along barrier or diversion systems. Record the depth of sediment within containment structures, any erosion near outlet and overflow structures, and verify the ability of rock filters around perforated risers pipes to pass water; and

Immediately report to the Operator any deficiencies that are identified with the implementation of the SWPPP.

SITE PLAN/SKETCH

Inspector(Printname)

Date of Inspection

Qualified Professional (print name)

Qualified Professional Signature

The above signed acknowledges that, to the best of his/her knowledge, all information provided on the forms is accurate and complete



MAINTAINING WATER QUALITY				
Yes	No	N/A	Item	Comments
			Is there an increase in turbidity causing a substantial visible contrast to natural conditions?	
			Is there residue from oil and floating substances, visible oil film, or globules or grease?	
			All disturbances are within the limits of the approved plans?	
			Have receiving lake/bay, stream, and/or wetland been impacted by silt from project?	

HOUSEKEEPING				
Yes	No	N/A	Item	Comments
			Is construction site litter and debris appropriately managed?	
			Are facilities and equipment necessary for implementation or erosion and sediment control in working order and/or properly maintained?	
			Is construction impacting the adjacent property?	
			Is dust adequately controlled?	

RUNOFF CONTROL PRACTICES				
Yes	No	N/A	Item	Comments
			Is sediment laden water from work area being discharged to silt trapping device(s)?	

SOIL STABILIZATION				
Yes	No	N/A	Item	Comments
			Are stockpiles are stabilized with vegetation and/or mulch?	
			Do stockpiles have silt fence at base?	
			Is sediment control installed at the toe of the slope?	
			Is silt fence installed off-mound areas only?	
			Have temporary seedings and mulch been applied to idle areas?	
			Has 4 inches minimum of topsoil been applied under permanent seedings?	

SEDIMENT CONTROL PRACTICES				
<i>Stabilized Construction Entrance</i>				
Yes	No	N/A	Item	Comments
			Stone is clean enough to effectively remove mud from vehicles?	
			Installed per standards and specifications?	
			Does all traffic use the stabilized entrance to enter and leave site?	
			Is adequate drainage provided to prevent ponding at entrance?	
<i>Silt Fence/Straw Bale Dike</i>				
Yes	No	N/A	Item	Comments
			Installed on contour, 10 feet from toe of slope (not across conveyance channels)?	
			Installed per standards and specifications?	
			Silt Fence: joints constructed by wrapping the two ends together for continuous support?	
			Silt Fence: fabric buried 6 inches minimum?	
			Straw Bale: embedded 4 inches minimum?	
			Silt Fence: posts are stable, fabric is tight and without rips or frayed areas?	
			Straw Bale: securely anchored in place?	
Sediment accumulation is _____% of design capacity.				
<i>Sediment Trap</i>				
Yes	No	N/A	Item	Comments
			Drainage area is 5 acre or less?	
			Installed per standards and specifications?	

CONDITIONS OF OUTFALLS (ANNUAL AND AFTER MAJOR STORM EVENTS)				
Yes	No	N/A	Item	Comments
			Riprap failure?	
			Slope Erosion?	
			Storm drain pipe condition?	
			Headwall Structure condition?	

Note: Not all erosion and sediment control practices are included in this document. Additional pages shall be included as required for this project. Construction inspection checklists for post-development stormwater management practices can be found in Appendix F and G of the New York State Stormwater Management Design Manual.

APPENDIX J:
MONTHLY SUMMARY OF SITE INSPECTION ACTIVITIES

APPENDIX K:
CONTRACTOR'S CERTIFICATIONS AND FORMS

CONTRACTOR'S CERTIFICATION STATEMENT

I. SITE INFORMATION

Construction Site Name: The Masters School Innovation and Entrepreneurship Center

Site Location: 49 Clinton Avenue, Dobbs Ferry, NY 10522

II. CONTRACTOR'S INFORMATION

Contracting Firm: Yorke Construction Corporation

Contracting Firm Address: 140 West 31st Street, 4th Floor, New York, NY 10001

Contact: _____

Telephone Number: _____

III. STORMWATER MEASURES

Contractor is responsible for but not limited to the following stormwater measures.

- | | | |
|--------------------------|----------|----------|
| 1. Piping | 4. _____ | 7. _____ |
| 2. Underground Detention | 5. _____ | 8. _____ |
| 3. Landscaping | 6. _____ | 9. _____ |

IV. CERTIFICATION

"I certify under penalty of law that I understand and agree to comply with the terms and conditions of the SWPPP for the construction site identified in such SWPPP as a condition of authorization to discharge stormwater. I also understand that the operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System (SPDES) general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards."

V. SIGNATURE: _____ DATE: _____

Name (print): _____

Title: _____



SUB-CONTRACTOR'S CERTIFICATION STATEMENT

The General Contractor, _____ shall have this statement completed and signed by all subcontractors of the project that will be responsible for any measure outlined in this stormwater pollution prevention plan.

I. SITE INFORMATION

Construction Site Name: _____

Site Location: _____

II. SUB-CONTRACTORS INFORMATION

Sub-Contracting Firm: _____

Sub-Contracting Firm: _____

Telephone Number(s): _____

Contact(s): 1) _____

2) _____

III. STORMWATER MEASURES

Sub-Contractor is responsible for but not limited to the following storm water measures.

1. _____ 4. _____ 7. _____

2. _____ 5. _____ 8. _____

3. _____ 6. _____ 9. _____

IV. STORMWATER MEASURES

"I certify under penalty of law that I understand and agree to comply with the terms and conditions of the SWPPP for the construction site identified in such SWPPP as a condition of authorization to discharge storm water. I also understand that the operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System (SPDES) general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards."

V. SIGNATURE: _____ DATE: _____

Name (print): _____

Title: _____



CERTIFICATE OF ISSUANCE

As directed by the Operator, a copy of the storm water pollution prevention plan will be retained at the site, along with all signed statements, reports and schedules contained herein for completion by the contractor. Upon completion the storm water pollution prevention plan and all records shall be returned to the operator.

Date of Issuance: _____

Name: _____

Title: _____

Firm: _____

Signature:

Received from:

Name: _____

Title: _____

Firm: _____

Address/ Phone No: _____

Signature:

Inquiries in regards to copies of pollution prevention plan by either the State Director or any local agency having jurisdiction to be directed to owner's project representative.



EROSION AND WATER QUALITY CONTROL IDENTIFICATION

The contractor and/or subcontractors that will implement each erosion control measure must be identified:

IDENTIFICATION

NAME OF CONTRACTOR AND/OR SUBCONTRACTOR	MEASURE TO BE IMPLEMENTED

Each contractor and subcontractor identified must sign a copy of the certification statement.

This identification does not reassign or remove responsibility for all measures as agreed to the contract documents. The contractor is responsible for all subcontractors.



CONSTRUCTION STABILIZATION

The Contractor shall initiate stabilization measures as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. When construction activity is precluded by snow cover, stabilization measures shall be initiated as soon as practicable. When construction activity will resume within 21 days from when activity ceased, then stabilization measures do not have to be initiated on that portion of the site by the 14th day after construction activity temporarily ceased.

THE CONTRACTOR IS RESPONSIBLE TO KEEP THE FOLLOWING RECORDS:

MAJOR GRAVITY ACTIVITY	PORTION OF THE SITE	DATE COMMENCED	DATE CEASED (PERMANENTLY OR TEMPORARILY)	DATE STABILIZATION MEASURES INITIATED

THESE MUST BE KEPT UP TO DATE AND ON-SITE FOR INSPECTION AT ANYTIME.

CERTIFICATE OF CHANGE BY CONTRACTOR

To: _____

Project: _____

Site Address: _____

Enclosed, please find your written notification of the following provision(s) of the SWPPP not being met:

Provisions of the plan requiring modification:

Action taken to modify plan to bring project into compliance:

Date Completed: _____

Received By: _____

Name: _____

Name: _____

Title: _____

Title: _____

Contracting Firm: _____

Firm: _____

Address: _____

Address: _____

Phone Number: _____

Phone Number: _____

Signature: _____

Signature: _____



APPENDIX L:
END OF CONSTRUCTION DOCUMENTS

FINAL STABILIZATION AND RETENTION OF RECORDS

A. Qualified Professional Certification - A qualified professional shall perform a final site inspection.

- | Yes | No | NA | |
|--------------------------|--------------------------|--------------------------|--|
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Final site drainage will prevent erosion, concentrated flows to adjacent properties, uncontrolled overflow, and ponding. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Conveyance systems are stabilized. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Channels and stream banks are seeded at the outlet points. |

"I hereby certify that the site has undergone final stabilization. Final stabilization means that all soil disturbing activities have been completed and a uniform, perennial vegetative cover with a density of eighty (80) percent has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structures. Further, all temporary erosion and sediment controls (such as silt fence) not specified for permanent erosion control have been removed."

Name of Qualified Professional:

Signature: _____

B. Retention of Records - The Operator shall retain copies of SWPPPs and any reports and records of all data for a period of at least three years from the date that the site is finally stabilized.

C. Maintenance of SWPPP and any reports at the construction site - The Operator shall retain a copy of the SWPPP at the construction site from the data of initiation of construction activities to the date of final stabilization.



CERTIFICATE OF RETURN

As directed by the Owner's representative, the copy of the storm water pollution prevention plan retained at the site, along with all signed statements, reports and schedules contained herein for completion by the contractor are to be returned to the owner. The owner shall retain the plan, reports and records of all data for a period of three years from the date that the site is stabilized. This period may be extended by the State director at any time upon written notification.

Date of site stabilization: _____

Name: _____

Title: _____

Firm: _____

Signature: _____

Received by: _____

Name/ Title: _____

Address/ Phone No: _____

Signature: _____

Inquiries in regards to copies of pollution prevention plan by either the State Director or any local agency having jurisdiction to be directed to owner's project representative.



APPENDIX M:
EROSION AND SEDIMENT CONTROL MATERIAL SPECS

PROJECT INFORMATION	
ENGINEERED PRODUCT MANAGER:	JUSTIN PICCILLO 917-716-6420 JUSTIN.PICCILLO@ADS-PIPE.COM
ADS SALES REP:	TIMOTHY KUZIO 315-925-7760 TIMOTHY.KUZIO@ADS-PIPE.COM
PROJECT NO:	S254171



SiteASSIST™
FOR STORMTECH
INSTRUCTIONS,
DOWNLOAD THE
INSTALLATION APP



THE MASTERS SCHOOL

DOBBS FERRY, NY

MC-3500 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH MC-3500.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS.
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" CHAMBER CLASSIFICATION 45x76 DESIGNATION SS.
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 3".
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT SHALL BE GREATER THAN OR EQUAL TO 450 LBS/IN/IN. THE ASC IS DEFINED IN SECTION 6.2.8 OF ASTM F2418. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
 - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
 - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
 - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF MC-3500 CHAMBER SYSTEM

- STORMTECH MC-3500 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH MC-3500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
- CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
 - STONESHOOTER LOCATED OFF THE CHAMBER BED.
 - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
 - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- MAINTAIN MINIMUM - 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS.
- INLET AND OUTLET MANIFOLDS MUST BE INSERTED A MINIMUM OF 12" (300 mm) INTO CHAMBER END CAPS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE MEETING THE AASHTO M43 DESIGNATION OF #3 OR #4.
- STONE MUST BE PLACED ON THE TOP CENTER OF THE CHAMBER TO ANCHOR THE CHAMBERS IN PLACE AND PRESERVE ROW SPACING.
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
- ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

NOTES FOR CONSTRUCTION EQUIPMENT

- STORMTECH MC-3500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
- THE USE OF EQUIPMENT OVER MC-3500 CHAMBERS IS LIMITED:
 - NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
 - NO RUBBER Tired LOADER, DUMP TRUCK, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
 - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
- FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.

USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY USING THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.

PROPOSED LAYOUT

14	STORMTECH MC-3500 CHAMBERS
6	STORMTECH MC-3500 END CAPS
12	STONE ABOVE (in)
9	STONE BELOW (in)
40	% STONE VOID
3,316	INSTALLED SYSTEM VOLUME (CF) (PERIMETER STONE INCLUDED)
1,063	SYSTEM AREA (ft ²)
151	SYSTEM PERIMETER (ft)

PROPOSED ELEVATIONS


134.58	MAXIMUM ALLOWABLE GRADE (TOP OF PAVEMENT/UNPAVED)
128.58	MINIMUM ALLOWABLE GRADE (UNPAVED WITH TRAFFIC)
128.08	MINIMUM ALLOWABLE GRADE (UNPAVED NO TRAFFIC)
128.08	MINIMUM ALLOWABLE GRADE (BASE OF FLEXIBLE PAVEMENT)
128.08	MINIMUM ALLOWABLE GRADE (TOP OF RIGID PAVEMENT)
127.58	TOP OF STONE
126.58	TOP OF MC-3500 CHAMBER
124.00	12" MANIFOLD INVERT
123.00	24" ISOLATOR ROW PLUS CONNECTION INVERT
122.94	12" BOTTOM CONNECTION INVERT
122.83	BOTTOM OF MC-3500 CHAMBER
122.08	UNDERDRAIN INVERT
121.33	BOTTOM OF STONE

EXPECTED ELEVATIONS FOR MODELLED STORM EVENTS

122.83	1-YR STORM
124.59	10-YR STORM
125.51	25-YR STORM
126.93	100-YR STORM

NOTES

- MANIFOLD SIZE TO BE DETERMINED BY SITE DESIGN ENGINEER. SEE TECHNICAL NOTE 6.32 FOR MANIFOLD SIZING GUIDANCE.
- DUE TO THE ADAPTATION OF THIS CHAMBER SYSTEM TO SPECIFIC SITE AND DESIGN CONSTRAINTS, IT MAY BE NECESSARY TO CUT AND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD COMPONENTS IN THE FIELD.
- THE SITE DESIGN ENGINEER MUST REVIEW ELEVATIONS AND IF NECESSARY ADJUST GRADING TO ENSURE THE CHAMBER COVER REQUIREMENTS ARE MET.
- THIS CHAMBER SYSTEM WAS DESIGNED WITHOUT SITE-SPECIFIC INFORMATION ON SOIL CONDITIONS OR BEARING CAPACITY. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR DETERMINING THE SUITABILITY OF THE SOIL AND PROVIDING THE BEARING CAPACITY OF THE INSITU SOILS. THE BASE STONE DEPTH MAY BE INCREASED OR DECREASED ONCE THIS INFORMATION IS PROVIDED.



THE MASTERS SCHOOL

DOBBS FERRY, NY

DATE: 08-19-21 DRAWN: TSG
PROJECT #: S254171 CHECKED: XXX


DATE	ISSN/CHD	DESCRIPTION

stormTech®
Chamber System
888-892-2694 | WWW.STORMTECH.COM


4640 TRUEHEMAN BLVD
HILLIARD, OH 43026

2 SHEET OF 6

THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ACCURATELY REFLECT THE INTENTION OF THE USER. STORMTECH, INC. ASSUMES NO LIABILITY FOR THE USE OF THIS DRAWING. THE USER SHALL BE RESPONSIBLE FOR THE SITE DESIGN ENGINEER TO ENSURE THAT THE PROJECT IS DESIGNED AND CONSTRUCTED TO MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS. IT IS THE USER'S RESPONSIBILITY TO VERIFY ALL INFORMATION PROVIDED TO STORMTECH, INC. IS ACCURATE AND COMPLETE.



4640 TRUEMAN BLVD
HILLIARD, OH 43026



StormTech®
Chamber System

888-852-2654 | WWW.STORMTECH.COM

DATE	DRAWN	CHKD	DESCRIPTION

THE MASTERS SCHOOL

DOBBS FERRY, NY

DATE: 08-19-21 DRAWN: TSG

PROJECT #: S254171 CHECKED: XXX

3 SHEET
OF 6


THIS DRAWING HAS BEEN PREPARED BY AN UNLICENSED PERSON OR THE DESIGN OR THE PRODUCTS DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS. THE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCTS DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.

ACCEPTABLE FILL MATERIALS: STORMTECH MC-3500 CHAMBER SYSTEMS

MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 24" (600 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	AASHTO M145 ¹ A-1, A-2-4, A-3 OR AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 24" (600 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 12" (300 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS.
B	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE AASHTO M43 ¹ 3, 4	NO COMPACTION REQUIRED.
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE AASHTO M43 ¹ 3, 4	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. ^{2,3}

PLEASE NOTE:

- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
- STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 9" (230 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
- ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.



NOTES:

- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" CHAMBER CLASSIFICATION 45x78 DESIGNATION SS.
- MC-3500 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 3".
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 500 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

THE MASTERS SCHOOL

DOBBS FERRY, NY
DATE: 08-19-21
DRAWN: TSG
PROJECT #: S254171
CHECKED: XXX

DATE	DRWN	CHKD	DESCRIPTION

StormTech®
Chamber System
888-882-2654 | WWW.STORMTECH.COM


4640 TRUEMAN BLVD
HILLIARD, OH 43026



THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE LIABILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCTS DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS AND PROJECT REQUIREMENTS.


UNDERDRAIN DETAIL

NTS



MC-SERIES END CAP INSERTION DETAIL


NTS



NOTE: MANIFOLD STUB MUST BE LAID HORIZONTAL FOR A PROPER FIT IN END CAP OPENING.

MC-3500 TECHNICAL SPECIFICATION

NTS



*ASSUMES 12" (305 mm) STONE ABOVE, 9" (229 mm) STONE FOUNDATION, 6" (152 mm) STONE BETWEEN CHAMBERS, 6" (152 mm) STONE PERIMETER IN FRONT OF END CAPS AND 40% STONE POROSITY.

PARTIAL CUT HOLES AT BOTTOM OF END CAP FOR PART NUMBERS ENDING WITH "B"
PARTIAL CUT HOLES AT TOP OF END CAP FOR PART NUMBERS ENDING WITH "T"
END CAPS WITH A PREFABRICATED WELDED STUB END WITH "W"
END CAPS WITH A WELDED CROWN PLATE END WITH "C"

PART #	STUB	B	C
MC3500IEPP06T		33.21" (844 mm)	---
MC3500IEPP06B	6" (150 mm)	---	0.66" (17 mm)
MC3500IEPP08T		31.16" (791 mm)	---
MC3500IEPP08B	8" (200 mm)	---	0.81" (21 mm)
MC3500IEPP10T		29.04" (738 mm)	---
MC3500IEPP10B	10" (250 mm)	---	0.93" (24 mm)
MC3500IEPP12T		26.36" (670 mm)	---
MC3500IEPP12B	12" (300 mm)	---	1.35" (34 mm)
MC3500IEPP15T		23.39" (594 mm)	---
MC3500IEPP15B	15" (375 mm)	---	1.50" (38 mm)
MC3500IEPP18TC		20.03" (509 mm)	---
MC3500IEPP18TW		---	---
MC3500IEPP18BC	18" (450 mm)	---	1.77" (45 mm)
MC3500IEPP18BW		---	---
MC3500IEPP24TC		14.48" (368 mm)	---
MC3500IEPP24TW	24" (600 mm)	---	---
MC3500IEPP24BC		---	2.06" (52 mm)
MC3500IEPP24BW		---	---
MC3500IEPP30BC	30" (750 mm)	---	2.75" (70 mm)

NOTE: ALL DIMENSIONS ARE NOMINAL

CUSTOM PARTIAL CUT INVERTS ARE AVAILABLE UPON REQUEST.
INVENTORIED MANIFOLDS INCLUDE 12-24" (300-600 mm) SIZE ON SIZE AND 15-48" (375-1200 mm) ECCENTRIC MANIFOLDS. CUSTOM INVERT LOCATIONS ON THE MC-3500 END CAP CUT IN THE FIELD ARE NOT RECOMMENDED FOR PIPE SIZES GREATER THAN 10" (250 mm). THE INVERT LOCATION IN COLUMN 'B' ARE THE HIGHEST POSSIBLE FOR THE PIPE SIZE.

THE MASTERS SCHOOL
DOBBS FERRY, NY

DATE: 08-19-21 DRAWN: TSG
PROJECT #: S264171 CHECKED: XXX

DATE: [] [] [] DESCRIPTION: []

888-892-2654 | WWW.STORMTECH.COM

StormTech
Chamber System

4640 TRUEMAN BLVD
HILLIARD, OH 43026

ADS

6 SHEET
OF 6

THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER FOR THE PROJECT. THE USER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCTS DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS AND PROJECT REQUIREMENTS.

PROJECT INFORMATION	
ENGINEERED PRODUCT MANAGER	
ADS SALES REP	
PROJECT NO.	



SiteASSIST™
FOR STORMTECH
INSTRUCTIONS,
DOWNLOAD THE
INSTALLATION APP



THE MASTERS SCHOOL - PERIMETER DRAIN

DOBB'S FERRY, NY

DC-780 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH DC-780.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS.
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 LBS/IN/IN, AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
 - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
 - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
 - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF THE DC-780 CHAMBER SYSTEM

- STORMTECH DC-780 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH DC-780 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
 - STONESHOOTER LOCATED OFF THE CHAMBER BED.
 - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
 - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- MAINTAIN MINIMUM - 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4-2" (20-50 mm).
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
- ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.


NOTES FOR CONSTRUCTION EQUIPMENT


- STORMTECH DC-780 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- THE USE OF CONSTRUCTION EQUIPMENT OVER DC-780 CHAMBERS IS LIMITED:
 - NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
 - NO RUBBER Tired LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
 - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.

USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.

PROPOSED LAYOUT		CONCEPTUAL ELEVATIONS		PART TYPE			ITEM ON LAYOUT		DESCRIPTION		*INVERT ABOVE BASE OF CHAMBER	
										INVERT*	MAX FLOW	
4	STORMTECH DC-780 CHAMBERS	MAXIMUM ALLOWABLE GRADE (TOP OF PAVEMENT/UNPAVED):	15.25	PREFABRICATED END CAP	A	24" BOTTOM PREFABRICATED END CAP, PART#: SC740EPE24BR / TYP OF ALL 24" ISOLATOR ROW PLUS CONNECTIONS	0.10"					
4	STORMTECH DC-780 END CAPS	MINIMUM ALLOWABLE GRADE (UNPAVED WITH TRAFFIC):	5.25									
6	STONE ABOVE (in)	MINIMUM ALLOWABLE GRADE (UNPAVED NO TRAFFIC):	4.75	MANIFOLD	B	12" x 12" TOP MANIFOLD, ADS N-12	12.50"					
9	STONE BELOW (in)	MINIMUM ALLOWABLE GRADE (TOP OF RIGID CONCRETE PAVEMENT):	4.75	NYLOPLAST (INLET W/ ISO PLUS ROW)	C	30" DIAMETER (24.00" SUMP MIN)						
40	STONE VOID	MINIMUM ALLOWABLE GRADE (BASE OF FLEXIBLE PAVEMENT):	4.75									
	INSTALLED SYSTEM VOLUME (CF) (PERIMETER STONE INCLUDED)	TOP OF STONE:	3.75									
470	(COVER STONE INCLUDED)	TOP OF DC-780 CHAMBER:	3.25									
	(BASE STONE INCLUDED)	12" x 12" TOP MANIFOLD INVERT:	1.79									
239	SYSTEM AREA (SF)	24" ISOLATOR ROW PLUS INVERT:	0.76									
65.5	SYSTEM PERIMETER (ft)	BOTTOM OF DC-780 CHAMBER:	0.75									
		BOTTOM OF STONE:	0.00								2.3 CFS IN	



 ISOLATOR ROW PLUS (SEE DETAIL)

 PLACE MINIMUM 12.50' OF ADSPLUS125 WOVEN GEOTEXTILE OVER BEDDING STONE AND UNDERNEATH CHAMBER FEET FOR SCOUR PROTECTION AT ALL CHAMBER INLET ROWS

 BED LIMITS

NOTES

- MANIFOLD SIZE TO BE DETERMINED BY SITE DESIGN ENGINEER. SEE TECH NOTE #6.32 FOR MANIFOLD SIZING GUIDANCE.
- DUE TO THE ADAPTATION OF THIS CHAMBER SYSTEM TO SPECIFIC SITE AND DESIGN CONSTRAINTS, IT MAY BE NECESSARY TO CUT AND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD COMPONENTS IN THE FIELD.
- THE SITE DESIGN ENGINEER MUST REVIEW ELEVATIONS AND IF NECESSARY ADJUST GRADING TO ENSURE THE CHAMBER COVER REQUIREMENTS ARE MET.
- THIS CHAMBER SYSTEM WAS DESIGNED WITHOUT SITE-SPECIFIC INFORMATION ON SOIL CONDITIONS OR BEARING CAPACITY. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR DETERMINING THE SUITABILITY OF THE SOIL AND PROVIDING THE BEARING CAPACITY OF THE INSITU SOILS. THE BASE STONE DEPTH MAY BE INCREASED OR DECREASED ONCE THIS INFORMATION IS PROVIDED.
- **NOT FOR CONSTRUCTION:** THIS LAYOUT IS FOR DIMENSIONAL PURPOSES ONLY TO PROVE CONCEPT & THE REQUIRED STORAGE VOLUME CAN BE ACHIEVED ON SITE.

THE MASTERS SCHOOL - PERIMETER DRAIN DOBBS FERRY, NY

DRAWN: JP
CHECKED: N/A

DATE: _____ PROJECT #: _____

REV	DRW	CHK	DESCRIPTION

StormTech®
Chamber System
888-892-2694 | WWW.STORMTECH.COM

4640 TRUEEMAN BLVD
HILLIARD, OH 43026
1-800-733-7473



THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCTS DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.


SHEET
2 OF 6

ACCEPTABLE FILL MATERIALS: STORMTECH DC-780 CHAMBER SYSTEMS

MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	AASHTO M145' A-1, A-2-4, A-3 OR AASHTO M43' 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).
B	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	AASHTO M43' 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	AASHTO M43' 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. ^{2,3}

PLEASE NOTE:

- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
- STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 9" (230 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
- ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.



NOTES:

- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- DC-780 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 LBS/IN² (IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

THE MASTERS SCHOOL -
PERIMETER DRAIN
DOBB'S FERRY, NY

DESCRIPTION	REV	DRW	CHK	DATE	PROJECT #	CHECKED: N/A

StormTech®
Chamber System

888-892-2694 | WWW.STORMTECH.COM


4640 TRUEMAN BLVD
HILLIARD, OH 43026
1-800-733-7473

SHEET
3 OF 6


THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THE DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT IS SPECIFIED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS AND PROJECT REQUIREMENTS.

DC-780 TECHNICAL SPECIFICATION

NTS




ACCEPTS 4" (100 mm) SCH 40 PVC PIPE FOR INSPECTION PORT. FOR PIPE SIZES LARGER THAN 4" (100 mm) UP TO 10" (250 mm) USE INSERTA TEE CONNECTION CENTERED ON A CHAMBER CREST CORRUGATION



NOMINAL CHAMBER SPECIFICATIONS

SIZE (W X H X INSTALLED LENGTH)	51.0" X 30.0" X 85.4"	(1295 mm X 762 mm X 2169 mm)
CHAMBER STORAGE	46.2 CUBIC FEET	(1.30 m ³)
MINIMUM INSTALLED STORAGE*	78.4 CUBIC FEET	(2.20 m ³)
WEIGHT	75.0 lbs.	(33.6 kg)

*ASSUMES 6" (152 mm) STONE ABOVE, 9" (229 mm) BELOW, AND 6" (152 mm) BETWEEN CHAMBERS



STUBS AT BOTTOM OF END CAP FOR PART NUMBERS ENDING WITH "B"
STUBS AT TOP OF END CAP FOR PART NUMBERS ENDING WITH "T"

PART #	STUB	A	B	C
SC740EPE06T / SC740EPE06TPC			18.5" (470 mm)	---
SC740EPE06B / SC740EPE06BPC	6" (150 mm)	10.9" (277 mm)	---	0.5" (13 mm)
SC740EPE08T / SC740EPE08TPC			16.5" (419 mm)	---
SC740EPE08B / SC740EPE08BPC	8" (200 mm)	12.2" (310 mm)	---	0.6" (15 mm)
SC740EPE10T / SC740EPE10TPC			14.5" (368 mm)	---
SC740EPE10B / SC740EPE10BPC	10" (250 mm)	13.4" (340 mm)	---	0.7" (18 mm)
SC740EPE12T / SC740EPE12TPC			12.5" (318 mm)	---
SC740EPE12B / SC740EPE12BPC	12" (300 mm)	14.7" (373 mm)	---	1.2" (30 mm)
SC740EPE15T / SC740EPE15TPC			9.0" (229 mm)	---
SC740EPE15B / SC740EPE15BPC	15" (375 mm)	18.4" (467 mm)	---	1.3" (33 mm)
SC740EPE18T / SC740EPE18TPC			5.0" (127 mm)	---
SC740EPE18B / SC740EPE18BPC	18" (450 mm)	19.7" (500 mm)	---	1.6" (41 mm)
SC740EPE24B*	24" (600 mm)	18.5" (470 mm)	---	0.1" (3 mm)

ALL STUBS, EXCEPT FOR THE SC740EPE24B ARE PLACED AT BOTTOM OF END CAP SUCH THAT THE OUTSIDE DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.


* FOR THE SC740EPE24B THE 24" (600 mm) STUB LIES BELOW THE BOTTOM OF THE END CAP APPROXIMATELY 1.75" (44 mm). BACKFILL MATERIAL SHOULD BE REMOVED FROM BELOW THE N-12 STUB SO THAT THE FITTING SITS LEVEL.

NOTE: ALL DIMENSIONS ARE NOMINAL

	THE MASTERS SCHOOL - PERIMETER DRAIN DOBBS FERRY, NY				
REV	DRAW	CHK	DATE	PROJECT #	CHECKED
					N/A
StormTech Chamber System			888-892-2694 WWW.STORMTECH.COM		
4640 TRUEMAN BLVD HILLIARD, OH 43026 1-800-733-7473			THIS DRAWING HAS BEEN PREPARED BY AN UNLICENSED PERSON OR FIRM. THE USER ASSUMES ALL RESPONSIBILITY FOR THE ACCURACY OF THE INFORMATION SHOWN HEREON. THE USER ASSUMES ALL RESPONSIBILITY FOR THE ACCURACY OF THE INFORMATION SHOWN HEREON. THE USER ASSUMES ALL RESPONSIBILITY FOR THE ACCURACY OF THE INFORMATION SHOWN HEREON.		
SHEET					
5 OF 6					

NYLOPLAST DRAIN BASIN

NTS



NOTES

1. 8-30" (200-750 mm) GRATES/SOLID COVERS SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
2. 12-30" (300-750 mm) FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
3. DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS
4. DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D3212 FOR CORRUGATED HDPE (ADS & HANCOR DUAL WALL) & SDR 35 PVC
5. FOR COMPLETE DESIGN AND PRODUCT INFORMATION: WWW.NYLOPLAST-US.COM
6. TO ORDER CALL: 800-821-6710

A	PART #	GRATE/SOLID COVER OPTIONS		
8" (200 mm)	2808AG	PEDESTRIAN LIGHT DUTY	STANDARD LIGHT DUTY	SOLID LIGHT DUTY
10" (250 mm)	2810AG	PEDESTRIAN LIGHT DUTY	STANDARD LIGHT DUTY	SOLID LIGHT DUTY
12" (300 mm)	2812AG	PEDESTRIAN AASHTO H-10	STANDARD AASHTO H-20	SOLID AASHTO H-20
15" (375 mm)	2815AG	PEDESTRIAN AASHTO H-10	STANDARD AASHTO H-20	SOLID AASHTO H-20
18" (450 mm)	2818AG	PEDESTRIAN AASHTO H-10	STANDARD AASHTO H-20	SOLID AASHTO H-20
24" (600 mm)	2824AG	PEDESTRIAN AASHTO H-10	STANDARD AASHTO H-20	SOLID AASHTO H-20
30" (750 mm)	2830AG	PEDESTRIAN AASHTO H-20	STANDARD AASHTO H-20	SOLID AASHTO H-20

	DESCRIPTION				
REV	DRW	CHK	DATE	PROJECT #	CHECKED
<p>Nyloplast[®]</p> <p>770-932-2443 WWW.NYLOPLAST-US.COM</p>					
<p>4640 TRUENAN BLVD LURAY, OH 43026 1-800-735-7473</p>					
<p>ADS</p>					
<p>THE DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO DATE. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND REGULATIONS. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND REGULATIONS. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND REGULATIONS.</p>					
<p>THE MASTERS SCHOOL - PERIMETER DRAIN DOBBS FERRY, NY</p>					
<p>DRAWN: JP</p>					
<p>CHECKED: N/A</p>					
<p>REVIEW THE DRAWING PRIOR TO CONSTRUCTION. IT IS THE USER'S RESPONSIBILITY TO OBTAIN ALL NECESSARY PERMITS AND REGULATIONS.</p>					
<p>SHEET 6 OF 6</p>					

STORMTECH MC-3500 CHAMBER

Designed to meet the most stringent industry performance standards for superior structural integrity while providing designers with a cost-effective method to save valuable land and protect water resources. The StormTech system is designed primarily to be used under parking lots, thus maximizing land usage for private (commercial) and public applications. StormTech chambers can also be used in conjunction with Green Infrastructure, thus enhancing the performance and extending the service life of these practices.



STORMTECH MC-3500 CHAMBER (not to scale)

Nominal Chamber Specifications

Size (L x W x H)
 90" x 77" x 45"
 2,286 mm x 1,956 mm x 1,143 mm

Chamber Storage
 109.9 ft³ (3.11 m³)

Min. Installed Storage*
 175.0 ft³ (4.96 m³)

Weight
 134 lbs (60.8 kg)

Shipping
 15 chambers/pallet
 7 end caps/pallet
 7 pallets/truck

*Assumes a minimum of 12" (300 mm) of stone above, 9" (230 mm) of stone below chambers, 6" (150 mm) of stone between chambers/end caps and 40% stone porosity.

STORMTECH MC-3500 END CAP (not to scale)

Nominal End Cap Specifications



Size (L x W x H)
 26.5" x 71" x 45.1"
 673 mm x 1,803 mm x 1,145 mm

End Cap Storage
 14.9 ft³ (0.42 m³)

Min. Installed Storage*
 45.1ft³ (1.28 m³)

Weight
 49 lbs (22.2 kg)

*Assumes a minimum of 12" (300 mm) of stone above, 9" (230 mm) of stone below, 6" (150 mm) of stone perimeter, 6" (150 mm) of stone between chambers/end caps and 40% stone porosity.



*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 24" (600 mm).

MC-3500 CHAMBER SPECIFICATION

STORAGE VOLUME PER CHAMBER FT³ (M³)

	Bare Chamber Storage ft ³ (m ³)	Chamber and Stone Foundation Depth in. (mm)			
		9" (230 mm)	12" (300 mm)	15" (375 mm)	18" (450 mm)
MC-3500 Chamber	109.9 (3.11)	175.0 (4.96)	179.9 (5.09)	184.9 (5.24)	189.9 (5.38)
MC-3500 End Cap	14.9 (.42)	45.1 (1.28)	46.6 (1.32)	48.3 (1.37)	49.9 (1.41)

Note: Assumes 6" (150 mm) row spacing, 40% stone porosity, 12" (300 mm) stone above and includes the bare chamber/end cap volume.

AMOUNT OF STONE PER CHAMBER

ENGLISH TONS (yds ³)	Stone Foundation Depth			
	9"	12"	15"	18"
MC-3500 Chamber	8.5 (6.0)	9.1 (6.5)	9.7 (6.9)	10.4 (7.4)
MC-3500 End Cap	3.9 (2.8)	4.1 (2.9)	4.3 (3.1)	4.5 (3.2)
METRIC KILOGRAMS (m ³)	230 mm	300 mm	375 mm	450 mm
MC-3500 Chamber	7711 (4.6)	8255 (5.0)	8800 (5.3)	9435 (5.7)
MC-3500 End Cap	3538 (2.1)	3719 (2.2)	3901 (2.4)	4082 (2.5)

Note: Assumes 12" (300 mm) of stone above and 6" (150 mm) row spacing and 6" (150 mm) of perimeter stone in front of end caps.

VOLUME EXCAVATION PER CHAMBER YD³ (M³)

	Stone Foundation Depth			
	9" (230 mm)	12" (300 mm)	15" (375mm)	18" (450 mm)
MC-3500 Chamber	11.9 (9.1)	12.4 (9.5)	12.8(9.8)	13.3 (10.2)
MC-3500 End Cap	4.0 (3.1)	4.1 (3.2)	4.3 (3.3)	4.4 (3.4)

Note: Assumes 6" (150 mm) of separation between chamber rows and 24" (600 mm) of cover. The volume of excavation will vary as depth of cover increases.



Working on a project?
Visit us at www.stormtech.com
and utilize the StormTech Design Tool

For more information on the StormTech MC-3500 Chamber and other ADS products, please contact our Customer Service Representatives at 1-800-821-6710

THE MOST **ADVANCED** NAME IN WATER MANAGEMENT SOLUTIONS®

Advanced Drainage Systems, Inc.
4640 Trueman Blvd., Hilliard, OH 43026
1-800-821-6710 www.ads-pipe.com

ADS "Terms and Conditions of Sale" are available on the ADS website, www.ads-pipe.com
The ADS logo and the Green Stripe are registered trademarks of Advanced Drainage Systems, Inc.
StormTech® is a registered trademark of StormTech, Inc.
© 2019 Advanced Drainage Systems, Inc. #5150909 06-19 CS



MC-3500 & MC-4500 Design Manual

StormTech® Chamber Systems for Stormwater Management




THE MOST **ADVANCED** NAME IN WATER MANAGEMENT SOLUTIONS®



StormTech MC-3500 Chamber

MC-3500 Chamber

Designed to meet the most stringent industry performance standards for superior structural integrity while providing designers with a cost-effective method to save valuable land and protect water resources. The StormTech system is designed primarily to be used under parking lots, thus maximizing land usage for commercial and municipal applications.



StormTech MC-3500 Chamber (not to scale)

Nominal Chamber Specifications

Size (L x W x H)	90" (2286 mm) x 77" (1956 mm) x 45" (1143 mm)
Chamber Storage	109.9 ft ³ (3.11 m ³)
Min. Installed Storage*	175.0 ft ³ (4.96 m ³)
Weight	134 lbs (60.8 kg)

*This assumes a minimum of 12" (300 mm) of stone above, 6" (150 mm) of stone between chambers/end caps and 40% stone porosity.

StormTech MC-3500 End Cap (not to scale)


Nominal Chamber Specifications

Size (L x W x H)	26.5" (673 mm) x 71" (1803 mm) x 45.1" (1145 mm)
Chamber Storage	14.9 ft ³ (0.42 m ³)
Min. Installed Storage*	45.1 ft ³ (1.28 m ³)
Weight	49 lbs (22.2 kg)

*This assumes a minimum of 12" (300 mm) of stone above, 9" (230 mm) of stone below, 6" (150 mm) of stone perimeter, 6" (150 mm) between chambers/end caps and 40% stone porosity.

Shipping

- 15 chambers/pallet
- 16 end caps/pallet
- 7 pallets/truck



StormTech MC-3500 Chamber

Storage Volume Per Chamber/End Cap ft³ (m³)

	Bare Unit Storage ft ³ (m ³)	Chamber/End Cap and Stone Volume — Stone Foundation Depth in. (mm)			
		9	12	15	18
		(230)	(300)	(375)	(450)
MC-3500 Chamber	109.9 (3.11)	175.0 (4.96)	179.9 (5.09)	184.9 (5.24)	189.9 (5.38)
MC-3500 End Cap	14.9 (0.42)	45.1 (1.28)	46.6 (1.32)	48.3 (1.37)	49.9 (1.41)

NOTE: Assumes 6" (150 mm) row spacing, 40% stone porosity, 12" (300 mm) stone above and includes the bare chamber/end cap volume. End cap volume assumes 6" (150 mm) stone perimeter.

Amount of Stone Per Chamber

ENGLISH tons (yd ³)	Stone Foundation Depth			
	9"	12"	15"	18"
MC-3500	8.5 (6.0)	9.1 (6.5)	9.7 (6.9)	10.4 (7.4)
End Cap	3.9 (2.8)	4.1 (2.9)	4.3 (3.1)	4.5 (3.2)
METRIC kg (m ³)	230 mm	300 mm	375 mm	450 mm
MC-3500	7711 (4.6)	8255 (5.0)	8800 (5.3)	9435 (5.7)
End Cap	3538 (2.1)	3719 (2.2)	3901 (2.4)	4082 (2.5)

NOTE: Assumes 12" (300 mm) of stone above, and 6" (150 mm) row spacing, and 6" (150 mm) of perimeter stone in front of end caps.


Volume of Excavation Per Chamber/End Cap yd³ (m³)

	Stone Foundation Depth			
	9" (230 mm)	12" (300 mm)	15" (375 mm)	18" (450 mm)
MC-3500	11.9 (9.1)	12.4 (9.5)	12.8 (9.8)	13.3 (10.2)
End Cap	4.0 (3.1)	4.1 (3.2)	4.3 (3.3)	4.4 (3.4)

NOTE: Assumes 6" (2150 mm) separation between chamber rows and 24" (600 mm) of cover. The volume of excavation will vary as the depth of cover increases.



General Cross Section




Special applications will be considered on a project by project basis. Please contact our application department should you have a unique application for our team to evaluate.

StormTech MC-4500 Chamber

MC-4500 Chamber

Designed to meet the most stringent industry performance standards for superior structural integrity while providing designers with a cost-effective method to save valuable land and protect water resources. The StormTech system is designed primarily to be used under parking lots, thus maximizing land usage for commercial and municipal applications.



StormTech MC-4500 Chamber (not to scale)

Nominal Chamber Specifications	
Size (L x W x H)	52" (1321 mm) x 100" (2540 mm) x 60" (1524 mm)
Chamber Storage	106.5 ft ³ (3.01 m ³)
Min. Installed Storage*	162.6 ft ³ (4.60 m ³)
Weight	120 lbs (54.4 kg)

*This assumes a minimum of 12" (300 mm) of stone above, 9" (230 mm) of stone below chambers, 9" (230 mm) between chambers/end caps and 40% stone porosity.

StormTech MC-4500 End Cap (not to scale)


Nominal Chamber Specifications	
Size (L x W x H)	35.1" (891 mm) x 90.2" (2291 mm) x 59.4" (1509 mm)
Chamber Storage	35.7 ft ³ (1.01 m ³)
Min. Installed Storage*	108.7 ft ³ (3.08 m ³)
Weight	120 lbs (54.4 kg)

*This assumes a minimum of 12" (300 mm) of stone above, 9" (230 mm) of stone below, 6" (150 mm) of stone perimeter, 9" (230 mm) between chambers/end caps and 40% stone porosity.

Shipping

7 chambers/pallet

11 pallets/truck



StormTech MC-4500 Chamber

Storage Volume Per Chamber/End Cap ft³ (m³)

	Bare Unit Storage ft ³ (m ³)	Chamber/End Cap and Stone Volume — Stone Foundation Depth in. (mm)			
		9	12	15	18
		(230)	(300)	(375)	(450)
MC-4500 Chamber	106.5 (3.02)	162.6 (4.60)	166.3 (4.71)	169.9 (4.81)	173.6 (4.91)
MC-4500 End Cap	35.7 (1.01)	108.7 (3.08)	111.9 (3.17)	115.2 (3.26)	118.4 (3.35)

NOTE: Assumes 9" (230 mm) row spacing, 40% stone porosity, 12" (300 mm) stone above and includes the bare chamber/end cap volume. End cap volume assumes 12" (300 mm) stone perimeter.

Amount of Stone Per Chamber


ENGLISH tons (yd ³)	Stone Foundation Depth			
	9"	12"	15"	18"
MC-4500	7.4 (5.2)	7.8 (5.5)	8.3 (5.9)	8.8 (6.2)
End Cap	9.6 (6.8)	10.0 (7.1)	10.4 (7.4)	10.9 (7.7)
METRIC kg (m ³)	230 mm	300 mm	375 mm	450 mm
MC-4500	6681 (4.0)	7117 (4.2)	7552 (4.5)	7987 (4.7)
End Cap	8691 (5.2)	9075 (5.4)	9460 (5.6)	9845 (5.9)

NOTE: Assumes 12" (300 mm) of stone above, and 9" (230 mm) row spacing, and 12" (300 mm) of perimeter stone in front of end caps.


Volume of Excavation Per Chamber/End Cap yd³ (m³)

	Stone Foundation Depth			
	9" (230 mm)	12" (300 mm)	15" (375 mm)	18" (450 mm)
MC-4500	10.5 (8.0)	10.8 (8.3)	11.2 (8.5)	11.5 (8.8)
End Cap	9.3 (7.1)	9.6 (7.3)	9.9 (7.6)	10.2 (7.8)

NOTE: Assumes 9" (230 mm) separation between chamber rows, 12" (300 mm) of perimeter in front of end caps, and 24" (600 mm) of cover. The volume of excavation will vary as the depth of cover increases.



General Cross Section



Special applications will be considered on a project by project basis. Please contact our application department should you have a unique application for our team to evaluate.

1.0 Product Information



1.1 PRODUCT DESIGN

StormTech's commitment to thorough product testing programs, materials evaluation and adherence to national standards has resulted in two more superior products. Like other StormTech chambers, the MC-3500 and MC-4500 are designed to meet the full scope of design requirements of the American Society of Testing Materials (ASTM) International specification F2787 "Standard Practice for Structural Design of Thermoplastic Corrugated Wall Stormwater Collection Chambers" and produced to the requirements of the ASTM F 2418 "Standard Specification for Polypropylene (PP) Corrugated Stormwater Collection Chambers".

The StormTech MC-3500 and MC-4500 chambers provide the full AASHTO safety factors for live loads and permanent earth loads. The ASTM F 2787 standard provides specific guidance on how to design thermoplastic chambers in accordance with AASHTO Section 12.12. of the AASHTO LRFD Bridge Design Specifications. ASTM F 2787 requires that the safety factors included in the AASHTO guidance are achieved as a prerequisite to meeting ASTM F 2418. The three standards provide both the assurance of product quality and safe structural design.

The design of larger chambers in the same tradition of our other chambers required the collaboration of experts in soil-structure interaction, plastics and manufacturing. Years of extensive research, including laboratory testing and field verification, were required to produce chambers that are ready to meet both the rigors of installation and the longevity expected by engineers and owners.

This Design Manual provides the details and specifications necessary for consulting engineers to design stormwater management systems using the MC-3500 and MC-4500 chambers. It provides specifications for storage capacities, layout dimensions as well as requirements for design to ensure a long service life. The basic design concepts for foundation and backfill materials, subgrade bearing capacities and row spacing remain equally as pertinent for the MC-3500 and MC-4500 as the SC-740, SC-310 and DC-780 chamber systems. However, since many design values and dimensional requirements are different for these larger chambers than the SC-740, SC-310 and DC-780 chambers, design manuals and installation instructions are not interchangeable.

This manual includes only those details, dimensions, cover limits, etc for the MC-3500 and MC-4500 and is intended to be a stand-alone design guide for the MC-3500 and MC-4500 chambers. A Construction Guide specifically for these two chamber models has also been published.

1.2 TECHNICAL SUPPORT

The StormTech Technical Services Department is available to assist the engineer with the layout of MC-3500 and MC-4500 chamber systems and answer questions regarding all the StormTech chamber models. Call the Technical Services Department, email us at info@stormtech.com or contact your local StormTech representative.

1.3 MC-3500 AND MC-4500 CHAMBERS

All StormTech chambers are designed to the full scope of AASHTO requirements without repeating end walls or other structural reinforcing. StormTech's continuously curved, elliptical arch and the surrounding angular backfill are the key components of the structural system. With the addition of patent pending integral stiffening ribs (**Figure 5**), the MC-3500 and MC-4500 are assured to provide a long, safe service life. Like other StormTech chambers, the MC-3500 and MC-4500 are produced from high quality, impact modified resins which are tested for short-term and long-term mechanical properties.



With all StormTech chambers, one chamber type is used for the start, middle and end of rows. Rows are formed by overlapping the upper joint corrugation of the next chamber over the lower joint corrugation of the previous chamber (**Figure 6**).

1.4 CHAMBER JOINTS

All StormTech chambers are designed with an optimized joining system. The height and width of the end corrugations have been designed to provide the required structural safety factors while providing an unobstructed flow path down each row.

To assist the contractor, StormTech chambers are molded with simple assembly instructions and arrows that indicate the direction in which to build rows. The corrugation valley immediately adjacent to the lower joint corrugation is marked "Overlap Here - Lower Joint." The corrugation valley immediately adjacent to the upper joint corrugation is marked "Build This Direction - Upper Joint."

Two people can safely and efficiently carry and place chambers without cumbersome connectors, special tools or heavy equipment. Each row of chambers must begin and end with a joint corrugation. Since joint corrugations are of a different size than the corrugations along the body of the chamber, chambers cannot be field cut and installed. Only whole MC-3500 and MC-4500 chambers can be used. For system layout assistance contact StormTech.

1.5 MC-3500 AND MC-4500 END CAPS

The MC-3500 and MC-4500 end caps are easy to install. These end caps are designed with a corrugation joint that fits over the top of either end of the chamber. The end cap joint is simply set over the top of either the upper or lower chamber joint corrugations (**Figure 7**).

The MC-3500 end cap has pipe cutting guides for 12"-24" (300 mm-600 mm) top inverts (**Figure 9**).

The MC-4500 end cap has pipe cutting guides for 12"-42" (300 mm-1050 mm) bottom inverts and 12"-24" (300 mm-600 mm) top inverts (**Figure 8**).

Standard and custom pre-cored end caps are available. Pre-cored end caps, 18" in diameter and larger include a welded crown plate.

FIGURE 5—Chamber and End Cap Components




FIGURE 6—Chamber Joint Overlap




FIGURE 7—End Cap Joint Overlap




FIGURE 8—MC-4500 End Cap Inverts





FIGURE 9—MC-3500 End Cap Inverts




2.0 Foundations for Chambers

2.1 FOUNDATION REQUIREMENTS

StormTech chamber systems can be installed in various soil types. The subgrade bearing capacity and the cover height over the chambers determine the required depth of clean, crushed, angular foundation stone below the chambers. Foundation stone, also called bedding, is the stone between the subgrade soils and the feet of the chamber. Flexible structures are designed to transfer a significant portion of both live and dead loads through the surrounding soils. Chamber systems accomplish this by creating load paths through the columns of embedment stone between and around the rows of chambers. This creates load concentrations at the base of the columns between the rows. The foundation stone spreads out the concentrated loads to distributed loads that can be supported by the subgrade soils.

Since increasing the cover height (top of chamber to finished grade) causes increasing soil load, a greater depth of foundation stone is necessary to distribute the load to the subgrade soils. **Table 1** and **2** specify the minimum required foundation depths for varying cover heights and allowable subgrade bearing capacities. These tables are based on StormTech service loads. The minimum required foundation depth is 9" (230 mm) for both chambers.



2.2 WEAKER SOILS

StormTech has not provided guidance for subgrade bearing capacities less than 2000 pounds per square foot [(2.0 ksf) (96 kPa)]. These soils are often highly variable, may contain organic materials and could be more sensitive to moisture. A geotechnical engineer must be consulted if soils with bearing capacities less than 2000 psf (96 kPa) are present.

2.0 Foundations for Chambers


TABLE 1—MC-3500 Minimum Required Foundation Depth in inches (millimeters)

Assumes 9" (230 mm) row spacing.

Cover Hgt. ft. (m)	Minimum Bearing Resistance for Service Loads ksf (kPa)																								
	4.4 (211)	4.3 (206)	4.2 (201)	4.1 (196)	4.0 (192)	3.9 (187)	3.8 (182)	3.7 (177)	3.6 (172)	3.5 (166)	3.4 (163)	3.3 (158)	3.2 (153)	3.1 (148)	3.0 (144)	2.9 (139)	2.8 (134)	2.7 (129)	2.6 (124)	2.5 (120)	2.4 (115)	2.3 (110)	2.2 (105)	2.1 (101)	2.0 (96)
2.0 (0.61)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)
2.5 (0.76)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)
3.0 (0.91)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)
3.5 (1.07)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	24 (600)	24 (600)
4.0 (1.22)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)
4.5 (1.37)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)
5.0 (1.52)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)
5.5 (1.68)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)	30 (750)
6.0 (1.83)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)	30 (750)	30 (750)
6.5 (1.98)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)	30 (750)	30 (750)	30 (750)
7.0 (2.13)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)	30 (750)	30 (750)	30 (750)	36 (900)
7.5 (2.30)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)	30 (750)	30 (750)	30 (750)	36 (900)	36 (900)
8.0 (2.44)	9 (230)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)	30 (750)	30 (750)	36 (900)	36 (900)	36 (900)	36 (900)

NOTE: The design engineer is solely responsible for assessing the bearing resistance (allowable bearing capacity) of the subgrade soils and determining the depth of foundation stone. Subgrade bearing resistance should be assessed with consideration for the range of soil moisture conditions expected under a stormwater system.

FIGURE 10A—MC-3500 Structural Cross Section Detail (Not to Scale)



Special applications will be considered on a project by project basis. Please contact our applications department should you have a unique application for our team to evaluate.

2.0 Foundations for Chambers


TABLE 2—MC-4500 Minimum Required Foundation Depth in inches (millimeters)

Assumes 9" (230 mm) row spacing.

Cover Hgt. ft. (m)	Minimum Bearing Resistance for Service Loads ksf (kPa)																										
	4.4 (211)	4.3 (206)	4.2 (201)	4.1 (196)	4.0 (192)	3.9 (187)	3.8 (182)	3.7 (177)	3.6 (172)	3.5 (168)	3.4 (163)	3.3 (158)	3.2 (153)	3.1 (148)	3.0 (144)	2.9 (139)	2.8 (134)	2.7 (129)	2.6 (124)	2.5 (120)	2.4 (115)	2.3 (110)	2.2 (105)	2.1 (101)	2.0 (98)		
2.0 (0.61)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	18 (450)	
2.5 (0.76)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	18 (450)	24 (600)
3.0 (0.91)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	18 (450)	24 (600)
3.5 (1.07)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	24 (600)	24 (600)
4.0 (1.22)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	24 (600)	24 (600)
4.5 (1.37)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	24 (600)	24 (600)
5.0 (1.52)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	24 (600)	24 (600)
5.5 (1.68)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	24 (600)	24 (600)
6.0 (1.83)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	24 (600)	24 (600)
6.5 (1.98)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	9 (230)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	18 (450)	24 (600)	24 (600)
7.0 (2.13)	12 (300)	12 (300)	12 (300)	12 (300)	15 (375)	15 (375)	15 (375)	15 (375)	15 (375)	18 (450)	18 (450)	18 (450)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	24 (600)	30 (750)	30 (750)	30 (750)	30 (750)	36 (900)	36 (900)	42 (1050)	42 (1050)

NOTE: The design engineer is solely responsible for assessing the bearing resistance (allowable bearing capacity) of the subgrade soils and determining the depth of foundation stone. Subgrade bearing resistance should be assessed with consideration for the range of soil moisture conditions expected under a stormwater system.

FIGURE 10B—MC-4500 Structural Cross Section Detail (Not to Scale)



Special applications will be considered on a project by project basis. Please contact our applications department should you have a unique application for our team to evaluate.

3.0 Required Materials/Row Separation



3.1 Foundation and Embedment Stone

The stone surrounding the chambers consists of the foundation stone below the chambers and embedment stone surrounding the chambers. The foundation stone and embedment stone are important components of the structural system and also provide open void space for stormwater storage. Table 3 provides the stone specifications that achieve both structural requirements and a porosity of 40% for stormwater storage. Figure 11 specifies the extents of each backfill stone location.


TABLE 3—Acceptable Fill Materials

MATERIAL LOCATION	DESCRIPTION	AASHTO DESIGNATION	COMPACTION/DENSITY REQUIREMENT
D FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 24" (600 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 ¹ A-1, A-2, A-3 OR AASHTO M43 ¹ 3, 3S7, 4, 4E7, 5, 5E, 57, 6, 67, 68, 7, 7E, 8, 8S, 9, 10	BEGIN COMPACTIONS AFTER 24" (600 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 12" (300 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL-GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS.
B EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FORM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	NO COMPACTION REQUIRED
A FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. ¹

PLEASE NOTE:

- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
- STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 9" (230 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.

FIGURE 11—Fill Material Locations



Once layer 'C' is placed, any soil/material can be placed in layer 'D' up to the finished grade. Most pavement subbase soils can be used to replace the materials of layer 'C' or 'D' at the design engineer's discretion.

3.0 Required Materials/Row Separation

3.2 FILL ABOVE CHAMBERS

Refer to **Table 3** and **Figure 11** for acceptable fill material above the clean, crushed, angular stone. StormTech requires a minimum of 24" (600 mm) from the top of the chamber to the bottom of flexible pavement. For non-paved installations where rutting from vehicles may occur StormTech requires a minimum of 30" (750 mm) from top of chamber to finished grade.

3.3 GEOTEXTILE SEPARATION

A non-woven geotextile meeting AASHTO M288 Class 2 separation requirements must be installed to completely envelope the system and prevent soil intrusion into the crushed, angular stone. Overlap adjacent geotextile rolls per AASHTO M288 separation guidelines. Contact StormTech for a list of acceptable geotextiles.

3.4 PARALLEL ROW SEPARATION/ PERPENDICULAR BED SEPARATION

Parallel Row Separation

The minimum installed spacing between parallel rows after backfilling is 9" (230 mm) for the MC-4500 chambers and 6" (150mm) for the MC-3500 (measurement taken between the outside edges of the feet). Spacers may be used for layout convenience. Row spacing wider than the minimum spacing above may be specified.

Perpendicular Bed Separation

When beds are laid perpendicular to each other, a minimum installed spacing of 36" (900 mm) between beds is required.

3.5 Special Structural Designs

StormTech engineers may provide special structural designs to enable deeper cover depths or increase the capacity to carry higher live loads. Special designs may utilize the additional strength that can be achieved by compaction of embedment stone or by increasing the spacing between rows.

Increasing the spacing between chamber rows may also facilitate the application of StormTech chambers with either less foundation stone or with weaker subgrade soils. This may be a good option where vertical restrictions on site prevent the use of a deeper foundation.

Contact ADS Engineering Services for more information on special structural designs.



System Cross Section



Minimum Row Spacing

4.1 GENERAL

StormTech subsurface chamber systems offer the flexibility for a variety of inlet and outlet configurations. Contact the StormTech Technical Services Department or your local StormTech representative for assistance configuring inlet and outlet connections.

The open graded stone around and under the chambers provides a significant conveyance capacity ranging from approximately 0.8 cfs (23 l/s) to 13 cfs (368 l/s) per MC-3500 chamber and 0.54 cfs (15 l/s) to 8.5 cfs (240 l/s) for the MC-4500 chamber. The actual conveyance capacity is dependent upon stone size, depth of foundation stone and head of water. Although the high conveyance capacity of the open graded stone is an important component of the flow network, StormTech recommends that a system of inlet and outlet manifolds be designed to distribute and convey the peak flow through the chamber system.

It is the responsibility of the design engineer to provide the design flow rates and storage volumes for the stormwater system and to ensure that the final design meets all conveyance and storage requirements. However, StormTech will work with the design engineer to assist with manifold and chamber layouts that meet the design objectives.

4.2 THE ISOLATOR® ROW


The Isolator Row is a patented system that inexpensively captures total suspended solids (TSS) and debris and provides easy access for inspection and maintenance. A double layer of woven geotextile between the bottom of the chambers and the foundation stone provides the filter media that satisfies most contaminant removal objectives. Each installed MC-3500 chamber and MC-3500 end cap provides 42.9 ft² (4.0 m²) and 7.5 ft² (0.7 m²) of bottom filter area respectively. Each installed MC-4500 chamber and MC-4500 end cap provides 30.1 ft² (2.80 m²) and 12.8 ft² (1.19 m²) of bottom filter area respectively.

The Isolator Row can be configured for maintenance objectives or, in some regulatory jurisdictions, for water quality objectives. For water quality applications, Isolator Rows can be sized based on water quality volume or flow rate.

All Isolator Rows require: 1) a manhole for maintenance access, 2) a means of diversion of flows to the Isolator Row and 3) a high flow bypass. Flow diversion can be accomplished by either a weir in the upstream access manhole or simply by feeding the Isolator Row at a lower elevation than the high flow bypass. Contact StormTech for assistance sizing Isolator Rows.


When additional stormwater treatment is required, StormTech systems can be configured using a treatment train approach where other stormwater BMPs are located in series.

FIGURE 12—StormTech Isolator Row Detail



4.0 Hydraulics

FIGURE 13—Typical Inlet Configuration With Isolator Row and Scour Protection



4.3 INLET MANIFOLDS

The primary function of the inlet manifold is to convey and distribute flows to a sufficient number of rows in the chamber bed such that there is ample conveyance capacity to pass the peak flows without creating an unacceptable backwater condition in upstream piping or scour the foundation stone under the chambers.

Manifolds are connected to the end caps either at the top or bottom of the end cap. Standard distances from the base of chamber to the invert of inlet and outlet manifolds connecting to StormTech end caps can be found in table 6. High inlet flow rates from either connection location produce a shear scour potential of the foundation stone. Inlet flows from top inlets also produce impingement scour potential. Scour potential is reduced when standing water is present over the foundation stone. However, for safe design across the wide range of applications, StormTech assumes minimal standing water at the time the design flow occurs.

To minimize scour potential, StormTech recommends the installation of woven scour protection fabric at each inlet row. This enables a protected transition zone from the concentrated flow coming out of the inlet pipe to a uniform flow across the entire width of the chamber for both top and bottom connections.

Allowable flow rates for design are dependent upon: the elevation of inlet pipe, foundation stone size and scour protection. With an appropriate scour protection geotextile installed from the end cap to at least 14.5 ft (4.42 m) in front of the inlet pipe for the MC-3500 and for the MC-4500, for both top and bottom feeds, the flow rates listed in **Table 4** can be used for all StormTech specified foundation stone gradations.

*See StormTech's Tech Sheet #7 for manifold sizing guidance.

Table 4—Allowable Inlet Flows*

Inlet Pipe Diameter Inches (mm)	Allowable Maximum Flow Rate cfs (l/s)
12 (300)	2.48 (70)
15 (375)	3.5 (99)
18 (450)	5.5 (156)
24 (600)	8.5 (241) [MC-3500]
24 (600)	9.5 (269) [MC-4500]

*Assumes appropriate length of scour fabric per section 4.3

Table 5—Maximum Outlet Flow Rate Capacities From StormTech Outlet Manifolds

PIPE DIA.	FLOW (CFS)	FLOW (L/S)
6" (150 mm)	0.4	11.3
8" (200 mm)	0.7	19.8
10" (250 mm)	1.0	28.3
12" (300 mm)	2.0	56.6
15" (375 mm)	2.7	76.5
18" (450 mm)	4.0	113.3
24" (600 mm)	7.0	198.2
30" (750 mm)	11.0	311.5
36" (900 mm)	16.0	453.1
42" (1050 mm)	22.0	623.0
48" (1200 mm)	28.0	792.9

Table 6—Standard Distances From Base of Chamber to Invert of Inlet and Outlet Manifolds on StormTech End Caps

MC-3500 ENDCAPS			
	PIPE DIA.	INV. (IN)	INV. (MM)
TOP	6" (150 mm)	33.21	841
	8" (200 mm)	31.16	789
	10" (250 mm)	29.04	738
	12" (300 mm)	26.36	671
	15" (375 mm)	23.39	594
	18" (450 mm)	20.03	509
BOTTOM	24" (600 mm)	14.48	369
	12" (750 mm)	1.35	34
	15" (900 mm)	1.5	40
	18" (1050 mm)	1.77	46
24" (1200 mm)	2.06	52	
MC-4500 ENDCAPS			
	PIPE DIA.	INV. (IN)	INV. (MM)
TOP	12" (300 mm)	35.69	907
	15" (375 mm)	32.72	831
	18" (450 mm)	29.36	746
	24" (600 mm)	23.05	585
BOTTOM	12" (750 mm)	1.55	34
	15" (900 mm)	1.7	43
	18" (1050 mm)	1.97	50
	24" (1200 mm)	2.26	57

5.0 Cumulative Storage Volumes



4.4 OUTLET MANIFOLDS


The primary function of the outlet manifold is to convey peak flows from the chamber system to the outlet control structure. Outlet manifolds are often sized for attenuated flows. They may be smaller in diameter and have fewer row connections than inlet manifolds. In some applications however, the intent of the outlet piping is to convey an unattenuated bypass flow rate and manifolds may be sized similar to inlet manifolds.

Since chambers are generally flowing at or near full at the time of the peak outlet flow rate, scour is generally not governing and outlet manifold sizing is based on pipe flow equations. In most cases, StormTech recommends that outlet manifolds connect the same rows that are connected to an inlet manifold. This provides a continuous flow path through open conduits to pass the peak flow without dependence on passing peak flows through stone.

The primary function of the underdrains is to draw down water stored in the stone below the invert of the manifold. Underdrains are generally not sized for conveyance of the peak flow.


The maximum outlet flow rate capacities from StormTech outlet manifolds can be found in **Table 5**.

FIGURE 14—Typical Inlet, Outlet and Underdrain Configuration



4.5 INSERTA TEE INLET CONNECTIONS

FIGURE 15—Inserta Tee Detail



CHAMBER	MAX DIAMETER OF INSERTA TEE	HEIGHT FROM BASE OF CHAMBER (X)
MC-3500	12" (250 mm)	6" (150 mm)
MC-4500	12" (250 mm)	8" (200 mm)

INSERTA TEE FITTINGS AVAILABLE FOR SDR 26, SDR 35, SCH 40 IPS GASKETED & SOLVENT WELD, N-12, HP STORM, C-900 OR DUCTILE IRON

NOTE:
PART NUMBERS WILL VARY BASED ON INLET PIPE MATERIALS. CONTACT STORMTECH FOR MORE INFORMATION.

5.0 Cumulative Storage Volumes



Tables 7 and 8 provide cumulative storage volumes for the MC-3500 chamber and end cap. These tables can be used to calculate the stage-storage relationship for the retention or detention system. Digital spreadsheets in which the number of chambers and end caps can be input for quick

cumulative storage calculations are available at www.stormtech.com. For assistance with site-specific calculations or input into routing software, contact the StormTech Technical Services Department.

TABLE 7 – MC-3500 Incremental Storage Volume Per Chamber

Assumes 40% stone porosity. Calculations are based upon a 9" (230 mm) stone base under the chambers, 12" (300 mm) of stone above chambers, and 6" (150 mm) of spacing between chambers.

Depth of Water in System Inches (mm)	Cumulative Chamber Storage ft ³ (m ³)	Total System Cumulative Storage ft ³ (m ³)
66 (1676)	0.00	175.02 (4.956)
65 (1651)	0.00	173.36 (4.909)
64 (1626)	0.00	171.71 (4.862)
63 (1600)	Stone 0.00	170.06 (4.816)
62 (1575)	Cover 0.00	168.41 (4.769)
61 (1549)	0.00	166.76 (4.722)
60 (1524)	0.00	165.10 (4.675)
59 (1499)	0.00	163.45 (4.628)
58 (1473)	0.00	161.80 (4.582)
57 (1448)	0.00	160.15 (4.535)
56 (1422)	0.00	158.49 (4.488)
55 (1397)	0.00	156.84 (4.441)
54 (1372)	109.95 (3.113)	155.19 (4.394)
53 (1346)	109.89 (3.112)	153.50 (4.347)
52 (1321)	109.69 (3.106)	151.73 (4.297)
51 (1295)	109.40 (3.098)	149.91 (4.245)
50 (1270)	109.00 (3.086)	148.01 (4.191)
49 (1245)	108.31 (3.067)	145.95 (4.133)
48 (1219)	107.28 (3.038)	143.68 (4.068)
47 (1194)	106.03 (3.003)	141.28 (4.000)
46 (1168)	104.61 (2.962)	138.77 (3.930)
45 (1143)	103.04 (2.918)	136.17 (3.856)
44 (1118)	101.33 (2.869)	133.50 (3.780)
43 (1092)	99.50 (2.818)	130.75 (3.702)
42 (1067)	97.56 (2.763)	127.93 (3.623)
41 (1041)	95.52 (2.705)	125.06 (3.541)
40 (1016)	93.39 (2.644)	122.12 (3.458)
39 (991)	91.16 (2.581)	119.14 (3.374)
38 (965)	88.86 (2.516)	116.10 (3.288)
37 (940)	86.47 (2.449)	113.02 (3.200)
36 (914)	84.01 (2.379)	109.89 (3.112)
35 (889)	81.49 (2.307)	106.72 (3.022)
34 (864)	78.89 (2.234)	103.51 (2.931)
33 (838)	76.24 (2.159)	100.27 (2.839)

NOTE: Add 1.65 ft³ (0.047 m³) of storage for each additional inch (25 mm) of stone foundation. Contact StormTech for cumulative volume spreadsheets in digital format.

Depth of Water in System Inches (mm)	Cumulative Chamber Storage ft ³ (m ³)	Total System Cumulative Storage ft ³ (m ³)
32 (813)	73.52 (2.082)	96.98 (2.746)
31 (787)	70.75 (2.003)	93.67 (2.652)
30 (762)	67.92 (1.923)	90.32 (2.558)
29 (737)	65.05 (1.842)	86.94 (2.462)
28 (711)	62.12 (1.759)	83.54 (2.366)
27 (686)	59.15 (1.675)	80.10 (2.268)
26 (680)	56.14 (1.590)	76.64 (2.170)
25 (635)	53.09 (1.503)	73.16 (2.072)
24 (610)	49.99 (1.416)	69.65 (1.972)
23 (584)	46.86 (1.327)	66.12 (1.872)
22 (559)	43.70 (1.237)	62.57 (1.772)
21 (533)	40.50 (1.147)	59.00 (1.671)
20 (508)	37.27 (1.055)	55.41 (1.569)
19 (483)	34.01 (0.963)	51.80 (1.467)
18 (457)	30.72 (0.870)	48.17 (1.364)
17 (432)	27.40 (0.776)	44.53 (1.261)
16 (406)	24.05 (0.681)	40.87 (1.157)
15 (381)	20.69 (0.586)	37.20 (1.053)
14 (356)	17.29 (0.490)	33.51 (0.949)
13 (330)	13.88 (0.393)	29.81 (0.844)
12 (305)	10.44 (0.296)	26.09 (0.739)
11 (279)	6.98 (0.198)	22.37 (0.633)
10 (254)	3.51 (0.099)	18.63 (0.527)
9 (229)	0.00	14.87 (0.421)
8 (203)	0.00	13.22 (0.374)
7 (178)	0.00	11.57 (0.328)
6 (152)	Stone 0.00	9.91 (0.281)
5 (127)	Foundation 0.00	8.26 (0.234)
4 (102)	0.00	6.61 (0.187)
3 (76)	0.00	4.96 (0.140)
2 (51)	0.00	3.30 (0.094)
1 (25)	0.00	1.65 (0.047)

5.0 Cumulative Storage Volume



TABLE 8 – MC-3500 Incremental Storage Volume Per End Cap

Assumes 40% stone porosity. Calculations are based upon a 9" (230 mm) stone base under the chambers, 12" (300 mm) of stone above end caps, and 6" (150 mm) of spacing between end caps and 6" (150 mm) of stone perimeter.

Depth of Water in System Inches (mm)	Cumulative End Cap Storage ft ³ (m ³)	Total System Cumulative Storage ft ³ (m ³)	Depth of Water in System Inches (mm)	Cumulative Chamber Storage ft ³ (m ³)	Total System Cumulative Storage ft ³ (m ³)
66 (1676)	0.00	45.10 (1.277)	33 (838)	12.53 (0.355)	24.82 (0.703)
65 (1651)	0.00	44.55 (1.262)	32 (813)	12.18 (0.345)	24.06 (0.681)
64 (1626)	0.00	44.00 (1.246)	31 (787)	11.81 (0.335)	23.30 (0.660)
63 (1600)	Stone 0.00	43.46 (1.231)	30 (762)	11.42 (0.323)	22.53 (0.638)
62 (1575)	Cover 0.00	42.91 (1.215)	29 (737)	11.01 (0.312)	21.75 (0.616)
61 (1549)	0.00	42.36 (1.200)	28 (711)	10.58 (0.300)	20.96 (0.594)
60 (1524)	0.00	41.81 (1.184)	27 (686)	10.13 (0.287)	20.17 (0.571)
59 (1499)	0.00	41.27 (1.169)	26 (660)	9.67 (0.274)	19.37 (0.549)
58 (1473)	0.00	40.72 (1.153)	25 (635)	9.19 (0.260)	18.57 (0.526)
57 (1448)	0.00	40.17 (1.138)	24 (610)	8.70 (0.246)	17.76 (0.503)
56 (1422)	0.00	39.62 (1.122)	23 (584)	8.19 (0.232)	16.94 (0.480)
55 (1397)	0.00	39.08 (1.107)	22 (559)	7.67 (0.217)	16.12 (0.456)
54 (1372)	15.64 (0.443)	38.53 (1.091)	21 (533)	7.13 (0.202)	15.29 (0.433)
53 (1346)	15.64 (0.443)	37.98 (1.076)	20 (508)	6.59 (0.187)	14.45 (0.409)
52 (1321)	15.63 (0.443)	37.42 (1.060)	19 (483)	6.03 (0.171)	13.61 (0.385)
51 (1295)	15.62 (0.442)	36.85 (1.043)	18 (457)	5.46 (0.155)	12.76 (0.361)
50 (1270)	15.60 (0.442)	36.27 (1.027)	17 (432)	4.88 (0.138)	11.91 (0.337)
49 (1245)	15.56 (0.441)	35.68 (1.010)	16 (406)	4.30 (0.122)	11.06 (0.313)
48 (1219)	15.51 (0.439)	35.08 (0.993)	15 (381)	3.70 (0.105)	10.20 (0.289)
47 (1194)	15.44 (0.437)	34.47 (0.976)	14 (356)	3.10 (0.088)	9.33 (0.264)
46 (1168)	15.35 (0.435)	33.85 (0.959)	13 (330)	2.49 (0.071)	8.46 (0.240)
45 (1143)	15.25 (0.432)	33.22 (0.941)	12 (305)	1.88 (0.053)	7.59 (0.215)
44 (1118)	15.13 (0.428)	32.57 (0.922)	11 (279)	1.26 (0.036)	6.71 (0.190)
43 (1092)	14.99 (0.424)	31.91 (0.904)	10 (254)	0.63 (0.018)	5.83 (0.165)
42 (1067)	14.83 (0.420)	31.25 (0.885)	9 (229)	0.00	4.93 (0.139)
41 (1041)	14.65 (0.415)	30.57 (0.866)	8 (203)	0.00	4.38 (0.124)
40 (1016)	14.45 (0.409)	29.88 (0.846)	7 (178)	0.00	3.83 (0.108)
39 (991)	14.24 (0.403)	29.18 (0.826)	6 (152)	Stone 0.00	3.28 (0.093)
38 (965)	14.00 (0.396)	28.48 (0.806)	5 (127)	Foundation 0.00	2.74 (0.077)
37 (948)	13.74 (0.389)	27.76 (0.786)	4 (102)	0.00	2.19 (0.062)
36 (914)	13.47 (0.381)	27.04 (0.766)	3 (76)	0.00	1.64 (0.046)
35 (889)	13.18 (0.373)	26.30 (0.745)	2 (51)	0.00	1.09 (0.031)
34 (864)	12.86 (0.364)	25.56 (0.724)	1 (25)	0.00	0.55 (0.015)

NOTE: Add 0.56 ft³ (0.016 m³) of storage for each additional inch (25 mm) of stone foundation. Contact StormTech for cumulative volume spreadsheets in digital format.

5.0 Cumulative Storage Volumes



Tables 9 and 10 provide cumulative storage volumes for the MC-4500 chamber and end cap. These tables can be used to calculate the stage-storage relationship for the retention or detention system. Digital spreadsheets in which the number of chambers and end caps can be input for quick

cumulative storage calculations are available at www.stormtech.com. For assistance with site-specific calculations or input into routing software, contact the StormTech Technical Services Department.

TABLE 9 – MC-4500 Incremental Storage Volume Per Chamber

Assumes 40% stone porosity. Calculations are based upon a 9" (230 mm) stone base under the chambers, 12" (300 mm) of stone above chambers, and 9" (230 mm) of spacing between chambers.

Depth of Water in System Inches (mm)	Cumulative Chamber Storage ft ³ (m ³)	Total System Cumulative Storage ft ³ (m ³)
81 (2057)	0.00	162.62 (4.065)
80 (2032)	0.00	161.40 (4.570)
79 (2007)	0.00	160.18 (4.536)
78 (1981)	Stone 0.00	158.98 (4.501)
77 (1956)	Cover 0.00	157.74 (4.467)
76 (1930)	0.00	156.62 (4.432)
75 (1905)	0.00	155.30 (4.398)
74 (1880)	0.00	154.09 (4.363)
73 (1854)	0.00	152.87 (4.329)
72 (1829)	0.00	151.65 (4.294)
71 (1803)	0.00	150.43 (4.294)
70 (1778)	0.00	149.21 (4.225)
69 (1753)	106.51 (3.016)	147.99 (4.191)
68 (1727)	106.47 (3.015)	146.75 (4.156)
67 (1702)	106.35 (3.012)	145.46 (4.119)
66 (1676)	106.18 (3.007)	144.14 (4.082)
65 (1651)	105.98 (3.001)	142.80 (4.044)
64 (1626)	105.71 (2.993)	141.42 (4.005)
63 (1600)	105.25 (2.981)	139.93 (3.962)
62 (1575)	104.59 (2.962)	138.31 (3.917)
61 (1549)	103.79 (2.939)	136.61 (3.869)
60 (1524)	102.88 (2.913)	134.85 (3.819)
59 (1499)	101.88 (2.885)	133.03 (3.767)
58 (1473)	100.79 (2.854)	131.16 (3.714)
57 (1448)	99.63 (2.821)	129.24 (3.660)
56 (1422)	98.39 (2.786)	127.28 (3.604)
55 (1397)	97.10 (2.749)	125.28 (3.548)
54 (1372)	95.73 (2.711)	123.25 (3.490)
53 (1346)	94.32 (2.671)	121.18 (3.490)
52 (1321)	92.84 (2.629)	119.08 (3.372)
51 (1295)	91.32 (2.586)	116.94 (3.311)
50 (1270)	89.74 (2.541)	114.78 (3.250)
49 (1245)	88.12 (2.495)	112.59 (3.188)
48 (1219)	86.45 (2.448)	110.37 (3.125)
47 (1194)	84.75 (2.400)	108.13 (3.062)
46 (1168)	83.00 (2.350)	105.86 (2.998)
45 (1143)	81.21 (2.300)	103.56 (2.933)
44 (1118)	79.38 (2.248)	101.25 (2.867)
43 (1092)	77.52 (2.195)	98.91 (2.801)

NOTE: Add 1.22 ft³ (0.035 m³) of storage for each additional inch (25 mm) of stone foundation. Contact StormTech for cumulative volume spreadsheets in digital format.

Depth of Water in System Inches (mm)	Cumulative Chamber Storage ft ³ (m ³)	Total System Cumulative Storage ft ³ (m ³)
42 (1067)	75.62 (2.141)	96.55 (2.734)
41 (1041)	73.69 (2.087)	94.18 (2.667)
40 (1016)	71.72 (2.031)	91.78 (2.599)
39 (991)	69.73 (1.974)	89.36 (2.531)
38 (965)	67.70 (1.917)	86.93 (2.462)
37 (948)	65.65 (1.859)	84.48 (2.392)
36 (914)	63.57 (1.800)	82.01 (2.322)
35 (889)	61.46 (1.740)	79.53 (2.252)
34 (864)	59.32 (1.680)	77.03 (2.181)
33 (838)	57.17 (1.619)	74.52 (2.110)
32 (813)	54.98 (1.557)	71.99 (2.038)
31 (787)	52.78 (1.495)	69.45 (1.966)
30 (762)	50.55 (1.431)	66.89 (1.894)
29 (737)	48.30 (1.368)	64.32 (1.821)
28 (711)	46.03 (1.303)	61.74 (1.748)
27 (686)	43.74 (1.239)	59.19 (1.675)
26 (680)	41.43 (1.173)	56.55 (1.601)
25 (610)	39.11 (1.107)	53.93 (1.527)
24 (609)	36.77 (1.041)	51.31 (1.453)
23 (584)	34.41 (0.974)	48.67 (1.378)
22 (559)	32.03 (0.907)	46.03 (1.303)
21 (533)	29.64 (0.839)	43.38 (1.228)
20 (508)	27.23 (0.771)	40.71 (1.153)
19 (483)	24.81 (0.703)	38.04 (1.077)
18 (457)	22.38 (0.634)	35.37 (1.001)
17 (432)	19.94 (0.565)	32.68 (0.925)
16 (406)	17.48 (0.495)	29.99 (0.849)
15 (381)	15.01 (0.425)	27.29 (0.773)
14 (356)	12.53 (0.355)	24.58 (0.696)
13 (330)	10.05 (0.284)	21.87 (0.619)
12 (305)	7.55 (0.214)	19.15 (0.542)
11 (279)	5.04 (0.143)	16.43 (0.465)
10 (254)	2.53 (0.072)	13.70 (0.388)
9 (229)	0.00	10.97 (0.311)
8 (203)	0.00	9.75 (0.276)
7 (178)	0.00	8.53 (0.242)
6 (152)	Stone 0.00	7.31 (0.207)
5 (127)	Foundation 0.00	6.09 (0.173)
4 (102)	0.00	4.87 (0.138)
3 (76)	0.00	3.66 (0.104)
2 (51)	0.00	2.44 (0.069)
1 (25)	0.00	1.22 (0.035)

5.0 Cumulative Storage Volumes



TABLE 10 – MC-4500 Incremental Storage Volume Per End Cap
 Assumes 40% stone porosity. Calculations are based upon a 9" (230 mm) stone base under the chambers, 12" (300 mm) of stone above end caps, and 9" (230 mm) of spacing between end caps and 6" (150 mm) of stone perimeter.

Depth of Water in System Inches (mm)	Cumulative End Cap Storage ft ³ (m ³)	Total System Cumulative Storage ft ³ (m ³)
81 (2057)	0.00	108.69 (3.078)
80 (2032)	0.00	107.62 (3.047)
79 (2007)	0.00	106.54 (3.017)
78 (1981)	Stone 0.00	105.46 (2.986)
77 (1956)	Cover 0.00	104.38 (2.956)
76 (1930)	0.00	103.31 (2.925)
75 (1905)	0.00	102.23 (2.895)
74 (1880)	0.00	101.15 (2.864)
73 (1854)	0.00	100.07 (2.834)
72 (1829)	0.00	99.00 (2.803)
71 (1803)	0.00	97.92 (2.773)
70 (1778)	0.00	96.84 (2.742)
69 (1753)	35.71 (1.011)	95.76 (2.712)
68 (1727)	35.71 (1.011)	94.69 (2.681)
67 (1702)	35.70 (1.011)	93.60 (2.651)
66 (1676)	35.67 (1.010)	92.51 (2.620)
65 (1651)	35.62 (1.009)	91.40 (2.588)
64 (1626)	35.56 (1.007)	90.29 (2.557)
63 (1600)	35.47 (1.004)	89.16 (2.525)
62 (1575)	35.36 (1.001)	88.01 (2.492)
61 (1549)	35.21 (0.997)	86.85 (2.459)
60 (1524)	35.05 (0.992)	85.67 (2.426)
59 (1499)	34.86 (0.987)	84.48 (2.392)
58 (1473)	34.64 (0.981)	83.27 (2.358)
57 (1448)	34.40 (0.974)	82.05 (2.323)
56 (1422)	34.13 (0.966)	80.81 (2.288)
55 (1397)	33.83 (0.958)	79.55 (2.253)
54 (1372)	33.51 (0.949)	78.28 (2.217)
53 (1346)	33.16 (0.939)	77.00 (2.180)
52 (1321)	32.79 (0.928)	75.70 (2.144)
51 (1295)	32.39 (0.917)	74.38 (2.106)
50 (1270)	31.98 (0.906)	73.06 (2.069)
49 (1245)	31.54 (0.893)	71.71 (2.031)
48 (1219)	31.07 (0.880)	70.36 (1.992)
47 (1194)	30.59 (0.866)	68.99 (1.954)
46 (1168)	30.09 (0.852)	67.61 (1.915)
45 (1143)	29.56 (0.837)	66.22 (1.875)
44 (1118)	29.02 (0.822)	64.81 (1.835)
43 (1092)	28.45 (0.806)	63.40 (1.795)

NOTE: Add 1.08 ft³ (0.031 m³) of storage for each additional inch (25 mm) of stone foundation. Contact StormTech for cumulative volume spreadsheets in digital format.

Depth of Water in System Inches (mm)	Cumulative Chamber Storage ft ³ (m ³)	Total System Cumulative Storage ft ³ (m ³)
42 (1067)	27.87 (0.789)	61.97 (1.755)
41 (1041)	27.27 (0.772)	60.53 (1.714)
40 (1016)	26.65 (0.755)	59.08 (1.673)
39 (991)	26.01 (0.736)	57.62 (1.632)
38 (965)	25.35 (0.718)	56.15 (1.590)
37 (948)	24.68 (0.699)	54.67 (1.548)
36 (914)	23.99 (0.679)	53.18 (1.506)
35 (889)	23.28 (0.659)	51.68 (1.463)
34 (864)	22.56 (0.639)	50.17 (1.421)
33 (838)	21.82 (0.618)	48.64 (1.377)
32 (813)	21.06 (0.596)	47.11 (1.334)
31 (787)	20.29 (0.575)	45.57 (1.290)
30 (762)	19.50 (0.552)	44.02 (1.247)
29 (737)	18.70 (0.530)	42.46 (1.202)
28 (711)	17.88 (0.506)	40.89 (1.158)
27 (686)	17.04 (0.483)	39.31 (1.113)
26 (680)	16.19 (0.459)	37.73 (1.068)
25 (610)	15.33 (0.434)	36.14 (1.023)
24 (609)	14.46 (0.410)	34.53 (0.978)
23 (584)	13.58 (0.384)	32.93 (0.932)
22 (559)	12.68 (0.359)	31.31 (0.887)
21 (533)	11.77 (0.333)	29.69 (0.841)
20 (508)	10.85 (0.307)	28.06 (0.794)
19 (483)	9.91 (0.281)	26.42 (0.748)
18 (457)	8.97 (0.254)	24.77 (0.702)
17 (432)	8.01 (0.227)	23.12 (0.655)
16 (406)	7.04 (0.199)	21.46 (0.608)
15 (381)	6.07 (0.172)	19.80 (0.561)
14 (356)	5.08 (0.144)	18.13 (0.513)
13 (330)	4.08 (0.116)	16.45 (0.466)
12 (305)	3.07 (0.087)	14.77 (0.418)
11 (279)	2.06 (0.058)	13.09 (0.371)
10 (254)	1.03 (0.029)	11.39 (0.323)
9 (229)	0.00	9.70 (0.275)
8 (203)	0.00	8.62 (0.244)
7 (178)	0.00	7.54 (0.214)
6 (152)	Stone 0.00	6.46 (0.183)
5 (127)	Foundation 0.00	5.39 (0.153)
4 (102)	0.00	4.31 (0.122)
3 (76)	0.00	3.23 (0.092)
2 (51)	0.00	2.15 (0.061)
1 (25)	0.00	1.08 (0.031)

The following steps provide the calculations necessary for preliminary sizing of an MC-3500 chamber system. For custom bed configurations to fit specific sites, contact the StormTech Technical Services Department or your local StormTech representative.

1) Determine the amount of storage volume (VS) required. It is the design engineer's sole responsibility to determine the storage volume required.

TABLE 11—Storage Volume Per Chamber/End Cap ft³ (m³)

	Bare Unit Storage ft ³ (m ³)	Chamber/End Cap and Stone Volume — Stone Foundation Depth in. (mm)			
		9 (230)	12 (300)	15 (375)	18 (450)
MC-3500 Chamber	109.9 (3.11)	175.0 (4.96)	179.9 (5.09)	184.9 (5.24)	189.9 (5.38)
MC-3500 End Cap	14.9 (0.42)	45.1 (1.28)	46.6 (1.32)	48.3 (1.37)	49.9 (1.41)

NOTE: Assumes 6" (150 mm) row spacing, 40% stone porosity, 12" (300 mm) stone above and includes the bare chamber/end cap volume. End cap volume assumes 6" (150 mm) stone perimeter.

2) Determine the number of chambers (C) required. To calculate the number of chambers required for adequate storage, divide the storage volume (Vs) by the storage volume of the chamber (from **Table 11**), as follows: **C = Vs / Storage Volume per Chamber**

3) Determine the number of end caps required. The number of end caps (EC) required depends on the number of rows required by the project. Once the number of chamber rows is determined, multiply the number of chamber rows by 2 to determine the number of end caps required. **EC = No. of Chamber Rows x 2**

NOTE: Additional end caps may be required for systems having inlet locations within the chamber bed.

4) Determine additional storage provided by end caps. End Caps will provide additional storage to the project. Multiply the number of end caps (EC) by the storage volume per end cap (ECS) to determine the additional storage (As) provided by the end caps. **As = EC x ECS**

5) Adjust number of chambers (C) to account for additional end cap storage (As). The original number of chambers (C) can now be reduced due to the additional storage in the end caps. Divide the additional storage (As) by the storage volume per chamber to determine the number of chambers that can be removed. **Number of chambers to remove = As/ volume per chamber**

NOTE: Additional storage exists in the stone perimeter as well as in the inlet and outlet manifold systems. Contact StormTech's Technical Services Department for assistance with determining the number of chambers and end caps required for your project.

6) Determine the required bed size (S). The size of the bed will depend on the number of chambers and end caps required:

MC-3500 area per chamber = 49.6 ft² (4.6 m²)

MC-3500 area per end cap = 16.4 ft² (1.5 m²)

S = (C x area per chamber) + (EC x area per end cap)

NOTE: It is necessary to add 12" (300 mm) of stone perimeter parallel to the chamber rows and 6" (150 mm) of stone perimeter from the base of all end caps. The additional area due to perimeter stone is not included in the area numbers above.

7) Determine the amount of stone (Vst) required. To calculate the total amount of clean, crushed, angular stone required, multiply the number of chambers (C) and the number of end caps (EC) by the selected weight of stone from **Table 12**.

NOTE: Clean, crushed, angular stone is also required around the perimeter of the system.

TABLE 12—Amount of Stone Per Chamber/End Cap

ENGLISH tons (yd ³)	Stone Foundation Depth			
	9"	12"	15"	18"
MC-3500	8.5 (6.0)	9.1 (6.5)	9.7 (6.9)	10.4 (7.4)
End Cap	3.9 (2.8)	4.1 (2.9)	4.3 (3.1)	4.5 (3.2)
METRIC kg (m ³)	230 mm	300 mm	375 mm	450 mm
MC-3500	7711 (4.6)	8255 (5.0)	8800 (5.3)	9435 (5.7)
End Cap	3538 (2.1)	3719 (2.2)	3901 (2.4)	4082 (2.5)

NOTE: Assumes 12" (300 mm) of stone above, and 6" (150 mm) row spacing, and 6" (150 mm) of perimeter stone in front of end caps.

8) Determine the volume of excavation (Ex) required. Each additional foot of cover will add a volume of excavation of 1.9 yd³ (1.5 m³) per MC-3500 chamber and

TABLE 13—Volume of Excavation Per Chamber/End Cap yd³ (m³)

	Stone Foundation Depth			
	9" (230 mm)	12" (300 mm)	15" (375 mm)	18" (450 mm)
MC-3500	11.9 (9.1)	12.4 (9.5)	12.8 (9.8)	13.3 (10.2)
End Cap	4.0 (3.1)	4.1 (3.2)	4.3 (3.3)	4.4 (3.4)

NOTE: Assumes 6" (150 mm) separation between chamber rows, 6" (150 mm) of perimeter in front of end caps, and 24" (600 mm) of cover. The volume of excavation will vary as the depth of cover increases.

0.6 yd³ (0.5 m³) per MC-3500 end cap.

9) Determine the area of geotextile (F) required. The bottom, top and sides of the bed must be covered with a non-woven geotextile (filter fabric) that meets AASHTO M288 Class 2 requirements. The area of the sidewalls must be calculated and a 24" (600 mm) overlap must be included for all seams. Geotextiles typically come in 15 foot (4.57 m) wide rolls.

6.0 MC-4500 Chamber System Sizing



The following steps provide the calculations necessary for preliminary sizing of an MC-4500 chamber system. For custom bed configurations to fit specific sites, contact the StormTech Technical Services Department or your local StormTech representative.

1) Determine the amount of storage volume (VS) required. It is the design engineer's sole responsibility to determine the storage volume required.

TABLE 14—Storage Volume Per Chamber/End Cap ft³ (m³)

	Bare Unit Storage ft ³ (m ³)	Chamber/End Cap and Stone Volume — Stone Foundation Depth in. (mm)			
		9 (230)	12 (300)	15 (375)	18 (450)
MC-4500 Chamber	106.5 (3.01)	162.6 (4.60)	166.3 (4.71)	169.9 (4.81)	173.6 (4.91)
MC-4500 End Cap	35.7 (1.01)	108.7 (3.08)	111.9 (3.17)	115.2 (3.26)	118.4 (3.35)

NOTE: Assumes 9" (230 mm) row spacing, 40% stone porosity, 12" (300 mm) stone above and includes the bare chamber/end cap volume. End cap volume assumes 12" (300 mm) stone perimeter.

2) Determine the number of chambers (C) required. To calculate the number of chambers required for adequate storage, divide the storage volume (Vs) by the storage volume of the chamber (from Table 14), as follows: **C = Vs / Storage Volume per Chamber**

3) Determine the number of end caps required. The number of end caps (EC) required depends on the number of rows required by the project. Once the number of chamber rows is determined, multiply the number of chamber rows by 2 to determine the number of end caps required. **EC = No. of Chamber Rows x 2**

NOTE: Additional end caps may be required for systems having inlet locations within the chamber bed.

4) Determine additional storage provided by end caps. End Caps will provide additional storage to the project. Multiply the number of end caps (EC) by the storage volume per end cap (ECS) to determine the additional storage (As) provided by the end caps. **As = EC x ECS**

5) Adjust number of chambers (C) to account for additional end cap storage (As). The original number of chambers (C) can now be reduced due to the additional storage in the end caps. Divide the additional storage (As) by the storage volume per chamber to determine the number of chambers that can be removed. **Number of chambers to remove = As / volume per chamber**

NOTE: Additional storage exists in the stone perimeter as well as in the inlet and outlet manifold systems. Contact StormTech's Technical Services Department for assistance with determining the number of chambers and end caps required for your project.

6) Determine the required bed size (S). The size of the bed will depend on the number of chambers and end caps required:

MC-4500 area per chamber = 36.6 ft² (3.4 m²)
MC-4500 area per end cap = 23.2 ft² (2.2 m²)

S = (C x area per chamber) + (EC x area per end cap)

NOTE: It is necessary to add 12" (300 mm) of stone perimeter parallel to the chamber rows and 6" (150 mm) of stone perimeter from the base of all end caps. The additional area due to perimeter stone is not included in the area numbers above.

7) Determine the amount of stone (Vst) required. To calculate the total amount of clean, crushed, angular stone required, multiply the number of chambers (C) and the number of end caps (EC) by the selected weight of stone from Table 15.

NOTE: Clean, crushed, angular stone is also required around the perimeter of the system.

TABLE 15—Amount of Stone Per Chamber

ENGLISH tons (yd ³)	Stone Foundation Depth			
	9"	12"	15"	18"
MC-4500	7.4 (5.2)	7.8 (5.5)	8.3 (5.9)	8.8 (6.2)
End Cap	9.6 (6.8)	10.0 (7.1)	10.4 (7.4)	10.9 (7.7)
METRIC kg (m ³)	230 mm	300 mm	375 mm	450 mm
MC-4500	6681 (4.0)	7117 (4.2)	7552 (4.5)	7987 (4.7)
End Cap	8691 (5.2)	9075 (5.4)	9460 (5.6)	9845 (5.9)

NOTE: Assumes 12" (300 mm) of stone above, and 9" (230 mm) row spacing, and 12" (300 mm) of perimeter stone in front of end caps.

8) Determine the volume of excavation (Ex) required. Each additional foot of cover will add a volume of excavation of 1.4 yd³ (1.0 m³) per MC-4500 chamber and 1.4 yd³ (0.8 m³) per MC-4500 end cap.

TABLE 16—Volume of Excavation Per Chamber/End Cap yd³ (m³)


	Stone Foundation Depth			
	9" (230 mm)	12" (300 mm)	15"(375 mm)	18"(450 mm)
MC-4500	10.5 (8.0)	10.8 (8.3)	11.2 (8.5)	11.5 (8.8)
End Cap	9.3 (7.1)	9.6 (7.3)	9.9 (7.6)	10.2 (7.8)

NOTE: Assumes 9" (230 mm) separation between chamber rows, 12" (300 mm) of perimeter in front of end caps, and 24" (600 mm) of cover. The volume of excavation will vary as the depth of cover increases.

9) Determine the area of geotextile (F) required. The bottom, top and sides of the bed must be covered with a non-woven geotextile (filter fabric) that meets AASHTO M288 Class 2 requirements. The area of the sidewalls must be calculated and a 24" (600 mm) overlap must be included for all seams. Geotextiles typically come in 15 foot (4.57 m) wide rolls.

7.0 Structural Cross Sections and Specifications

FIGURE 16—MC-3500 Structural Cross Section Detail (Not to Scale)



Special applications will be considered on a project by project basis. Please contact our application department should you have a unique application for our team to evaluate.


MC-3500 STORMWATER CHAMBER SPECIFICATIONS

- Chambers shall be StormTech MC-3500 or approved equal.
- Chambers shall be made from virgin, impact-modified polypropylene copolymers.
- Chamber rows shall provide continuous, unobstructed internal space with no internal panels that would impede flow.
- The structural design of the chambers, the structural backfill and the installation requirements shall ensure that the load factors specified in the AASHTO LRFD Bridge Design Specifications, Section 12.12 are met for: 1) long-duration dead loads and 2) short-duration live loads, based on the AASHTO Design Truck with consideration for impact and multiple vehicle presences.
- Chambers shall meet the requirements of ASTM F 2418, "Standard Specification for Polypropylene (PP) Corrugated Wall Stormwater Collection Chambers."
- Chambers shall conform to the requirements of ASTM F 2787, "Standard Practice for Structural Design of Thermoplastic Corrugated Wall Stormwater Collection Chambers."
- Only chambers that are approved by the engineer will be allowed. The contractor shall submit (3 sets) of the following to the engineer for approval before delivering chambers to the project site:
 - A structural evaluation by a registered structural engineer that demonstrates that the load factors specified in the AASHTO LRFD Bridge Design Specifications, Section 12.12 are met. The 50-year creep modulus data specified in ASTM F 2418 must be used as part of the AASHTO structural evaluation to verify long-term performance.
 - Structural cross section detail on which the structural cross section is based.
- The installation of chambers shall be in accordance with the manufacturer's latest Construction Guide.

Detail drawings available in Cad Rev. 2000 format at www.stormtech.com

7.0 Structural Cross Sections and Specifications

FIGURE 16—MC-4500 Structural Cross Section Detail (Not to Scale)



Special applications will be considered on a project by project basis. Please contact our application department should you have a unique application for our team to evaluate.

MC-4500 STORMWATER CHAMBER SPECIFICATIONS

1. Chambers shall be StormTech MC-4500 or approved equal.
2. Chambers shall be made from virgin, impact-modified polypropylene copolymers.
3. Chamber rows shall provide continuous, unobstructed internal space with no internal panels that would impede flow.
4. The structural design of the chambers, the structural backfill and the installation requirements shall ensure that the load factors specified in the AASHTO LRFD Bridge Design Specifications, Section 12.12 are met for: 1) long-duration dead loads and 2) short-duration live loads, based on the AASHTO Design Truck with consideration for impact and multiple vehicle presences.
5. Chambers shall meet the requirements of ASTM F 2418, "Standard Specification for Polypropylene (PP) Corrugated Wall Stormwater Collection Chambers."
6. Chambers shall conform to the requirements of ASTM F 2787, "Standard Practice for Structural Design of Thermoplastic Corrugated Wall Stormwater Collection Chambers."
7. Only chambers that are approved by the engineer will be allowed. The contractor shall submit (3 sets) of the following to the engineer for approval before delivering chambers to the project site:
 - A structural evaluation by a registered structural engineer that demonstrates that the load factors specified in the AASHTO LRFD Bridge Design Specifications, Section 12.12 are met. The 50-year creep modulus data specified in ASTM F 2418 must be used as part of the AASHTO structural evaluation to verify long-term performance.
 - Structural cross section detail on which the structural cross section is based.
8. The installation of chambers shall be in accordance with the manufacturer's latest Construction Guide.

Detail drawings available in Cad Rev. 2000 format at www.stormtech.com

8.0 General Notes



1. StormTech requires installing contractors to use and understand the latest **StormTech MC-3500 and MC-4500 Construction Guide** prior to beginning system installation.
2. StormTech offers installation consultations to installing contractors. Contact our Technical Service Department or local StormTech representative at least 30 days prior to system installation to arrange a pre-installation consultation. Our representatives can then answer questions or address comments on the StormTech chamber system and inform the installing contractor of the minimum installation requirements before beginning the system's construction. Call 860-529-8188 to speak to a Technical Service Representative or visit www.stormtech.com to receive a copy of our Construction Guide.
3. StormTech requirements for systems with pavement design (asphalt, concrete pavers, etc.): Minimum cover is 18" (450mm) for the MC-3500 and 24"(600mm) for the MC-4500 not including pavement; MC-3500 maximum cover is 8.0' (1.98 m) and MC-4500 maximum cover is 7.0' (2.43 m) both including pavement. For designs with cover depths deeper than these maximums, please contact Stormtech. For installations that do not include pavement, where rutting from vehicles may occur, minimum required cover is increased to 30" (762 mm).
4. The contractor must report any discrepancies with the bearing capacity of the subgrade materials to the design engineer.
5. AASHTO M288 Class 2 non-woven geotextile (ADS601 or equal) (filter fabric) must be used as indicated in the project plans.
6. Stone placement between chamber rows and around perimeter must follow instructions as indicated in the most current version of StormTech MC-3500 / MC-4500 Construction Guide.
7. Backfilling over the chambers must follow requirements as indicated in the most current version of StormTech MC-3500 / MC-4500 Construction Guide.
8. The contractor must refer to StormTech MC-3500 / MC-4500 Construction Guide for a Table of Acceptable Vehicle Loads at various depths of cover. This information is also available at the StormTech website: www.stormtech.com. The contractor is responsible for preventing vehicles that exceed StormTech requirements from traveling across or parking over the stormwater system. Temporary fencing, warning tape and appropriately located signs are commonly used to prevent unauthorized vehicles from entering sensitive construction areas.
9. The contractor must apply erosion and sediment control measures to protect the stormwater system during all phases of site construction per local codes and design engineer's specifications.
10. STORMTECH PRODUCT WARRANTY IS LIMITED. Contact StormTech for warranty information.

9.0 Inspection and Maintenance



9.1 ISOLATOR ROW INSPECTION

Regular inspection and maintenance are essential to assure a properly functioning stormwater system. Inspection is easily accomplished through the manhole or optional inspection ports of an Isolator Row. Please follow local and OSHA rules for a confined space entry.

Inspection ports can allow inspection to be accomplished completely from the surface without the need for a confined space entry. Inspection ports provide visual access to the system with the use of a flashlight. A stadia rod may be inserted to determine the depth of sediment. If upon visual inspection it is found that sediment has accumulated to an average depth exceeding 3" (76 mm), cleanout is required.

A StormTech Isolator Row should initially be inspected immediately after completion of the site's construction. While every effort should be made to prevent sediment from entering the system during construction, it is during this time that excess amounts of sediments are most likely to enter any stormwater system. Inspection and maintenance, if necessary, should be performed prior to passing responsibility over to the site's owner. Once in normal service, a StormTech Isolator Row should be inspected bi-annually until an understanding of the sites characteristics is developed. The site's maintenance manager can then revise the inspection schedule based on experience or local requirements.

9.2 ISOLATOR ROW MAINTENANCE


JetVac maintenance is recommended if sediment has been collected to an average depth of 3" (76 mm) inside the Isolator Row. More frequent maintenance may be required to maintain minimum flow rates through the Isolator Row. The JetVac process utilizes a high pressure water nozzle to propel itself down the Isolator Row while scouring and suspending sediments. As the nozzle is retrieved, a wave of suspended sediments is flushed back into the manhole for vacuuming. Most sewer and pipe maintenance companies have vacuum/ JetVac combination vehicles. Fixed nozzles designed for culverts or large diameter pipe cleaning are preferable. Rear facing jets with an effective spread of at least 45" (1143 mm) are best. The JetVac process shall only be performed on StormTech Rows that have AASHTO class 1 woven geotextile over their foundation stone (ADS 315WTM or equal).



Looking down the Isolator Row



A typical JetVac truck (This is not a StormTech product.)




Examples of culvert cleaning nozzles appropriate for Isolator Row maintenance. (These are not StormTech products).


SiteASSIST™

by StormTech®

The SiteASSIST App enables ADS to take customer service and field support to unprecedented levels. With detailed instructions on proper installation techniques for StormTech chambers and supporting video animations, this tool is designed to insure installed performance.



DOWNLOAD THE APP TODAY



ADS Terms and Conditions of Sale are available on the ADS website, www.ads-pipe.com
Advanced Drainage Systems, the ADS logo and the Green Stripe are registered trademarks of Advanced Drainage Systems, Inc.
StormTech and the Isolator Row are registered trademarks of StormTech, Inc.
Green Building Council Member Logo is a registered trademark of the U.S. Green Building Council.
© 2019 Advanced Drainage Systems, Inc. S250211 07/19 CS



MC-4500 MC-3500 DC-780 SC-740 SC-310 SC-160LP

A Family of Products and Services for the Stormwater Industry:

- MC-3500 and MC-4500 Chambers and End Caps
- SC-310 and SC-740 Chambers and End Caps
- DC-780 Chambers and End Caps
- Fabricated End Caps
- Fabricated Manifold Fittings
- Patented Isolator Row for Maintenance and Water Quality
- Chamber Separation Spacers
- In-House System Layout Assistance
- On-Site Educational Seminars
- Worldwide Technical Sales Group
- Centralized Product Applications Department
- Research and Development Team
- Technical Literature, O&M Manuals and Detailed CAD drawings all downloadable via our Website

StormTech provides state-of-the-art products and services that meet or exceed industry performance standards and expectations. We offer designers, regulators, owners and contractors the highest quality products and services for stormwater management that "Saves Valuable Land and Protects Water Resources."



Advanced Drainage Systems, Inc.
4640 Trueman Blvd. Hilliard, OH 43026

1-800-821-6710

www.ads-pipe.com

THE MOST **ADVANCED** NAME IN WATER MANAGEMENT SOLUTIONS®





StormTech Construction Guide

REQUIRED MATERIALS AND EQUIPMENT LIST

- Acceptable fill materials per Table 1
- StormTech solid end caps, pre-cored and pre-fabricated end caps
- Woven and non-woven geotextiles
- StormTech chambers, manifolds and fittings

NOTE: MC-3500 chamber pallets are 77" x 90" (2.0 m x 2.3 m) and weigh about 2010 lbs. (912 kg) and MC-4500 pallets are 100" x 52" (2.5 m x 1.3 m) and weigh about 840 lbs. (381 kg). Unloading chambers requires 72" (1.8 m) (min.) forks and/or tie downs (straps, chains, etc).

IMPORTANT NOTES:

- A. This installation guide provides the minimum requirements for proper installation of chambers. Nonadherence to this guide may result in damage to chambers during installation. Replacement of damaged chambers during or after backfilling is costly and very time consuming. It is recommended that all installers are familiar with this guide, and that the contractor inspects the chambers for distortion, damage and joint integrity as work progresses.
- B. Use of a dozer to push embedment stone between the rows of chambers may cause damage to chambers and is not an acceptable backfill method. Any chambers damaged by using the "dump and push" method are not covered under the StormTech standard warranty.
- C. Care should be taken in the handling of chambers and end caps. End caps must be stored standing upright. Avoid dropping, prying or excessive force on chambers during removal from pallet and initial placement.

Requirements for System Installation



Excavate bed and prepare subgrade per engineer's plans.



Place non-woven geotextile over prepared soils and up excavation walls.




Place clean, crushed, angular stone foundation 9" (230 mm) min. Install underdrains if required. Compact to achieve a flat surface.

Manifold, Scour Fabric and Chamber Assembly



Install manifolds and lay out woven scour geotextile at inlet rows [min. 17.5 ft (5.33 m)] at each inlet end cap. Place a continuous piece (no seams) along entire length of Isolator® Row(s) in two layers.




Align the first chamber and end cap of each row with inlet pipes. Contractor may choose to postpone stone placement around end chambers and leave ends of rows open for easy inspection of chambers during the backfill process.




Continue installing chambers by overlapping chamber end corrugations. Chamber joints are labeled “Lower Joint – Overlap Here” and “Build this direction – Upper Joint” Be sure that the chamber placement does not exceed the reach of the construction equipment used to place the stone. Maintain minimum 6” (150 mm) spacing between MC-3500 rows and 9” (230 mm) spacing between MC-4500 rows. For the Isolator Row place two continuous layers of ADS Woven fabric between the foundation stone and the isolator row chambers, making sure the fabric lays flat and extends the entire width of the chamber feet.

Manifold Insertion



Insert inlet and outlet manifolds a minimum 12” (300 mm) into chamber end caps. Manifold header should be a minimum 12” (300 mm) from base of end cap.

StormTech Isolator Row Detail



Initial Anchoring of Chambers – Embedment Stone




Initial embedment shall be spotted along the centerline of the chamber evenly anchoring the lower portion of the chamber. This is best accomplished with a stone conveyor or excavator reaching along the row.




No equipment shall be operated on the bed at this stage of the installation. Excavators must be located off the bed. Dump trucks shall not dump stone directly on to the bed. Dozers or loaders are not allowed on the bed at this time.


Backfill of Chambers – Embedment Stone




UNEVEN BACKFILL



EVEN BACKFILL



PERIMETER NOT BACKFILLED



PERIMETER FULLY BACKFILLED


Backfill chambers evenly. Stone column height should never differ by more than 12" (300 mm) between adjacent chamber rows or between chamber rows and perimeter.

Perimeter stone must be brought up evenly with chamber rows. Perimeter must be fully backfilled, with stone extended horizontally to the excavation wall.

Backfill of Chambers – Embedment Stone and Cover Stone



Continue evenly backfilling between rows and around perimeter until embedment stone reaches tops of chambers and a minimum 12" (300 mm) of cover stone is in place. Perimeter stone must extend horizontally to the excavation wall for both straight or sloped sidewalls. The recommended backfill methods are with a stone conveyor outside of the bed or build as you go with an excavator inside the bed reaching along the rows. Backfilling while assembling chambers rows as shown in the picture will help to ensure that equipment reach is not exceeded.




Only after chambers have been backfilled to top of chamber and with a minimum 12" (300 mm) of cover stone on top of chambers can skid loaders and small LGP dozers be used to final grade cover stone and backfill material in accordance with ground pressure limits in Table 2. Equipment must push material parallel to rows only. Never push perpendicular to rows. StormTech recommends the contractor inspect chamber rows before placing final backfill. Any chambers damaged by construction equipment shall be removed and replaced.

Final Backfill of Chambers – Fill Material



Install non-woven geotextile over stone. Geotextile must overlap 24" (600 mm) where edges meet. Compact at 24" (600 mm) of fill. Roller travel parallel with rows.

Inserta Tee Detail



NOTE:
PART NUMBERS WILL VARY BASED ON INLET PIPE MATERIALS.
CONTACT STORMTECH FOR MORE INFORMATION.

CHAMBER	MAX DIAMETER OF INSERTA TEE	HEIGHT FROM BASE OF CHAMBER (X)
SC-310	6" (150 mm)	4" (100 mm)
SC-740	10" (250 mm)	4" (100 mm)
DC-780	10" (250 mm)	4" (100 mm)
MC-3500	12" (300 mm)	6" (150 mm)
MC-4500	12" (300 mm)	8" (200 mm)

INSERTA TEE FITTINGS AVAILABLE FOR SDR 26, SDR 35, SCH 40 IPS GASKETED & SOLVENT WELD, N-12, HP STORM, C-900 OR DUCTILE IRON

Table 1- Acceptable Fill Materials

Material Location	Description	AASHTO M43 Designation ¹	Compaction/Density Requirement
(D) Final Fill: Fill Material for layer 'D' starts from the top of the 'C' layer to the bottom of flexible pavement or unpaved finished grade above. Note that the pavement subbase may be part of the 'D' layer.	Any soil/rock materials, native soils or per engineer's plans. Check plans for pavement subgrade requirements.	N/A	Prepare per site design engineer's plans. Paved installations may have stringent material and preparation requirements.
(C) Initial Fill: Fill Material for layer 'C' starts from the top of the embedment stone ('B' layer) to 24" (600 mm) above the top of the chamber. Note that pavement subbase materials can be used in lieu of this layer.	Granular well-graded soil/ aggregate mixtures, <35% fines or processed aggregate. Most pavement subbase materials can be used in lieu of this layer.	AASHTO M145 A-1, A-2-4, A-3 or AASHTO M431 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	Begin compaction after min. 24" (600 mm) of material over the chambers is reached. Compact additional layers in 12" (300 mm) max. lifts to a min. 95% Proctor density for well-graded material and 95% relative density for processed aggregate materials.
(B) Embedment Stone: Fill the surrounding chambers from the foundation stone ('A' layer) to the 'C' layer above.	Clean, crushed, angular stone	AASHTO M43 ¹ 3, 357, 4	No compaction required.
(A) Foundation Stone: Fill below chambers from the subgrade up to the foot (bottom) of the chamber.	Clean, crushed, angular stone,	AASHTO M43 ¹ 3, 357, 4	Place and compact in 9" (230 mm) max lifts using two full coverages with a vibratory compactor. ^{2,3}

PLEASE NOTE:

1. The listed AASHTO designations are for gradations only. The stone must also be clean, crushed, angular. For example, a specification for #4 stone would state: "clean, crushed, angular no. 4 (AASHTO M43) stone".
2. StormTech compaction requirements are met for 'A' location materials when placed and compacted in 9" (230 mm) (max) lifts using two full coverages with a vibratory compactor.
3. Where infiltration surfaces may be comprised by compaction, for standard installations and standard design load conditions, a flat surface may be achieved by raking or dragging without compaction equipment. For special load designs, contact StormTech for compaction requirements.

Figure 1- Inspection Port Detail





Figure 2 - Fill Material Locations



NOTES:

1. 36" (900 mm) of stabilized cover materials over the chambers is required for full dump truck travel and dumping.
2. During paving operations, dump truck axle loads on 24" (600mm) of cover may be necessary. Precautions should be taken to avoid rutting of the road base layer, to ensure that compaction requirements have been met, and that a minimum of 24" (600 mm) of cover exists over the chambers. Contact StormTech for additional guidance on allowable axle loads during paving.
3. Ground pressure for track dozers is the vehicle operating weight divided by total ground contact area for both tracks. Excavators will exert higher ground pressures based on loaded bucket weight and boom extension.
4. Mini-excavators (<8,000lbs/3,628 kg) can be used with at least 12" (300 mm) of stone over the chambers and are limited by the maximum ground pressures in Table 2 based on a full bucket at maximum boom extension.
5. StormTech does not require compaction of initial fill at 18" (450 mm) of cover. However, requirements by others for 6" (150 mm) lifts may necessitate the use of small compactors at 18" (450 mm) of cover.
6. Storage of materials such as construction materials, equipment, spoils, etc. should not be located over the StormTech system. The use of equipment over the StormTech system not covered in Table 2 (ex. soil mixing equipment, cranes, etc) is limited. Please contact StormTech for more information.
7. Allowable track loads based on vehicle travel only. Excavators shall not operate on chamber beds until the total backfill reaches 3 feet (900 mm) over the entire bed. Excavators shall not operate on chamber beds until the total backfill reaches 3 feet (900 mm) over the entire bed.

ADS "Terms and Conditions of Sale" are available on the ADS website, www.ads-pipe.com. Advanced Drainage Systems, the ADS logo, and the green stripe are registered trademarks of Advanced Drainage Systems, Inc. StormTech® and the Isolator® Row are registered trademarks of StormTech, Inc.

#10816 05/19 CS

©2019 Advanced Drainage Systems, Inc.

Table 2 - Maximum Allowable Construction Vehicle Loads⁶

Material Location	Fill Depth over Chambers in. [mm]	Maximum Allowable Wheel Loads		Maximum Allowable Track Loads ⁶		Maximum Allowable Roller Loads				
		Max Axle Load for Trucks lbs [kN]	Max Wheel Load for Loaders lbs [kN]	Track Width in. [mm]	Max Ground Pressure psf [kPa]	Max Drum Weight or Dynamic Force lbs [kN]				
D Final Fill Material	36" [900] Compacted	32,000 [142]	16,000 [71]	12" [305]	3420 [164]	38,000 [169]				
				18" [457]	2350 [113]					
				24" [610]	1850 [89]					
				30" [762]	1510 [72]					
				36" [914]	1310 [63]					
C Initial Fill Material	24" [600] Compacted	32,000 [142]	16,000 [71]	12" [305]	2480 [119]	20,000 [89]				
				18" [457]	1770 [85]					
				24" [610]	1430 [68]					
				30" [762]	1210 [58]					
				36" [914]	1070 [51]					
				24" [600] Loose/Dumped	24,000 [107]		12,000 [53]	12" [305]	2245 [107]	16,000 [71]
	18" [450]	24,000 [107]	12,000 [53]	18" [457]	1625 [78]					
				24" [610]	1325 [63]					
				30" [762]	1135 [54]					
				36" [914]	1010 [48]					
	B Embedment Stone	12" [300]	NOT ALLOWED	NOT ALLOWED	12" [305]	1100 [53]	NOT ALLOWED			
					18" [457]	715 [34]				
24" [610]					660 [32]					
30" [762]					580 [28]					
6" [150]					NOT ALLOWED	NOT ALLOWED		12" [305]	2010 [96]	5,000 [22] (static loads only) ⁶
								18" [457]	1480 [71]	
				24" [610]	1220 [58]					
				30" [762]	1060 [51]					

Table 3 - Placement Methods and Descriptions

Material Location	Placement Methods/ Restrictions	Wheel Load Restrictions	Track Load Restrictions	Roller Load Restrictions
		See Table 2 for Maximum Construction Loads		
D Final Fill Material	A variety of placement methods may be used. All construction loads must not exceed the maximum limits in Table 2.	36" (900 mm) minimum cover required for dump trucks to dump over chambers.	Dozers to push parallel to rows. ⁴	Roller travel parallel to rows only until 36" (900 mm) compacted cover is reached.
C Initial Fill Material	Excavator positioned off bed recommended. Small excavator allowed over chambers. Small dozer allowed.	Asphalt can be dumped into paver when compacted pavement subbase reaches 24" (600 mm) above top of chambers.	Small LGP track dozers & skid loaders allowed to grade cover stone with at least 12" (300 mm) stone under tracks at all times. Equipment must push parallel to rows at all times.	Use dynamic force of roller only after compacted fill depth reaches 24" (600 mm) over chambers. Roller travel parallel to chamber rows only.
B Embedment Stone	No equipment allowed on bare chambers. Use excavator or stone conveyor positioned off bed or on foundation stone to evenly fill around all chambers to at least the top of chambers.	No wheel loads allowed. Material must be placed outside the limits of the chamber bed.	No tracked equipment is allowed on chambers until a min. 12" (300 mm) cover stone is in place.	No rollers allowed.
A Foundation Stone	No StormTech restrictions. Contractor responsible for any conditions or requirements by others relative to subgrade bearing capacity, dewatering or protection of subgrade.			



MEMORANDUM

TO: Mayor Rossillo and Members of the Village Board of Trustees

FROM: Valerie Monastra, AICP

CC: Richard Leins, Esq. Village Administrator
Lori Lee Dickson Esq. Village Attorney
Ed Manley, Building Inspector

DATE: September 21, 2021

RE: 49 Clinton Avenue

The Masters School (“Applicant”) is seeking Site Plan approval to construct a three-story (plus cellar), approximately 22,361 square foot Innovation and Entrepreneurship Center (“IEC”) on its campus in front of the Middle School Building. The IEC would be a new, educational and workshop building for the school’s engineering and computer science curriculum. The engineering and computer science classes are already offered at the Masters School, and therefore, the development of IEC is for existing students and the project would not increase the student body population or faculty. The project would not require additional new parking because the building is being built to centralize these classes into one building.

The project would also include the installation of green stormwater management practices, including a bioretention pond and subsurface controlled-flow stormwater detention. The project proposes new landscaping and a vegetated buffer along the nearby parking area. Views to and from the nearby historically designated Estherwood Mansion and Carriage House would be preserved.

The project also proposes to merge the six (6) tax lots comprising the property into a single tax lot, and this is being undertaken administratively by the Town of Greenburgh.

The property is located at 49 Clinton Avenue, Section Block and Lot 3.90-66-1 (“Project Site”) and is located in the EI, Educational/Institutional, zoning district.

This Application was before the Planning Board for a recommendation, and one was issued at the September 9, 2021, Planning Board meeting. The recommendation and supporting information are attached to the end of this memorandum, including the Village Engineer’s comment letter.

GENERAL AND PROCEDURAL COMMENTS

1. **SEQR.** The Village Board declared itself Lead Agency and designated the project as an Unlisted action under SEQRA at its April 13, 2021, Village Board meeting. See SEQR comments below.
2. **Site Plan Approval.** This application requires Site Plan approval by the Village Board of Trustees. A public hearing conducted by the Village Board will be required for Site Plan approval.
3. **Zoning.** The Applicant provided a zoning table demonstrating compliance with the Zoning chapter.
4. **Local Waterfront Revitalization Consistency.** The Village Board will need to make a consistency determination with the Village's LWRP per §300-52(D) as part of the final Site Plan approval. The Applicant has provided a Coastal Consistency Form.

SEQR/ENVIRONMENTAL REVIEW COMMENTS

Part I of the EAF is complete and Part II of the EAF is being provided to the Village Board for your consideration. There were a few topics on the EAF Part I that required additional information from the Applicant and those topic areas are summarized below. The Applicant has provided all outstanding information.

1. **Threatened or Endangered Species.** The EAF identified the following threatened or endangered species: Shortnose Sturgeon and Atlantic Sturgeon. These species are related to the Hudson River and not the Project Site. A consultation with the NYS DEC was undertaken, and an email dated July 30, 2021, was sent by NYS DEC (see attachment) that stated that they did not anticipate any impacts to either sturgeon species.
2. **Archaeological Site.** The Project Site is substantially contiguous to the Estherwood and Carriage House and is within an archaeologically sensitive area. The Applicant undertook consultation with SHPO, and a response in the form of a letter dated July 16, 2021, was received (see attachment). SHPO concluded that the project would have No Adverse Impact on the historic or archaeological resources.
3. **Construction.** The construction schedule estimates an average of 15 daily construction truck trips per day during months 2-5, with a peak of 30 truck trips per day. The Applicant anticipates that there will be a peak of 15 daily truck trips from months 6-12. The truck traffic for months 12-18 will average about 4-8 daily trips. The construction staging area and all construction equipment will be located on the Project Site. It is anticipated that construction trucks will travel to the Project Site using Broadway and Clinton Avenue, and there will be no queuing of construction vehicles on Clinton Avenue.



VILLAGE OF DOBBS FERRY
112 Main Street
Dobbs Ferry, New York 10522
TEL: (914) 231-8500 • FAX: (914) 693-3470

RESOLUTION 12-2021

VILLAGE OF DOBBS FERRY PLANNING BOARD RECOMMENDATION RESOLUTION
Property: 49 Clinton Avenue (Section Block and Lot 3.90-66-1 and EI,
Educational/Institutional Zoning District)

Background

WHEREAS, the Masters School ("Applicant") is seeking Site Plan approval to construct a three-story (plus cellar), approximately 22,361 square foot Innovation and Entrepreneurship Center ("IEC") on its campus in front of the Middle School Building ("Project"). The subject property is located at 49 Clinton Avenue, Dobbs Ferry New York, Section Block and Lot 3.90-66-1 ("Project Site"). The Project Site is located in the Educational/Institutional (EI) Zoning District; and

WHEREAS, this application requires Site Plan approval by the Village Board of Trustees and a recommendation by the Planning Board per Section 300-52 of the Zoning and Land Use chapter; and

WHEREAS, The Planning Board has carefully examined the Application and the Applicant's materials as follows:

1. Site Plan Application Form dated April 1, 2021
2. Full Environmental Assessment Form February 16, 2021
3. Coastal Assessment Form dated April 1, 2021
4. Stormwater Pollution Prevention Plan by MFS Consulting Engineers & Surveyor dated August 30, 2021
5. Revised Site Plan Designs prepared by Marvel, last revised August 31, 2021
 - a. G001V Sheet Index
 - b. G-010 and G-011 Survey, prepared BY Kenneth B. Salzman dated January 27, 2021
 - c. Z-100 Zoning Map
 - d. C-101 Civil Notes
 - e. C-300 Demolition and Site Clearing Plan
 - f. C-400 Soil and Erosion Control Plan
 - g. C-500 Site Plan
 - h. C-502 Construction Access Plan
 - i. C-600 Proposed Grading and Drainage Plan
 - j. C-700 Utility Plan
 - k. C-701 Utility Relocation Plan
 - l. C-900 and C-901 Construction Details
 - m. L-100 Layout Plan
 - n. L-200 Material Plan

- o. L-400 Tree Plan
- p. L-410 Understory Plan
- q. L-600 and L-601 Site Section
- r. L-620 Site Plan
- s. L-700 and L-701 Typical Details
- t. A-100 through A-104 Floor Plans
- u. A-300 and A-301 Building Elevations
- v. A-320 and A-321 Building Sections
- w. S-501 Retailing Wall Detail
- x. S-505 Typical Details
- y. LL-010 Site Lighting Plan
- z. LL-011 Site Lighting Photometric

WHEREAS, the Planning Board has also reviewed and examined letters, reports, and memorandum from the Board's consulting engineer and planner; and

WHEREAS, the Planning Board conducted a duly noticed public hearing on July 1, 2021, at which time all those wishing to be heard were given the opportunity to be heard, and the public hearing remained open until August 5, 2021; and

WHEREAS, the Planning Board deliberated in public on the Applicant's request for recommendation.

Planning Board Determination

NOW, THEREFORE, BE IT RESOLVED, the Planning Board recommends the application for Site Plan approval with the following additional recommendations as set forth below:

1. The Village Board should require the Applicant to address to the full satisfaction of the Village Engineer, all outstanding stormwater, and engineering issues raised in the hearings and documents submitted to the Board, including the September 7, 2021, engineering review letter.

Motion by: Chairman Hunter

Seconded by: Mr. Brosnahan

CHAIRMAN HUNTER	<input checked="" type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
STEPHEN BROSNAHAN	<input checked="" type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
ROB LANE	<input checked="" type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
ALLEN HALE	<input checked="" type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
LAURA HAUPT	<input checked="" type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input type="checkbox"/> ABSENT/EXCUSED
PETER WINDER, 1 ST ALTERNATE MEMBER	<input type="checkbox"/> AYE	<input type="checkbox"/> NAY	<input type="checkbox"/> ABSTAIN	<input type="checkbox"/> RECUSE	<input checked="" type="checkbox"/> ABSENT/EXCUSED
VOTE TOTALS	5 AYE	0 NAY	0 ABSTAIN	0 RECUSE	1 ABSENT/EXCUSED
RESULT:	MOTION: PASSES				

I hereby attest that the above Resolution was approved by the Planning Board at its September 9, 2021 meeting, and that I have been authorized to sign this Resolution by decision of the Planning Board.



Chairman Hunter

Date: September 9, 2021

MEMORANDUM

To: Stephen Hunter, Planning Board Chairman

C: Planning Board Members
Richard Leins, Interim Village Administrator
Ed Manley, Building Inspector
Dan Pozin, Planning Board Attorney,
Valerie Monastra, Village Planner

From: Anthony Oliveri, P.E.

Date: September 7, 2021

Re: Site Plan
The Masters School
49 Clinton Avenue
Village of Dobbs Ferry

With regard to the above mentioned project, this office has reviewed the following plans and submittals:

- Plans entitled: “The Masters School Innovation and Entrepreneurship Center”, prepared by Marvel, last dated 8/31/2021;
- Stormwater Pollution Prevention Plan (SWPPP), prepared by MFS Consulting Engineers & Surveyor, DPC, dated 8/30/2021;

Our remaining comments are as follows:

1. It is our understanding that the applicant’s engineer is waiting for determination from the Westchester County Health Department regarding permitting requirements for the relocation of the existing 10” sanitary sewer. This should be made a condition of any approval.
2. Pipe crossings and clearances should be shown on the sanitary sewer profile; as noted previously, standard leakage testing requirements in conformance with current Health Department standards should also be noted.
3. Bioretention pond details seem to be missing from the site plan.
4. A final review of the SWPPP will be conducted prior to acceptance and NYSDEC general permit coverage, however our previous comments have been substantially addressed.

Thank you

Full Environmental Assessment Form
Part 2 - Identification of Potential Project Impacts

Agency Use Only [If applicable]
Project : 49 Clinton Avenue
Date : 9/22/21

Part 2 is to be completed by the lead agency. Part 2 is designed to help the lead agency inventory all potential resources that could be affected by a proposed project or action. We recognize that the lead agency's reviewer(s) will not necessarily be environmental professionals. So, the questions are designed to walk a reviewer through the assessment process by providing a series of questions that can be answered using the information found in Part 1. To further assist the lead agency in completing Part 2, the form identifies the most relevant questions in Part 1 that will provide the information needed to answer the Part 2 question. When Part 2 is completed, the lead agency will have identified the relevant environmental areas that may be impacted by the proposed activity.

If the lead agency is a state agency **and** the action is in any Coastal Area, complete the Coastal Assessment Form before proceeding with this assessment.

Tips for completing Part 2:

- Review all of the information provided in Part 1.
- Review any application, maps, supporting materials and the Full EAF Workbook.
- Answer each of the 18 questions in Part 2.
- If you answer "Yes" to a numbered question, please complete all the questions that follow in that section.
- If you answer "No" to a numbered question, move on to the next numbered question.
- Check appropriate column to indicate the anticipated size of the impact.
- Proposed projects that would exceed a numeric threshold contained in a question should result in the reviewing agency checking the box "Moderate to large impact may occur."
- The reviewer is not expected to be an expert in environmental analysis.
- If you are not sure or undecided about the size of an impact, it may help to review the sub-questions for the general question and consult the workbook.
- When answering a question consider all components of the proposed activity, that is, the "whole action".
- Consider the possibility for long-term and cumulative impacts as well as direct impacts.
- Answer the question in a reasonable manner considering the scale and context of the project.

1. Impact on Land Proposed action may involve construction on, or physical alteration of, the land surface of the proposed site. (See Part 1. D.1) <i>If "Yes", answer questions a - j. If "No", move on to Section 2.</i>			
		<input type="checkbox"/> NO	<input checked="" type="checkbox"/> YES
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may involve construction on land where depth to water table is less than 3 feet.	E2d	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may involve construction on slopes of 15% or greater.	E2f	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may involve construction on land where bedrock is exposed, or generally within 5 feet of existing ground surface.	E2a	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may involve the excavation and removal of more than 1,000 tons of natural material. 2,950 cubic yards of fill will be excavated from the site	D2a	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e. The proposed action may involve construction that continues for more than one year or in multiple phases. Construction is anticipated for 18 months	D1e	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f. The proposed action may result in increased erosion, whether from physical disturbance or vegetation removal (including from treatment by herbicides).	D2e, D2q	<input checked="" type="checkbox"/>	<input type="checkbox"/>
g. The proposed action is, or may be, located within a Coastal Erosion hazard area.	B1i	<input checked="" type="checkbox"/>	<input type="checkbox"/>
h. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

2. Impact on Geological Features

The proposed action may result in the modification or destruction of, or inhibit access to, any unique or unusual land forms on the site (e.g., cliffs, dunes, minerals, fossils, caves). (See Part 1. E.2.g)

NO

YES

If "Yes", answer questions a - c. If "No", move on to Section 3.

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. Identify the specific land form(s) attached: _____ _____	E2g	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may affect or is adjacent to a geological feature listed as a registered National Natural Landmark. Specific feature: _____	E3c	<input type="checkbox"/>	<input type="checkbox"/>
c. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

3. Impacts on Surface Water

The proposed action may affect one or more wetlands or other surface water bodies (e.g., streams, rivers, ponds or lakes). (See Part 1. D.2, E.2.h)

NO

YES

If "Yes", answer questions a - l. If "No", move on to Section 4.

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may create a new water body.	D2b, D1h	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may result in an increase or decrease of over 10% or more than a 10 acre increase or decrease in the surface area of any body of water.	D2b	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may involve dredging more than 100 cubic yards of material from a wetland or water body.	D2a	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may involve construction within or adjoining a freshwater or tidal wetland, or in the bed or banks of any other water body.	E2h	<input type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may create turbidity in a waterbody, either from upland erosion, runoff or by disturbing bottom sediments.	D2a, D2h	<input type="checkbox"/>	<input type="checkbox"/>
f. The proposed action may include construction of one or more intake(s) for withdrawal of water from surface water.	D2c	<input type="checkbox"/>	<input type="checkbox"/>
g. The proposed action may include construction of one or more outfall(s) for discharge of wastewater to surface water(s).	D2d	<input type="checkbox"/>	<input type="checkbox"/>
h. The proposed action may cause soil erosion, or otherwise create a source of stormwater discharge that may lead to siltation or other degradation of receiving water bodies.	D2e	<input type="checkbox"/>	<input type="checkbox"/>
i. The proposed action may affect the water quality of any water bodies within or downstream of the site of the proposed action.	E2h	<input type="checkbox"/>	<input type="checkbox"/>
j. The proposed action may involve the application of pesticides or herbicides in or around any water body.	D2q, E2h	<input type="checkbox"/>	<input type="checkbox"/>
k. The proposed action may require the construction of new, or expansion of existing, wastewater treatment facilities.	D1a, D2d	<input type="checkbox"/>	<input type="checkbox"/>

1. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>
----------------------------------	--	--------------------------	--------------------------

4. Impact on groundwater The proposed action may result in new or additional use of ground water, or may have the potential to introduce contaminants to ground water or an aquifer. <input type="checkbox"/> NO <input checked="" type="checkbox"/> YES (See Part 1. D.2.a, D.2.c, D.2.d, D.2.p, D.2.q, D.2.t) <i>If "Yes", answer questions a - h. If "No", move on to Section 5.</i>			
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may require new water supply wells, or create additional demand on supplies from existing water supply wells.	D2c	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. Water supply demand from the proposed action may exceed safe and sustainable withdrawal capacity rate of the local supply or aquifer. Cite Source: _____	D2c	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may allow or result in residential uses in areas without water and sewer services.	D1a, D2c	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may include or require wastewater discharged to groundwater.	D2d, E2l	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may result in the construction of water supply wells in locations where groundwater is, or is suspected to be, contaminated.	D2c, E1f, E1g, E1h	<input checked="" type="checkbox"/>	<input type="checkbox"/>
f. The proposed action may require the bulk storage of petroleum or chemical products over ground water or an aquifer.	D2p, E2l	<input checked="" type="checkbox"/>	<input type="checkbox"/>
g. The proposed action may involve the commercial application of pesticides within 100 feet of potable drinking water or irrigation sources.	E2h, D2q, E2l, D2c	<input checked="" type="checkbox"/>	<input type="checkbox"/>
h. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

5. Impact on Flooding The proposed action may result in development on lands subject to flooding. <input checked="" type="checkbox"/> NO <input type="checkbox"/> YES (See Part 1. E.2) <i>If "Yes", answer questions a - g. If "No", move on to Section 6.</i>			
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may result in development in a designated floodway.	E2i	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may result in development within a 100 year floodplain.	E2j	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may result in development within a 500 year floodplain.	E2k	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may result in, or require, modification of existing drainage patterns.	D2b, D2e	<input type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may change flood water flows that contribute to flooding.	D2b, E2i, E2j, E2k	<input type="checkbox"/>	<input type="checkbox"/>
f. If there is a dam located on the site of the proposed action, is the dam in need of repair, or upgrade?	E1e	<input type="checkbox"/>	<input type="checkbox"/>

g. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>
----------------------------------	--	--------------------------	--------------------------

6. Impacts on Air

The proposed action may include a state regulated air emission source.
(See Part 1. D.2.f., D.2.h, D.2.g)
If "Yes", answer questions a - f. If "No", move on to Section 7.

NO

YES

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. If the proposed action requires federal or state air emission permits, the action may also emit one or more greenhouse gases at or above the following levels: i. More than 1000 tons/year of carbon dioxide (CO ₂) ii. More than 3.5 tons/year of nitrous oxide (N ₂ O) iii. More than 1000 tons/year of carbon equivalent of perfluorocarbons (PFCs) iv. More than .045 tons/year of sulfur hexafluoride (SF ₆) v. More than 1000 tons/year of carbon dioxide equivalent of hydrochloroflourocarbons (HFCs) emissions vi. 43 tons/year or more of methane	D2g D2g D2g D2g D2g D2h	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>
b. The proposed action may generate 10 tons/year or more of any one designated hazardous air pollutant, or 25 tons/year or more of any combination of such hazardous air pollutants.	D2g	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may require a state air registration, or may produce an emissions rate of total contaminants that may exceed 5 lbs. per hour, or may include a heat source capable of producing more than 10 million BTU's per hour.	D2f, D2g	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may reach 50% of any of the thresholds in "a" through "c", above.	D2g	<input type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may result in the combustion or thermal treatment of more than 1 ton of refuse per hour.	D2s	<input type="checkbox"/>	<input type="checkbox"/>
f. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

7. Impact on Plants and Animals

The proposed action may result in a loss of flora or fauna. (See Part 1. E.2. m.-q.)
If "Yes", answer questions a - j. If "No", move on to Section 8.

NO

YES

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may cause reduction in population or loss of individuals of any threatened or endangered species, as listed by New York State or the Federal government, that use the site, or are found on, over, or near the site.	E2o	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may result in a reduction or degradation of any habitat used by any rare, threatened or endangered species, as listed by New York State or the federal government.	E2o	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may cause reduction in population, or loss of individuals, of any species of special concern or conservation need, as listed by New York State or the Federal government, that use the site, or are found on, over, or near the site.	E2p	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may result in a reduction or degradation of any habitat used by any species of special concern and conservation need, as listed by New York State or the Federal government.	E2p	<input type="checkbox"/>	<input type="checkbox"/>

e. The proposed action may diminish the capacity of a registered National Natural Landmark to support the biological community it was established to protect.	E3c	<input type="checkbox"/>	<input type="checkbox"/>
f. The proposed action may result in the removal of, or ground disturbance in, any portion of a designated significant natural community. Source: _____	E2n	<input type="checkbox"/>	<input type="checkbox"/>
g. The proposed action may substantially interfere with nesting/breeding, foraging, or over-wintering habitat for the predominant species that occupy or use the project site.	E2m	<input type="checkbox"/>	<input type="checkbox"/>
h. The proposed action requires the conversion of more than 10 acres of forest, grassland or any other regionally or locally important habitat. Habitat type & information source: _____	E1b	<input type="checkbox"/>	<input type="checkbox"/>
i. Proposed action (commercial, industrial or recreational projects, only) involves use of herbicides or pesticides.	D2q	<input type="checkbox"/>	<input type="checkbox"/>
j. Other impacts: _____		<input type="checkbox"/>	<input type="checkbox"/>

8. Impact on Agricultural Resources			
The proposed action may impact agricultural resources. (See Part 1. E.3.a. and b.)		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> YES
<i>If "Yes", answer questions a - h. If "No", move on to Section 9.</i>			
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may impact soil classified within soil group 1 through 4 of the NYS Land Classification System.	E2c, E3b	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may sever, cross or otherwise limit access to agricultural land (includes cropland, hayfields, pasture, vineyard, orchard, etc).	E1a, E1b	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may result in the excavation or compaction of the soil profile of active agricultural land.	E3b	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may irreversibly convert agricultural land to non-agricultural uses, either more than 2.5 acres if located in an Agricultural District, or more than 10 acres if not within an Agricultural District.	E1b, E3a	<input type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may disrupt or prevent installation of an agricultural land management system.	E1 a, E1b	<input type="checkbox"/>	<input type="checkbox"/>
f. The proposed action may result, directly or indirectly, in increased development potential or pressure on farmland.	C2c, C3, D2c, D2d	<input type="checkbox"/>	<input type="checkbox"/>
g. The proposed project is not consistent with the adopted municipal Farmland Protection Plan.	C2c	<input type="checkbox"/>	<input type="checkbox"/>
h. Other impacts: _____		<input type="checkbox"/>	<input type="checkbox"/>

9. Impact on Aesthetic Resources

The land use of the proposed action are obviously different from, or are in sharp contrast to, current land use patterns between the proposed project and a scenic or aesthetic resource. (Part 1. E.1.a, E.1.b, E.3.h.)

NO

YES

If "Yes", answer questions a - g. If "No", go to Section 10.

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. Proposed action may be visible from any officially designated federal, state, or local scenic or aesthetic resource.	E3h	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may result in the obstruction, elimination or significant screening of one or more officially designated scenic views.	E3h, C2b	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may be visible from publicly accessible vantage points: i. Seasonally (e.g., screened by summer foliage, but visible during other seasons) ii. Year round	E3h	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>	<input type="checkbox"/> <input type="checkbox"/>
d. The situation or activity in which viewers are engaged while viewing the proposed action is: i. Routine travel by residents, including travel to and from work ii. Recreational or tourism based activities	E3h E2q, E1c	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>	<input type="checkbox"/> <input type="checkbox"/>
e. The proposed action may cause a diminishment of the public enjoyment and appreciation of the designated aesthetic resource.	E3h	<input checked="" type="checkbox"/>	<input type="checkbox"/>
f. There are similar projects visible within the following distance of the proposed project: 0-1/2 mile 1/2 -3 mile 3-5 mile 5+ mile	D1a, E1a, D1f, D1g	<input checked="" type="checkbox"/>	<input type="checkbox"/>
g. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

10. Impact on Historic and Archeological Resources

The proposed action may occur in or adjacent to a historic or archaeological resource. (Part 1. E.3.e, f. and g.)

NO

YES

If "Yes", answer questions a - e. If "No", go to Section 11.

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may occur wholly or partially within, or substantially contiguous to, any buildings, archaeological site or district which is listed on the National or State Register of Historical Places, or that has been determined by the Commissioner of the NYS Office of Parks, Recreation and Historic Preservation to be eligible for listing on the State Register of Historic Places.	E3e	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may occur wholly or partially within, or substantially contiguous to, an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory.	E3f	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may occur wholly or partially within, or substantially contiguous to, an archaeological site not included on the NY SHPO inventory. Source: _____	E3g	<input checked="" type="checkbox"/>	<input type="checkbox"/>

d. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>
e. If any of the above (a-d) are answered "Moderate to large impact may occur", continue with the following questions to help support conclusions in Part 3:			
i. The proposed action may result in the destruction or alteration of all or part of the site or property.	E3e, E3g, E3f	<input checked="" type="checkbox"/>	<input type="checkbox"/>
ii. The proposed action may result in the alteration of the property's setting or integrity.	E3e, E3f, E3g, E1a, E1b	<input checked="" type="checkbox"/>	<input type="checkbox"/>
iii. The proposed action may result in the introduction of visual elements which are out of character with the site or property, or may alter its setting.	E3e, E3f, E3g, E3h, C2, C3	<input checked="" type="checkbox"/>	<input type="checkbox"/>

11. Impact on Open Space and Recreation			
The proposed action may result in a loss of recreational opportunities or a reduction of an open space resource as designated in any adopted municipal open space plan. (See Part 1. C.2.c, E.1.c., E.2.q.) <i>If "Yes", answer questions a - e. If "No", go to Section 12.</i>		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> YES
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may result in an impairment of natural functions, or "ecosystem services", provided by an undeveloped area, including but not limited to stormwater storage, nutrient cycling, wildlife habitat.	D2e, E1b E2h, E2m, E2o, E2n, E2p	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may result in the loss of a current or future recreational resource.	C2a, E1c, C2c, E2q	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may eliminate open space or recreational resource in an area with few such resources.	C2a, C2c E1c, E2q	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may result in loss of an area now used informally by the community as an open space resource.	C2c, E1c	<input type="checkbox"/>	<input type="checkbox"/>
e. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

12. Impact on Critical Environmental Areas			
The proposed action may be located within or adjacent to a critical environmental area (CEA). (See Part 1. E.3.d) <i>If "Yes", answer questions a - c. If "No", go to Section 13.</i>		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> YES
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may result in a reduction in the quantity of the resource or characteristic which was the basis for designation of the CEA.	E3d	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may result in a reduction in the quality of the resource or characteristic which was the basis for designation of the CEA.	E3d	<input type="checkbox"/>	<input type="checkbox"/>
c. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

13. Impact on Transportation

The proposed action may result in a change to existing transportation systems.

 NO YES

(See Part 1. D.2.j)

If "Yes", answer questions a - f. If "No", go to Section 14.

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. Projected traffic increase may exceed capacity of existing road network.	D2j	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may result in the construction of paved parking area for 500 or more vehicles.	D2j	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action will degrade existing transit access.	D2j	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action will degrade existing pedestrian or bicycle accommodations.	D2j	<input type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may alter the present pattern of movement of people or goods.	D2j	<input type="checkbox"/>	<input type="checkbox"/>
f. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

14. Impact on Energy

The proposed action may cause an increase in the use of any form of energy.

 NO YES

(See Part 1. D.2.k)

If "Yes", answer questions a - e. If "No", go to Section 15.

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action will require a new, or an upgrade to an existing, substation.	D2k	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. The proposed action will require the creation or extension of an energy transmission or supply system to serve more than 50 single or two-family residences or to serve a commercial or industrial use.	D1f, D1q, D2k	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may utilize more than 2,500 MWhrs per year of electricity.	D2k	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may involve heating and/or cooling of more than 100,000 square feet of building area when completed.	D1g	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e. Other Impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

15. Impact on Noise, Odor, and Light

The proposed action may result in an increase in noise, odors, or outdoor lighting.

 NO YES

(See Part 1. D.2.m., n., and o.)

If "Yes", answer questions a - f. If "No", go to Section 16.

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may produce sound above noise levels established by local regulation.	D2m	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may result in blasting within 1,500 feet of any residence, hospital, school, licensed day care center, or nursing home.	D2m, E1d	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may result in routine odors for more than one hour per day.	D2o	<input checked="" type="checkbox"/>	<input type="checkbox"/>

d. The proposed action may result in light shining onto adjoining properties.	D2n	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may result in lighting creating sky-glow brighter than existing area conditions.	D2n, E1a	<input checked="" type="checkbox"/>	<input type="checkbox"/>
f. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

16. Impact on Human Health

The proposed action may have an impact on human health from exposure to new or existing sources of contaminants. (See Part 1.D.2.q., E.1. d. f. g. and h.)

NO

YES

If "Yes", answer questions a - m. If "No", go to Section 17.

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action is located within 1500 feet of a school, hospital, licensed day care center, group home, nursing home or retirement community.	E1d	<input type="checkbox"/>	<input type="checkbox"/>
b. The site of the proposed action is currently undergoing remediation.	E1g, E1h	<input type="checkbox"/>	<input type="checkbox"/>
c. There is a completed emergency spill remediation, or a completed environmental site remediation on, or adjacent to, the site of the proposed action.	E1g, E1h	<input type="checkbox"/>	<input type="checkbox"/>
d. The site of the action is subject to an institutional control limiting the use of the property (e.g., easement or deed restriction).	E1g, E1h	<input type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may affect institutional control measures that were put in place to ensure that the site remains protective of the environment and human health.	E1g, E1h	<input type="checkbox"/>	<input type="checkbox"/>
f. The proposed action has adequate control measures in place to ensure that future generation, treatment and/or disposal of hazardous wastes will be protective of the environment and human health.	D2t	<input type="checkbox"/>	<input type="checkbox"/>
g. The proposed action involves construction or modification of a solid waste management facility.	D2q, E1f	<input type="checkbox"/>	<input type="checkbox"/>
h. The proposed action may result in the unearthing of solid or hazardous waste.	D2q, E1f	<input type="checkbox"/>	<input type="checkbox"/>
i. The proposed action may result in an increase in the rate of disposal, or processing, of solid waste.	D2r, D2s	<input type="checkbox"/>	<input type="checkbox"/>
j. The proposed action may result in excavation or other disturbance within 2000 feet of a site used for the disposal of solid or hazardous waste.	E1f, E1g E1h	<input type="checkbox"/>	<input type="checkbox"/>
k. The proposed action may result in the migration of explosive gases from a landfill site to adjacent off site structures.	E1f, E1g	<input type="checkbox"/>	<input type="checkbox"/>
l. The proposed action may result in the release of contaminated leachate from the project site.	D2s, E1f, D2r	<input type="checkbox"/>	<input type="checkbox"/>
m. Other impacts: _____ _____			

17. Consistency with Community Plans

The proposed action is not consistent with adopted land use plans.

(See Part 1. C.1, C.2. and C.3.)

If "Yes", answer questions a - h. If "No", go to Section 18.

NO

YES

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action's land use components may be different from, or in sharp contrast to, current surrounding land use pattern(s).	C2, C3, D1a E1a, E1b	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action will cause the permanent population of the city, town or village in which the project is located to grow by more than 5%.	C2	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action is inconsistent with local land use plans or zoning regulations.	C2, C2, C3	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action is inconsistent with any County plans, or other regional land use plans.	C2, C2	<input type="checkbox"/>	<input type="checkbox"/>
e. The proposed action may cause a change in the density of development that is not supported by existing infrastructure or is distant from existing infrastructure.	C3, D1c, D1d, D1f, D1d, E1b	<input type="checkbox"/>	<input type="checkbox"/>
f. The proposed action is located in an area characterized by low density development that will require new or expanded public infrastructure.	C4, D2c, D2d D2j	<input type="checkbox"/>	<input type="checkbox"/>
g. The proposed action may induce secondary development impacts (e.g., residential or commercial development not included in the proposed action)	C2a	<input type="checkbox"/>	<input type="checkbox"/>
h. Other: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>

18. Consistency with Community Character

The proposed project is inconsistent with the existing community character.

(See Part 1. C.2, C.3, D.2, E.3)

If "Yes", answer questions a - g. If "No", proceed to Part 3.

NO

YES

	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may replace or eliminate existing facilities, structures, or areas of historic importance to the community.	E3e, E3f, E3g	<input type="checkbox"/>	<input type="checkbox"/>
b. The proposed action may create a demand for additional community services (e.g. schools, police and fire)	C4	<input type="checkbox"/>	<input type="checkbox"/>
c. The proposed action may displace affordable or low-income housing in an area where there is a shortage of such housing.	C2, C3, D1f D1g, E1a	<input type="checkbox"/>	<input type="checkbox"/>
d. The proposed action may interfere with the use or enjoyment of officially recognized or designated public resources.	C2, E3	<input type="checkbox"/>	<input type="checkbox"/>
e. The proposed action is inconsistent with the predominant architectural scale and character.	C2, C3	<input type="checkbox"/>	<input type="checkbox"/>
f. Proposed action is inconsistent with the character of the existing natural landscape.	C2, C3 E1a, E1b E2g, E2h	<input type="checkbox"/>	<input type="checkbox"/>
g. Other impacts: _____ _____		<input type="checkbox"/>	<input type="checkbox"/>



**Parks, Recreation,
and Historic Preservation**

ANDREW M. CUOMO
Governor

ERIK KULLESEID
Commissioner

July 16, 2021

Mr. Charles Vandrei
Agency Historic Preservation Officer
NYS Environmental Conservation
Division of Lands and Forests
625 Broadway
Albany, NY 12233-4255

Re: DEC
The Masters School Innovation and Entrepreneurship Center
49 Clinton Ave, Dobbs Ferry, NY 10522
21PR04192

Dear Mr. Vandrei:

Thank you for requesting the comments of the Division for Historic Preservation of the Office of Parks, Recreation and Historic Preservation (OPRHP). We have reviewed the submitted materials in accordance with the New York State Historic Preservation Act of 1980 (section 14.09 of the New York Parks, Recreation and Historic Preservation Law). These comments are those of the Division for Historic Preservation and relate only to Historic/Cultural resources. They do not include potential environmental impacts to New York State Parkland that may be involved in or near your project. Such impacts must be considered as part of the environmental review of the project pursuant to the State Environmental Quality Review Act (New York Environmental Conservation Law Article 8) and its implementing regulations (6NYCRR Part 617).

We note that the proposed new construction is within the boundaries of the Estherwood Mansion and Carriage House, which is listed in the State and National Registers of Historic Places. Our office has reviewed the materials submitted for the proposed Innovation and Entrepreneurship Center building received on June 22, 2021. Based upon our review, it is the OPRHP's opinion that the project will have No Adverse Impact on historic or archaeological resources.

If there are substantive changes to the project or to the design of the new construction, consultation with our office should resume. If you have any questions, I am best reached by email.

Sincerely,

Derek Rohde
Historic Site Restoration Coordinator
e-mail: derek.rohde@parks.ny.gov

via e-mail only

From: [Jennifer Olson](#)
To: dep.r3@dec.ny.gov
Cc: [Valerie Monastra](#); [Biddle, Ed](#); [Marx, Seth](#); [Brad Schwartz](#); [Lissa So](#)
Subject: NYSDEC review request - The Masters School IEC
Date: Friday, July 16, 2021 1:10:21 PM
Attachments: [image001.png](#)
[6.17.21 Masters School IEC Site Plan Application - EAF.pdf](#)
[2029 2021 0716 Masters IEC NYSDEC EAF review memo.pdf](#)

Hello Mr. Petronella –

We are the project architects for The Masters School in connection with its proposed construction of a new educational building called the Innovation and Entrepreneurship Center (“IEC”) on an approximately 10-acre site located at 49 Clinton Avenue, Dobbs Ferry, New York 10522 (“Site”). The Site comprises a portion of the School’s overall approximately 91-acre campus.

The purpose of this letter is to request a consultation with your Department as part of the SEQRA process for the IEC, which is being led by the Village of Dobbs Ferry Board of Trustees. In our team’s preparation of the Full Environmental Assessment Form (“EAF”) for the Project, the EAF Mapper identified two endangered species, Atlantic Sturgeon and Shortnose Sturgeon, on Section E.2.(o)(i) of the EAF (copy enclosed). These species were identified as a result of the Site being located in the Hudson River Estuary. These species are not found on the Site, which is approximately 0.57 miles upgradient from the River.

The Village asked that we initiate this consultation to determine if this project poses a potential threat to the Shortnose Sturgeon and Atlantic Sturgeon. We hope that you will agree that this proposed educational building far from the River does not pose such a threat, and that you will issue a No Adverse Impact or similar letter that we can provide to the Village. We copied the Village’s planning consultant on this submission.

Attached to this email you will find a letter from our office stating this request, a copy of our full EAF submitted to the Village of Dobbs Ferry Planning Board, and a below link to applicable project drawings.

 [2021-07-16_Masters IEC DEC drawings](#)

We appreciate if you could please acknowledge receipt of this request, and confirm if you will in fact be able to review the project.

Thank you very much,
Jennifer

Jennifer Olson, AIA, LEED AP
Director

MARVEL

145 Hudson Street, New York, NY 10013
646 237 4149 direct
919 434 5751 mobile

MASTERS SCHOOL SITE PLAN APPLICATION – SCHEDULE PUBLIC HEARING

WHEREAS, on April 13, 2021 the Board of Trustees of the Village of Dobbs Ferry acknowledged receipt of a site plan application for construction of a proposed 22,361 s.f. Innovation and Entrepreneurship Center educational building and related site improvements on an undeveloped portion of the 90-acre Masters School campus (the “Project”), declared itself Lead Agency for purposes of SEQRA and directed referral of the matter to the Dobbs Ferry and County Planning Boards and the Dobbs Ferry AHRB in accordance with legal requirements; and

WHEREAS, the matter having now been returned to the Board’s agenda by the Dobbs Ferry Planning Board, it is necessary to schedule a public hearing in advance of further review and action.

NOW BE IT RESOLVED, that, the Board of Trustees of the Village of Dobbs Ferry hereby calls for a public hearing to be scheduled on Tuesday, October 12, 2021 at 6:30 p.m., or as soon thereafter as the matter may be heard, to receive public comment and consider the request for site plan approval for the Project on the Masters School campus at 49 Clinton Avenue.